

GOVERNMENT OF INDIA
DEPARTMENT OF ARCHAEOLOGY
CENTRAL ARCHÆOLOGICAL
LIBRARY


CALL No. 891.05/C.R.A.S.
Acc. No. 24876

D.G.A. 79.

GIPN—S4—2D. G. Arch. N. D./57.—25-9 58—1,00,000.



~~A 355~~
82





JOURNAL

OF THE

CEYLON BRANCH

OF THE

ROYAL ASIATIC SOCIETY,

1885—1886.

20876

VOLUME IX.

EDITED BY THE HONORARY SECRETARY.

"The design of the Society is to institute and promote inquiries into the History, Religion, Literature, Arts, and Social Condition of the present and former Inhabitants of the Island, with its Geology, Mineralogy, its Climate and Meteorology, its Botany and Zoology."

891.05

C. R. A. S.

COLOMBO:

G. J. A. SKEEN, GOVERNMENT PRINTER, CEYLON.

1888.

CEN

LIBRARY

Y, NEW DELHI.

Acc. No. 24876

Date.....18.12.56

Call No. 87105

A.3.

CONTENTS OF VOLUME IX.

No. 30.—1885.

	PAGE
A Systematic Catalogue of the Flowering Plants and Ferns indigenous to or growing wild in Ceylon, with the Vernacular names, and with references to Thwaites' "Enumeratio."—By HENRY TRIMEN, Esq., M.B., F.L.S., Director of the Royal Botanic Gardens, Ceylon ...	1.

No. 31.—1885.

Remarks on the Composition, Geographical Affinities, and Origin of the Ceylon Flora.—By HENRY TRIMEN, Esq., M.B., F.L.S. ...	139
Rice Cultivation under Irrigation in Ceylon.—By E. ELLIOTT, Esq., C.C.S. ...	160
Piumbago : with special reference to the position occupied by the Mineral in the Commerce of Ceylon ; and the question discussed of the alleged existence in the Island of the allied substance Anthracite.—By A. M. FERGUSON, Esq., C.M.G. ...	171

No. 32.—1886.

Professor Virchow's Ethnological Studies on the Singhalese Race.—Translated by W. R. KYNSEY, Esq., F.K.Q.C.P., and J. D. MACDONALD, Esq., M.D. ...	267
Outline of Two Years' Scientific Researches in Ceylon.—By Drs C. F. and P. B. SARASIN ...	289
A Brief Sketch of the Medical History of Ceylon.—By J. L. VANDERSTRAATEN, Esq., M.D. ...	306
The Veddás of Ceylon.—By C. J. R. LE MESURIER, Esq., C.C.S., F.G.S., &c. ...	336

No. 33.—1886.

The Veddás of Ceylon, and their relation to the Neighbouring Tribes.—By Professor R. VIRCHOW ...	349
Proceedings, 1885 ...	i
Proceedings, 1886 ...	cxi

ERRATA ET ADDENDA.

- Page 351, note §, for "p. 124" read "p. 62."
 „ 352, line 2, for "Van Goen" read "Van Goens."
 „ 353, note †, for "Norasa" read "Novasa."
 „ 358, note *, for "p. 123" read "p. 62."
 „ 358, note †, for "p. 126" read "p. 63."
 „ 359, line 30, for "Taylor" read "Tylor."
 „ 359, note *, omit "Die omfänge der cultur übers."
 „ 359, note †, for "Taylor" read "Tylor."
 „ 359, note †, for "Spangel" read "Spangel."
 „ 368, note †, for "Zuitf." read "Zeits. für" *passim*.
 „ 378, note *, for "Mokna" read "Mokua."
 „ 381, line 2, for "Flu" read "Elu."
 „ 381, note *, for "p. 104" read "p. 61."
 „ 384, line 12, for "κολορα" read "κολοβὰ."
 „ 387, last line, after "precipices" insert "(λιθινοῖς σπηλαιοῖς)."
 „ 388, line 16, for "Zvortvan berwe beandend," &c., read "Zwart van
 verwe, brandend," &c.
 „ 394, line 6, after "Skull No. 1" insert "(Table I.)."
 „ 394, line 11, for "Dewilané" read "Denilane."
 „ 398, line 13, for "Busle" read "Busk."
 „ 398, line 14, for "two last" read "last two."
 „ 398, line 31, after "Museum," insert "(Table I., Fig. 3)."
 „ 399, line 21, for "Weleker" read "Welcker."
 „ 402, line 11, for "occipitale" read "occipitalis."
 „ 404, line 10, for "76" read "7.6."
 „ 404, line 12, after "skull" insert "(Flower, No. 683)."
 „ 406, line 16, for "chamæprosopous" read "chamæprosopic."
 „ 406, line 29, after "skull," insert "(No. 675)."
 „ 406, line 35, for "alreolar" read "alveolar."
 „ 406, line 36, for "basilar alvesli" length read "basi-alveolar length."
 „ 407, line 2, for "basinasel" read "basinasal."
 „ 409, line 2, for "Bernard" read "Barnard."
 „ 411, line 18, for "von" read "van."
 „ 411, line 19, for "vrijser ruf tig" read "vrij vernuftig."
 „ 411, note *, for "Tambulus" read "Jambulus."

EXPLANATORY NOTE.

THE *Natural Orders* and the *Genera* in this Catalogue are each numbered consecutively throughout, the sequence followed being that of the "Genera Plantarum" by Bentham and Hooker. The *Species* are generally named in accordance with the "Flora of British India," so far as that work has yet been published (to end of Genus 594, p. 67).

Names of species or varieties printed in SMALL CAPITALS are believed to be *endemic* (i. e., found in Ceylon only, or peculiar to the Island).

Names with an asterisk (*) prefixed are exotic species which have become more or less *naturalized*, usually as *weeds* in cultivated or waste land. Many are thoroughly established and very common; others merely casual and rarely found. A dagger (†) prefixed to a name indicates a suspicion of exotic origin or a doubt as to true nativity.

Names enclosed in round brackets () are exotic species which, being largely *cultivated* for use or ornament, are often found apparently wild, but are not really naturalized here.

A query (?) prefixed to a name indicates doubt as to the occurrence of the plant in Ceylon; placed *after* a name it means doubt as to the correctness of the determination.

Names enclosed in square brackets [] are species which have been recorded for Ceylon, but the occurrence of which is a matter of grave doubt or requires verification. Most of them are, in all probability, *errors*, but as they are given in books of more or less authority, it is thought well to include them, thus clearly distinguished from the others.

The additional names (synonyms) in *italics* are those of Thwaites's "Enumeratio Plantarum Zeylanicæ" (1858-64) when different from the ones here adopted. The numbers following the names refer to the pages of the same book, to which this Catalogue forms a complete classified index.

In the case of a few species of which I have not seen Ceylon specimens—and for the most part not included in the "Enumeratio"—I have quoted the name of the collector given by the author recording the species as Ceylonese,

thus ("Walker"). Most of them, it will be seen, were collected by Col. or Mrs. Walker (in 1830-40), and many, it seems, have not been again found.

"C. P." refers to the distributed sets of dried specimens of *Ceylon Plants*. The numbers given here are the whole of those subsequent to the ones quoted in the "Enumeratio," which terminated with C. P. 3860. A few of the earlier numbers however are occasionally quoted in this Catalogue, when necessary to secure precision in nomenclature.

New Species.—There are a few MS. names here printed for the first time. It is my intention to publish descriptions of these supposed new species in the "Journal of Botany" (London) without delay.

Vernacular Names.—The letters "S." and "T." after these signify *Sinhalese* and *Tamil* respectively. With regard to the former, it is believed that a fair amount of accuracy has been attained, and that the spelling is in accordance with the rules for transliteration prescribed by the Ceylon Government. In the case of the Tamil names, however, it is to be feared that but a small number of those in use in the North and East of the Colony have been obtained, and that these are not always rightly determined or properly transliterated. But it may be hoped that the publication of this list will serve as a basis for a more systematic and accurate collection.

English names have been added to the few plants which have acquired them.

H. T.

Pérádeniya, February, 1885.

Corrections and Additions.

PAGE 2, No. 15 ; *Cyathocalyx zeylanicus* is not endemic, and should not be printed in small capitals.

13, line 8 from bottom ; add at end of line, 54.

22, line 7 from bottom ; insert before 410, *Var. β*.

38, line 8 from bottom ; for "*Cerasiocarpus*" read *Cerasiocarpum*.

44, line 19 ; after var. *pubescens* add, *Var. β*. 155.

54, line 19 ; for "L." read, and.

ib., line 4 from bottom ; after *Rothii* insert, var. *puberula*.

ib., line 15 from bottom ; for "*Pori*" read *Poir*.

55, line 12 from bottom ; add at end of line, 197.

ib., line 18 from bottom ; for "*Mēda-kangu*" read *Mēda-hangu*.

56, line 6 ; add at end of line, 196.

64, line 16 ; for "20" read 208.

79, line 15 from bottom ; for "*P. flexuosus*" read *Peltandra flexuosa*.

81, line 13 ; for "trilboa" read *triloba*.

82, line 2 ; before 271 insert, *C. longifolium*.

86, line 16 ; add at end of line, 294.

96, line 13 ; for "*fasciculata*" read *fasciculatum*.

89, after line 27, insert


794 bis. *OCTABRHENA PARVULA*, *Thw.* 305.

104, line 11 from bottom ; for "*P. infidum*, *Steud.*?" read *P. glumare*, *Trin.* (This grass is *Urochloa glabra*, Brongn.)

105, line 11 ; for "3090" read 3890.

Add to Index in its proper place :—

Peltandra . . . 695.



DICOTYLEDONS.

POLYPETALÆ THALAMIFLORÆ.

1. Ranunculaceæ.

1. *Clematis smilacifolia*, *Wall.* 1.
Nara-wel, *S.*
C. Gowriana, *Roxb.* 1.
2. *Naravelia zeylanica*, *DC.* 1.
3. *Anemone rivularis*, *Ham.* 1.
4. *Thalictrum javanicum*, *Bl.* *T. glyphocarpum*. 1.
5. *RANUNCULUS SAGITTIFOLIUS*, *Hk.* 1.
R. Wallichianus, *W. & A.* 1.

2. Dilleniaceæ.

6. *Delima sarmentosa*, *L.* 2.
Korasa-wel, *S.*
7. *Tetracera lævis*, *Vahl.* 2.
Et-korasa-wel, *S.*
8. *ACROTREMA UNIFLORUM*, *Hk.* 2. & C.P. 3896.
var. *rotundatum*, *Thw.*
var. *bullatum*, *Thw.* (sp.) 2.
var. *rugatum*, *Thw. ms.* (sp.) C.P. 3899, 3905.
var. *sylvaticum*, *Thw.* (sp.) 2. & C.P. 3882.
var. (? hybr.) *membranaceum*, *Thw. ms.* (sp.)
C.P. 3897, 3898.
var. *Walkeri*, *Thw.* (sp.) 3, 398.
var. (? hybr.) *appendiculatum*, *Thw. ms.* (sp.) C.P. 3880.
var. (? hybr.) *dentatum*, *Thw. ms.* (sp.) C.P. 3881.
A. INTERMEDIUM, *Thw.* 3.
A. LANCEOLATUM, *Hk.* 3.
A. GARDNERI, *Thw.* 3.
A. THWAITESII, *Hk. f. & Th.* 3. & C.P. 3969.
A. DISSECTUM, *Thw.* 3.
A. LYRATUM, *Thw.* 3.
9. *SCHUMACHERIA ANGUSTIFOLIA*, *Hk. f. & Th.* 4.
S. ALNIFOLIA, *Hk. f. & Th.* 4.
var. *scabra*, *Thw.*
var. *dentata*, *Wight.*
var. *subulabra*, *Thw.*

S. CASTANÆFOLIA, Vahl. 4.

Kekiriwará, S.

10. *WORMIA TRIQUETRA*, Rottb. 4.

Diyapara, S.

11. *Dillenia indica*, L. *D. speciosa*. 5.

Hondapara, *Wam-para*, S.

D. RETUSA, Thunb. 5.

Godapara, S. *Pasu*, *Punali*, T.

3. Magnoliaceæ.

12. *Michelia nilagirica*, Zenk. 5.

Wal-sapu, *Wal-buruta*, S.

var. *glauca*, Wight (sp.) (Includes var. *ovalifolia*.)

var. *Walkeri*, Wight (sp.)

(*M. Champaca*, L.) 5.

Sapu, S. *Senpakam*, T. *Champak*.

13. *Kadsura Wightiana*, Arn. 5.

4. Anonaceæ.

14. *UVARIA SPHENOCARPA*, Hk. f. & Th. 6.

U. macrophylla, Roxb. 6.

U. semecarpifolia, Hk. f. & Th. 6.

U. MACROPODA, Hk. f. & Th. 6.

U. Narum, Wall. 6.

U. zeylanica, L. 6.

Palu-kaz, S.

15. *CYATHOCALYX ZEYLANICUS*, Champ. 9.

Kekala, *I'petta*, S.

16. *Artabotrys odoratissimus*, R. Br. 9.

A. zeylanicus, Hk. f. & Th. 9.

Petiká-wel, S.

17. *UNONA ELEGANS*, Thw. 398.

U. ZEYLANICA, Hk. f. & Th. 9.

18. *Polyalthia longifolia*, Bedd. *Guatteria*. 10.

P. coffæoides, Bedd. *Guatteria*. 10.

Nedunárai, T.

P. ACUMINATA, Thw. 399.

P. Korinti, Hk. f. & Th. 10.

Ulavintai, T.

P. suberosa, Bedd. 10.

Kalaṭi, S.

P. MOONII, Thw. 9.

P. PERSICIFOLIA, Bedd. *Guatteria*. 10. C.P. 3917.

19. *Anaxagorea luzonensis*, Gray. *A. zeylanica*. 10. C.P. 3883.
20. *Goniiothalamus Thwaitesii*, Hk. f. & Th. 7.
Kalukêra, S.
G. GARDNERI, Hk. f. & Th. 7.
G. HOOKERI, Thw. 6.
G. WALKERI, Hk. f. & Th. 8.
Kapuru, S.
G. THOMSONI, Thw. 7.
G. RETICULATUS, Thw. 7.
G. SALICINUS, Hk. f. & Th. 7.
21. *Mitrephora Heyneana*, Thw. 8.
22. *XYLOPIA PARVIFLORA*, Hk. f. & Th. 9.
Netawu, S.
X. NIGRICANS, Hk. f. & Th. 9.
X. CHAMPIONII, Hk. f. & Th. 9.
Datkeṭiyá, S.
23. *Miliusa indica*, Lesch. *M. montana*. 10.
M. ZEYLANICA, Gardn. 11.
24. *Alphonsea lutea*, Hk. f. & Th. 399.
A. zeylanica Hk. f. & Th. 11.
A. SCLEROCARPA, Thw. 11.
25. *Orophea zeylanica*, Hk. f. & Th. 8.
26. *BOCAGEA THWAITESII*, Hk. f. & Th. *Sageræa*. 6.
B. CORIACEA, Hk. f. & Th. *Orophea*. 8.
Keku, S.
B. OBLIQUA, Hk. f. & Th. *Orophea*. 8.

5. Menispermaceæ.

27. *Tinospora malabarica*, Miers.
var. *tomentosa*, Miers (sp.) 12.
Bú-kinda, *Wal-kinda*, S.
† *T. crispa*, Miers.
Titta-kinda, S.
T. cordifolia, Miers. 12.
Rasa-kinda, S. *Seenthil*, T.
28. *Anamirta paniculata*, Colebr. *A. Cocculus*. 12.
Titta-wel, S.
29. *Cosciniun fenestratum*, Colebr. 12.
Weni-wel, S.
30. *Tiliacora racemosa*, Colebr. *T. acuminata*. 12.

31. *Limacia cuspidata*, *Hk. f. & Th.* 12.
Niri-wel, S.

32. *Cocculus macrocarpus*, *W. & A.* 13.

33. *Stephania hernandifolia*, *Walp.* 13.
Lunu-keṭiya-wel, S.

34. *Cissampelos Pareira*, *L.* 13.

Diya-mitta, S.

var. *subpeltata*, *Thw.* 399.

35. *Cyclea Burmanni*, *Miers.* 13.

Kēhi-pittan, *Kēsi-pissan*, S.

[*C. peltata*, *Hk. f. & Th.*] 13.

36. *Pachygone ovata*, *Miers.* 13.

6. Berberideæ.

37. *Berberis aristata*, *DC.* 13.

7. Nymphæaceæ.

38. *Nymphæa Lotus*, *L.* 14.

var. *pubescens*, *Hk. f. & Th.*

O'lu, S.

- N. stellata*, *Willd.* 14.

Mānel, S.

39. *Nelumbium speciosum*, *Willd.* 14.

Nelun, S. *Tamarai*, T.

8. Cruciferæ.

40. *Nasturtium indicum*, *DC.* 399.

* *N. officinale*, *L.* *Kakkutu-palā*, S. *Water-cress.*

41. *Cardamine africana*, *L.* 399.

C. subumbellata, *Hk.* *C. hirsuta*. 14.

* *Brassica juncea*, *Hk. f. & Th.* 399.

Aba, S.

9. Capparideæ.

42. *Cleome monophylla*, *L.* 14.

C. tenella, *L. f.*

C. aspera, *Koen.* 14.

[*C. Burmanni*, *W. & A.*]

C. viscosa, *L.* *Polanisia viscosa*. 14.

Wal-aba, S.

43. *Gynandropsis pentaphylla*, *DC.* 14.

Wēla, S.

44. *Mærua arenaria*, *Hk. f. & Th.* *M. oblongifolia*. 15.

45. *Cratæva Roxburghii*, R. Br. 14.
Lunu-warana, S. *Navala*, T.
46. *Cadaba trifoliata*, W. & A. 15.
C. indica, Lam. 15.
47. *Capparis zeylanica*, L. *C. brevispina*. 15.
 [C. Heyneana, Wall.]
C. divaricata, Lam. *C. stylosa*. 15.
C. Moonii, Wight. 16.
C. Roxburghii, DC. 15.
C. grandis, L. f. 16.
C. pedunculosa, Wall. 16.
C. sepiaria, L. 16.
 var. *RETUSELLA*, Thw. (sp.) 16.
C. floribunda, Wight. 399.
C. horrida, L. f. 15.
Welangiriya, S.
C. tenera, Dalz., var. *ZEYLANICA*, Hk. f. & Th. *C. tetrasperma*. 15.

10. Violaceæ.

48. *Viola Patrinii*, DC. 20.
V. distans, Wall. *V. Wightiana*, var. *glabra*. 20.
V. serpens, Wall. *V. Wightiana*, var. *pubescens*. 20.
49. *Ionidium suffruticosum*, Ging. 20.
I. RAMOSISSIMUM, Thw. 21.
50. *Alsodeia zeylanica*, Thw. 21.
A. DECORA, Trim. ms. C. P. 4006.
A. VIRGATA, Hk. f. & Th. *Scyphellandra*. 21.

11. Bixineæ.

- (*Cochlospermum Gossypium*, DC.) *Kini-hiriya*, *Ela-imbul*, S.
 (Bixa Orellana, L.) 16. *Kaha*, S. *Annatto*.
51. *Scolopia crenata*, Clos. *S. chinensis*. 400.
 var. *acuminata*, Clos. (sp.) 400.
 var. *crassipes*, Clos. (sp.) 400.
Katu-kurundu, *Katukenda* S.
52. *ERYTHROSPERMUM PHYTOLACCOIDES*, Gardn. 18.
53. (*Flacourtia inermis*, Roxb.) *Lovi-lovi*.
F. Ramontchi, L'Herit. *F. sapida*. 17.
Uguressa, S.
 (var. *Cataphracta*, Roxb. (sp.)) *Raṭa-uguressa*, S.

F. sepiaria, *Roxb.* 17.

54. *ABERIA GARDNERI*, *Clos.* 400.

Ket-ambilla, *S.*

55. *TRICHADENIA ZEYLANICA*, *Thw.* 19.

Titta-gas, *Tolol*, *S.*

56. *HYDNOCARPUS VENENATA*, *Gaertn.* *H. ine brians.* 18.

Makulu, *S.*

H. alpina, *Wight.* 19.

H. OCTANDRA, *Thw.* 19.

12. Pittosporaceæ.

57. *Pittosporum tetraspermum*, *W. & A.* 68.

P. nilghirens, *W. & A.?* C.P. 3994.

P. ZEYLANICUM, *Wight.* 68.

Ketiya, *S.*

13. Polygalaceæ.

58. *Polygala arillata*, *Ham.* 22.

P. javana, *DC.* 22.

P. leptalea, *DC.* 22.

P. GLAUCOIDES, *L.* *P. arvensis*, vars. b. & a. 400.

var. *hirsutula*, *Thw.* *P. elongata*, var. *hirsutula.* 22.

[*P. elongata*, *Klein.*]

P. chinensis, *L.* *P. arvensis*, var. c. 400.

P. rosmarinifolia, *W. & A.* *P. rosm.*, var. *puberula.* 22.

P. sibirica, *L.*, var. *macrolophos*, *Hassk.* *P. glomerata.* 400.

P. telephioides, *Willd.* 22.

59. *SALOMONIA CILIATA*, *DC.* *S. cordata.* 22.

S. oblongifolia, *DC.* 22.

60. *Xanthophyllum flavescens*, *Roxb.* *X. virens.* 400.

14. Caryophyllaceæ.

61. *Cerastium indicum*, *W. & A.* 24.

† *C. vulgatum*, *L.* var. *glomeratum*, *Thuill.* (sp.)

62. *STELLARIA DRYMARIOIDES*, *Thw.* 24.

* *S. media*, *With.* 24. *Chickweed.*

* *Sagina procumbens*, *L.*

* *Spergula arvensis*, *L.* *Spurrey.*

63. *Drymaria cordata*, *Willd.* 25.

64. *Polycarpon Loefflingiæ*, *B. & Hk. f.* *Harpalosia.* 25.

65. *Polycarpæa corymbosa*, *Lam.* 25.

15. Portulacaceæ.

66. *Portulaca oleracea*, *L.* 23.
Genda kola, *S. Purslane.*
[P. Wightiana, Wall.]
P. quadrifida, *L.* 23.
Hin-genda-kola, *S.*
P. tuberosa, *Roxb.* 401.
Uru-genda, *S.*
P. suffruticosa, *Wight.* 24.

16. Tamariscineæ.

67. *Tamarix gallica*, *L.* 401. *Tamarisk.*
[T. ericoides, Roxb.]

17. Elatineæ.

68. *Bergia ammanioides*, *Roxb.* 23.
B. verticillata, *Willd.* 23.

18. Hypericaceæ.

69. *Hypericum mysorense*, *Heyne.* 48.
H. japonicum, *Thunb.* 48.
 * *H. humifusum*, *L.*

19. Guttiferæ.

70. *Garcinia Cambogia*, *Desr.* 48.
Goraka, *S. Korukkai-puli*, *T.*
 var. *Papilla*, *Wight.* (sp.)
G. ECHINOCARPA, *Thw.* 49.
Madol, *S.*
G. Morella, *Desr.* 49.
Gokaṭu, *Kana-goraka*, *S. Gamboge.*
G. TERPNOPHYLLA, *Thw.* 49, 406.
Kokaṭiya, *S.*
 var. *acuminata*, *Pl. & Tri.* (sp.)
G. spicata, *Hk. f. Xanthochymus ovalifolius.* 49.
Ela-gokaṭu, *S. Kokatai*, *T.*
 var. *acutifolia*, *T. And.*
 71. *Calophyllum spectabile*, *Willd. C. Moonii.* 52.
Domba-kina, *S.*
C. Burmanni, *Wight.* 52.
Guru-kina, *S. Chiru-punnai*, *T.*
C. Inophyllum, *L.* 51.
Domba, *S. Punnai*, *T.*

- C. tomentosum*, *Wight*. 51.
Kina, S.
 var. *elatum*, *Bedd.*, (sp.) (*C. angustifolium*, *Roxb.* ?)
Tombu-kata, T.
- C. BRACTEATUM*, *Thw.* 51.
Walu-kina, S.
- C. TRAPEZIFOLIUM*, *Thw.* 51.
- C. THWAITESII*, *Pl. & Tri.* 407.
- C. CORDATO-OBLONGUM*, *Thw.* 407.
- C. CUNEIFOLIUM*, *Thw.* 51.
- C. WALKERI*, *Wight*. 51.
Kina, S.
72. *KAYEA STYLOSA*, *Thw.* 50.
Suwanda, S.
73. *Mesua ferrea*, *L.* 50.
Ná, S. *Naka*, T. *Iron-wood*.
 var. *sclerophylla*, *Thw.* (sp.) 407.
 var. *pulchella*, *Pl. & Tri.* (sp.) 407.
- M. THWAITESII*, *Pl. & Tri.* 407.
Diya-ná, S.

20. Ternstroëmiaceæ.

74. *Ternstroemia japonica*, *Thunb.* *Cleyera gymnanthera*. 40.
T. EMARGINATA, *Chois.* *Cleyera*. 40.
75. *ADINANDRA LASIOPETALA*, *Chois.* *Sarosanthra*. 41.
76. *Eurya japonica*, *Thunb.* 41.
Neya-dasse, S. *Wild Tea*.
 var. *chinensis*, *R. Br.* (sp.) var. *parviflora*. 41.
 var. *ZEYLANICA*, *Wight* (sp.) var. *chinensis*. 41.
- E. acuminata*, *DC.* *E. japonica*, var. *acuminata*. 41.
77. *GORDONIA ZEYLANICA*, *Wight*. 40.
G. ELLIPTICA, *Gardn.*
G. SPECIOSA, *Thw.* 40.

21. Dipterocarpaceæ.

78. *DIPTEROCARPUS HISPIDUS*, *Thw.* Includes *D. oblongifolius*. 33.
Bú-hora, S.
- D. ZEYLANICUS*, *Thw.* 33.
Hora, S.
- D. GLANDULOSUS*, *Thw.* 34.
D.

- D. SCABRIDUS, *Thw.* 34.
 D. INSIGNIS, *Thw.* 34.
79. SUNAPTEA SCABRIUSCULA, *Trim. Vateria (Stemonoporus.)* 404.
 S. ? DISTICHA, *Trim. Vateria (Stemonoporus.)* 404.
80. Vatica Roxburghiana, *Bl. (V. chinensis, L.)* 404, 37.
Menḍora, S.
 V. AFFINIS, *Thw.* 404.
 V. OBSCURA, *Trim. ms.*
Tumpalai, T.
 V. ? CORDIFOLIA, *Thw.* 404.
81. SHOREA OBLONGIFOLIA, *Thw.* 36.
 S. DYERII, *Thw. ms. C.P.* 4010.
 S. LISSOPHYLLA, *Thw.* 402.
 S. STIPULARIS, *Thw.* 36.
 var. minor, *Thw. ms. C.P.* 3987 (part) & 4024.
 S. RETICULATA, *Thw. (in Fl. Brit. Ind.) C.P.* 3884.
 S. BREVIPETIOLARIS, *Thw. ms. C.P.* 4008.
82. HOPEA DISCOLOR, *Thw.* 36.
 H. JUCUNDA, *Thw.* 403.
 var. modesta, *A. DC.*
83. DOONA ZEYLANICA, *Thw.* 34.
Dún, S.
 D. NERVOSA, *Thw.* 35.
 D. AFFINIS, *Thw.* 35.
 D. TRAPEZIFOLIA, *Thw.* 35.
Yaka-halu, S.
 D. CONGESTIFLORA, *Thw.* 35.
Tiniya, S.
 D. OBLONGA, *Thw. ms. C.P.* 3986.
 D. GARDNERI, *Thw.* 35.
 D. CORDIFOLIA, *Thw.* 35.
Beraliya, S.
 D. MACROPHYLLA, *Thw.* 402 & *C.P.* 3987 (part).
Honda-beraliya, S.
 D. OVALIFOLIA, *Thw.* 402.
 D. VENULOSA, *Thw.* 402.
84. VATERIA ACUMINATA, *Hayne. V. indica.* 37.
Hal, S. Pinai, T.
 V. (STEMONOPORUS) ZEYLANICA, *Wight. V. Wightii.* 37,
 403.
 V. (S.) GARDNERI, *Thw.* 403.

- V. (S.) JUCUNDA**, *Thw. (in Fl. Brit. Ind.) V. acuminata.* 403.
V. (S.) AFFINIS, *Thw.* 403.
V. (S.) LANCEOLATA, *Thw.* 403.
V. (S.) CANALICULATA, *Thw.* 403.
V. (S.) PETIOLARIS, *Thw.* 403.
V. (S.) RIGIDA, *Thw.* 403.
V. (S.) OBLONGIFOLIA, *Thw.* 403.
V. (S.) RETICULATA, *Thw.* 403.
V. (S.) NITIDA, *Thw.* 403.
 var. lancifolia, Dyer. V. lancifolia. 404.
V. (S. ?) NERVOSA, *Thw. ms. C.P.* 3885.
V. (S.) MOONII, *Thw.* 403.
 85. **MONOPORANDRA CORDIFOLIA**, *Thw.* 39. *Vateria.* 404.
 M. ELEGANS, *Thw.* 39. *Vateria.* 404.

21 bis. *Ancistrocladeæ.*

86. **ANCISTROCLADUS VAHLII**, *Arn.* 188.
 Góna-wel, S.

22. *Malvaceæ.*

- * **Malvastrum carpinifolium**, *A. Gr.* 441.
 87. **Sida humilis**, *Willd.* 28.
 Bevila, S.
 S. mysorensis, W. & A. 28.
 S. spinosa, L. S. alba. 28.
 S. carpinifolia, L. S. acuta. 27.
 S. rhombifolia, L. S. retusa. 28.
 Kotikan-bevila, S.
 var. rhomboidea. S. rhombifolia. 28.
 S. cordifolia, L. 28.
 † **Wissadula zeylanica**, *Medik. W. periplocifolia.* 27.
 Kiri-kaju, S.
 (*W. Leschenaultiana, Mast.*) *Abutilon*, 401.
 88. † **Abutilon polyandrum**, *W. & A.* 27.
 A. asiaticum, D. Don. 27.
 Anódá, S.
 A. indicum, G. Don. 27.
 Perun-tutti, T.
 A. graveolens, W. & A. 27.
 A. muticum, G. Don. A. tomentosum. 27.
 A. crispum, G. Don. 401.

89. *Urena lobata*, L. 25.
Paṭṭā-ṇepala, S.
U. sinuata, L. 25.
Hin-ṇepala, S.
90. *Pavonia glechomifolia*, A. Rich.
P. zeylanica, Cav. 26.
P. odorata, Willd. 26.
91. *JULOSTYLIS ANGUSTIFOLIA*, Thw. 30.
92. *DICELLOSTYLES AXILLARIS*, Benth. 401.
93. *Hibiscus surattensis*, L. 26.
Hin-nāpiritta, S.
H. furcatus, Roxb. 26.
Nāpiritta, S.
H. micranthus, L. 26.
Pir-amati, T.
H. Solandra, L'Herit. *Lagunēa lobata*. 27.
H. collinus, Roxb. *H. eriocarpus*. 26.
Paritti, T.
H. lunariifolius, Willd. 401.
H. panduræfolius, Burm. 26.
H. vitifolius, L. 26.
H. cannabinus, L. 401.
(*H. Sabdariffa*, L.) *Rozelle*.
H. ficulneus, L. *Abelmoschus*. 27.
H. angulosus, Mast. *Abelmoschus*. 26.
Kapu-kinissa, S.
var. *grandiflorus*, Thw.
var. *purpureus*, Thw.
H. Abelmoschus, L. *Abelmoschus moschatus*. 27.
(*H. esculentus*, L.) *Bandakai*, T.
H. tiliaceus, L. *Paritum*. 26.
Beli-paṭṭā, S.
94. *Thespesia Lampas*, Dalz. & Gibs. *Hibiscus*. 26.
T. populnea, Corr. 27.
Sūriya, S. *Pu-varasu*, T. *Tulip tree*.
(*Adansonia digitata*, L.) *Paparu-pulli*, T. *Baobab*.
95. *Bombax malabaricum*, DC. *Salmalia*. 28.
Kaṭu-imbul, S. *Parutti*, T. *Red Cotton tree*.
96. *Eriodendron anfractuosum*, DC. *E. orientale*. 28.
Imbul, S. *Elavum*, Illaku, T. *White Cotton tree*.
97. *Cullenia excelsa*, Wight. 28.
Kaṭu-bod a, S. *Konji*, T. *Wild Durian*.

23. Sterculiaceæ.

98. *Sterculia foetida*, L. 29.
Telambu, S. *Kaditeni*, *Pinari*, T.
S. urens, Roxb. 29.
Kavali, T.
S. guttata, Roxb. 29.
S. Balanghas, L. 29.
Náva, S.
S. colorata, Roxb. *Firmiana*. 29.
S. THWAITESII, Mast. *Pterygota alata* 29.
99. *Heritiera littoralis*, Dryand. 28.
Etuna, S.
100. *Helicteres Isora*, L. 28.
Lániya, S. *Vullum-puri*, T.
101. *Pterospermum suberifolium*, Lam. 30.
Velanga, S. *Toddi*, *Vinnaku*, T.
102. *Melochia corchorifolia*, L. 30.
103. *Waltheria indica*, L. 30.
* *Guazuma tomentosa*, Kunth. 29.
Patti-parutti, T.

24. Tiliaceæ.

104. *PITYRANTHE VERRUCOSA*, Thw. 29.
105. *Berrya Ammonilla*, Roxb. 32.
Hal-milla, S. *Chamandalé*, *Malé*, *Kada-manakku* T.
Trincomalee Wood.
106. *Grewia columnaris*, Sm. 31.
Koddi-thuvattai, T.
* *G. orientalis*, L. 31.
Thuvattai, T.
G. populifolia, Vahl.
G. orbiculata, Rottl. *G. rotundifolia*. 402.
G. tiliæfolia, Vahl. 32.
Daminiya, S. *Chadachi*, T.
(*G. asiatica*, L.)
G. bracteata, Roth.
G. DIPLOCARPA, Thw. 31.
G. hirsuta, Vahl. 31.
* *G. polygama*, Roxb. *G. helicterifolia*. 31.
G. Microcos, L. 32.
Kēliya, S.
107. *Triumfetta tomentosa*, Boj. *T. pilosa*, var. *a.* 31.

- T. pilosa*, Roth. *T. pilosa*, var. β . 31.
T. rhomboidea, Jacq. *T. angulata*. 31.
Epala, S.
T. CONSPICUA Trim. ms.
T. neglecta, W. & A. *T. pilosula*. 401.
 108. *Corchorus capsularis*, L. 31.
C. olitorius, L. 31.
C. urticæfolius, W. & A. 31.
C. fascicularis, Lam. 401.
C. tridens, L. 401.
C. acutangulus, Lam. 31.
 109. *Elæocarpus serratus*, L. 32.
 var. *cuneatus*, Wight, (sp.)
 Weralu, S. Wild Olive.
 [E. robustus, Roxb.]
E. amœnus, Thw. 32 & C.P. 3906.
E. OBOVATUS, Arn. 32.
E. MONTANUS, Thw. 32.
E. SUBVILLOSUS, Arn. 33.
 Gal-weralu, S.
E. ZEYLANICUS, Arn. *Monocera Walkeri*. 33.
E. GLANDULIFER, Mast. *Monocera*. 33.
25. Linacææ.
 110. *Linum mysoreuse*, Heyne. 25.
 111. *Hugonia Mystax*, L. 25.
 Maha- or Bû-geṭiya, S. *Morthiré-kuma*, T.
H. FERRUGINEA, W. & A. 25.
 112. *Erythroxylum monogynum*, Roxb. *Sethia indica*. 53.
 Tevaturam, T.
E. lanceolatum, Hk. f. *Sethia*. 54.
E. LUCIDUM, Moon. *Sethia acuminata*. 54.
 Baṭa-kirilla, S. *Siru-chenumutthi*, T.
 var. minor. C. P. 4011.
E. OBTUSIFOLIUM, Hk. f. *Sethia*.
26. Malpighiacææ.
 113. *Hiptage Madablota*, Gaertn. 53.
 Puwah-geṭiya-wel, S.
H. parviflora, W. & A. 53.
27. Zygophyllacææ.
 114. *Tribulus terrestris*, L. 68.
 Sembu-nerenchi, S. & T.

28. Geraniaceæ.

115. *Geranium nepalense*, Sweet. 64.
116. *Oxalis corniculata*, L.
Hin-embul-embiliya, S.
 * *O. purpurata*, Jacq.
117. *Biophytum sensitivum*, DC. *Oxalis*. 409.
 var. *nervifolia*, Edgew. & Hk. f.
Gas-nidi-kumba, S.
B. Reinwardtii, Walp.
B. NUDUM, Arn. *Oxalis sensitiva*, var. β . 409.
B. PROLIFERUM, Arn. *O. sensitiva*, var. γ . 409.
 ? *B. intermedium*, Wight.
 (*Averrhoa Bilimbi*, L.) *Bilin*, S. *Blimbing*.
 (*A. Carambola*, L.) *Kámaranga*, S.
118. *Impatiens acaulis*, Arn. 68.
I. oppositifolia, L. *I. rosmarinifolia*. 65.
I. cuspidata, W. & A. 65.
 var. *bipartita*, Arn. (sp.)
I. Balsamina, L. 65.
I. GLANDULIFERA, Arn. 66.
I. MACROPHYLLA, Gardn. 66.
I. REPENS, Moon. 66.
Gal-demaṭa, S.
I. LEPTOPODA, Arn. 65.
I. TRUNCATA, Thw. 66.
I. flaccida, Arn. 65.
Kúḍalu-mal, S.
I. Henslowiana, Arn. 65.
I. JANTHINA, Thw. 68.
I. SUBCORDATA, Arn. 67.
I. HOOKERIANA, Arn. 66.
I. LEUCANTHA, Thw. 67.
I. LINEARIS, Arn. 67.
I. APPENDICULATA, Arn. 67.
I. ELONGATA, Arn. 67.
I. CORNIGERA, Arn. 67.
I. ARNOTTII, Thw. 67.
I. WALKERI, Hook. 66.
119. *Hydrocera triflora*, W. & A. 68.
Diya-kúḍalu, S.

29. Rutaceæ.

120. *Evodia Roxburghiana*, *Benth.* *E. triphylla*. 409.
Lunu-ankenda, S.
121. *Zanthoxylum tetraspermum*, *W. & A.* 69.
(*Z. Rhetsa*, *DC.*) 69.
Katu-kina, S.
122. *Toddalia aculeata*, *Pers.* 69.
Kudu-miris, S.
123. *Acronychia laurifolia*, *Bl.* *A. pedunculata*. 409.
Ankenda, S.
124. *Glycosmis pentaphylla*, *Corr.* Includes *G. arborea*. 45.
var. *longifolia*, *Oliv.*
Dodan-paná, S. *Kulla-pannai*, T.
G. BILOCULARIS, *Thw.* 45.
125. *Micromelum pubescens*, *Bl.* 46.
Wal-karapincha, S.
126. *Murraya exotica*, *L.* 45.
Ettériya, S.
(var. *buxifolia*, *Thw.*)
var. *paniculata*, *Thw.*
M. GLENIEI, *Thw.* 406.
M. Koenigii, *Spreng.* 406.
Karapincha, S. *Kurrivuppu*, T. *Curry-leaf*.
127. *Clausena indica*, *Oliv.* 406.
Migoz-karapincha, S. *Purunhé-nurai*, T.
- C. Willdenovii*, *W. & A.* 47.
var. *pubescens*, *Thw.* 407.
128. *Limonia alata*, *W. & A.* 45.
Tumpat-kurundu, S.
129. *Luvunga eleutherandra*, *Dalz.* 48, 406.
130. *Paramignya monophylla*, *Wight.* 47.
Wellangiriya, S.
- P. ARMATA*, *Oliv.* 406.
131. *Atalantia monophylla*, *DC.* 44.
Perum-kurundu, T.
A. racemosa, *W. & A.* 405.
A. zeylanica, *Oliv.* 405.
Yakináran, S. *Né-kurundu*, T.
var. *rotundifolia*, *Oliv.*
A. Missionis, *Oliv.* 405.
Pamburu, S. *Kurundu*, T.

132. *Feronia elephantum*, *Corr.* 48.

Diwul, S. *Méladi-kurundu*, T. *Wood Apple*.
(*Ægle Marmelos*, *Corr.*) *Beli*, S. *Vila*, *Vilva*, T. *Bael*.

30. Simarubaceæ.

133. *Ailantus malabarica*, *DC.* 69.

Kumbatā, *Wal-bilin*, S.

134. *Samadera indica*, *Gaertn.* 70.

Samadarā, S.

* *Brucea sumatrana*, *Roxb.* 69.

31. Ochnaceæ.

135. *Ochna squarrosa*, *L.* Includes *O. rufescens*. 70.

Mal-kêra, S.

var. *cordata*, *Thw.* 409.

O. Wightiana, *Wall.* Includes *O. Moonii*. 70.

136. *Gomphia angustifolia*, *Vahl.* 71.

Bô-kêra, S.

32. Burseraceæ.

(*Boswellia serrata*, *Roxb.*) C. P. 3878.

137. *Balsamodendrum caudatum*, *March.* *Protium*. 78.

Kilivai, T.

B. *Berryi*, *W. & A.?*

Mul-kilivai, T.

138. *CANARIUM BRUNNEUM*, *Bedd.* *Scutinanthe*. 78.

Maha-bulu-mora, S.

C. *ZEYLANICUM*, *Bl.* 79.

Kêkuna, S.

139. *Filicium decipiens*, *Thw.* 408.

Pehimbiya, S.

33. Meliaceæ.

140. *MUNRONIA PUMILA*, *Wight*, 59.

Bin-kohomba, S.

141. *Azadirachta indica*, *A Juss.* 59.

Kohomba, S. *Vempu*, T.

142. (*Melia Azedarach*, *L.*) *Bead tree*. *Indian Lilac*.

M. dubia, *Cav.* *M. composita*. 59.

Lunu-midella, S. *Malai-vempu*, *Patiri*, T.

143. *Cipadessa fruticosa*, *Bl.* *Mallea Rothii*. 60.

Hâl-bembiya, S.

144. *Dysoxylum binectariferum*, *Hk. f.* *D. macrocarpum*. 60.

145. (*Aglaia odorata*, *Lour.*)
A. APIOCARPA, *Hiern.* *Milnea.* 60.
A. Roxburghiana, *Miq.* *Milnea.* 60.
146. *Amoora Rohituka*, *W. & A.* 60.
Hingul, *S.*
147. *PSEUDOCARAPA CHAMPIONII*, *Hemsl.* *Amoora.* 409.
148. *WALSUBA GARDNERI*, *Thw.* 61.
W. Piscidia, *Roxb.* 61.
Kiri-kōṇ, *S.* *Chadda-vakku*, *Walsurai*, *Kanná-kampu*, *T.*
149. *Carapa moluccensis*, *Lam.* *Xylocarpus Granatum.* 61.
(*Soymida febrifuga*, *A. Juss.*)
150. *Chickrassia tabularis*, *A. Juss.* 61.
Hulaṇ-hik, *S.* *Aglai*, *Kulothi*, *T.*
151. *Chloroxylon Swietenia*, *DC.* 61.
Buruta, *S.* *Mutirai*, *T.* *Satinwood.*

34. Chailletiaceæ.

152. *Chailletia gelonioides*, *Hk.f.* *Moacurra.* 79.
Balu-nakuṭa, *S.*

35. Olacineæ.

153. *Ximenia americana*, *Willd.* *C.P.* 2332.
154. *Olax scandens*, *Roxb.* 42.
O. Wightiana, *Wall.* 42.
O. ZEYLANICA, *L.* 42.
Mella, *S.*
155. *Strombosia zeylanica*, *Gardn.* *S. javanica.* 42.
156. *Causjera Rheedei*, *Gmel.* 251.
157. *Opilia amentacea*, *Roxb.* 41.
158. *Lasianthera apicalis*, *Thw.* 405.
U'rukanu, *S.*
159. *Gomphandra axillaris*, *Wall.* *Platea.* 44.
G. polymorpha, *Wight.* *Platea coriacea.* 44.
160. *APODYTES GARDNERIANA*, *Miers.* 42.
161. *Mappia ovata*, *Miers.* *M. fœtida.* 43.
var. *Championiana*, *Miers.* (sp.)
Gandapána, *S.*
162. *Pyrenacantha volubilis*, *Hook.* 290.

36. Ilicineæ.

163. *Ilex Walkeri*, *Wight & Gardn.* 184.
I. denticulata, *Wall.* 183.

I. Wightiana, Wall. 183.

Andun-wenna, S.

37. Celastraceæ.

164. EUONYMUS REVOLUTUS, Wight. 73.
E. THWAITESII, Laws. *E. dichotomus*. 73.
E. WALKERI, Wight. 73.
 ? *E. dichotomus*, Heyne.
165. Glyptopetalum zeylanicum, Thw. 73.
166. MICROTROPIS WALLICHIANA, Wight. 71.
M. ramiflora, Wight. 72.
167. Kokoona zeylanica, Thw. 52.
Wana-potu, *Kokun-potu*, S.
168. Pleurostyliia Wightii, Thw. 71.
Piyari, S.
169. Celastrus paniculata, Willd. 72.
Dukudu, S.
170. GYMNOSPORA FRUTICOSA, Hk. f. 409.
G. emarginata, Roth. 409.
171. KURRIMIA ZEYLANICA, Arn. 72.
Pelan, *Hurukandu*, *Et-heraliya*, S. *Konnai*, T.
172. Elæodendrum glaucum, Pers. 73.
 var. MONTANUM, Thw.
Neralu, S. *Pieri*, & (with serrate leaves) *Karukku-vâchchi*, T.
173. Hippocratea obtusifolia, Roxb. 52.
Diya-kirindi-wel, S.
H. Arnottiana, Wight. *Salacia terminalis*. 407.
H. indica, Willd. 52.
174. Salacia prinoides, DC. 53.
Hin-himbutu-wel, S.
S. reticulata, Wight. 53.
 var. diandra, Laws. *S. diandra*. 53.
Himbutu-wel, S.
S. oblonga, Wall. 53.

38. Rhamnaceæ.

175. Ventilago maderaspatana, Gaertn. 74.
Vaimbadam, T.
176. Zizyphus Jujuba, Lam. 74.
Maha-debara, *Masan*, S. *Ilanthai*, T.
Z. CENOPHIA, Mill. 74.
Hin-eraminiyâ, S. *Churai*, T.

Z. xylopyra, Willd. 74.

Nani-ilanthai, T.

Z. NAPECA, Willd.

var. *lucida*, Moon (sp.) (*Z. Linnæi*, Laws. ?) 74.

Z. rugosa, Lam. 73.

Maha-eramiñiyd, S. *Churai*, T.

177. *RHAMNUS ARNOTTIANUS*, Gardn. 74.

R. Wightii, W. & A. 74.

178. *Scutia indica*, Brongn. 75.

179. *Sageretia costata*, Miq. *S. affinis*. 410 (C.P. 2477).

180. *Colubrina asiatica*, Brongn. 75.

Tel-hiriya, S.

181. *Gouania microcarpa*, DC. 75.

39. Ampelideæ.

182. *Vitis quadrangularis*, Wall. *Cissus edulis*. 62.

Hiressa, S.

V. GLYPTOCARPA, Laws. *Cissus*. 62.

V. LONCHIPHYLLA, Laws. *Cissus*. 62.

V. pallida, W. & A. ? *Cissus glauca*. 62.

V. repanda, W. & A. *Cissus acuminata* & *C. repens*,
62 & C.P. 3962.

V. adnata, Wall. *Cissus*. 62.

Wal-diya-labu, S.

V. Linnæi, Wall. *Cissus angulata*. 62.

Kaddu-montherai, T.

V. tomentosa, Heyne.

V. erioclada, W. & A. *V. indica*. 63.

To-wel, *Rita-bulat-wel*, S.

V. Rheedii, W. & A. *Cissus trilobata*. 62.

V. setosa, Wall. *Cissus*. 63.

V. carnosa, Wall. *Cissus*. 63.

Wal-rat-diya-labu, S.

V. RETICULATA, Laws. *Cissus*. 63.

V. GARDNERI, Laws. *Cissus*. 63.

V. lanceolaria, Wall. Includes *Cissus muricata*. 63.

V. pedata, Vahl. *Cissus*. 63.

Meḍiya-wel, S.

183. *Leea sambucina*, Willd. *L. Staphylea*. 64.

Burulla, *Gurulla*, S.

40. Sapindaceæ.

184. *Cardiospermum Halicacabum*, L. 54.

Penela-wel, S.

- C. canescens*, *Wall.*
185. *Hemigyroa canescens*, *Thw.* 56.
var. *trichocarpa*, *Thw.* (sp.) 56.
(*Dittelasma Rarak*, *Hk. f.*)
186. *Allophylus zeylanicus*, *L.* *Schmidelia allophylla.* 55.
var. *ACUMINATA*, *Hiern.* *Schmidelia.* 55.
var. *varians*, *Hiern.* *Schmidelia.* 408.
var. *THWAITESII*, *Hiern.*
- A. HISPIDA.* *Schmidelia.* 55.
- A. Cobbe*, *Bl.* *Schmidelia.* 55.
var. *villosa*, *Hiern.* *Schmidelia.* 55.
Kobbé, *S.*
187. *Schleichera trijuga*, *Willd.* 58.
Kón, *S.* *Pucu*, *Kúlá*, *T.* *Ceylon Oak.*
188. *GLENIEA ZEYLANICA*, *Hk. f.* 408.
var. *unijuga*, *Thw.* 408, 56.
var. *fuscata*, *Thw.* 408, 58.
189. *Sapindus laurifolius*, *Vahl.* 55.
Kaha-penela, *S.*
S. emarginatus, *Vahl.* 55.
Penela, *S.* *Pávanti*, *T.*
S. ERECTUS, *Hiern.* *Nephelium.* 57.
S. THWAITESII, *Hiern.* *Nephelium simplicifolium.* 57.
S. bifolius, *Hiern.* *Nephelium.* 57.
190. *Nephelium Longana*, *Camb.* 58.
Mora, *S.* *Moreli*, *T.*
N. GARDNERI, *Thw.* 58.
191. *Pometia eximia*, *Hk. f.* 408.
Gal-mora, *S.* (Kandy country.)
192. *Harpullia cupanioides*, *Roxb.* *H. imbricata.* 56.
Ná-imbul, *S.*
193. *Dodonaea viscosa*, *L.* *D. Burmanniana.* 59.
Ēta-werella, *S.* *Virali*, *T.*
194. *Turpiuia pomifera*, *DC.* *T. nepalensis.* 71.
Ēta-kirilla, *Kaṅkumbalá*, *S.*

41. *Sabiaceæ.*

195. *Meliosma Wightii*, *Planch.* *M. pungens.* 59.
M. simplicifolia, *Walp.* 59.
Ēlbedda, *S.*
M. Arnottiana, *Wight.* 59.

42. *Anacardiaceæ*.(Mangifera indica, L.) *Mango*.

196. *M. ZEYLANICA*, *Hk. f.* *M. indica*. 75.
Amba, Wal-amba, S. Ma, Káddu Má, T. Wild
Mango.

(Anacardium occidentale, L.) *Kaju, S. Cashew-nut.*

197. *Buchanania angustifolia*, *Roxb.* 78.

198. *Odina Woodier, Roxb.* 78.

Hik, S. Othi, T.

199. *SEMECARPUS PUBESCENS, Thw.* 77.

*S. THWAITESII, Hk. f. C. P. 3886.**S. MARGINATA, Thw.* 77.*S. OBOVATA, Moon.* 77.*S. MOONII, Thw.* 77.*S. CORIACEA, Thw.* 77.*S. SUBPELTATA, Thw.* 75.*Maha-badulla, S.**S. GARDNERI, Thw.* 76.*Badulla, S.**S. WALKERI, Hk. f. S. obscura* (in part). 410.*S. OBSCURA, Thw.* Includes *S. oblongifolia*, α . 76, 410.*S. ACUMINATA, Thw. S. oblongifolia*, γ . 76, 410.*S. NIGRO-VIRIDIS, Thw. S. oblongifolia*, β . 76, 410.*S. PARVIFOLIA, Thw.**Hin-badulla, S.**S. LÆVIGATA, Thw. (in Fl. Brit. Ind.) C. P. 3948.*

200. *Nothopegia Colebrookiana, Bl.* 441.

Bala, S.

201. *CAMPNOSPERMA ZEYLANICUM, Thw.* 78.

Arida, S.

202. *Spondias mangifera, Willd. Evia amara*. 78.

Embarélla, S. Ampallai, T. Hog-Plum.

(Moringeæ.)

(Moringa pterygosperma, Gaertn.)

Murungá, S. Murunkai, T. Horse-radish Tree.

POLYPETALÆ CALYCIFLORÆ.

43. *Connaraceæ*.

203. *Rourea santaloides, W. & A.* 80.

Kirindi-wel, S.

204. *Connarus monocarpus*, *L.* 80.
Radaliya, *S.*
C. CHAMPIONII, *Thw.* 80.
Wel-radaliya, *S.*

205. *ELLIPANTHUS THWAITESII*, *Hk. f.* 410.

44. Leguminosæ.

206. *Rothia trifoliata*, *Pers.* 82.
 207. *Heylandia latebrosa*, *DC.* 81.
 208. *Crotalaria biflora*, *L.* 81. Includes *C. globosa*. 410.
C. prostrata, *Roxb.* 81.
C. ferruginea, *Grah.* 81.
C. evolvuloides, *Wight.* 81.
[C. bifaria, L.]
C. MULTIFLORA, *Benth.* 81.
C. rubiginosa, *Willd.* *C. Wightiana.* 81.
C. mysorensis, *Roth.* 82.
C. triquetra, *Dalz.* 410.
C. albida, *Heyne.* 82.
C. nana, *Burm.* Includes *C. umbellata*. 82.
C. linifolia, *L. f.* 82.
C. calycina, *Schrank.* 82.
C. retusa, *L.* 81.
Kaha-andana-hiriya, *S.*
 var. *maritima*, *Trim.*
C. verrucosa, *L.* 81.
Nil-andana-hiriya, *S.*
C. semperflorens, *Vent.*, var. *Walkeri*, *Arn. (sp.)* 81.
C. juncea, *L.*
Hana, *S.* *San* or *Sunn Hemp.*
(C. fulva, Roxb.)
C. lunulata, *Heyne.* 81.
C. medicaginea, *Lam.* 82.
 * *C. Willdenowiana*, *DC.* 441.
 * *C. incana*, *L.* 82.
C. striata, *DC.* 82.
 var. *acutifolia*, *Trim.* 410.
C. laburnifolia, *L.* 82.
Yakbériya, *S.*
C. quinquefolia, *L.* 82.
 * *Trifolium repens*, *L.* 82.
 * *T. minus*, *Sm.*
 209. *Parochetus communis*, *Ham.* 82.

210. *Indigofera echinata*, Willd. *Acanthonotus*. 83.
I. linifolia, Retz. 83.
I. enneaphylla, L. 83.
I. aspalathoides, Vahl. 83.
Chivanâr-vémbu, T.
I. pentaphylla, L. 411.
I. tenuifolia, Rottl. 83.
I. viscosa, Lam. 83.
I. trifoliata, L. 83.
I. trita, L. f. 83.
I. subulata, Vahl. *I. flaccida*. 83.
I. paucifolia, Del. 83.
I. hirsuta, Del. 83.
* *I. tinctoria*, L. 411.
Nil-awari, S. *Indigo*.
I. constricta, Trim. ms. *I. flaccida*, var. *constricta*. 411.
I. Wightii, Grah. *I. inamæna*. 83.
I. galegoides, DC. 83.
211. *Psoralea corylifolia*, L. 84.
212. *Mundulea suberosa*, Benth. *Tephrosia*. 84.
213. *Tephrosia tinctoria*, Pers. 84.
Alu-pila, S.
var. *intermedia*, W. & A.
var. *pulcherrima*, Wight.
T. spinosa, Pers. 411.
[T. *senticosa*, Pers.]
T. purpurea, Pers. 84.
Pila, S.
var. *maxima*, Baker. *T. maxima*. 84.
T. Hookeriana, W. & A. *T. hirta*. 84 (C. P. 2776.)
T. villosa, Pers. 84.
Bû-pila, S.
var. *argentea*, Thw.
214. *Sesbania ægyptiaca*, Pers. 84.
Karum-chembai, T.
S. aculeata, Pers.
var. *SERICEA*, Benth. 441.
(S. *grandiflora*, Pers.) *Akatti*, T. *Katuru-murungá*, S.
[*Geissaspis cristata*, W. & A.]
215. *Zornia diphylla*, Pers.
var. *zeylonensis*, Baker. *Z. angustifolia* & *Z. conjugata*. 84, 85.

- var. *WALKERI*, Arn. (sp.) 85.
216. *Stylosanthes mucronata* Willd. 84.
Wel-nánu, S.
217. *Smithia sensitiva*, Ait. C. P. 3946.
S. geminiflora, Roth, var. *conferta*, Baker. *S. conferta*. 85.
S. blanda, Wall. 85.
var. *racemosa*, Baker.
218. *Æschynomene indica*, L. 85.
Diya-siyambalá, S.
Æ. aspera, L. 85.
Maha-diya-siyambalá, S. *Attunetta*, T.
219. *Ormocarpum sennoides*, DC. 85.
220. *Eleiotis sororia*, DC. 412.
221. *Pycnospora hedysaroides*, R. Br. *P. nervosa*, 92.
222. *Pseudarthria viscida*, W. & A. 87.
223. *Uraria picta*, Desv. 85.
(*U. crinita*, Desv.) 85.
U. hamosa, Wall. 85.
224. *Alysicarpus monilifer*, DC. 412.
A. vaginalis, DC. 87.
A. bupleurifolius, DC. 87.
Aswenna, S.
A. longifolius, W. & A. 412.
A. rugosus, DC. *A. Heyneanus*, 88.
var. *styracifolius*, W. & A. (sp.) *A. scariosus*. 88.
225. *Desmodium umbellatum*, DC. *Dendrolobium*, 86.
D. cephalotes, Wall. *Dendrolobium*, 86.
D. pulchellum, Benth. *Phyllodium*. 86.
Hampinna, S.
D. biarticulatum, Benth. *Dicerna*. 86.
D. laburnifolium, DC. *Catenaria*. 86.
D. triquetrum, DC. *Pteroloma*. 86.
Báloliyá, S.
D. ormocarpoides, DC. 87, 441.
D. Gardneri, Benth. *D. podocarpum*. 87.
D. Scalpe, DC. *D. strangulatum*. 87.
D. gangeticum, DC. 411.
D. latifolium, DC. 87.
* *D. cajanæfolium*, DC. Includes *Hedysarum mucronatum*. 87, 411.
D. THWAITESII, Baker. *D. strangulatum*, var. *minor*. 87.

- D. Wightii*, *Grah.* 87.
D. rufescens, *DC.* *D. ferrugineum.* 87.
D. polycarpum, *DC.* 86.
 var. trichocaulon, *DC.* (sp.)
D. JUCUNDUM, *Thw.* 411.
D. triflorum, *DC.* 86.
 Hin-undu-piyali, *S.*
D. heterophyllum, *DC.* 86.
 Maha-undu-piyali, *S.*
D. parvifolium, *DC.* 86.
D. gyrans, *DC.* 87.
 Chanchala, *S.* *Telegraph Plant.*
D. gyroides, *DC.* 87.
226. *Abrus precatorius*, *L.* 91.
 Olinda-wel, *S.* *Kundumani*, *T.*
 A. pulchellus, *Wall.* 91.
227. *Shuteria vestita*, *W. & A.* 88.
228. *Dumasia villosa*, *DC.*, *var. leiocarpa*, *Benth.* 88
229. *Glycine javanica*, *L.* *Soja Wightii.* 88.
230. *Teramnus labialis*, *Spreng.* *Glycine.* 88.
231. *Mucuna monosperma*, *DC.* 89.
 M. atropurpurea, *DC.* 89.
 M. gigantea, *DC.* 89.
 M. pruriens, *DC.* *M. prurita.* 89.
 var. biflora.
 Achāriyd-palu, *S.* *Cowitch.*
232. *Erythrina indica*, *L.* 89.
 Erabadu, *S.* *Murukku*, *T.*
 E. ovalifolia, *Roxb.* 89.
 Yak-erabadu, *S.*
 [*E. suberosa*, *Roxb.*]
233. *Strongylodon ruber*, *Vog.* 89.
234. *Galactia tenuiflora*, *W. & A.* 88.
235. *Spatholobus Roxburghii*, *Benth.* ("Walker, 1331.")
236. *Butea frondosa*, *Roxb.* 89.
 Gas-kēla, *S.*
237. † *Canavalia ensiformis*, *DC.* *C. gladiata.* 88.
 Wal-awara, *S.*
 var. virosa, *Baker.* *C. virosa.* 89.
 C. obtusifolia, *DC.* 88.
238. *Dioclea reflexa*, *Hk. f.* *D. Fergusonii.* 412.

239. *Phaseolus adenanthus*, G. F. Mey. *P. truxillensis*. 89
Wal-mé, S.
P. Grahamianus, W. & A. 90.
P. semierectus, L. 90.
P. trilobus, Ait. 90.
Bin-mé, S.
P. aconitifolius, Jacq.
† *P. Mungo*, L.
Mun-éta, S. *Green Gram*.
var. *radiatus*, L. (sp.) 89.
P. trinervius, L. 90.
P. calcaratus, Roxb. 412.
240. *Vigna luteola*, Benth. 90.
(V. Catiang, Endl.)
V. vexillata, Benth. 90.
* *Centrosæma Plumieri*, Benth.
241. *Clitoria Ternatea*, L. 88.
Nil-katarolu, S.
242. *Dolichos Lablab*, L. *Lablab vulgaris*. 90.
D. biflorus, L. *D. uniflorus*. 90.
Kollu, S. & T. *Horse Gram*, *Madras Gram*.
D. ciliatus, Klein. 90.
D. falcatus, Klein. 90.
243. *Atylosia Candollei*, W. & A. 91.
Et-tóra, S.
A. albicans, Benth. 91.
A. rugosa, W. & A. 91.
Wal-kollu, S.
A. scarabæoides, Benth. 91.
(*Cajanus indicus*, Spreng.) 90. *Raça-tóra*, S. *Thava-rai*, T. *Pigeon Pea*.
244. *Dunbaria ferruginea*, W. & A. 90. C. P. 3961.
D. Heynei, W. & A. 90.
245. *Eriosema chinense*, Vog.
246. *Rhynchosia rufescens*, DC. 91.
R. nummularia, DC. *Nomismia*. 91.
R. aurea, DC.
R. suaveolens, DC. 442.
R. cana, DC. 91.
R. cyanosperma, Benth. *Cyanospermum tomentosum*. 92.
R. minima, DC. 91.
R. viscosa, DC. *R. villosula*. 412. C. P. 3895

- R. acutissima*, Thw. 413.
R. densiflora, DC.
 247. *Flemingia strobilifera*, R. Br. 92.
 Hampilla, S.
 F. lineata, Roxb. 92.
 F. congesta, Roxb. 92.
 var. *semialata*, Roxb. (sp.) 92.
 248. (*Dalbergia latifolia*, Roxb.)
 D. Championii, Thw. 94.
 Bambara-wel, S.
 D. frondosa, Roxb. 94.
 Vel-urruvai, T.
 D. volubilis, Roxb. ("Mrs. Walker.")
 D. monosperma, Dalz. 94.
 249. *Pterocarpus Marsupium*, Roxb. 92.
 Malu, Gammalu, S. *Vengai*, *Udida Vengai*, T.
 250. *Pongamia glabra*, Vent. 92.
 Magul-karanda, S. *Pungai*, *Pun̄ku*, T.
 251. *Derris scandens*, Benth. 413.
 Kala-uēl, S.
 D. PARVIFLORA, Benth. 413.
 (*D. robusta*, Benth.)
 D. uliginosa, Benth. 92.
 D. PANICULATA, Benth. *D. Benthamii*. 413.
 D. oblonga, Benth. 413.
 D. sinuata, Benth. 93.
 252. *Sophora tomentosa*, L. 94.
 Mudu-murungā, S.
 S. VIOLACEA, Thw. 94.
 S. heptaphylla, L. 94.
 253. *PERICOPSIS MOONIANA*, Thw. 413.
 Nēdun, S.
 254. *Cæsalpinia Bonduc*, Roxb. *Guilandina*. 94.
 Kumburu-wēl, S.
 C. Nuga, Ait. *C. paniculata*. 95.
 Diya-wawuleṭiya, S.
 (*C. Sappan*, L.) *Pattangi*, S. *Sappan*.
 C. sepiaria, Roxb. 95.
 [*C. mimosoides*, Lam.]
 C. digyna, Rottl. 95.
 255. *Peltophorum ferrugineum*, Benth. *Cæsalp. Gleniei*. 414.

256. *Mezonenrum enneaphyllum*, *W. & A.* 414.
Godá-wawuletiya, S.
M. pubescens, *Desf.*
257. *Cassia Fistula*, *L.* 95.
Əhəla, S. *Kovani*, *Tirukkondai*, T.
C. marginata, *Roxb.* *C. Roxburghii*. 95.
Ratu-wá, S. *Vákai*. T.
C. occidentalis, *L.* 95.
Peti-tóra, S.
C. Sophora, *L.* 95.
Uru-tóra, S.
C. Tora, *L.*
Pəni-tóra, S.
 * *C. tomentosa*, *L.* 95.
 (*C. hirsuta*, *L.*)
 * *C. lævigata*, *Willd.*
C. auriculata, *L.* 96.
Raṇawará, S. *Avarai*, T.
C. obovata, *Collad.* *C. obtusa*. 441.
 * *C. alata*, *L.* 97. *Raṭa-tóra*, S.
C. siamea, *Lam.* *C. florida*. 96.
Wá, *Aramaná*, S. *Wagə*, *Vákai*, T.
C. timoriensis, *DC.* 96.
 (*C. glauca*, *Lam.*) 96.
 var. *suffruticosa*, *Kæn.* (sp.) ? 441.
C. Absus, *L.* 96.
Bú-tóra, S.
C. Kleinii, *W. & A.* 96.
Bin-siyambalá, S.
 [*C. pumila*, *L.*]
C. mimosoides, *L.* 96.
Bin-siyambalá, S.
 var. *auricomá*, *Grah.* (sp.) var. *villosula*. 96.
 var. *Wallichiana*, *Baker.* *C. Wallichiana*. 96.
258. *Cynometra ramiflora*, *L.* 97.
Gal-mendóra, S.
 var. *heterophylla*, *Thw.* 97.
 (*C. cauliflora*, *L.*) *Niam-niam*, Malay.
259. *DIALIUM OVOIDEUM*, *Thw.* 97.
Gal-siyambalá, S. *Katapuli*, T.
260. *CRUDIA ZEYLANICA*, *Benth.* *Detarium*, 414.
261. *Saraca indica*, *L.* *Jonesia Asoka*. 97.
Diya-ratambalá, *Diya-ratmal*, S.

- * *Tamarindus indica*, *L.* *T. officinalis*. 95.
Siyambalá, *S.* *Puli*, *T.* *Tamarind*.
262. *Humboldtia laurifolia*, *Vahl*. 97.
Gal-karanda, *S.*
263. *Bauhinia tomentosa*, *L.* 98.
Petan, *kaha-petan*, *S.* *Tiruvatti*, *Kat-atti*, *T.*
(B. acuminata, L.)
B. racemosa, *Lam.* *Piliostigma*. 98.
Mayila, *S.*
† *B. anguina*, *Roxb.*
264. *Neptunia oleracea*, *Lour.* 99.
Gas-nidi-kumba, *S.*
(N. plena, Benth.)
265. *Entada scandens*, *Benth.* 98.
Pus-wel, *S.*
266. *Adenanthera pavonina*, *L.* 98.
Madaṭiya, *S.* *Ani-kundumani*, *T.*
A. bicolor, *Moon.* 98.
Mas-mora, *S.*
267. *Dichrostachys cinerea*, *W. & A.* 99.
Andara, *S.* *Wara*, *Vadatara*, *T.*
(Desmanthus virgatus, Willd.) 98.
* *Leucæna glauca*, *Benth.*
* *Mimosa pudica*, *L.* 99.
Midi, *S.*
268. * *Acacia Farnesiana*, *Willd.* 99.
Siniya, *S.*
A. planifrons, *W. & A.*
Odái, *T.*
A. arabica, *Willd.* 415.
Kari-velam, *T.*
A. eburnea, *Willd.* 99.
Odái-velam, *T.*
A. tomentosa, *Willd.* 99.
Ani-mullu, *T.*
A. leucophlœa, *Willd.* 99.
Maha-andara, *Kaṭu-andara*, *S.* *Velam*, *Vel-
Velam*, *T.*
A. Suma, *Kurz.* *A. Catechu*, (part.) 99.
A. Sendra, *DC.* *A. Catechu*, (part.) 99.
Rat-kihiri, *S.* *Vanni*, *T.*
A. ferruginea, *DC.*

- A. concinna*, DC. 99.
Hinguru, S.
- A. cæsia*, Willd. *A. Intsia*. 99.
A. pennata, Willd. 99.
269. *Albizzia Lebbek*, Benth. 99.
Márá, S. *Manchadi*, Kona, *Ughil*, T.
A. odoratissima, Benth. 100.
Súriya-márá, S. *Karuvakái*, T.
A. stipulata, Boiv. 100.
Kabal-márá, *Hulan-márá*, S.
A. amara, Boiv. 100.
270. *PITHECOLOBIUM GEMINATUM*, Benth. 100.
P. umbellatum, Benth. 100.
Termalái, T.
P. bigeminum, Benth. 100.
Kalatiya, S.
P. subcoriaceum, Thw. 100.
Mmini-márá, S.
45. Rosaceæ.
271. *Pygeum Wightianum*, Bl. 102.
Ununu, S.
var. *parvifolium*, Thw.
P. ZEYLANICUM, Gaertn.
Kankumbal-kotiya, *Golu-mora*, S.
272. *Rubus glomeratus*, Bl. *R. rugosus*, var. β . 101.
R. moluccanus, L. *R. rugosus*, var. α . 101.
Wel-buté, S.
var. *Fairholmianus*, Gardn. (sp.) *R. rugosus*, var. γ . 101.
var. *macrocarpus*, Gardn. (sp.) *R. rugosus*, var. δ . 101.
R. ellipticus, Sm. *R. flacus*. 101.
R. lasiocarpus, Sm. 101.
var. *subglaber*, Thw.
273. *Potentilla Mooniana*, Wight. 101.
P. Kleiniana, W. & A. 102.
274. *Alchemilla indica*, Gardn. *A. vulgaris*, var. *sarmentosa*. 102.
var. *sibthorpioides*, Hk. f.
275. *AGRIMONIA ZEYLANICA*, Moon. *A. Eupatorium*. 102.
276. *POTERIUM INDICUM*, Gardn. 102.
277. *Photinia Notoniana*, W. & A. 100.

46. Saxifragaceæ.

278. *Vahlia oldenlandioides*, *Roxb.* 130.
[*V. viscosa*, *Roxb.*]

47. Crassulaceæ.

- * *Bryophyllum calycinum*, *Salisb.* 129.
Akká-pána, *Raṭa-gówa*, S.
279. *Kalanchoe floribunda*, *W. & A.*, var. *glabra*, *Cl.* 129.
K. laciniata, *DC.* 129, 417.

48. Droseraceæ.

280. *Drosera Burmanni*, *Vahl.* 21.
Waṭa-reṣṣa, S.
D. indica, *L.* 21.
Kandu-leṣṣa, S.
D. peltata, *Sm.* *D. lunata*. 22.

49. Haloragaceæ.

281. *SERPICULA ZEYLANICA*, *Arn.* *S. indica* (part.) 123.
var. *minor*, *Clarke.*
S. indica, *Thw.* 123.
282. *Myriophyllum indicum*, *Willd.* 123.
283. *Callitriche stagnalis*, *Scop.* *C. verna.* 290.

50. Rhizophoraceæ.

284. *Rhizophora mucronata*, *Lam.* 120.
Kaḍol, S. *Kandol*, T.
R. conjugata, *L.* 120.
Kaḍol, S. *Kandol*, T.
285. *Ceriops Candolleana*, *Arn.* 120.
[*Kandelia Rheedii*, *W. & A.*]
286. *Bruguiera gymnorhiza*, *Lam.* Includes *B. Rheedii*. 120.
B. caryophylloides, *Bl.* *Kanilia*. 120.
287. *Carallia integerrima*, *DC.* 120.
Dawata, S.
C. CALYCINA, *Thw.* 121.
Ubbériya, S.
288. *Weihea zeylanica*, *Baill.* *Anstrutheria*. 121.
Kannu, T.
289. *ANISOPHYLLEA ZEYLANICA*, *Benth.* 119.
Weli-penna, *Weli-piyánu*, S.

51. Combretaceæ.

290. (*Terminalia Catappa*, L.) *Kottambá*, S. *Kottai*, T.
Indian Almond.
 T. *BelERICA*, *Roxb.* 103.
Bulu, S. *Tándi*, T.
 var. *laurinoides*, *Miq.*
 T. *Chebula*, *Retz.* 103.
Aralu, S. *Kadukkádi*, T.
 T. PARVIFLORA, *Thw.* 103.
Hanpalandá, S.
 T. *glabra*, *W. & A.* 104.
Kumbuk, S. *Marutu*, T.
 [T. *tomentosa*, *Bedd.*]
 291. *Anogeissus latifolia*, *Wall.* *Conocarpus*. 103.
Dawu, S. *Vekkali*, T.
 292. *Lumnitzera racemosa*, *Willd.* 103.
Bériya, S.
 293. *Combretum acuminatum*, *Roxb.* *C. sarcopterum*. 415.
C. ovalifolium, *Roxb.* *C. Wightianum* (part.) 103.
Kaduruketiya-wel, S.
C. extensum, *Roxb.* *C. Wightianum* (part.) 103.
 294. *Gyrocarpus Jacquini*, *Roxb.* *G. asiaticus*. 258.
Hima, S. *Tanukku*, T.

52. Myrtaceæ.

- (*Psidium Guyava*, L. *Péra*, S. *Guava*.)
 295. *Rhodomyrtus tomentosa*, *Wight.* *Myrtus*. 114.
 296. *Eugenia aquea*, *Burm.* *Jambosa*. 115.
Wal-jambu, S.
E. grandis, *Wight.* *Syzygium firmum*. 417.
E. hemispherica, *Wight.* *Strongylocalyx*. 116.
E. CYLINDRICA, *Wight.* *Jambosa*. 115.
E. MICRANTHA, *Duth.* *Syzygium*. 117.
E. lanceolata, *Lam.* *Acmena*. 119.
E. zeylanica, *Wight (non Willd.)* *Acmena*. 118.
Marañ, *Maranda*, S. *Marungi*, T.
E. lissophylla, *Duth.* *Syzygium*. 118.
E. Gardneri, *Duth.* *Syzygium*. 117.
E. SUBAVENIS, *Duth.* *S. umbrosum*. 118.
E. caryophyllæa, *Wight.* *Syzygium*. 117.
Dañ, *Hin-dañ*, S.
E. CORDIFOLIA, *Wight.* *Syzygium*. 116.

- E. revoluta*, *Wight.* *Syzygium.* 117.
E. sylvestris, *Moon.* *Syzygium.* 116.
Alubó, S.
E. ASSIMILIS, *Duth.* *Syzygium.* 116.
E. NEESIANA, *Wight.* *Syzygium.* 117 & C. P. 4013.
Panukéra, S.
E. CYCLOPHYLLA, *Thw. (in Fl. B. Ind.)* C. P. 3915.
E. SCLEROPHYLLA, *Duth.* *Syzygium.* 118.
E. ROTUNDIFOLIA, *Wight.* *Syzygium.* 118.
E. CALOPHYLLIFOLIA, *Wight.* *Syzygium.* 118.
E. OLIGANTHA, *Duth.* *Syzygium.* 118.
E. OLIVIFOLIA, *Duth.* *S. spathulatum.* 118.
E. operculata, *Roxb.* *S. nervosum.* 417.
Bata-domba, *Kobo-mal*, S.
E. Jambolana, *Lam.* *Syzygium.* 417.
Maha-dañ, S. *Nával*, *Peru-nával*, T.
 var. *caryophyllifolia*, *Lam. (sp.)* var. *microcarpum.*
 417.
E. PHILLYRÆOIDES, *Trim. ms.*
E. lucida, *Lam.* C. P. 3865.
E. bracteata, *Roxb.* 114.
Tembiliya, S.
 var. *Roxburghii*, *Duth.* *E. Willdenovii.* 114.
Kaiya, *Káyán*, *Pandi-káyán*, T.
E. TERPNOPHYLLA, *Thw.* 114.
E. XANTHOCARPA, *Thw.* 416.
E. HÆCKELIANA, *Trim. ms.*
E. RUFO-FULVA, *Thw.* 416.
E. FLOCCIFERA, *Thw.* 115.
E. FULVA, *Thw.* 115.
E. RIVULORUM, *Thw.* 115.
E. INSIGNIS, *Thw.* 416.
E. DECORA, *Thw.* 115.
E. AMOENA, *Thw.* 114.
 var. *rotundata*, *Trim. ms.* *E. Mooniana*, var. β . 114.
E. Mooniana, *Wight. (non Gardn.)* 114.
Pinibaru, S.
 (E. uniflora, L.)
E. MABÆOIDES, *Wight.* 114.
E. THWAITESII, *Duth.* *E. concinna.* 416.
 297. *Barringtonia speciosa*, *D.* 119.
Múdilla, S.

- B. racemosa*, *Bl.* (C. P. 3610.) 119.
Diya-midella, *S.*
B. ZEYLANICA, *Gardn.* *B. racemosa*, var. (C. P. 2682.)
 119.
B. acutangula, *Gaertn.* 119.
Ela-midella, *S.* *Adampu*, *Radami*, *T.*
 298. *Careya arborea*, *Gaertn.* 119.
Kahata, *S.* *Ari-maru*, *Kasaddai*, *Panichai*, *T.*
Patana Oak.

53. Melastomaceæ.

299. *Osbeckia cupularis*, *Don*, var. *erythrocephala*, *Naud.* (sp.)
O. Leschenaultiana. 104.
 var. *parvifolia*, *Arn.* (sp.)
O. BHEEDI, *Gardn.* 104.
O. zeylanica, *Willd.* 104.
O. BUXIFOLIA, *Arn.* 105.
 var. *miuor*, *Thw.*
 var. *Beckettii*, *Thw.* (in *Triana Mon.*) C. P. 3906.
O. aspera, *Bl.* 105.
Bôwitiyá, *S.*
 var. *Kleinii*, *Arn.* (sp.)
 var. *minor*, *Triana.* (sp.)
 var. *Wightiana*, *Benth.* (sp.)
 (*O. glauca*, *Benth.*)
O. WALKERI, *Arn.* 105.
O. RUBICUNDA, *Arn.* 105.
O. MOONII, *Thw.* 105.
O. octaudra, *DC.* *O. virgata.* 105.
Hín-bôwitiyá, *S.*
 300. *Melastoma malabathricum*, *L.* 106.
Maha-bôwitiyá, *S.*
 301. *Kendrickia Walkeri*, *Hk. f.* *Pachycentria.* 107.
 302. *SONERILA ZEYLANICA*, *W. & A.* 109 & C. P. 3893.
 var. *pumila*, *Clarke.* *S. pumila.* 109.
 var. *Walkera*, *Clarke.*
S. TOMENTELLA, *Thw.* 109.
S. Brunonis, *W. & A.* ("C. P. 662.")
S. pedunculosa, *Thw.* 109.
S. ARNOTTIANA, *Thw.* 108.
S. WIGHTIANA, *Arn.* C. P. 3907.
S. HOOKERIANA, *Arn.* 108.

- S. GARDNERI*, *Thw.* 107.
 var. *firma*, *Triana.* C. P. 3873.
S. ROBUSTA, *Arn.* 107.
 var. *glabricaulis*, *Thw.* C. P. 3955.
S. HARVEYI, *Thw.* 107.
S. AFFINIS, *Arn.* 109.
 var. *rostrata*, *Clarke.* *S. rostrata.* 108.
S. RHOMBIFOLIA, *Thw.* 108.
 var. *angustata*, *Triana.* (sp.)
S. HIRSUTULA, *Arn.* 108.
S. PILOSULA, *Thw.* 108.
S. LANCEOLATA, *Thw.* 107.
S. GUNERATNEI, *Trim. ms.* C. P. 4012.
303. *MEDINILLA FUCHSIOIDES*, *Gardn.* 106.
 M. MACULATA, *Gardn.* 106.
 var. *cuneata*, *Thw.* 106.
304. *MEMECYLON ARNOTTIANUM*, *Wight.* 113.
 M. GARDNERI, *Thw.* 113.
 M. WIGHTII, *Thw.* 113.
 M. HOOKERI, *Thw.* 113.
 var. *exalata*, *Trim. ms.* C. P. 2686.*
 Kevitiya-kera, S.
 M. ELEGANTULUM, *Thw.* 112.
 M. ELLIPTICUM, *Thw.* 112.
 M. VARIANS, *Thw.* 112.
 var. *parvifolium*, *Thw.* (sp.) 113.
 var. *rotundatum*, *Thw.* 112.
 M. PROCERUM, *Thw.* 415.
 M. OVOIDEUM, *Thw.* 112. Includes *M. macrocarpum.* 110.
 M. MACROPHYLLUM, *Thw.* 111.
 M. ORBICULARE, *Thw.* 112.
 M. Heyneanum, *Benth.* *M. jambosoides.* 112.
 var. *latifolium*, *Clarke.*
 var. *angustifolium*, *Clarke.*
 M. FUSCESCENS, *Thw.* 111.
 Dodaṅ-kaha, S.
 M. ROSTRATUM, *Thw.* 111.
 Kuretiya, S.
 M. RHINOPHYLLUM, *Thw.* 110.
 M. angustifolium, *Wight.* 111.
 M. PHYLLANTHIFOLIUM, *Thw.* (in *Triana Mon.*) C. P.
 3901.

- M. lævigatum*, Bl., var. *sylvaticum*, Cl. *M. sylvaticum*. 110.
M. grande, Retz. *M. edule*, var. β . 110.
Dodaṇ-wenna, S.
M. capitellatum, L. 110.
Dodaṇ-kaha, *Weli-kaha*, S. *Katti-kaiya*, *Manchavarná*, T.
M. UMBELLATUM, Burm. 111. (C.P. 1561, 1562.)
Kora-kaha, S.
var. *Thwaitesii*, Clarke. (C. P. 387.)
M. edule, Roxb. 110.
var. *ovatum*, Sm. (sp.) var. γ . 110.
Dedi-kaha, S.
var. *RUBRO-CÆRULEUM*, Clarke. *M. rubro-cæruleum*. 415.
var. *CUNEATUM*, Clarke. *M. cuneatum*. 112.
var. *LEUCANTHUM*, Clarke. *M. leucanthum*. 110.

54. Lythraceæ.

305. *Ammannia peploides*, Spreng. *Ameletia indica*. 122.
A. Rotala, F. Muell. *Rotala verticillaris*. 122.
A. pentandra, Roxb. 122.
A. baccifera, L. *A. indica*. 121.
A. cordata, W. & A. *A. salicifolia*. var. β . 121.
A. lanceolata, Heyne. *A. salicifolia*. var. α . 121.
A. octandra, L. f. 121.
306. *Woodfordia floribunda*, Sal. *Grislea tomentosa*. 122.
Malita, S.
* *Nesaea triflora*, H. B. K. 417.
307. *Pemphis acidula*, Forst. 122.
308. *Lawsonia alba*, Lam. 122.
Marithondi, T. *Henna*. *Tree Mignonette*.
309. *Lagerstrœmia Flos-reginæ*, Retz. 122.
Muruta, S. *Kadalipuva*, T.
310. *Sonneratia acida*, L. f. 123.
Kirilla, S.
S. alba, Sm.
311. *AXINANDRA ZEYLANICA*, Thw. 122.
Kekiri-wará, S.

55. Onagraceæ.

312. *Jussiaea repens*, L. 123.
Béru-diyanilla, S.

J. suffruticosa, *L.* *J. villosa*. 123.

var. *angustifolia*, *Lam.* (sp.) var. *subglabra*.

313. *Ludwigia parviflora*, *Roxb.* 123.

L. prostrata, *Roxb.* 123.

314. *Trapa bispinosa*, *Roxb.* 124.

Ikiliya, *S.*

56. *Samydaceæ*.

315. *Casearia esculenta*, *Roxb.* *C. zeylanica* & *C. varians*,
(part.) 19.

Wal-warakhá, *S.*

var. *angusta*, *Clarke*.

var. *Championii*, *Clarke.* *C. Championii*. 19.

C. CORIACEA, *Thw.* Includes *C. varians*, var. γ . 20.

C. tomentosa, *Roxb.* 19.

316. *OSMELIA GARDNERI*, *Thw.* 20.

317. *Homalium zeylanicum*, *Benth.* 410.

Liyan, *S.*

(*Turneraceæ*.)

* *Turnera ulmifolia*, *L.*

57. *Passifloraceæ*.

318. *Modecca Wightiana*, *Wall.* 128.

M. palmata, *Lam.* 128.

Hondala, *Potu-hondá*, *S.*

* *Passiflora suberosa*, *L.*

* *P. edulis*, *Ait.*

* *P. glauca*, *Ait.*

* *P. foetida*, *L.*

(*Carica* *Papaya*, *L.* *Pepol*, *S.* *Papaw*.)

58. *Cucurbitaceæ*.

319. *Trichosanthes palmata*, *Roxb.* 127.

Titta-hondala, *S.*

var. *tomentosa*, *Heyne*.

T. nervifolia, *L.* 127.

T. cucumerina, *L.* 126.

Dummélla, *S.*

var. *laciniosa*, *Thw.*

(*T. anguina*, *L.*) *Patóla*, *S.* *Podivilángu*, *T.* *Snake*
Gourd.

T. THWAITESII, *Cogn.* *T. integrifolia*. 127.

320. *Gymnopetalum Wightii*, *Arn.* 127.

var. *tubiflorum*, *Cogn.* (sp.) *G. zeylanicum*. 127.

- (*Lagenaria vulgaris*, Sér.) *Diya-labu*, S. *Bottle Gourd*.
 321. *Luffa ægyptiaca*, Mill. *L. pentandra*. 126.
Niyan-veṭa-kolu, S.
L. acutangula, Roxb. 126.
Veṭa-kolu, *Dāra-veṭa-kolu*, S. *Pisukkaṇ-kái*, T.
 var. *amara*, Clarke. *L. amara*. 417.
 (Benincasa cerifera, Savi.) *Alu-puhul*, S. *Pūsani-kái*, T.
Ash Pumpkin.
 322. *Momordica Charantia*, L. 126.
Karivila, S.
M. dioica, Roxb. 126.
Tumba Karivila, S.
M. DENUDATA, Clarke. *M. dioica*, var. 126.
 323. *Cucumis trigonus*, Roxb. 127.
C. pubescens, Willd. 127.
Goṇ-kekiri, S.
 324. *Citrullus Colocynthis*, Schrad. 126.
Yak-komaḍu, S. *Colocynth*.
 (C. vulgaris, Schrad.) *Komaḍu*, S. *Water Melon*.
 325. *Cephalandra indica*, Naud. *Coccinea*. 128.
Kōwakká, S.
 326. *Bryonia laciniosa*, L. 126.
 (Cucurbita moschata, Duch.) *Raṭa-labu*, S. *Waṭṭak-kai*, T. *Pumpkin*.
 327. *Mukia scabrella*, Arn. 125.
Hin-kekiri, S.
M. leiosperma, Thw. 125.
 328. *Zehneria Hookeriana*, Arn. 125.
Z. umbellata, Thw. 125.
Kuḍu-kekiri, S.
 329. *MELOTHRIA ZEYLANICA*, Clarke. *M. deltoidea*. 124.
 330. *Corallocarpus epigœa*, Hk. f. *Æchmandra*. 125.
Go-palangá, S.
 331. *Cerasiocarpus zeylanicum*, Hk. f. *Æchmandra*. 125.
 332. *Ctenolepis Garcini*, Naud. *Zehneria*. 125.
 333. *Gynostemma pedata*, Bl. *Pestalozzia laxa*. 124.
 334. *Zanonia indica*, L. 124.
Wal-rasakinda, S.

59. Begoniaceæ.

335. *Begonia cordifolia*, Thw. 129.
B., sp. 129. (C. P. 3460.)

B. TENERA, *Dry.* B. *Thwaitesii*. 128. C. P. 3952.

B. THWAITESII, *Hook.* C. P. 3953.

B. subpeltata, *Wight.* 128.

B. malabarica, *Lam.* 128.

Maha-hakambald, S.

var. dipetala, *Thw.* 128. C. P. 3949.

60. Datisceæ.

336. *Tetrameles nudiflora*, *R. Br.* 252.

61. Cactaceæ.

337. *Rhipsalis Cassytha*, *Gaertn.* 129.

* *Opuntia Dillenii*, *Haw.*

Katupatuk, S.

62. Ficoideæ.

338. *Sesuvium Portulacastrum*, *L.* *S. repens.* 23.

339. *Trianthema monogyna*, *L.* *T. obcordata.* 23.

Hin-sárana, S.

T. crystallina, *Vahl.* 23.

T. decandra, *L.* 23.

Maha-sárana, S.

340. *Mollugo hirta*, *Thunb.* *Glinus dictamnoides.* 24.

M. Spergula, *L.* 24.

M. stricta, *L.* Includes *M. pentaphylla,* *L.* 24.

M. Cerviana, *Ser.* 24.

Patpadágam, T.

M. disticha, *Ser.* 24.

M. nudicaulis, *Lam.* 24.

341. *Gisekia pharnaceoides*, *L.* 250.

63. Umbelliferæ.

342. *Hydrocotyle javanica*, *Thunb.* 130.

Maha-goŕu-kola, S.

H. rotundifolia, *Roxb.* *H. nitidula.* 130.

H. asiatica, *L.* 130.

Hín-goŕu-kola, S. *Vallárai,* T.

343. *Sanicula europæa*, *L.* 130.

344. *Bupleurum mucronatum*, *W. & A.*, var. *virgata*, *Cl.* *B. falcatum*, var. 131.

Wal-endaru, S.

* *Carum Roxburghianum*, *Benth.*

[*C. nothum*, *Clarke.*]

345. *Pimpinella Heyneana*, Wall. *Helosciadium*. 130.
Wal-asamôdagan, S.
P. Leschenaultii, DC. 131.
346. *PEUCEDANUM ZEYLANICUM*, Gardn. *Palimbia ramosissima*. 131.
Wal-endaru, S.
347. *Heracleum zeylanicum*, Gardn. *H. Sprengelianum*, 131.
 var. *rigens*, Wall. (sp.)

64. Araliaceæ.

(*Panax fruticosum*, L.)

[*Pentapanax Leschenaultii*, Seem.]

348. *Polyscias acuminata*, Seem. *Hederā*. 131.
349. *Heptapleurum racemosum*, Bedd. *Hedera*. 132.
H. EMARGINATUM, Seem. *Hedera*. 132.
H. stellatum, Gaertn. *Hedera Vahlī*. 132.
Itta, S.
H. exaltatum, Seem. *Hedera*. 132.
Goda-itta, S.

65. Cornaceæ.

350. *Alangium Lamarckii*, Thw. 133.
Alangi, T.
A. GLANDULOSUM, Thw. 133.
351. *MASTIXIA TETRANDRA*, Clarke. *Bursinopetalum*. 42.
 var. *Thwaitesii*, Clarke. var. β . 42.
Diya-taliya, S.
M. arborea, Clarke. *Bursinopetalum*. 42.

GAMOPETALÆ.

66. Caprifoliaceæ.

352. *Viburnum coriaceum*, Bl. *V. hebanthum*. 136.
 var. *capitellata*, Clarke.
 var. *ZEYLANICA*, Gardn.
V. erubescens, Wall, 136.

67. Rubiaceæ.

353. *Sarcocephalus cordatus*, Miq. *Nauclea coadunata*. 137.
Bak-mī, S. *Vammi*, T.
354. *Anthocephalus Cadamba*, Miq. *Nauclea*. 137.
Vellai-kadamba, T.

355. *Adina cordifolia*, *Hk. f. Nauclea*. 137.
Kolon, S. Manjal-kadambu, T.
356. *Stephegyne parviflora*, *Korth. Nauclea*. 137.
Helamba, S. Nir-kadamba, T.
S. tubulosa, Hk. f. Nauclea. 137.
var. minor, Thw.
357. *NAUCLEA ZEYLANICA, Hk. f. N. peduncularis*. 137.
358. *Uncaria dasyoneura, Korth., var. THWAITESII, Hk. f.*
U. Gambier. 138.
359. *Wendlandia Notoniana, Wall.* 159.
Rawan-idala, S.
var. ZEYLANICA, Hk. f.
360. *Dentella repens, Forst.* 144.
361. *NEUROCALYX ZEYLANICUS, Hook.* 138.
N. Wightii, Arn. 138.
N. CAPITATA, Benth.
N. CHAMPIONII, Benth. 139.
N. GARDNERI, Thw. 139.
362. *ALLEOPHANIA DECIPIENS, Thw.* Includes *Hedyotis*
nodulosa, var. a. 143, 147.
var. flavescens, Thw. 147.
var. Arnottii, Hk. f. (sp.) ("C. P. 87.")
363. *Fergusonia zeylanica, Hk. f. Borreria tetracocca.* 442.
364. *Hedyotis fruticosa, L.* 142.
Weraniya, S.
H. EVENIA, Thw. 140.
H. CYMOSA, Thw. 142.
H. MACRAI, Hk. f.
H. OBSCURA, Thw. 141.
var. minor, Thw. (in Fl. Brit. Ind.)
H. COPROSMOIDES, Trim. ms. H. obscura, var. b. 141.
H. QUINQUENERVIA, Thw. 141.
H. LESSERTIANA, Arn. 141.
var. major, Thw.
var. confertiflora, Thw. Includes *H. flavescens*,
141, 419, & C.P. 3935.
H. RHINOPHYLLA, Thw. ms. C. P. 3984.
H. GARDNERI, Thw. 142.
H. MEMBRANACEA, Thw. 143.
H. THWAITESII, Hk. f. H. macrophylla. 142.

- H. NODULOSA*, *Arn.* *Var. β.* 143.
 var. Walkeri, Hk. f.
H. CINEREO-VIRIDIS, *Thw.* 419.
 var. subverticillata. Trim. ms. Var. β. 419.
 var. fumata, Thw. ms. C. P. 3909 (part.)
 var. truncata, Trim. ms. C. P. 3909 (part.)
H. verticillaris, W. & A. 142.
H. Lawsoniæ, W. & A. 140.
H. auricularia, L. 142.
 Geta-kola, S.
H. cœrulea, W. & A. 144.
H. nitida, W. & A. 143.
 Piṭa-sudu-palā, S.
H. INAMCENA, Thw. 143.
H. CYANESCENS, Thw. 143.
 365. *Oldenlandia corymbosa, L. Hedyotis Burmanniana.* 144.
 Wai-patpādāgam, S.
 var. racemosa, Thw. 419.
O. diffusa, Roxb. Hed. Burmanniana, var. brachypoda.
 419.
O. Heynei, Br. Hedyotis. 144.
O. umbellata, L. Hedyotis. 144.
 Saya-mul, S. Saya, T. Chay Root.
O. trinervia, Retz. Hedyotis. 144.
O. stricta, L. Hed. maritima. 144.
O. biflora, L. (Includes O. paniculata, L.) Hedyotis race-
 mosa. 144.
 366. *Anotis quadrilocularis, Hk. f. Hedyotis.* 144.
 A. NUMMULARIA, Hk. f. Hedyotis. 142.
 A. NUMMULARIFORMIS, (Arn.) H. nummularia, var.
 glabra. 142.
 A. RICHARDIANA, (Arn.) H. monosperma, var. sub-
 glabra. 142.
 367. *Ophiorrhiza Mungos, L.* 139.
 Dat-keṭiyā, S.
 var. NEMOROSA, Hk. f. O. nemorosa. 139.
 var. ANGUSTIFOLIA, Hk. f. O. angustifolia. 140.
O. Harrisiana, Heyne. var. decumbens, Hk. f. O. de-
 cumbens. 419.
O. RADICANS, Gardn. 139.
O. pectinata, Arn. 140.
 var. imbricata, Gardn. (sp.)

- O. PALLIDA, *Thw.* 140.
 O. GLECHOMIFOLIA, *Thw.* 140.
368. *Mussaenda frondosa*, *L.* 138.
Mussaenda, *Wel-but-sarapa*, *S.*
369. *ACRANTHERA ZEYLANICA*, *Arn.* 138.
370. *LEUCOCODON RETICULATUM*, *Gardn.* 138.
371. *UROPHYLLUM ELLIPTICUM*, *Thw.* 419.
U. ZEYLANICUM, *Thw.* 418.
372. *SCHIZOSTIGMA HIRSUTUM*, *Arn.* 139.
373. *Webera corymbosa*, *Willd.* *Stylocoryne Webera.* 158.
Tarana, *S.* *Taranai*, *T.*
 var. *montana*, *Thw.*
374. *BYRSOPHYLLUM ELLIPTICUM*, *Bedd.* *Stylocoryne.* 421.
375. *Randia uliginosa*, *DC.* 159.
Weideya, *Et-kukurumán*, *S.*
- R. dumetorum*, *Lam.* 159.
Kukurumán, *S.*
- R. malabarica*, *Lam.* *Griffithia fragrans.* 158.
- R. GARDNERI*, *Hk. f.* *Griffithia.* 158.
Ataketiya, *S.*
- R. rugulosa*, *Hk. f.* *Griffithia.* 159.
376. *Gardenia latifolia*, *Ait.* 159.
Galís, *S.* *Kumbai*, *T.*
- G. carinata*, *Wall.* 159.
377. *NARGEDIA MACROCARPA*, *Bedd.* *Hyptianthera.* 157.
378. *SCYPHOSTACHYS PEDUNCULARIS*, *Thw.* 157.
S. COFFÆOIDES, *Thw.* 157.
Wal-kópi, *S.*
379. *DIPLOSPORA DALZELLII*, *Hk. f.* *Discospermum.* 158.
D. ERYTHROSPORA, *Hk. f.* *Discospermum.* 158.
380. *Scyphiphora hydrophyllacea*, *Gaertn.* *Epithinia malayana.* 157.
381. *Guettarda speciosa*, *L.* 153.
Wal-pichea, *S.* *Paneer*, *T.*
382. *Timonius Jambosella*, *Thw.* 153.
Peddi-méla, *Angana*, *S.*
383. *DICHLANTHE ZEYLANICA*, *Thw.* 136.
384. *KNOXIA CORYMBOSA*, *Willd.* *K. stricta.* 152.
K. mollis, *W. & A.* *K. corymbosa.* 151.
- K. ZEYLANICA*, *L.* 152.
Ela-rat-mal, *S.*

- K. PLATYCARPA, *Arn.* 152.
 var. *hirsuta*, *Thw.*
 var. *foliosa*, *Thw.*
 var. *spicata*, *Thw. ms.* C. P. 3996.
385. *Canthium didymum*, *Roxb.* 152.
Porawa-márá, Gal-karanda, S. Yerkoli. T.
 var. *LANCEOLATUM*, *Thw.*
 var. *GRANDIFOLIUM*, *Thw.*
C. MONTANUM, *Thw.* 152.
C. PUBERULUM, *Thw. (in Fl. Brit. Ind.)* C. P. 3995.
C. Rheedii, *DC.* 153.
 var. *minus*, *Thw.*
C. MACROCARPUM, *Thw.* 152.
C. CAMPANULATUM, *Thw.* 153.
C. parviflorum, *Lam.* 152.
Kára, S. Kárai, T.
386. *IXORA CALYCINA*, *Thw.* 155.
I. THWAITESII, *Hk. f. I. acuminata.* 155.
 var. *pubescens.*
I. parviflora, *Vahl.* 155.
Maha-ratambalá, S. Karankuttai, Punkirai, T.
 var. *ZEYLANICA*, *Hk. f. I. jucunda*, var. γ . 155.
I. JUCUNDA, *Thw.* 155.
I. coccinea, *L.* 154.
Ratambalá, S.
387. *Pavetta indica*, *L.* 155.
Páwattá, S.
 var. *MONTANA*, *Thw.* 156.
P. hispidula, *W. & A.* 156.
 var. (? hybrid) *ZEYLANICA*, *Hk. f.* C. P. 3924.
P. ANGUSTIFOLIA, *Thw.* 156.
P. INVOLUCRATA, *Thw.* 156.
P. GLENIEL, *Thw. (in Fl. Brit. Ind.) P. tomentosa.* 156.
388. *Coffea Wightiana*, *W. & A.* 154.
C. travancorensis, *W. & A.* 154.
Gas-pichcha, S.
389. *Morinda citrifolia*, *L.*, var. *bracteata*, *Hk. f. M. bracteata*, 144.
Ahu, S.
M. tinctoria, *Roxb.* 145.
Ahu, S.

- M. umbellata*, *L.* 145.
Kiri-wel, Maha-kiri-wel, *S.*
390. *Prismatomeris albidiflora*, *Thw.* 154.
 var. *FERGUSONII*, *Thw. (in Bedd. Fl. Sylv.) (sp.)*.
391. *PSYCHOTRIA STENOPHYLLA*, *Hk. f. Grumilea.* 147.
P. GLANDULIFERA, *Thw. (in Fl. Brit. Ind.) C. P.* 3911.
P. GARDNERI, *Hk. f. Grumilea.* 147.
P. Thwaitesii, *Hk. f. G. nudiflora.* 147.
 var. *coronata*, *Hk. f.*
P. elongata, *Hk. f. Grumilea* 147.
P. sarmentosa, *Bl.* 148.
Wal-goniká, *S.*
- P. WIGHTIANA*, *Hk. f. Grumilea.* 148.
 var. *affinis*, *Hk. f. G. affinis.* 148.
P. MOONII, *Hk. f. Grumilea.* 148.
P. SORDIDA, *Thw.* 149.
P. LONGEPETIOLATA, *Thw.* 149.
P. PLURIVENIA, *Thw.* 149.
P. FILIPES, *Hk. f. P. bisulcata*, var. β . 148.
P. bisulcata, *W. & A.* 148.
392. *Chasalia curviflora*, *Thw.* 150.
393. *Geophila reniformis*, *Don.* 150.
Agu-karuni, *S.*
394. *LASIANTHUS MOONII*, *Wight.* 420. (145.)
 var. *subglabra*, *Thw. ms. C. P.* 3997.
L. THWAITESII, *Hk. f. L. strigosus* (part.) 420.
L. RHINOPHYLLUS, *Thw.* 420.
L. WALKERIANUS, *Wight. L. protractus*, (part.) and
L. varians, (part.) 420.
 var. *lanceolatus*, *Hk. f. ("C. P. 340.")*
L. OLIGANTHUS, *Thw.* 420.
L. GARDNERI, *Hk. f. L. strigosus* (part.) 420, and
C. P. 3985.
L. STRIGOSUS, *Wight. (non Thw.) L. Walkerianus* and
L. varians (part.) 420.
 var. *nitidus*, *Thw. (in Fl. Brit. Ind.) C. P.* 3910.
 var. *protractus*, *Hk. f. L. protractus*, (part.) 420.
L. VARIANS, *Thw. (part.)* 420.
L. OBLIQUUS, *Thw.* 420.
395. *Saprosma indicum*, *Dalz.*, var. *GARDNERI*, *Hk. f. Serissa*
Gardneri. 150.
S. SCABRIDUM, *Bedd. Serissa.* 151.
S. zeylaicum, *Bedd. Serissa.* 150.

396. *Hydrophylax maritima*, *L. f.* 151.
Múdu-geṭakola, S.
397. *Spermacoea stricta*, *L. f.* *S. hispida* (part.) 151.
S. oeymoides, *Burm.* *Borreria*. 151.
S. hispida, *L.* 151.

Hin-geṭa-kola, S.

398. *Rubia cordifolia*, *L.* 151.
Manda-madini-wel, S.
399. *Galium asperifolium*, *Wall.* 151.

68. Valerianaceæ.

400. VALERIANA MOONII, *Arn.* *V. Hardwickii*. 159.

69. Dipsacaceæ.

401. DIPSACUS WALKERI, *Arn.* 421.

70. Compositæ.

402. VERNONIA GARDNERI, *Thw.* 161.
V. THWAITESII, *Clarke.* *V. Gardneri*, var. *nervosa*. 161.
V. ANCEPS, *Clarke.* *V. Wightiana*, var. β . 160.
V. cinerea, *Less.* 160.

Monara-kudimbiya, S.

- V. SETIGERA*, *Arn.* *V. neilgherriensis*. 160.
V. HOOKERIANA, *Arn.* *V. conyzoides*. 160.
V. SCARIOSA, *Arn.* 161.

var. *CRASSA*, *Thw.* 161.

- † *V. anthelmintica*, *L.* 160.

Náyan, *Sanni-náyan*, S. *Kat-síragam*, T.

- V. NEMORALIS*, *Thw.* 161.

- V. Wightiana*, *Arn.* 160.

- V. ZEYLANICA*, *Less.* 160.

Pupula, S. *Kupula*, T.

- V. pectiniformis*, *DC.* 161.

- V. arborea*, *Ham.* *V. javanica*. 160.

403. *Elephantopus scaber*, *L.* 161.

Et-adi, S.

404. *Adenostemma viscosum*, *Forst.* 162.

var. *reticulatum*, *DC.* (sp.)

- * *Ageratum conyzoides*, *L.* 161.

Hulaṅ-talá, S. *Pum-pullu*, T. *Goat-weed. White-weed.*

(*Eupatorium Ayapana*, *Vent.*) *Ayapana*, S.

405. *Dichrocephala latifolia*, *DC.* 162.

406. *Grangea maderaspatana*, Poir. 163.
 407. *Myriactis Wightii*, DC. 162.
 408. *Lagenophora Billardieri*, Cass., var. *Harveyi*. *L. Harveyi*. 162.
 409.* *Erigeron linifolius*, Willd. C.P. 3928.
 E. asteroides, Roxb. *Conyza aegyptiaca*. 163.
 410. *Microglossa zeylanica*, Benth. *Amphiraphis*. 162.
 411. *Conyza viscidula*, Wall. 163.
 412. *Blumea amplexens*, DC. 163.
 var. *arenaria*, Clarke. *B. arenaria*. 163.
 B. bifoliata, DC. *B. amplexens* (part.) 163.
 [*B. Wightiana*, DC.]
 B. barbata, DC. 163.
 B. lacera, DC. 163.
 B. hieraciifolia, Thw. 163.
 B. ANGUSTIFOLIA, Thw. 164.
 B. membranacea, DC. var. *Gardneri*, Hk. f. *B. glandulosa*. 163.
 B. CRINITA, Arn. 163.
 B. flexuosa, Clarke. *B. hieraciifolia* (part.)
 B. spectabilis, DC. *B. myriocephala*. 163.
 B. balsamifera, DC. 422.
 413. *Laggera alata*, Sch.-Bip. *Blumea*. 163.
 414. *Epaltes divaricata*, Cass. 164.
 Hin-muda-mahana, S.
 415. *Sphæranthus amaranthoides*, Burm. 162.
 S. africanus, L. *S. microcephalus*. 162.
 S. indicus, L. *S. hirtus*, 162.
 Muda-mahana, S.
 416. *Blepharispernum petiolare*. DC.
 417. *Anaphalis cinnamomea*, Clarke. *Gnaphalium adnatum*.
 422.
 A. FRUTICOSA, Hk. f. *G. adnatum*, var. *spathulifolium*
 (part.) 422.
 A. oblonga, DC. *Gnaphalium*. 422.
 A. THWAITESII, Clarke. *G. adnatum*, var. *spathulifolium*
 (part.) 422.
 A. ZEYLANICA, Clarke. *G. Wightianum*. 166.
 A. marcescens, Clarke. *Gnaphalium*. 166.
 A. brevifolia, DC. *Gnaphalium*. 166.
 * *Gnaphalium indicum*, Auct. (non L.)
 418. *Helichrysum buddleoides*, DC. *Gnaph. Hookerianum*.
 166.

419. *Vicoa auriculata*, Cass. 164.
 * *Lagascea mollis*, Cav.
420. *Chrysogonum heterophyllum*, Benth. *Moonia*. 164.
421. *Xanthium Strumarium*, L. 164.
422. *Siegesbeckia orientalis*, L. 164.
423. *Eclipta erecta*, L. 164.
Kikirindi, S.
424. *Blainvillea latifolia*, DC. 164.
425. *Wedelia calendulacea*, Less. 165.
Raṅ-waṅ-kikirindi, S.
W. biflora, DC. *Wollastonia*. 165.
 * *Tithonia diversifolia*, Gray.
426. *Spilanthes Acmella*, L. 165.
Akmella, S.
 * *Synedrella nodiflora*, Gaertn. *Ximenesia encelioides*. 422.
 * *Cosmos bipinnatus*, Cav.
 * *C. sulphureus*, Cav.
427. † *Bidens pilosa*, L. 165.
 var. *decomposita*, Hook. f. *B. decomposita*. 165.
Wal-té-kola, S. *Spanish Needle*.
 * *Tridax procumbens*, L.
 * *Tajetes erecta*, L.
428. *Centipeda orbicularis*, Lour. *Myriogyne minuta*. 165.
429. *Artemisia vulgaris*, L. var. 165.
Wal-kolondu, S.
430. *Gynura lycopersicifolia*, DC. 166.
G. pseudo-china, DC. (non Benth.) *G. nepalensis*. 166.
G. HISPIDA, Thw. 166.
431. *Emilia sonchifolia*, DC. 167.
Kaḍu-pára, S.
E. ZEYLANICA, Clarke, *E. prenanthoidea*. 167.
 var. *Walkeri*, Hk. f. (sp.) 167.
432. *Notonia grandiflora*, DC. 168.
N. Walkeri, Clarke. *Senecio*. 167.
433. *Senecio zeylanicus*, DC. 167.
S. GARDNERI, Clarke. *Doronicum*. 167.
S. ludens, Clarke. *Doronicum Walkeri*. 167.
S. araneosus, DC. *S. corymbosus*, var. β . 167.
S. corymbosus, Wall. C. P. 3894.
S. scandens, Don. *S. Wightianus*. 167.

434. *Crepis japonica*, *Benth.* *Youngia lyrata*. 168.
C. fuscipappa, *Hk. f.* *Youngia*. 168.
435. *Lactuca Heyneana*, *DC.* *Brachyramphus sonchifolius*. 168.
 * *Sonchus asper*, *Vill.* *Sow thistle*.
 * *S. oleraceus*, *L.* 168.
436. *Launea pinnatifida*, *Cass.* *Microrhynchus sarmentosus*. 168.

71. Stylidiaceæ.

437. *Stylidium uliginosum*, *Sw.* 168.

72. Goodenoviaceæ.

438. *Scævola Koenigii*, *Vahl.* 169.
Takkaḍa, *S.*
S. Lobelia, *L.* *S. Plumieri*. 169.
Hin-takkaḍa, *S.*

73. Campanulaceæ.

- * *Isotoma longiflora*, *Presl.*
439. *Lobelia trigona*, *Roxb.* 169.
L. affinis, *Wall.* *L. trigona* (part.) 169.
L. zeylanica, *L.* *L. trigona* (part.) 169.
 var. *WALKERI*, *Clarke.*
L. excelsa, *Lesch.* 170.
Ras-ni, *S.*
 var. *trichandra*, *Wight* (sp.)
 [*Cephalostigma Schimperii*, *Hochst.*]
440. *Wahlenbergia gracilis*, *DC.* *W. agrestis*. 169.
441. *Sphenoclea zeylanica*, *Gaertn.* *S. Pongatium*. 170.
442. *Campanula canescens*, *Wall.* *Cephalostigma spathulatum*. 420.
C. fulgens, *Wall.* 169.

74. Vacciniaceæ.

443. *Vaccinium Leschenaultii*, *Wight.* 170.
 var. *ZEYLANICA*, *Clarke.*

75. Ericaceæ.

444. *Gaultheria fragrantissima*, *Wall.* 170.
 var. *HIRSUTA*, *Gardn.*
Kapuru, *S.*
445. *Rhododendron arboreum*, *Sm.*, var. *nilagiricum*, *Zenk.* (sp.) 170.
Má-ratmal, *S.*

76. Plumbagineæ.

446. *Plumbago zeylanica*, L. 244.
Ela-netul, S.

77. Primulaceæ.

447. *Lysimachia ramosa*, Wall., var. ZEYLANICA, Hk. f. 172.
L. deltoides, Wight., var. CORDIFOLIA, Hk. f. *L. japonica*. 172.
 * *Anagallis cœrulea*, Lam. 172.

78. Myrsineæ.

448. *Mæsa indica*, Wall. 172.
Mata-bimbiya, S.
449. *Myrsine capitellata*, Wall. 173.
 var. *lanceolata*, Wall. (sp.) var. β . & var. γ . 173.
 var. *avenis*, A. DC. (sp.) var. δ . *sessiliflora*. 173.
450. *Embelia Ribes*, Burm. 172.
Wel-embilla, S.
E. robusta, Roxb. 172.
E. viridiflora, Scheff. Samara. 173.
451. *ARDISIA MISSIONIS*, Wall. *A. courtallensis*. 423.
A. GARDNERI, Clarke. *A. divergens*. 174.
 var. *zeylanica*, Cl. (sp.) Var. β , Thw. 174.
A. MOONII, Clarke. *A. Wallichii*. 174.
 var. *subsessilis*, Clarke. *A. humilis*. 173.
Lunu-dan, S.
A. pauciflora, Heyne. 174.
A. humilis, Vahl. *A. elliptica*. 174.
Balu-dan, S.
452. *Ægiceras majus*, Gaertn. 174.
Hin-kadol, S. *Vitli-kanna*, T.

79. Sapotaceæ.

453. *Chrysophyllum Roxburghii*, G. Don, var. *sumatranum*,
Miq. (sp.) 174.
Lá-wulu, S.
454. *Sideroxylon tomentosum*, Roxb. *Sapota elengoides*. 175.
Mul-makil, T.
455. *Isonandra Wightiana*, A. DC. 177.
Kiri-warala, S.
 var. *ANGUSTATA*, Thw. 177.
 var. *MONTANA*, Thw. 177.
 var. *MAJOR*, Clarke.

- var. COMPTA, *Thw.* (in *Fl. B. Ind.*) C. P. 3912.
 var. lanceolata, *Wight*, non *Thw.* (sp.)
456. DICHOPSIS PETIOLARIS, *Thw.* 176.
 D. GRANDIS, *Benth.* *Isonandra.* 176.
Kiri-hembiliya, Kiri-hiriya, Mi-hiriya, S.
 var. parvifolia, *Clarke.* (C. P. 2402 part.)
 var. angustata, *Trim. ms.* (C. P. 2402 part.)
 D. RUBIGINOSA, *Benth.* *Isonandra.* 177.
 D. CANALICULATA, *Benth.* *Id.* 177.
 D. PAUCIFLORA, *Benth.* *Id.* 177.
 D. LÆVIFOLIA, *Benth.* *Id.* 177.
 D. LANCEOLATA, *Benth.* *Id.* 442.
457. Bassia longifolia, *L.* 175.
Mi, S. Iluppai, Enné-kannai, T.
 B. NERIIFOLIA, *Moon.* *Dasyaulus.* 175.
Gan-mi, S.
 B. MOONII, *Bedd.* *Id.* 176.
 B. FULVA, *Bedd.* *Id.* 176.
Wana-mi, S.
 B. MICROPHYLLA, *Hook.* *Id.* 175.
458. Mimusops Elengi, *L.* 175.
Mūnamal, S. Muchalai, T.
 M. hexandra, *Roxb.* *M. indica.* 175.
Palu, S. Pālai, T.
 ? M. Kauki, *L.*

80. Ebenaceæ.

459. MABA ACUMINATA, *Hiern.* *Macreightia.* 424.
M. OBLONGIFOLIA, Hiern. *Id.* 183.
M. OVALIFOLIA, Hiern. *Id.* 424.
 M. buxifolia, *Pers.* 183.
Kalu-habaraliya, S. Thucarai, Irum-palai, T.
 var. microphylla, *Thw.*
 var. Ebenus, *Thw.*
 var. angustifolia, *Thw.*
460. Diospyros montana, *Roxb.* Includes *D. cordifolia, Roxb.*
 423.
Kethi-kanni, Vukkana, T.
 D. Embryopteris, *Pers.* 178.
Timbiri, S. Panichekai, Tumbika, T. 24876
 var. atrata, *Thw.* 178.
 var. nervosa, *Thw.* 178.

- D. Toposia*, *Ham.* 179.
Kaha-kála, *S.*
D. ovalifolia, *Wight.* 181.
Vedū-kunari, *T.*
D. Ebum, *Koen.* 180.
Kaluwara, *S. Karuṅkáli*, *Chara*, *Acha*, *T. Ebony.*
D. sylvatica, *Roxb.* 178.
D. oocarpa, *Thw.* 180.
Kalu-kadumbériya, *S. Vellai-karuṅkáli*, *T.*
D. QUÆSITA, *Thw.* 179.
Kalumēdiriya, *S. Pū-karuṅkáli*, *T. Calamander.*
D. ATTENUATA, *Thw.* 182.
D. ACUTA, *Thw.* 182.
D. GARDNERI, *Thw.* 181.
Kadumbériya, *S. Vekandé*, *T.*
 [*D. Melanoxylon*, *Roxb.*]
D. insignis, *Thw.* 180.
Gona, *Porua-malla*, *Wal-mēdiriya*, *S.*
D. OPPOSITIFOLIA, *Thw.* 181.
Kalu-mēdiriya, *S.*
D. HIRSUTA, *L. f.* 181.
D. MOONII, *Thw.* 182.
D. THWAITESII, *Bedd. D. Candolleana.* 181.
Hó-mēdiriya, *S. Vellai-karuṅkáli*, *T.*
D. affinis, *Thw.* 179.
D. CRUMENATA, *Thw.* 179.
Chemel-paniché, *T.*
D. OPACA, *Clarke.* ("C. P. 2924 in part.")
D. pruriens, *Dalz. ?* 423.

81. *Styracæ.*

461. *Symplocos spicata*, *Roxb.*, var. *laurina*, *Wall.* (sp.) 184.
Bómbu, *Wal-bómbu*, *S. Elam-purukki*, *T.*
S. obtusa, *Wall.* 185.
 var. *major*, *Thw.* 185.
 var. *obovata*, *Thw.* 185.
 var. *cucullata*, *Thw.* 185.
S. LÆTA, *Thw.* 184.
S. BRACTEALIS, *Thw.* 185.
 var. *revoluta*, *Wight. & Gardn.*
S. VERSICOLOR, *Clarke. S. rufescens.* 184.
S. ACUTA, *Thw.* 186.

- S. CUNEATA*, Thw. 186.
S. HISPIDULA, Thw. 186.
S. JUCUNDA, Thw. 186.
S. ANGUSTATA, Clarke. *S. elegans*, var. *angustata* (pt.) 186.
S. LATIFLORA, Clarke. *S. hirsuta*. 185.
S. MINOR, Clarke. *S. hirsuta*, var. *minor*. 185.
 var. *glabrescens*, Thw. (in *Fl. B. Ind.*)
S. ELEGANS, Thw. 185.
S. HEBANTHA, Thw. (in *Fl. B. Ind.*) C. P. 3918.
S. CORDIFOLIA, Thw. 187.
S. APICALIS, Thw. 187.
 var. *glabrifolia*, Thw.
S. MARGINALIS, Thw. 187.
S. CORONATA, Thw. 187.
S. PAUCIFLORA, Wight (in *Fl. B. Ind.*) *S. pendula*. 184.

82. Oleaceæ.

462. *Jasminum Sambac*, Ait. 189.
 Pichcha, S.
 (*J. pubescens*, Willd.)
 J. Rottlerianum, Wall., var. *Thwaitesii*, Clarke. *J. glabriusculum*. 424.
 [*J. arborescens*, Roxb.]
 J. sessiliflorum, Vahl. (C. P. 1807 in part.)
 J. angustifolium, Vahl. 190.
 Wal-pichcha, S.
 [*J. Ritchiei*, Clarke.]
 [*J. rigidum*, Zenk.]
 J. auriculatum, Vahl. 190.
 J. flexile, Vahl. 190.
 J. humile, L. 190.
 (*Nyctanthes arbor-tristis*, L.) 190.
 Sépála, *Sépáliká*, S. *Pakala-mullai*, T.
 463. *LINOCIERA PURPUREA*, Vahl. *Chionanthus zeylanica*. 188.
 Gherriata-gas, S.
 L. ALBIDIFLORA, Clarke. *Chionanthus*. 189.
 var. *rostrata*, Clarke. *C. rostrata*. 189.
 L. LEPROCARPA, Clarke. *Chionanthus*. 189.
 464. *Olea glandulifera*, Wall. 188.
 O. polygama, Wight. *O. Gardneri*. 188.

465. *Ligustrum Walkeri*, *Decaisne*. *L. robustum*. 188.

83. *Salvadoraceæ*.

466. *Salvadora persica*, *Garcin*. *S. Wightiana*. 190.
Ughai, T. *Mustard Tree*.
 467. *Azima tetracantha*, *Lam*. 191.
Wel-dehi, S.

84. *Apocynaceæ*.

468. *Willughbeia zeylanica*, *Thw*. 191.
 469. *Carissa Carandas*, *L*. 191.
Maha-karamba, S. *Perukla*, *Klakái*, T.
C. spinarum, *L*. *C. diffusa*. 191.
Hin-karamba, S. *Chenu-klá*, T.
 470. *Rauwolfia serpentina*, *Benth*. *Ophioxylon*. 191.
Ekáwériya, S.
R. densiflora, *Benth*. *Ophioxylon*. 191.
 471. *Alyxia zeylanica*, *Wight*.
Wasa-kaduru, S.
 472. *Hunteria corymbosa*, *Roxb*. *H. zeylanica*. 191.
Mediya, S. *L. H. Roxburghiana*. 192.
 473. *Cerbera Odollam*, *Gaertn*. 192.
Gon-kaduru, S. *Kadaralai*, *Kadu*, T.
 474. *Ochrosia borbonica*, *Gmel*. 192.
Múdu-kaduru, S.
 * *Vincá rosea*, *L*.
 (*Plumeria acutifolia*, *Pori*.) *Alariya*, S. *Temple Tree*.
 475. *Alstonia scholaris*, *Brown*. 193.
Ruk-attana, S. *Ir-ellipalai*, T.
 476. *Tabernaemontana dichotoma*, *Roxb*. 192.
Divi-kaduru, S. "Forbidden Fruit."
 (*T. coronaria*, *Br*.)
 477. *Holarrhena mitis*, *Brown*. 194.
Kiri-walla, S.
 478. *Parsonsia spiralis*, *Wall*. *Heligme*. 193.
 479. *Vallisneria Heynei*, *Spreng*. *V. dichotoma*. 192.
 (*V. pergulana*, *Burm*.) 192.
 480. *Wrightia flavido-rosea*, *Trim. ms*. *W. Rothii*. 193.
W. angustifolia, *Thw*. 193.
Vet-palai, T.
W. tomentosa, *R. & S*. 193.

W. ZEYLANICA, *Brown.* 193.

Sudu-idda, Wal-idda, S.

481. *Chonemorpha macrophylla, G. Don.* 194.

482. *BAISSEA ACUMINATA, Benth. Cleghornia.* 194.

483. *Aganosma cymosa, G. Don, var. elegans, Hk. f.* 194.

484. *Anodendron paniculatum, A. DC.* 194.

Dúl, As-wel, S.

A. RHINOSPORUM, *Thw.* 194.

485. *Ichnocarpus frutescens, Brown.* 194.

Kiri-wel, S.

85. Asclepiadæ.

486. *Hemidesmus indicus, Brown.* 195.

Iramusu, S. Nannári, T. Indian Sarsaparilla.

487. *Cryptolepis Buchanani, R. & S.* 195.

488. *Secamone emetica, Brown.* 195.

489. *Toxocarpus Kleinii, W. & A.* 195.

490. *Oxystelma esculentum, Brown.* 196.

491. *Calotropis gigantea, Brown.* 196.

Wará, S. Yerkum, Errukum, T. Mudar.

* *Asclepias curassavica, L.*

492. *Pentatropis microphylla, W. & A.* 196.

493. *Dœmia extensa, Brown.* 196.

Meda-kangu, S. Véli-paritti, T.

494. *Cynanchum pauciflorum, Brown. Cynoetionum.* 195.

Kaṇ-kumbalá, S.

495. *Sarcostemma Brunonianum, W. & A.* 196.

Múwa-kiriya, S.

496. *Gymnema sylvestre, Brown.* 197. (C. P. 2549.)

var. ZEYLANICUM, *Hk. f.* var. *Decaisneanum.*

G. ROTUNDATUM, *Thw.* 197.

G. lactiferum, *Brown.* 198.

Kuriññan, S.

var. THWAITESII, *Hk. f.* Var. β. (C. P. 1847.) 198.

var. WALKERI, *Hk. f.* (sp.)

G. PERGULARIOIDES, *Wight & Gardn. Bidaria.* 198.

var. Gardneri, *Hk. f.*

var. stenoloba, *Hk. f.* (sp.)

497. *Marsdenia tenacissima, W. & A.* 197.

Muruvá-dúl, S.

498. *Tylophora fasciculata, Ham.* 424 (197.)

- T. Iphisia*, Decaisne. 424.
 [*T. pauciflora*, W. & A.]
T. MEMBRANIFOLIA, Thw. 424. (C. P. 3793.)
T. zeylanica, Decaisne. *T. micrantha*. 197.
T. tennis, Bl. *T. carnosa*. 196.
T. CORDIFOLIA, Thw.
T. asthmatica, W. & A. 197.
Bin-nuga, S. Pappalai, T. Indian *Ipecacuanha*.
T. FLAVA, Trim. ms.
Mûdu-bin-nuga, S.
 499. *Cosmostigma racemosum*, Wight. 197.
 500. *Dregea volubilis*, Benth. *Hoya viridiflora*. 199.
Kiri-anguna, S.
 501. *Heterostemma tanjorensis*, W. & A., var. *zeylanicum*,
Hk. f. 198.
 502. *Dischidia nummularia*, Brown, 198. C. P. 3875.
 503. *Hoya pauciflora*, Wight. *H. Wightiana*. 199.
H. ovalifolia, W. & A. 198.
 504. *Leptadenia reticulata*, W. & A. 198.
 505. *Ceropegia elegans*, Wall. 199.
C. WALKERÆ, Wight. *C. elegans* (part.) 199.
C. GARDNERI, Hook. 199.
C. biflora, L. *C. Candelabrum*. 199.
Wel-mottu, S.
C. Thwaitesii, Hook. 199.
 506. *Caralluma attenuata*, Wight. 200.
 507. *Boucerosia umbellata*, W. & A. 200.

86. Loganiaceæ.

508. *Mitrasacme alsinoides*, Brown. *M. indica*. 200.
 509. *Fagraea zeylanica*, Thunb. 200.
Êtamburu, S.
F. obovata, Wall. 200.
 var. *GARDNERI*, Clarke. *F. Gardneri*. 200.
 510. *STRYCHNOS MICRANTHA*, Thw. (in part.) 425.
S. colubrina, L., var. *ZEYLANICA*, Cl. 201.
S. BENTHAMII, Clarke. *S. minor*. 201.
 var. *parviflora*, Benth.
S. Beddomei, Clarke. *S. micrantha* (part.) 425.
 var. *CORIACEA*, Thw. (sp.) 425.
S. CINNAMOMIFOLIA, Thw. 201.
Êta-kirinda-wel, S.

S. Nux-vomica, *L.* 201.

Goda-kaduru, *S. Yetti, Kānchūrai*, *T.*

S. potatorum, *L. f.* 201.

Ingini, *S. Tēttān*, *T.*

511. *Gaertnera Koenigii*, *Wight.* 202.

Péra-tambala, *S.*

var. *thyrsiflora*, *Thw.*

var. *DIVARICATA*, *Clarke. G. divaricata.* 425 (149).

G. ROSEA, *Thw.* 201.

G. WALKERI, *Wight.* 202.

var. *Gardneri*, *Cl. G. Gardneri.* 202.

G. TERNIFOLIA, *Thw.* 202.

87. Gentianaceæ.

512. *EXACUM AXILLARE*, *Thw.* 203.

var. *pentamera*, *Clarke.*

E. WALKERI, *Arn.* Includes *E. zeylanicum*, var. β . 203.

E. ZEYLANICUM, *Roxb.* 203.

Bindara, Kirihiriya, *S.*

var. *macranthum*, *Clarke. E. macranthum.* 203.

E. pedunculatum, *L.* 203.

E. sessile, *L.* 203.

[*E. petiolare*, *Griseb.*]

513. *Hoppea fastigiata*, *Clarke. Pladeria pusilla.* 204.

514. *Enicostema littorale*, *Bl. Slevogtia orientalis.* 204.

Vallarugu, *T.*

515. *Canscora diffusa*, *Brown.* 204.

C. sessiliflora, *R. & S.* 204.

C. decussata, *A. & S.* 204.

C. Wallichii, *Clarke. C. Roxburghii.* 442.

516. *Crawfurdia japonica*, *S. & Z.*, var. *CHAMPIONI*, *Gardn.*
(sp.) *C. fasciculata.* 204.

517. *Gentiana quadrifaria*, *Bl. G. pedicellata.* 204.

518. *SWERTIA ZEYLANICA*, *Gardn. Ophelia.* 205.

[*S. Chirata*, *Ham. Ophelia.* 426.]

519. *Limnanthemum cristatum*, *Griseb.* 205.

L. indicum, *Thw.* 205.

O'lu, Ambala, *S.*

L. aurantiacum, *Dalz. L. biflorum.* 205.

Rēnu-ōlu, *S.*

? *L. FORBESIANUM*, *Griseb.* ("MacRae, 86, 87.")

L. parvifolium, *Griseb.*, var. *Moonii*, *Cl. L. Moonii.* 205.

Bin-ōlu, *S.*

88. Hydrophyllaceæ.

520. *Hydrolea zeylanica*, Vahl. 209.
Diya-kirilla, S.

89. Boragineæ.

521. *Cordia Myxa*, L. *C. Myxa*, var. *minor*. 214.
Lolu, S. *Naruvili*, Vidi, T.
var. *obliqua*, Willd. (sp.) *C. Myxa*. 213
C. monoica, Roxb. *C. diversa*. 214.
C. OBLONGIFOLIA, Thw. 214.
C. Rothii, R. & S.
(*C. salicifolia*, Cham. *C. Roxburghii*, Clarke.)
522. *Ehretia laevis*, Roxb. 214.
var. *canarensis*, Miq. (sp.)
Sira-pulichul, T.
(*E. ovalifolia*, Wight.)
E. buxifolia, Roxb. 214.
Hin-tambala, S.
523. *Coldenia procumbens*, L. 215.
Serappadi, T.
524. *Rhabdia lycioides*, Mart. 214.
525. *Tournefortia argentea*, L. f. 214.
Karon, S.
T. WALKERÆ, Clarke. *T. Wallichii*. 214.
526. *Heliotropium supinum*, L., var. *malabaricum*, Benth. 215.
H. paniculatum, Brown. *H. linifolium*. 215.
H. bracteatum, DC.
var. *laxiflora*, DC. (sp.)
H. marifolium, Retz., var. *Wallichii*, Clarke.
H. scabrum, Retz. ? *H. marifolium*. 215.
H. indicum, L. *Heliophytum*. 215.
527. *Trichodesma indicum*, Brown. 216.
T. zeylanicum, Brown. 216.
528. *Cynoglossum furcatum*, Wall. 215.
Bu-kattu-henda, S.
var. *lanceolatum*, Clarke. *C. micranthum*. 215.
[*C. denticulatum*, A. DC., var. *zeylanicum*, Clarke.]

90. Convolvulaceæ.

529. *Eriocye paniculata*, Roxb. 213.
Ēta-miriya, S.
530. *Rivea ornata*, Chois. 209.

531. *Argyreia tiliaefolia*, *Wight. Rivea*. 209.
Má-bandá, S.
 * *A. speciosa*, *Sweet*. 210.
Maha-dumudu, S.
A. splendens, *Sweet*. 210.
A. POPULIFOLIA, *Chois. Rivea zeylanica*, var. α . 209.
Giri-tilla, S.
 var. *Thwaitesii*, *Clarke*.
 var. *coacta*, (*Clarke*.) *Rivea zeylanica*, var. β . 209.
A. pomacea, *Chois.*, var. *TRIFLORA*, *Cl. A. Leschenaultii*.
 210.
532. *Lettsonia aggregata*, *Roxb.*, var. *osyrensis*, *Clarke. Argyreia*. 210.
L. elliptica, *Wight. Argyreia*. 210.
 [*L. setosa*, *Roxb.*]
L. HANCORNIEFOLIA, *Clarke. Argyreia*. 210.
533. *Ipomoea Bona-nox*, *L.*, var. *grandiflora*, *Roxb. Calonyction speciosum*. 211.
A'langá, S. *Moon-flower*.
 (*I. muricata*, *Jacq.*) *Kalu-álangá*, S. (C. P. 3580.)
I. grandiflora, *Lam.*, (*non Roxb.*) *Calonyction comospermum*. 211.
I. JUCUNDA, *Thw.* 211.
 * *I. coccinea*, *L.*
 * *I. Quamoclit*, *L.*
I. hederacea, *Jacq. Pharbitis Nil*. 210.
I. dissecta, *Willd. (non Pursh) I. coptica*. 212.
I. uniflora, *R. & S. Aniseia*. 212.
Potu-palá, S.
I. digitata, *L. Batatas paniculata*. 210.
Kiri-badu, S.
 (*I. Batatas*, *Lam.*) *Batala*, S. *Sweet Potato*.
I. Choisyana (*Wight.*) *Batatas*. 210.
 * *I. cissoides*, *Chois.* (C. P. 1491.)
I. pileata, *Roxb.* 212.
I. Wightii, *Chois.* 212.
 † *I. bracteata*, *Wight*.
I. Pes-tigridis, *L.* 212.
Divi-adiya, Divi-pahuru, S.
 var. *hepaticifolia*, *L. (sp.)*
I. eriocarpa, *Brown. I. sessiliflora*. 212.
I. angustifolia, *Jacq. I. tridentata*, var. β . 211.

- I. tridentata*, Roth. 211.
Hawari-madu, *Hin-madu*, S.
I. chryseides, Ker. 212.
Kaha-tel-kola, S.
I. reniformis, Chois. 211.
I. obscura, Ker. 212.
Maha-madu, S.
I. GLENIEL, Thw. (in *Fl. B. Ind.*)
I. denticulata, Chois. *I. littoralis*. 211.
I. sepiaria, Koen. 212.
Rasa-tel-kola, S.
 var. *sagittata*, Thw. 212.
I. Beladamboe, R. & S. *I. rugosa*. 211.
Bin-tamburu, S.
I. aquatica, Forsk. *I. reptans*. 211 and C. P. 3941.
Kaṇ-kun, S.
I. staphylina, R. & S.
I. campanulata, L. 211.
I. cymosa, R. & S. 212.
Kiri-madu, S.
 * *I. sidæfolia*, Chois.
I. Turpethum, Brown. 212.
Trasta-wálu, S.
I. biloba, Forsk. *I. Pes-capræ*. 211.
Mudu-bin-tamburu, S.
I. vitifolia, Sweet. 426.
 [*I. centrocaulos*, Clarke.]
 * *I. tuberosa*, L.
I. palmata, Forsk. 212.
 534. *Hewittia bicolor*, Wight. *Shutereia*. 212.
Wal-trasta-wálu, S.
 [*Calystegia hederacea*, Wall.]
 535. *Convolvulus parviflorus*, Vahl.
 536. *Evolvulus alsinoides*, L. 213.
Visnu-kránti, S.
 (*Porana paniculata*, Roxb.)
 537. *Breweria cordata*, Bl. *B. Roxburghii*. 213.
 538. *Cressa cretica*, L., var. *indica*, Retz. (sp.) 213
 539. *Cuscuta reflexa*, L. 213.
Aga-mula-neti-wel, S.
C. chinensis, Lam. 213.

91. Solanaceæ.

540. *Solanum nigrum*, *L.* 216.
Kalu-kan-wériya, *S.* *Mana-takkállí*, *T.*
S. verbascifolium, *L.* 216.
Hëkarilla, *S.*
var. *auriculatum*. *S. auriculatum*. 216.
S. pubescens, *Willd.* 216.
S. bigeminatum, *Nees*, var. *ZEYLANICA*, *Cl.* *S. membranaceum*. 216.
S. denticulatum, *Bl.* 216.
var. *Gonakai*, *Dun.* (sp.)
S. giganteum, *Jacq.* 216.
S. ferox, *L.* 216.
Mala-baṭu, *S.*
S. torvum, *Sw.* 216.
S. indicum, *L.* 217.
Tibbaṭu, *S.*
S. xanthocarpum, *Schrad. & Wendl.* 217.
Ela-baṭu, *S.*
var. *Jacquini*, *Thw.*
Kaṭu-wel-baṭu, *S.*
S. trilobatum, *L.* 217.
Wal-tibbaṭu, *S.*
* *Physalis minima*, *L.* 217.
* *P. angulata*, *L.* 217.
Mottu, *S.*
* *P. peruviana*, *L.* *Cape Gooseberry*.
* *Capsicum fastigiatum*, *Bl.*
Nayi-miris, *S.* *Bird Pepper*.
541. *Withania somnifera*, *Dun.* 217.
Amukkará, *S.* *Amkulang*, *T.*
* *Nicandra physaloides*, *Gaertn.*
542. *Datura fastuosa*, *L.* 217.
Attana, *S.*
var. *Metel*, *L.* (sp.)
* *D. Stramonium*, *L.*
Thorn-apple.
* *D. suaveolens*, *H. B. K.*
Raṭa-attana, *S.*

92. Scrophulariaceæ.

- * *Verbascum Thapsus*, *L.* *Mullein*.
543. *Celsia coromandelina*, *Vahl.* 217.

- * *Calceolaria chelidonioides*, *H. B. & K.*
 [Linaria ramosissima, *Rozb.*]
544. *ADENOSMA SUBREFENS*, *Benth.* *Pterostigma*. 426, & *Lindenbergia urticæfolia*. 218.
A. CAMPHORATUM, *Hk. f.* *Pterostigma villosum*. 218.
Kaha-góna-kola, *S.*
A. capitatum, *Benth.* *Pterostigma*. 218.
Nil-góna-kola, *S.*
545. *Limnophila conferta*, *Benth.* *L. serrata*. 218.
L. laxa, *Benth.*
L. gratissima, *Bl.* *L. punctata*. 218.
L. hirsuta, *Benth.* 218.
L. sessiliflora, *Bl.*
L. heterophylla, *Benth.* *L. sessiliflora* (in part.) 218.
L. racemosa, *Benth.* 218.
L. gratioloides, *Br.* 218.
546. *Herpestis Monniera*, *H. B. & K.*
Lunu-wila, *S.* 218.
H. floribunda, *Br.*
547. *Dopatrium nudicaule*, *Ham.* 218.
D. junceum, *Ham.* 219.
D. lobelioides, *Benth.* 219.
548. *Artanema sesamoides*, *Benth.* 219.
549. *Torenia asiatica*, *L.* 219.
Kotalá-wel, *S.*
 var. *parvifolia*, *Hk. f.*
T. hirtella, *Hk. f.* *T. rubens*. 219.
 var. *glabra*, *Trim. ms.*
550. *Vandellia crustacea*, *Benth.* 219.
V. hirsuta, *Benth.* *V. multiflora*. 219.
V. scabra, *Benth.* 219.
V. pedunculata, *Benth.* 219.
V. angustifolia, *Benth.* 219.
551. *Ilysanthes hyssopioides*, *Benth.* 219.
I. rotundifolia, *Benth.* *I. hyssopioides* (part). 219.
552. *Bonnaya veronicaefolia*, *Spreng.* 219.
Wila, *S.*
B. brachiata, *Link & Otto.* 426.
B. tenuifolia, *Spreng.* 220.
553. *Microcarpæa muscosa*, *Br.* 220.
554. *Peplidium humifusum*, *Del.* 426.
555. ? *Glossostigma spathulatum*, *Arn.*

- * *Scoparia dulcis*, *L.* C. P. 4014.
- * *Veronica polita*, *Fries.*
- [*Buchnera hispida*, *Ham.*] 220.
- 556. *Striga orobanchoides*, *Benth.*
- S. lutea*, *Lour.* *S. hirsuta*. 220.
- S. euphrasioides*, *Benth.* 220.
- 557. *Centranthera procumbens*, *Benth.* *C. Brunoniana*. 220.
- Duğu-satutu*, *S.*
- C. hispida*, *Br.* 220.
- C. humifusa*, *Wall.* 221.
- 558. *Sopubia delphinifolia*, *G. Don.* 220.
- S. trifida*, *Ham.* 220.
- 559. *Pedicularis zeylanica*, *Benth.* 221.

93. Orobanchaceæ.

- 560. *Æginetia indica*, *Roxb.* 221.
- Æ. pedunculata*, *Wall.* *Æ. acaulis*, var. *a.* 221.
- 561. *Campbellia cytinoides*, *Wight.* 427.
- 562. *Christisonia subacaulis*, *Gardn.* *Æginetia acaulis*, var. *β.* 221.
- C. THWAITESII*, *Trim. ms.* *C. unicolor* (in part). 222.
- (C. P. 2971.)
- ? *C. unicolor*, *Gardn.* (C. P. 1780 ?) 222.
- C. bicolor*, *Gardn.* 222.
- var. *PALLIDIFLORA*, *Thw.* 222.
- var. *SPECTABILIS*, *Thw. ms.* (sp.) C. P. 3983.
- C. ALBIDA*, *Thw. (in Fl. Brit. Ind.)* C. P. 3929.
- C. TRICOLOR*, *Gardn.* 222.
- var. *grandiflora*, *Hk. f.* *C. grandiflora*. 221.

94. Lentibulariaceæ.

- 563. *Utricularia stellaris*, *L. f.* C. P. 3960.
- U. flexuosa*, *Vahl.* 171.
- U. exoleta*, *Br.* *U. diantha*. 171.
- U. affinis*, *Wight.* *U. cœrulea*, var. 171.
- U. cœrulea*, *L.* 171.
- U. reticulata*, *L.* 171.
- Nil-monarçessa*, *S.*
- var. *uliginosa*, *Vahl.* var. *stricticaulis*. 171.
- U. bifida*, *L.* 171.
- U. Wallichiana*, *Wight.* *U. capillacea*. 171.
- U. ROSEA*, *Edgew.* *U. racemosa*, var. 172.

- U. racemosa*, *Wall.* 172.
U. orbiculata, *Wall.* 172.

95. Gesneraceæ.

564. *Æschynanthus zeylanicus*, *Gardn.* 206.
 var. pinguis, *Clarke.*
 565. *DIDYMOJARPUS HUMBOLDTIANUS*, *Gardn.* 207.
 var. primulæfolia, *Gardn. (sp.)* 207.
 var. recedens, *Clarke.*
 D. FLOCCOSUS, *Thw.* 207.
 D. ZEYLANICUS, *Br.* 207.
 566. *CHIRITA MOONII*, *Gardn.* 207.
 C. WALKERI, *Gardn.* 207.
 var. parviflora, *Clarke.* *Var. β.* 207.
 C. ZEYLANICA, *Hook.* 208.
 var. angusta, *Clarke.* *Var. β.* 208.
 567. *CHAMPIONIA RETICULATA*, *Gardn.* 20.
 568. *Klugia Notoniana*, *A. DC.* 208.
 Diyanilla, *S.*
 var. GLABRA, *Gardn. (sp.)*
 K. ZEYLANICA, *Gardn.* 208.
 [*Rhynchoglossum obliquum*, *Bl.*]
 569. *Epithema carnosum*, *Benth.*, *var. ZEYLANICUM*, *Gardn. (sp.)*
 208.
 var. hispidum, *Clarke.*
 570. *Isanthera permollis*, *Nees.* 208.

96. Bignoniaceæ.

- (*Millingtonia hortensis*, *L. f.*) *Indian Cork Tree.*
 571. *Oroxylum indicum*, *Vent.* *Calosanthès indica.* 206.
 Totila, *S.* *Achi*, *T.*
 572. *Dolichandrone Rheedii*, *Seem.* *Spathodea.* 206.
 Diya-dangá, *S.*
 ? *D. crispa*, *Seem.* ("Koenig.")
 573. *Stereospermum chelonoides*, *DC.* 206.
 Lunu-madálá, *S.* *Pátiri*, *T.*
 (*S. suaveolens*, *DC.*) 206.

97. Pedaliaceæ.

- * *Martynia diandra*, *Glox.*
 Náka-táfi, *T.*
 574. *Pedaliium Murex*, *L.* 209.
 Et-nerenchi, *S.*

- * *Sesamum indicum*, DC. 209.

Tel-tala, S. *Elļu*, T. *Gingely*.

var. *occidentale*, Heer & Reg. (sp.) 442.

98. Acanthaceæ.

575. *Thunbergia fragrans*, Roxb. 224.
var. *vestita*, Nees.
* *T. alata*, Roj.
(*T. Hawtayneana*, Wall.) 224.
(*T. coccinea*, Wall.) 223.
576. *Elytraria crenata*, Vahl. 224.
var. *lyrata*, Nees.
577. *Nelsonia campestris*, Br. *N. tomentosa*. 224.
578. *Ebermaiera zeylanica*, Nees. *E. glauca*. 224.
579. *Cardanthera uliginosa*, Ham.
C. balsamica, Benth. *Adenosma*. 224.
C. verticillata, Benth. *Adenosma*. 224.
C. THWAITESII, Benth. *Adenosma*. 224.
580. *Hygrophila salicifolia*, Nees. *H. quadrivalvis*, var. 225.
H. quadrivalvis, Nees. 225.
H. spinosa, T. And. 225.
Kaṭu-ikiri, S. *Neer-muḷli*, T.
581. *Calophanes Nagchana*, Nees. *C. depressa*. 225.
C. littoralis, T. And. 225.
582. *Ruellia ringens*, L., var. *dejecta*, Clarke. *R. prostrata*. 225.
R. patula, Jacq. 225.
[*R. repens*, L.]
583. *Phayloopsis parviflora*, Willd. *Ætheilema reniforme*. 225.
584. *Dædalacanthus montanus*, T. And. 229.
[*Hemigraphis flava*, Kurz.] *Strobilanthes scaber*. 227.
585. *Stenosiphonium Russellianum*, Nees. 226.
var. *subsericeum*, Nees. (sp.) C. P. 3876.
Bū-nelu, S.
586. *STROBILANTHES VISCOSUS*, T. And. 226.
Nelu, S. (applied to the whole genus.)
S. STENODON, Clarke. C. P. 3874.
S. EXAREOLATUS, Clarke. *S. consanguineus*. 226.
S. RHYTISPERMUS, Clarke. *S. hypoleucus*. 226.
S. NIGRESCENS, T. And. 226.
S. RHAMNIFOLIUS, T. And. 226.
S. DEFLEXUS, T. And. 227.
S. LANCEOLATUS, Hook. *S. adenophorus*. 223.

- S. WALKERI*, *Nees*. 227.
 var. stenocarpus, *Clarke*. (C. P. 3517.)
S. THWAITESII, *T. And.* 227.
S. caudatus, *T. And.* 228.
 var. LANICEPS, *Clarke*.
S. anceps, *Nees*. 229.
S. PUNCTATUS, *Nees*. *S. anceps*, *var.* 228. C. P. 3998.
S. ARNOTTIANUS, *Nees*. 228.
S. ASPERRIMUS, *Nees*. *S. trifidus* (part). 228.
S. TRIFIDUS, *Nees*. 228.
S. EXSERTUS, *Clarke*. *Stenosiphonium zeylanicum*. 225.
 var. integer, *Clarke*. *Var. β.* 226.
S. GARDNERIANUS, *T. And.* 226.
S. VESTITUS, *Nees*. 228.
S. HOOKERI, *Nees*. 227.
S. CALYCINUS, *T. And.* 227.
 var. parvifolius, *Clarke*.
S. LAXUS, *T. And.* 228.
S. ZEYLANICUS, *T. And.* 227.
S. SEXENNIS, *Nees*. *S. cerinthoides*. 229.
 var. HIRSUTISSIMUS, *T. And.* 229.
S. HELICOIDES, *T. And.* 229.
S. PANICULATUS, *T. And.* *S. rubicundus*. 229.
S. PULCHERRIMUS, *T. And.* 229.
587. *Blepharis boerhaaviæfolia*, *Pers.* 231.
 B. molluginifolia, *Pers.* 231.
 Sámadána, *S.*
588. *Acanthus ilicifolius*, *L.* 232.
 Ikili, *Kaṭu-ikili*, *S.*
 var. integrifolius, *T. And.* 232.
589. *Barleria Prionitis*, *L.* 230.
 Kaṭu-karandu, *S.*
 [*B. buxifolia*, *L.*]
 B. mysorensis, *Roth.* *B. bispinosa*. 230.
 B. noctiflora *L. f.* ("Rottler.")
 B. involucrata, *Nees*. *B. pentandra* (part). 230.
 B. VESTITA, *T. And.* 230.
 B. ARNOTTIANA, *Nees*. 230.
 var. pentandra, *Arn. (sp.)* *B. pentandra* (part). 230.
 (*B. cristata*, *L. (non Lam.)*) 230.
 B. NUTANS, *Nees*. 230.
 B. nitida, *Nees*. 443.
590. *Crossandra undulæfolia*, *Salisb.* *C. infundibuliformis*. 231.
 var. axillaris, *Nees. (sp.)*

591. *Asystasia coromandeliana*, *Nees* (*non Wight.*) *A. gangetica*. 235.
Puruk, S.
A. chelonoides, *Nees*. 236.
A. quadrangularis, (*Heyne in Fl. Brit. Ind.*) *A. chelonoides* (part). C. P. 552.
592. *Eranthemum malabaricum*, *Clarke*. *E. crenulatum*. 235.
593. *Andrographis paniculata*, *Nees*. 232.
Hin-bin-kohomba, S. *Nila-vémpu*, T.
A. alata, *Nees*. 232.
A. macrobotrys, *Nees*. 232.
var. *PARVIFOLIA*, *Clarke*. *A. zeylanica*. 232.
A. echinoides, *Nees*. 232.
594. *GYMNOSTACHYUM ZEYLANICUM*, *Arn. & Nees*. 232.
G. THWAITESII, *T. And.* 232.
G. PANICULATUM, *T. And.* 232.
G. SANGUINOLENTUM, *T. And.* 232.
G. HIRSUTUM, *T. And.* 233.
595. *Lepidagathis hyalina*, *Nees*, var. *LOPHOSTACHYOIDES*, *Nees*. 231.
L. fasciculata, *Nees*. 231.
L. ZEYLANICA, *Nees*. 231.
L. WALKERIANA, *Nees*. 231.
596. *Monotheceum aristatum*, *T. And.* 234.
597. *Justicia Betonica*, *L.* 233.
Sudu-puruk, S.
J. ZEYLANICA, *T. And.* 233. (C. P. 2718 = 2422 part, C. P. 713 part.)
var. *viridescens*.
var. *capitata*, *T. And.* C. P. 3919.
J. tranquebarensis, *L. f.* 233.
* *J. Gendurussa*, *L. f.* 233.
Kalos-wáraníya, S.
J. HOOKERIANA, *T. And.* 233.
J. glabra, *Koen.* 234. (C. P. 3110 = 2422 part, C. P. 3663 = 713 part.)
? *J. Monetiana*, *Vahl*.
J. ROYENIANA, *Clarke*. *Rostellularia*. 234.
J. diffusa, *Willd.* *Rostellularia*. 234.
J. procumbens, *L.* *R. Royeniana* (part). 234.
Mani, S.

598. *Adhatoda Vasica*, *Nees*. *Justicia adhatoda*. 233.
Agaládára, S. *A'dátódai*, T.
599. *Rhinacanthus communis*, *Nees*. 234.
Anitta, S.
 ? *Dianthera dichotoma*, *Clarke*. ("C. P. 2718.")
600. *PTYSSIGLOTTIS RADICOSA*, *T. And.* 235.
601. *Ecboium Linneanum*, *Kurz*. *Eranthemum Ecboium*. 235.
 var. *laevirens*, *Vahl*. (sp.)
 (*Graptophyllum hortense*, *Nees*.)
602. *Rungia longifolia*, *Nees*. 235.
Sulu-neyi, S.
R. apiculata, *Bedd.* *R. repens* (part). (C. P. 1973.)
R. repens, *Nees*. 235.
R. parviflora, *Nees*. 234.
 var. *pectinata*.
603. *Dicliptera zeylanica*, *Nees*. *D. biralvis*. 235.
604. *Peristrophe tinctoria*, *Nees*. ("Walker.") 234.
 ? *P. montana*, *Nees*.

99. Verbenaceæ.

605. *Lantana alba*, *Mill.* 242.
 * *L. trifolia*, *L.* 242.
 * *L. mixta*, *L.* (*L. Camara*, *L.*) 242.
Ganda-pána, *Rata-hinguru*, S. *Lantana*.
606. *Lippia nodiflora*, *Rich.*
Heri-mena-detta, S.
607. *Bouchea hyderabadensis*, *Walp.* 241.
608. † *Stachytarpheta indica*, *Vahl*. 241.
Balu-nakuṭa, S.
 var. * *jamaicensis*, *Vahl*. (sp.)
 (*S. mutabilis*, *Vahl*.)
609. *Priva leptostachya*, *Juss.*
610. *Callicarpa lanata*, *L.* *C. Wallichiana*. 243.
Illa, S.
 (*Tectona grandis*, *L.*) *Tekka*, S. *Tekku*, T. *Teak*.
611. *PREMNA PURPURASCENS*, *Thw.* 242.
P. serratifolia, *L.* 242.
Midi, S.
P. latifolia, *Roxb.* 242.
Mahamidi, S.
P. micrantha, *Schau.* 242.
P. tomentosa, *Willd.* 243.
Bu-séru, S. *Thain*. *Kolkutti*. T.

- P. PROCUMBENS, *Wall.* 243.
Lí-kola-palá, S.
- P. cordifolia, *Roxb.* 243.
612. Gmelina asiatica, *L.* 244.
Demata, S. *Kumil*, T.
G. arborea, *Roxb.* *G. Rheedii*. 244.
Et-demata, S. *Kumil*, T.
613. Vitex trifolia, *L.* 244.
Nochi, *Neer-nochi*, T.
V. Negundo, *L.* 244.
Nil-nika, *Sudu-nika*, S. *Nochi*, *Vellai-nochi*, T.
V. altissima, *L. f.* 244.
Milila, *Milla*, *Sapu-milila*, S. *Kata-manaku*,
Mailai, T.
var. zeylanica, *Turez.* (sp.)
V. pubescens, *Vahl.* 244. ("Walker, 1122.")
V. Leucoxydon, *L. f.* 244.
Nebēdda, S. *Minachi*, T.
614. Clerodendrum inerme, *Br.* 243.
Wal-gurenda, S. *Pinári*, T.
C. phlomoides, *L.* 243.
Wadamadichi, T.
C. serratum, *Spreng.* 243.
Keṅ-heṇda, S. *Vátham addakki*, T.
C. infortunatum, *L.* 243.
Gas-pinna, S.
(*C. Siphonanthus*, *Br.*) 243.
615. GLOSSOCARYA SCANDENS, (*L. f.*) *Clerodendron Linnæi*.
243.
616. Symphorema involucratum, *Roxb.* 242.
617. Avicennia officinalis, *L.* 244.

100. Labiatae.

618. Ocimum canum, *Sims.* 236.
Hin-talá, S.
* *O. basilicum*, *L.* 236.
O. gratissimum, *L.* 236.
O. suave, *Willd.* 236.
O. sanctum, *L.* 236.
Maduru-talá, S.
O. adscendens, *Willd.* C. P. 3999.
619. GENIOSPORUM ELONGATUM, *Benth.* 236.
G. prostratum, *Benth.* 237.
var. gracile, *Thw.* 237.

620. *Moschosma polystachyum*, *Benth.* 237.
621. *Orthosiphon diffusus*, *Benth.* 237.
O. glabratus, *Benth.* 237.
622. *PLECTRANTHUS CAPILLIPES*, *Benth.* 237.
P. nigrescens, *Benth.* 237.
var. *WALKERI*, *Arn.* (sp.) (C. P. 90.)
P. Coetsa, *Don.* 237.
P. subincisus, *Benth.* 237.
P. GARDNERI, *Thw.* 237.
P. ZEYLANICUS, *Benth.* 238.
Iri-wériya, *S.*
(*P. tuberosus*, *Bl.*) *Innala*, *S.* (C. P. 2068.)
623. *Coleus barbatus*, *Benth.* 238.
(*C. aromaticus*, *Benth.*) *Kappra-walliya*, *S.* C. P. 3971.
C. malabaricus, *Benth.* 238.
var. *LEPTOSTACHYS*, *Benth.* (sp.) (C. P. 17.)
C. INFLATUS, *Benth.* 238.
C. Wightii, *Benth.* C. P. 3942.
624. *Anisochilus carnosus*, *Wall.* 238.
Gal-kappra-walliya, *S.*
A. PANICULATUS, *Benth.* 238.
A. suffruticosus, *Wight.* 238.
625. *Pogostemon Heyneanus*, *Benth.* 239.
Gaṇ-kollaṇ-kola, *S.*
P. RUPESTRIS, *Benth.* 239.
var. *hirsutus*, *Thw.* 239.
P. REFLEXUS, *Benth.* 239.
626. *Dysophylla auricularia*, *Bl.* 239.
Hēmanilla, *S.*
D. verticillata, *Benth.* 239.
627. *Mentha javanica*, *Bl.* *M. arvensis.* 239.
Odu-tulan. *S.*
* *M. sylvestris*, *L.*, var. *crispa*, *Benth.* (C. P. 2891.)
628. *Calamintha umbrosa*, *Benth.* *C. Clinopodium*, var. 239.
629. *Scutellaria violacea*, *Heyne.* 239.
var. *glabra*, *Trim.* Var. β . 240.
var. *floribunda*, *Benth.* (sp.) Var. γ . 240.
S. SPICATA, *Trim. ms.*
S. OBLONGA, *Benth.* 240.
630. *Anisomeles ovata*, *Br.* 240.
Yak-wanassa, *S.* *Pémarutti*, *T.*
A. malabarica, *Br.* 240.
Retai-pémarutti, *T.*

* *Stachys arvensis*, L.

631. *Leucas mollissima*, Wall. 240.

L. marrubioides, Desf. 240.

Sudu-tumba, S.

[*L. pubescens*, Benth.] 240.

L. procumbens, Desf. 240.

L. zeylanica, Br. 240.

Geta-tumba, S.

632. *Leonotis nepetæfolia*, Br. 241.

Maha Yak-wanassa, S.

633. *Teucrium tomentosum*, Heyne. 241.

101. Plantagineæ.

634. *Plantago asiatica*, L. *P. major*. 245.

* *P. lanceolata*, L. (C. P. 2247.) 245.

APETALÆ.

102. Nyctagineæ.

* *Mirabilis Jalapa*, L. *Sendrika*, S. *Marvel of Peru*.

635. *Boerhaavia diffusa*, L. 245.

Piṭa-sudu-palá, S. *Mukkarati*, T.

B. repanda, Willd.

636. *Pisonia aculeata*, 245.

103. Amarantaceæ.

637. *Celosia polygonoides*, Retz. 247.

C. pulchella, Moq. 247.

C. argentea, L. 247.

Kiri-henda, S.

638. *Allmania nodiflora*, Br. *Chamissoa*. 247.

Kumatiya, *Weni-wella*, S.

639. *Digera arvensis*, Forsk. 249.

640. (*Amarantus caudatus*, L.) 247. *Love-lies-bleeding*.

(*A. hypochondriacus*, L. 247. *Prince's Feather*.)

* *A. paniculatus*, L. *A. frumentaceus*. 247.

Rana-tam-palá, S.

A. spinosus, L. 247.

Katu-tam-palá, S.

* *A. gangeticus*, L. *A. oleraceus*. 247.

Sudu-tam-palá, S.

var. *melancholicus*, L. (sp.)

- A. polygamus*, *L.* 247.
Walu-tam-palá, *S.*
- A. polygonoides*, *L. Euxolus*. 248.
Kúra-tam-palá, *S.*
- A. gracilis*, *Desf. Euxolus caudatus*. 248.
641. *Cyathula geniculata*, *Lour. C. prostrata*. 249.
Bin-karal-heba, *S.*
- C. capitata*, *Moq.* 249.
642. *Pupalia atropurpurea*, *Moq.* 249.
P. orbiculata, *Wight.* 249.
643. *PSILOTRICHUM SCLERANTHUM*, *Thu.* 248.
P. ovatum, *Moq. Ptilotus*. 248.
644. *Nothosærua brachiata*, *Wight.* 248.
Tampalá, *S.*
645. *Ærua javanica*, *Juss.* 248.
Æ. lanata, *Juss.* 248.
Pol-kudu-palá, *S.*
- Æ. Monsonia*, *Moq.* 248. (C. P. 3324.)
646. *Achyranthes bidentata*, *Bl.* 249.
A. aspera, *L.* 249.
Gas-karal heba, *S.*
var. *argentea. A. argentea.* 249.
- A. diandra*, *Roxb. Centrostachys.* 249.
647. *Alternanthera triandra*, *Lam. A. sessilis.* 250.
Muku-nu-wenna, *S.*

104. Chenopodiaceæ.

648. *Chenopodium murale*, *L.* 246.
* *C. opulifolium*, *Schrad.*
* *C. ambrosioides*, *L.*
649. *Atriplex repens*, *Roth.* 246.
650. *Arthrocnemum indicum*, *Moq.* 246.
651. *Salicornia brachiata*, *Roxb.* 443.
652. *Suaeda nudiflora*, *Moq.* 246.
S. indica, *Moq.* 246.
S. maritima, *Dum.*
653. *Basella alba*, *L.*
Niviti, *S. Pachalai*, *T.*
var. *rubra*, *L. (sp.)*

Phytolaccaceæ.

- * *Rivina humilis*, *L. R. lævis.* 250. (C. P. 1899.)

- * *Mohlana nemoralis*, *Mart.*
(*Phytolacca octandra*, *Moq.*)

105. Polygonaceæ.

654. *Polygonum barbatum*, *L.* 245.
 Ratu-kimbulwenna, *S.*
P. minus, *Huds.* *P. Posumbu.* 245.
P. serrulatum, *Lag.* 245.
P. glabrum, *Willd.* 245.
P. tomentosum, *Willd.* 246.
 Sudu-kimbulwenna, *S.*
P. perforatum, *Meisn.* 246.
P. chinense, *L.* 246.
P. strigosum, *R. Br.* 246.
 var. *horridum*, *Roxb.* (sp.) *P. pedunculare.* 246.
* *Rumex obtusifolius*, *L.*
* *R. Acetosella*, *L.*

106. Podostemaceæ.

655. *TERNIOLA ZEYLANICA*, *Tul. Dalzellia.* 223.
656. *Podostemon olivaceum*, *Gardn. Hydrobryum.* 223.
 P. SUBULATUM, *Gardn.* 222.
 P. GARDNERI, *Harv.* 223.
 P. ELONGATUM, *Gardn. Dicræa.* 222.
 P. algæforme, (*Bedd.*)

107. Nepenthaceæ.

657. *NEPENTHES DISTILLATORIA*, *L.* 290.
 Bándurá-wel, *S.*

108. Aristolochiaceæ.

658. *Bragantia Wallichii*, *Br.* 291.
 var. *latifolia*, *Duch.*
659. *Aristolochia bracteata*, *Retz.* 291.
 A'du-thinnápálé, *T.*
A. indica, *L.* 291.
 Sap-sanda, *S. Perumurundu*, *T.*
 [*A. Thwaitesii*, *Hook.*]

109. Piperaceæ.

660. * *Piper Chawya*, *Ham. Chavica Churya.* 428 and 292.
 Siwiya-wel, *S.*
P. longum, *L. Chavica Roxburghii.* 292.
 Tippili, *S. & T.*

- P. THWAITESII*, *Cas. DC.* *P. arcuatum* (part. C. P. 2178.) 293.
P. arborescens, *Roxb.* (C. P. 2461.) 293.
 (P. Betle, *L.*) *Chavica*. 292.
Bulat-wel, *S.*
 var. *Siriboa*, *L.* (sp.) *Chavica Siriboa*. 292.
Siribó, *Raṭa-bulat-wel*, *S.*
 ? var. *Malamiris*, *L.* (sp.)
P. arcuatum, *Bl.* (C. P. 2177.) 293.
P. sylvestre, *Lam.* 293.
Wal-gammiris-wel, *Malamiris-wel*, *S.*
P. INSULARE, *Cas. DC.* *P. trineuron*. 293.
 var. *laxiflorum*, *Trim. ms.* (*P. zeylanicum*, *Cas. DC.* non *Miq.*) *Muldera diandra*. 428.
P. TRINEURON, *Miq.* ("Walker.")
P. bantamense, *Bl.* *P. arborescens* (part. C. P. 35.) 293.
P. WALKERI, *Miq.* ("Walker.")
P. nigrum, *L.* 292.
Gammiris-wel, *S.* *Milagu*, *T.* *Black Pepper*.
 var. *trioicum*, *Cas. DC.*
P. ARGYROPHYLLUM, *Miq.* 293.
P. ZEYLANICUM, *Miq.* (non *Cas. DC.*) ("Walker, No. 31.")
P. subpeltatum, *Willd.* *Pothomorphe*. 292.
Mala-labu, *S.*
661. * *Peperomia Fraseri*, *Cas. DC.*
P. Wightiana, *Miq.* C. P. 3954.
P. PSEUDO-RHOMBEEA, *Cas. DC.* *P. courtallensis*, var. 292.
P. THWAITESII, *Cas. DC.* *P. Heyneana*. 292.
P. reflexa, *A. Dietr.* 292.
P. ZEYLANICA, *Miq.* ("Walker, No. 1904.")
P. COURTALLENSIS, *Miq.* 292.

110. Chloranthaceæ.

662. *Chloranthus brachystachys*, *Bl.* 293.

111. Myristicaceæ.

663. *MYRISTICA LAURIFOLIA*, *Hk. f. & Th.* 11.
Malaboda, *S.*
 var. *zeylanica*, *Thw.* 11 & 399.
M. HORSFIELDIA, *Bl.* 11.
Ruk, *S.*
M. Irya, *Gaertn.* 11.
Priya, *S.*

112. Monimiaceæ.

664. HORTONIA FLORIBUNDA,
- Wight*
- . 11.

Wáwiya, S.var. *ovalifolia*, *Thw.* 12.*H. ANGUSTIFOLIA*, *Thw.* (var.) 12.

113. Lauraceæ.

665. Cryptocarya Wightiana.
- Thw.*
- 254.

Gal-mora, S. (of low-country) *More*, *Kaddu-more*, T.*C. MEMBRANACEA*, *Thw.* 254.

666. BEILSCHMIEDIA ZEYLANICA.
- Apollonias*
- . 253.

667. Cinnamomum zeylanicum,
- Bl.*
- 252 and C. P. 4000.

Kurundu, S. *Karrurá*, T. *Cinnamon*.* var. *vulgare*, *Hayne*. (C. P. 2285.)var. *MULTIFLORUM*, *Thw.* (part.) 252.var. *iners*, *Reinw.* (sp.) Var. *multiflorum* (part.) 252.*C. LITSEÆFOLIUM*, *Thw.* 253.*C. CITRIODORUM*, *Thw.* 253.*Pengiri-kurundu*, S.*C. OVALIFOLIUM*, *Wight*. *C. zeylanicum*, var. 252.

668. Machilus glaucescens,
- Wight*
- , var. ZEYLANICA,
- Meissn.*

M. macrantha. 254.*Ululu*, S.

669. Persea semecarpifolia (
- Nees*
-), var. ANGUSTIFOLIA,
- Meissn.*

Alseodaphne. 254.*Wéwarani*, S. *Yávaranai*, *Ranai*, T.

670. ACTINODAPHNE MOLOCHINA,
- Nees*
- . 257.

var. *glabresceus*, *Meissn.* *A. Moonii*. 256.*A. STENOPHYLLA*, *Thw.* (C. P. 2491.) 256.*A. THWAITESII*, *Meissn.* (C. P. 304.) *A. stenophylla* (part.) 256.*A. ELEGANS*, *Thw.* 256.[*A. salicina*, *Meissn.*]*A. GLAUCA*, *Nees*. 256.var. *Walkeri*, *Meissn.*[*A. Hookeri*, *Meissn.*][*A. lanata*, *Meissn.*]*A. SPECIOSA*, *Nees*. 257.*A. CANDOLLEANA*, *Meissn.* *A. speciosa*, var. 256.

671. Litsea tomentosa,
- Heyne*
- .
- Tctranthera*
- . 254.

Kos-bada. S.

- L. sebifera*, Pers., var. *Roxburghii*, Meissn. *Tetranthera Roxburghii*. 255.
Bó-mi, S. *Elumburiki*, T.
 var. *SALIGNA*, Meissn.
- L. ligustrina* (Nees), var. *celastroides*, Meissn. *Tetranthera*. 254.
- L. læta*. (Wall.), var. *GLAUCA*, Meissn. *Tetranthera longifolia* (part). 255.
- L. GLABERRIMA*, (Thw.) 255. *Tetranthera*. 255.
 var. *chartacea*, Meissn. *Tetr. longifolia*, var. 255.
- L. longifolia*. (Nees). (C. P. 223.) 255.
Rat-kéliya, S.
- L. NEMORALIS*, (Thw.) (Includes *T. Hookeriana*, Meissn.)
Tetranthera. 255.
- L. FUSCATA*, Thw. 258.
- L. ORBICULARIS*, Thw. 258.
- L. ZEYLANICA*, Nees. 257.
Dawul-kurundu, *Kudu-dawulu*, S.
 var. *VENOSA*, Meissn. (C. P. 2278.)
 var. *rubrinervia*, Meissn. (C. P. 3449.)
- L. AMBIGUA*, Meissn. (C. P. 72, 2280.) *L. zeylanica*,
 var. 257.
- L. GARDNERI*, (Thw.) (Includes *Tetr. zeylanica*,
 Meissn.) 255.
 var. *rigida*, Meissn. (sp.)
- L. OVALIFOLIA*, (Wight.) 256.
 var. *parvifolia*, Meissn. *Tetr. Iteodaphne*, vars.
 255, 6.
 var. *angustata*, Meissn. *Tetr. Iteodaphne*. 255.
 ? *L. WALKERI* (Meissn.) ("Walker, No. 1382.")
672. *LINDERA LANCIFOLIA*, (Thw.) *Daphnidium*. 257.
673. *Cassytha filiformis*, L. 258.
C. capillaris, Meissn. C. P. 3982.
674. *Hernandia peltata*, Meissn. *H. Sonera*. 258.
Palutu, S.

114. Proteaceæ.

675. *HELICIA ZEYLANICA*, Gardn. 250.

115. Thymelæaceæ.

676. *Wikstrœmia virgata*, Meissn. 250.
677. *Lasiosiphon eriocephalus*, Decne. 250.
Naha, S.
 var. *INSULARIS*, Meissn. (sp.) 251.

678. PHALERIA CAULIFLORA, (*Thw.*) *Drymispermum*. 251.

679. GYRINOPS WALLA, *Gaertn.* 251.

Wallá, Pattá-wallá, S.

116. Elæagnaceæ.

680. Elæagnus latifolia, *L.* 252.

Wel-embilla, Kaṭu-embilla, S.

var. *Thwaitesii, Schlecht. (sp.) (C. P. 2724.)*

117. Loranthaceæ.

681. LORANTHUS NODIFLORUS, *Thw.* 134.

L. Hookerianus, W. & A. 134.

L. buiddæoides, Desv. 136.

L. tomentosus, Heyne. 135.

var. *lanuginosus, Thw.*

L. neilgherrensis, W. & A. 134.

L. cuneatus, Heyne. 135.

L. SCLEROPHYLLUS, Thw. 135.

L. longiflorus, Desv. 134.

Pilila, S. (Applied to whole genus.)

var. *amplexifolius, Thw.* 134.

L. LONCHIPHYLLUS, Thw. 418.

L. ENSIFOLIUS, Thw. 134.

L. SUBORBICULARIS, Thw. 134.

L. LIGULATUS, Thw. 135.

L. GARDNERI, Thw. 133.

L. loniceroides, L. 133.

L. capitellatus, W. & A. 133.

682. Viscum orientale, *Willd.* 136.

V. capitellatum, Sm. 136.

V. attenuatum, DC. 136.

V. moniliforme, Bl. 136.

683. NOTOTHIXOS FLOCCOSUS, *Oliv. Viscum.* 418.

684. GINALLOA SPATHULIFOLIA, *Oliv. Viscum.* 136.

118. Santalaceæ.

(*Santalum album, L.*) (C. P. 2915.)

685. *Osyris arborea, Wall.* 251.

686. *Scleropyron Wallichianum, Arn. Pyrularia.* 251.

Kaṭu-pamburu, S. Iddu-mullai, T.

119. Balanophoraceæ.

687. *Balanophora indica, Wall.* 293.

B. THWAITESII, Eichl. B. indica (part). 293.

120. Euphorbiaceæ.

688. *Euphorbia Atoto*, *Forst.* 427.
E. fimbriata, *Roth.* 269.
E. parviflora, *L.* *E. hypericifolia.* 268.
Ela-dadakiriya, *S.*
E. hirta, *L.* *E. pilulifera.* 269.
Bü-dada-kiriya. *S.*
E. Chamæsyce. *L.?* 269.
E. thymifolia, *L.* *E. Burmanniana.* 269.
Biṅ-dada-kiriya, *S.*
E. rosea, *Retz.* 269.
Múdu-dada-kiriya, *S.*
(*E. neriifolia*, *L.*) *Patuk*, *S.*
E. antiquorum, *L.* 268.
Daluk, *S.*
E. tortilis, *Rottl.* 268.
Sinuk, *S.* *Tirtu-kalḥi*, *T.*
* *E. Tirucalli*, *L.* 268.
Nawa-handi, *S.* *Kullḥi*, *Kalḥi*, *T.* *Milk-hedge.*
E. oreophila, *Miq.* *E. Rothiana.* 269.
689. *Sarcococca pruniformis*, *Lindl.* 290.
var. *ZEYLANICA*, *Baill.* (sp.)
690. *Bridelia retusa*, *Spreng.* 279.
Keṭa-kála, *S.* *Mullu-venké*, *T.*
B. MOONII, *Thw.* 279.
Pat-kála, *S.*
B. scandens, *Willd.* *C. P.* 3932.
691. *CLEISTANTHUS ROBUSTUS*, *Mull. Arg.* *Amanoa indica.*
428.
C. patulus, *Mull. Arg.* *A. acuminata* (in part) & *A. indica* f. *minor.* 428.
C. ACUMINATUS, *Mull. Arg.* *Amanoa.* 428.
C. FERRUGINEUS, *Mull. Arg.* *Amanoa.* 280.
C. PALLIDUS, *Mull. Arg.* *Amanoa.* 280.
var. *subglaucus*, *Thw. ms.* (sp.) *C. P.* 3981.
C. collina, (*Roxb.*) *Amanoa.* 280.
Madará, *S.*
692. *ACTEPHILA ZEYLANICA*, *Mull. Arg.* *A. neilgherrensis.*
280.
693. *Agyneia bacciformis*, *A. Juss.* 283.
Ēt-pitawakká, *S.*
694. *Sauropus albicans*, *Bl.* *S. Gardnerianus.* 284.

- S. RETROVERSUS, *Wight.* 284.
 S. ASSIMILIS, *Thw.* 284.
 S. RIGIDUS, *Thw.* 284.
 695. *Phyllanthus zeylanicus*, *Mull. Arg. Glochidion.* 285.
 Hunu-kirilla, S.
 var. *tomentosus*. Var. β . 285.
 P. BRACHYLOBES, *Mull. Arg. Gloch. coriaceum* (part).
 (C. P. 3016.) 285.
 P. CORIACEUS, *Mull. Arg. Glochidion* (part). (C.P. 342.)
 285.
 P. PYCNOCARPUS, *Mull. Arg. Gl. coriaceum* (part.) (C.P.
 2529.) 285.
 P. stellatus, *Retz. Gloch. Jussieuianum.* 285.
 P. SYMPLOCOIDES, *Mull. Arg. Gloch. montanum.* 286.
 P. LEPTOGYNUS, *Mull. Arg. Gloch. Gardneri.* 286.
 P. NEMORALIS, *Mull. Arg. Glochidion.* 286.
 P. PUBESCENS, *Moon. Gloch. Moonii.* 286.
 Bú-hunu-kirilla, S.
 var. *glaucogynus*. *Mull. Arg. (sp.)* (C. P. 2150.)
 var. *subglabra*. (C. P. 68.)
 P. reticulatus, *Poir. Kirganelia multiflora.* 282.
 Wēl-kayila, S.
 var. *glaber*, *Thw. (part.)* 282.
 P. microcarpus, *Mull. Arg. K. multiflora*, var. *glaber*
 (part). 282.
 P. THWAITESIANUS, *Mull. Arg. P. flexuosus.* 281.
 P. Emblica, *L.* 282.
 Nelli, S. *Tópu-nelli.* T.
 P. INDICUS, *Mull. Arg. Prosorus.* 281.
 Karawu, S.
 P. cyanospermus, *Mull. Arg. Prosorus.* 281.
 Sudu-liyañ, S.
 P. polyphyllus, *Willd.* 282.
 P. EMBLICOIDES, *Mull. Arg. ? P. polyphyllus* (part.) 282.
 P. maderaspatensis, *L.* 282.
 P. Rheedii, *Wight. P. flaccidus.* 283.
 P. urinaria, *L.* 282.
 Rat-pitawakká, S.
 P. simplex, *Retz.* 282.
 var. *Gardnerianus*. *Mull. Arg. P. Gardneri.* 282.

- P. MYRTIFOLIUS, *Moon.* 283.
 P. rotundifolius, *Klein.* 282.
 P. Niruri, *L.* 282.
 Pīṭa-wakká, S.
 P. OREOPHILUS, *Mull. Arg. Epistylum polyphyllum*
 var. 428.
 P. ANABAPTIZATUS, *Mull. Arg. Epistylum polyphyllum.*
 283.
 P. Baillonianus, *Mull. Arg. Epistylum latifolium.* 283.
 P. CINEBEUS, *Mull. Arg. Epistylum floribundum* (part),
 & C. P. 3872.
 P. AFFINIS, *Mull. Arg. Epistylum floribundum* (part).
 283.
 P. HARGALENSIS, *Thw. ms. C. P. 4015.*
 696. Fluggea Leucopyrus, *Willd.* 281.
 Hin-kaṭu-pīla, S.
 697. Breynia rhamnoides, *Mull. Arg. Melanthesa.* 285.
 Gas-kayīla, S.
 B. patens, (*Roxb.*) *Melanthesa turbinata.* 285.
 Wal-murungá, S.
 698. Putranjiva Roxburghii, *Wall.* 287.
 Kirri-pálai, T.
 P. ZEYLANICA, *Mull. Arg. Palenga.* 287.
 Pelaz, S.
 699. Hemicyclia sepiaria, *W. & A.* 287.
 Wira, S. *Véré*, T.
 H. GARDNERI, *Thw.* 287.
 H. LANCEOLATA, *Thw.* 287.
 700. Cyclostemon macrophyllus, *Bl. C. zeylanicus.* 286.
 701. MISCHODON ZEYLANICUS, *Thw.* 275.
 Tammanná, S. & T.
 702. APOROSA LATIFOLIA, *Thw.* 288.
 Pepiliya, Má-pat-kebella, Kampottá, S.
 A. FUSIFORMIS, *Thw.* 288.
 A. Lindleyana, *Baill.* 288.
 Kebella, S.
 A. ACUMINATA, *Thw.* 288.
 A. lanceolata, *Thw.* 288.
 Hin-kebella, S.
 703. Daphniphyllum glaucescens, *Bl. D. neilgherrense.* 290.
 704. Antidesma Ghæsembilla, *Gaertn. A. paniculatum.* 289.
 Bú-embilla, S.

- A. ALEXITERIA, *L.* *A. zeylanicum*. 289.
Hin-embilla, S.
- A. BUNII, *Spr.* 289.
 var. THWAITESIANUM, *Mull. Arg.* (sp.) Var. β . 289.
Karavala-kebella, S.
- A. PYRIFOLIUM, *Mull. Arg.* *A. montanum*. 289.
- A. LANCEOLATUM, *Tul.* *A. lanceolarium*. 289.
 [*Microdesmis casearifolia*, *Planch.*]
- * Jatropha glandulifera, *Roxb.* *J. glauca*. 277.
 (*J. gossypifolia*, *L.*)
 (*J. Curcas*, *L.*) *Raṭa-eṇḍaru*, S. *Kāddamanakku*, T.
Physic Nut.
- * Aleurites triloba, *Forst.* *Tel-keḥuna*, S. *Candle Nut.*
705. ? Croton oblongifolium. *Roxb.* 276.
 C. ZEYLANICUM, *Mull. Arg.* *C. hypoleucum*. 276.
C. lacciferum, *L.* 275.
Keppitiyā, *Gas-keppitiyā*, S.
C. aromaticum, *L.* 275.
Wēl-keppitiyā, S. *Vid-punē*, T.
- C. MOONII, *Thw.* 276.
C. caudatum, *Giescl.* ("Thunberg.")
 (*C. Tiglium*, *L.*) *Jaya-pāla*, S. *Nērvāḷum*, T.
- C. NIGRO-VIRIDE, *Thw.* 276.
 C. THWAITESIANUM, *Mull. Arg.* *C. Klotzschianum*. 276.
706. Givotia rottleriformis, *Griff.* 278.
Kuri-kurité, *Puttala*, T.
707. TRIGONOSTEMON DIPLOPETALUS, *Thw.* 277.
 T. NEMORALIS, *Thw.* 277.
708. Ostodes zeylanica, *Mull. Arg.* *Desmostemon*. 278.
Wal-keḥuna, *Olupetta*, S.
 O. MINOR, *Mull. Arg.* *D. zeylanicus*, var. 278.
Wal-jayapāla, S.
709. Blachia umbellata, *Baill.* 277.
Kosatta, S.
710. Dimorphocalyx glabellus, *Thw.* 278.
Wēli-wēnna, S. *Taintukki*, T.
711. Agrostistachys indica, *Dalz.* 279.
A. longifolia, (*Wight.*) *Sarcoclinium*. 279.
Bēru, S.
A. HOOKERI, (*Thw.*) *Sarcoclinium*. 279.
Diya-bēru, *Maha-bēru*, S.
712. Chrozophora plicata, *A. Juss.*, var. *Rottleri*, *Mull. Arg.*
 443.

713. *ADENOCHLÆNA ZEYLANICA*. *Thw.* 270.
714. *CLAOXYLON OLIGANDRUM*. *Mull. Arg.* 271.
715. *Micrococca Mercurialis*, *Benth.* *Claoxylon*. 271.
716. *Acalypha paniculata*, *Miq.* *A. Wallichii*. 271.
A. fruticosa, *Forsk.* *A. betulina*. 271.
A. indica, *L.* 271.
Kuppa-méniga, *S.* *Kuppaimáni*, *T.*
A. fallax, *Mull. Arg.* *A. hispida*. 271.
A. ciliata, *Forsk.* 271.
717. ? *CÆLODISCUS THENBERGIANUS*. *Mull. Arg.* ("Thunberg.")
718. *PODADENIA SAPIDA*. *Thw.* 274.
719. *Trewia nudiflora*, *L.* 272.
720. ? *Mallotus moluccanus*, *Mull. Arg.* ("Hermann.")
M. ERIOCARPUS, *Mull. Arg.* *Rottlera*. 273.
M. albus, *Mull. Arg.* *Rottlera tetracocca*. 272.
Bû-kenda, *S.*
M. MICRANTHUS, *Mull. Arg.* ("C. P. 2106.")
M. muricatus, *Mull. Arg.* *Rottlera*. 273.
M. ZEYLANICUS, *Mull. Arg.* *Rottl. oppositifolia*. 273.
Marai-thinni, *T.*
M. FUSCESCENS, *Mull. Arg.* *Rottlera*. 273.
M. NITIDUS, *Mull. Arg.* C. P. 3930 (olim 2469).
M. philippineus, *Mull. Arg.* *Rottl. tinctoria*. 272.
Hampiila, *S.* *Kapila-podi*, *T.*
M. repandus, *Mull. Arg.* *Rottl. rhombifolia*. 272.
721. *Cleidion javanicum*, *Bl.* 272.
Okuru, *S.*
722. *Macaranga digyna*, *Mull. Arg.* *Rottlera*. 273.
Ota, *S.*
[M. depressa, Mull. Arg.]
M. indica, *Wight.* 428.
M. tomentosa, *Wight.* 274.
Kenda, *Put-kenda*, *S.*
 * *Ricinus communis*, *L.*
Endaru, *S.* *Sittá-manaku*, *T.* *Castor-oil*.
723. *Homonoia riparia*, *Lour.* *Spathostemon javense*. 272.
724. *Chaetocarpus castanocarpus*, *Thw.* 275.
Hédawaka, *Hedôka*, *S.* *Palakuna*, *Sadavaku*, *T.*
C. CORIACEUS, *Thw.* 275.
725. *Gelonium lanceolatum*, *Willd.* 274.
 var. *ANGUSTIFOLIUM*, *Baill.* (sp.) (C. P. 252.)
Kakai-palé, *Varit-thulai*, *T.*

726. *Tragia involucrata*, *L.* 270.
 var. INTERMEDIA, *Mull. Arg.* *T. cannabina*. 270.
 var. CORDATA, *Mull. Arg.* (C. P. 3519.)
 var. MONTANA, *Mull. Arg.* (sp.) *non Thw.* (C. P. 2100.)
Wēl-kahambiliyá, S.
727. *Dalechampia ternata*, *Mull. Arg.*, var. ZEYLANICA, *Mull.*
D. bidentata. 270.
728. *Sapium indicum*, *Willd.* 269.
Kiri-makulu, S.
S. insigne, (*Royle.*) *Falconeria*. 270.
Tilai, T.
729. *Sebastiania Chamælea*, *Mull. Arg.* *Microstachys*. 270.
Rat-piṭawakká, S.
730. *Excoecaria Agallocha*, *L.* 269.
Telu-kiriya, S.
E. cochinchinensis, *Lour.* *E. oppositifolia*. 269.
121. **Urticaceæ.**
731. *Holoptelea integrifolia*, *Planch.* *Ulmus*. 267.
Godá-kirilla, S. *Ail*, *Aiyilli*, *Kanchá*, T.
732. *Celtis cinnamomea*, *Lindl.* *C. Dysodoxylon*. 267.
Gurenda, S.
C. Wightii, *Planch.* 267.
733. *Trema orientalis*. (*L.*) *Sponia*. 267.
Gēdumba, S.
734. *Gironniera parvifolia*, *Planch.* *G. subæqualis*, var. *zeylanica*. 267.
G. reticulata, *Thw.* 263.
735. *Taxotrophis zeylanica*, *Thw.* 264.
736. *Phyllocllamys spiuosa*, *Bur.* *Taxotrophis Roxburghii*. 267.
737. *Streblus asper*, *Lour.* 264.
Gēta-netul, S. *Palpirái*, T.
738. *ALLÆANTHUS ZEYLANICUS*, *Thw.* 263.
Alandu, S.
739. *Plecospermum spinosum*, *Tréc.* 263.
Kaṭu-timbol, S.
740. *Dorstenia indica*, *Wall.* 264.
741. † *Ficus religiosa*, *L.* *Urostigma*. 264.
Bó, S. *Arasu* or *Arasa*, T.
F. Arnottiana, (*Miq.*) *Urostigma*. 264.
Kaudu-bó, *Pulila*, S.

- F. Tsjakela, *Burm.* *Urostigma infectarium*, (part.) 265.
Kiri-pella, S.
- F. infectoria, *Willd.* *Urostigma* (part). 265.
 var. *Wightiana*, *King.* *U. Wightianum*. 265.
Kalaha, S.
- F. Mooniana, *King ms.* *U. Wightianum*, var. *majus*. 265.
- F. bengalensis, *L.* *Urostigma*. 265.
Maha-nuga, S. *Al. T. Banyan*.
- F. tomentosa, *Roxb.* *Urostigma*. 265.
- F. mysorensis, *Heyne.* *Urostigma*. 265.
Bu-nuga, S.
- F. pseudo-Tsiela, (*Miq.*) *U. lacciferum*, (part.)
- F. altissima, *Bl.* var. *laccifera*, *Roxb.* (sp.) *U. lacciferum*.
 265.
Nuga, S.
- F. Trimeni, *King ms.* *U. Tjiela* (part). (C.P. 2220.) 265.
Tel-nuga, S.
- F. Tsiela, *Roxb.* (C. P. 2218.) *U. Tjiela* (part.) 265.
Ela-nuga, *Ehefu*, S.
- F. CAUDICULATA, *Trim. ms.*
- F. retusa, *L.* *Urostigma* (& C. P. 2537). 265.
 var. *nitida*, *Thunb.*
- F. nervosa, *Heyne*, var. *minor*, *King.* *Urostigma modestum*. 266.
Kalamaduwa, S.
- F. ZEYLANICA, (*Miq.*) *Pogonotrophe dasyphylla*. 266.
- F. asperrima, *Roxb.* 266.
Sewana-mediya, S.
- F. callosa, *Willd.* *F. cinerascens*. 266.
Wal-gonna, S.
- F. heterophylla, *L. f.* 266.
Wal-ehetu, S.
- F. gibbosa, *Bl.* var. *parasitica*, *Koen.* (sp.) 266.
Gas-neful, *Wel-ehetu*, S.
- F. THWAITESII, *Miq.* *F. disticha*. 266.
- F. DIVERSIFORMIS, *Miq.* 266.
- F. hispida, *L. f.*, var. *oppositifolia*, *Willd.* *Covellia oppositifolia*. 266.
Kota-dimbulá, S.
- F. glomerata, *Willd.* *Covellia*. 267.
Attikka, S. *Atti*, T.
742. *Antiaris innoxia*, *Bl.*
Riti, S. *Netaril*, T.

743. *Cudrania javanensis*, *Tréc.* *Cudranus Rumphii*. 262.
 744. *Artocarpus Lakoocha*, *Roxb.* 262.
 Kana-gonna, S.
 A. NOBILIS, *Thw.* 262.
 Del, *Wal-del*. S.
 (A. *incisa*, L.) *Rata-del*, S. *Bread Fruit*,
 * A. *integrifolia*, L. (C. P. 2233.)
 Kos. S. *Pulá*, T. *Jack*.
 745. *Fleurya interrupta*, *Gaud.* 258.
 Wal-kahambiliyá. S.
 746. *Laportea terminalis*, *Wight.* 259.
 L. crenulata, *Gaud.* 259.
 Má-ussá, S.
 747. *Girardinia palmata*, *Gand.* *G. Leschenaultiana*, 259.
 Nilgiri Nettle.
 G. zeylanica, *Decne.* 259.
 Gas-kahambiliyá, S.
 748. *Pilea Wightii*, *Wedd.* 259.
 P. triuervia, *Wight.* 259.
 P. angulata, *Bl.* 259.
 * *P. microphylla*, *Liebm.*
 749. *Lecantheus Wightii*, *Wedd.* C. P. 3870.
 750. *Pellionia Heyneana*, *Wedd.* 259.
 751. *Elatostema sessile*, *Forst.* 427.
 E. acuminatum, *Wedd.* C. P. 3970.
 E. lineolatum, *Wight.* 260.
 var. *majus*, *Wedd.*
 var. *falcigerum*, *Wedd.*
 var. *lineare*, *Wedd.*
 var. *PETIOLARE*, *Thw. ms.* C. P. 3920.
 E. diversifolium, *Wedd.* *E. surculosum*. 260.
 752. *Procris lævigata*, *Bl.* 260.
 753. *Boehmeria malabarica*, *Wedd.* 260.
 Maha-diya-dúl, S.
 B. platyphylla, *Don.* 260.
 var. *macrostachya*, *Wedd.* 260.
 var. *ZEYLANICA*, *Wedd.* 260.
 var. *rugosissima*, *Wedd.*
 754. *Chamabaina cuspidata*, *Wight.* 260.
 755. *Pouzolzia indica*, *Gaud.* 260.
 var. *alienata*, (L.) (sp.) 260.
 var. *suffruticosa*, *Wight.* (sp.)? C. P. 4001.
 P. auriculata, *Wight.* 260.

P. WALKERIANA, *Wight. Hyrtanandra.* 261.

P. hirta, *Hossk. Hyrtanandra.* 261.

var. *Bennettiana, Wedd.* 261.

var. *Gardneri, Wedd.*

P. PARVIFOLIA, *Wedd. Hyrtanandra triandra.* 261.

756. *Villebrunea sylvatica, Bl. Orescnide.* 261.

757. *Debregeasia velutina, Gaud. Morocarpus longifolia.* 261.

Gas-dúl, S.

D. *Wallichiana, Wedd. Morocarpus.* 262.

Casuarineæ.

(*Casuarina equisetifolia, Forst.*) *Kasa, S. Chowkku, T.*

122. Ceratophyllaceæ.

758 *Ceratophyllum verticillatum, Roxb.* 290.

GYMNOSPERMEÆ.

123. Cycadeæ.

759. *Cycas circinalis, L.*

Madu, S.

† *C. Rumphii, Miq. C. P. 3862.*

MONOCOTYLEDONS.

124. Hydrocharideæ.

760. *Hydrilla ovalifolia, Rich. H. verticillata.* 331.

761. *Lagarosiphon Roxburghii, Benth. Nechamandra olternifolia.* 332.

762. *Blyxa Roxburghii, Rich. B. octandra.* 332.

Diya-hawari, S.

763. *Ottelia alismoides, Pers.* 332.

764. *Enhalus acoroides, Rich. E. marinus.* 332.

765. *Thalassia Hemprichii, Asch Posidonia serrulata.* 333.

766. *Halophila ovalis, Hk. f. Thalassia stipulacea.* 333.

125. Burmanniaceæ.

767. *Burmannia disticha, L. B. distachya.* 325.

Meḍiya-jáwála, S.

B. PUSILLA, *Thw.* 325.

var. *elatior.* Var. β . 325.

B. CHAMPIONII, *Thw.* 325.

768. THISMIA GARDNERIANA, *Hk. f.* C. P. 4009. 325.

126. Orchideæ.

769. *Microstylis Rheedii*, *Lindl.* 296.
M. luteola, *Wight.* (C. P. 2743.) *M. Rheedii* (part.) 296.
M. DISCOLOR, *Lindl.* 297.
M. LANCIFOLIA, *Thw.* 297.
M. PURPUREA, *Lindl.* 297 & 429.
M. congesta, *Walp.* C. P. 3950.
 var. *FUSCA*, *Lindl.* (sp.) *Dienia fusca.* 297.
770. *Oberonia Brunoniana*, *Wight.* C. P. 3869.
O. FORCIPATA, *Lindl.* 296.
O. LONGIBRACTEATA, *Lindl.* 296.
O. TRUNCATA, *Lindl.* 296. C. P. 3913 ?
O. verticillata, *Wight*, var. *PUBESCENS*, *Lindl.* 296.
O. TENUIS, *Lindl.* 296.
O. Wightiana, *Lindl.* 296.
O. GARDNERIANA, *Thw.* 296.
O. SCYLLÆ, *Lindl.* 296.
771. *LIPARIS ATROPURPUREA*, *Lindl.* (*non Wight.*) 295.
L. WALKERIÆ, *Grah.* (*non Wight.*) 295.
L. Wightiana, *Thw.* 295.
L. brachyglottis, *Rehb. f.* C. P. 4002.
L. paradoxa, *Rehb. f.* *Empusa.* 429.
L. BARBATA, *Lindl.* ("Macrae 1829.") 295.
L. longipes, *Lindl.* 295.
L. viridiflora, *Lindl.* 295.
L. angustifolia, *Lindl.* 296.
L. gregaria, *Lindl.* 296.
772. *Dendrobium Macraei*, *Lindl.* 297.
 † *D. crumenatum*, *Sw.* 297.
 Sudu-parejimal, S.
D. aureum, *Lindl.* 297.
 Primrose Orchid.
 var. *pallidum*, *Lindl.*
D. MACCARTHIÆ, *Thw.* 297.
 Wesak-mal, S.
D. MACROSTACHYUM, *Lindl.* 297.
D. nutans, *Lindl.* 298.
D. hæmoglossum, *Thw.* 429.
 [*D. SANGUINOLENTUM*, *Lindl.*] 298.

- [D. CRINIFERUM, *Lindl.*] ("Mr. Power.")
 [D. COMPRESSUM, *Lindl.*] ("Nightingale.")
 D. PURPURASCENS, *Thw.* 298.
 D. PANDURATUM, *Lindl.* 298.
 D. ALBIDULUM, *Thw. ms.* C. P. 3926 (& C. P. 2353
 (part).)
773. BULBOPHYLLUM ELEGANS, *Gardn.* 298.
 B. CRASSIFOLIUM, *Thw. ms.* C. P. 3879.
 B. PETIOLARE, *Thw.* 298.
 B. PURPUREUM, *Thw.* 298.
774. CIRRHOPETALUM MACRÆI, *Lindl.* 299.
 C. GRANDIFLORUM, *Wight.* 299.
 C. ELLIÆ, *Rehb. f.* (C. P. 3160.) *C. Wightii* (part). 299.
 C. THWAITESII, *Rehb. f.* (C. P. 2740.) *C. Wightii* (part).
 299.
775. ERIA BICOLOR, *Lindl.* 299.
Lily-of-the-Valley Orchid.
 E. LINDLEYI, *Thw.* 299.
 E. TRICOLOR, *Thw.* 429.
 E. braccata, *Lindl.* 299.
 E. MUSCICOLA, *Lindl.* 299.
 var. oblonga, *Trim. ms.* C. P. 2355 (part).
 E. ARTICULATA, *Lindl.* *Alwisia tenuis.* 300.
 E. THWAITESII, *Trim.* *E. velutina.* 299.
 E. sp. C. P. 4017.
 [E. profusa, *Lindl.*] ("Nightingale.")
776. Phreatia elegans, *Lindl.* 299.
777. PACHYSTOMA SPECIOSUM, *Rehb. f.* *Ipsæa.* 301.
Daffodil Orchid.
 P. MONTANUM, *Rehb. f.* ("Macrae.")
778. ACANTHEPHIPIUM BICOLOR, *Lindl.* 307.
779. PHAIUS BICOLOR, *Lindl.* 300.
 P. LURIDUS, *Thw.* 300.
780. Tainia bicornis, (*Lindl.*) *Ania.* 301.
 T. MACULATA, (*Thw.*) *Ania.* 301.
781. Josephia lanceolata, *Wight.* 307.
782. Cœlogyne breviscapa, *Lindl.* 300.
 C. odoratissima, *Lindl.* 300.
783. Pholidota imbricata, *Lindl.* 300.
784. CALANTHE PURPUREA, *Lindl.* *C. Masuca.* 308.
 C. veratrifolia, *Br.* 308.
 var. discolor, *Thw.* 308.

785. ARUNDINA MINOR, *Lindl.* 301.
786. Eulophia macrostachya, *Lindl.* 301.
E. virens, *Br.* 302.
 [*E. herbacea*, *Lindl.*] ("Macrae.")
 [*E. bracteosa*, *Lindl.*] *E. grandiflora*, 301.
 [*E. explanata*, *Lindl.*] 301.
E., sp. C. P. 3958.
787. Cymbidium ensifolium, *Sw.*, var. HÆMATODES, *Lindl.* (sp.) 307.
C. BICOLOR, *Lindl.* 308.
Wisa-dūli, *S.*
C. aloifolium, *Sw.* 308.
Panaṅ-kattāli, *T.*
788. Geodorum dilatatum, *Br.* 308.
G. FUCATUM, *Lindl.* 308.
789. Polystachya luteola, *Hk.* 308.
790. CYRTOPODIUM RUFUM, (*Thw.*) *Cyrtopera*. 302.
C. fuscum, (*Wight.*) *Cyrtopera*. 302, 429.
791. Luisia tenuifolia, *Bl.* 302.
L. ZEYLANICA, *Lindl.* 302.
792. Cottonia macrostachya, *Wight.* 303.
C. Championi, *Lindl.* *Luisia bicaudata*. 302 ; *Vanda*. 429.
793. DORITIS LATIFOLIA, (*Thw.*) *Aerides*. 429.
794. SARCOCHILUS PULCHELLUS, (*Thw.*) *Dendrocolla*, 430 ;
Cylindrochilus, 307.
S. serræformis, *Rchb. f.* *Dendrocolla*. 306.
795. Aerides cylindricum, *Lindl.* 306.
A. viridiflorum, *Thw.* 430.
A. tessellatum, *Wight.* 305.
796. Vanda parviflora, *Wight.* *Aerides Wightianum*. 305.
V. Roxburghii, *Br.* 303.
V. spathulata, *Spreng.* 303.
797. Saccolabium guttatum, *Lindl.* 303.
 [*S. curvifolium*, *Lindl.*] 303.
S. NIVEUM, *Lindl.* 304.
S. GRACILE, *Lindl.* 304.
S. roseum, *Lindl.* 304.
S. BREVIFOLIUM, *Lindl.* 304.
S. filiforme, *Lindl.* *Schænorchis juncifolia*. 304.
S. tenerum, (*Lindl.*) *Œceoclades*. 306.
S. paniculatum, *Wight.* 429

798. *Acampe Wightiana*, *Lindl.* 303.
var. *longepedunculata*. Var. β . 303.
[*A. congesta*, *Lindl.*] 303.
799. *Sarcanthus peninsularis*, *Dalz.* *Saccolabium acuminatum*. 304.
800. *CLEISOSTOMA MACULOSUM*, *Lindl.* (fide *Benth.*) *Saccolabium lineolatum*. 304.
C. ACAULE, *Lindl.* 305.
C. GALEATUM, *Thw.* 305.
C. THWAITESIANUM, *Trim.* *C. maculosum*. 304.
801. *TENIOPHYLLUM ALWISII*, *Lindl.* 305.
802. *Diplocentrum recurvum*, *Lindl.* 306.
803. *MYSTACIDIUM ZEYLANICUM*, (*Lindl.*) *Angræcum*. 306.
804. *PODOCHILUS FALCATUS*, *Lindl.* 306.
var. *angustatus*, *Thw. ms.* C. P. 3889.
P. SAXATILIS, *Lindl.* 307.
805. *Appendicula longifolia*, *Bl.* 306.
806. *Galeola javanica*, *Benth.* *Cyrtosia*. 311.
807. *VANILLA WALKERIE*, *Wight.* 311.
V. MOONII, *Thw.* 312.
808. *Corymbis disticha*, *Thouars.* 314.
809. *Tropidia cureuligoides*, *Lindl.* 314.
T. BAMBUSIFOLIA, (*Thw.*) *Cnemidia*. 314.
810. *Spiranthes australis*, *Lindl.* 312.
811. *Physurus Blumei*, *Lindl.* 314.
812. *Anæctochilus setaceus*, *Bl.* 314.
Wana-rāja, *S.*
var. *inornatus*, *Hook.*
813. *Zeuxine sulcata*, *Lindl.* 312.
Z. longilabris, (*Lindl.*) *Monochilus*. 313.
Z. nervosa, (*Wall.*) *Monochilus*. 313.
Z. flava, (*Wall.*) *Monochilus*. 313.
Z. REGIA, (*Lindl.*) *Monochilus*. 313.
Iru-rāja, *S.*
814. *CHEIROSTYLIS PARVIFOLIA*, *Lindl.* 313.
C. flabellata, *Wight.* 313.
815. *Goodyera procera*, *Hook.* 313.
G. fumata, *Thw.* 314.
[*G. cordata*, (*Lindl.*)] *Georchis*. 314.
816. *Hetæria elongata*, *Lindl.* *Rhamphidia*. 313.
H. GARDNERI, (*Thw.*) *Rhamphidia*. 313.
817. *APHYLLORCHIS MONTANA*, *Rchb. f.* *Apaturia*. 301.

818. *Cryptostylis arachnites*, (Bl.) *Zosterostylis zeylanica*. 312.
819. *Pogonia Juliana*, Wall. 430.
820. *Gastrodia javanica*, Lindl. 311.
821. *Epipogum nutans*, Lindl. 311.
822. *Habenaria goodyeroides*, (Don.) *Peristylus*. 310.
H. Wightii, Trim. ms. *Peristylus plantagineus*. 310.
H. spiralis, (Wight.) *Peristylus*. 310.
H. aristata, (Lindl.) *Peristylus*. 310.
H. BREVILOBA, (Thw.) *Peristylus*. 311.
H. CUBITALIS, Br. *Platanthera*. 310.
H. RHYNCHOCARPA, (Thw.) *Platanthera*. 310.
H. MACROSTACHYA, Lindl. 309.
H. DICHOPETALA, Thw. 309.
H. DOLICHOSTACHYA, Thw. 309.
H. viridiflora, Br. 309.
H. PTEROCARPA, Thw. 309.
? *H. LATIFOLIA*, Lindl. 310.
H. plantaginea, Lindl. 310.
H. CRINIFERA, Lindl. 310.
H. barbata, Wight. *Ate virens*. 309.
H. ACUMINATA, Thw. *Ate*. 309.
823. *Satyrium nepalense*, D. Don. 308.
824. *Disperis zeylanica*, Trim. ms. *D. tripetaloides*. 311.
825. *Apostasia Wallichii*, Br. 315.

127. Scitamineæ.

826. *Globba marantinoides*, Wight. *G. bulbifera*. 315.
827. (*Kaempferia Galanga*, L.) 316.
Hinguru-piyali, S.
K. pandurata, Roxb. 316.
Amba-kaha, S.
† *K. rotunda*, L. 316.
Fawakenda, S.
828. *Hedychium coronarium*, Koen. 319.
Ela-mal, S.
var. *flavescens*, Carey (sp.). Var. β. 319.
H. angustifolium, Roxb. 319.
829. *Curcuma Zerumbet*, Roxb. 316.
Harap-kaha, S.
C. aromatica, Salisb. 316.
Dada-kaha, Wal-kaha. S.

- (*C. longa*, *L.*) *Kaha*, *S. Manjel*, *T. Turmeric*.
C. ALBIFLORA, *Thw.* 316.
C. OLIGANTHA, *Trim. ms.* (*C. P.* 3700.)
830. *AMOMUM INVOLUCRATUM*, (*Thw.*) *Elettaria.* 319.
A. FLORIBUNDUM, (*Thw.*) *Elettaria.* 319.
A. NEMORALE, (*Thw.*) *Elettaria.* 319.
A. echinatum, *Willd.* 316.
A. FULVICEPS, *Thw.* 317.
A. BENTHAMIANUM, *Trim. ms.* *C. P.* 3864.
A. PTEROCARPUM, *Thw.* 317.
A. MASTICATORIUM, *Thw.* 317.
A. ACUMINATUM, *Thw.* 317.
A. GRAMINIFOLIUM, *Thw.* 430.
A. HYPOLEUCUM, *Thw.* 318.
A. RUFESCENS, (*Thw.*) *Elettaria.* 430.
831. *CYPHOSTIGMA PULCHELLUM*, *Benth.* *Amomum.* 318.
832. *Elettaria Cardamomum*, *Maton*, var. *MAJOR*, *Sm.* (sp.) 318.
Ensdl, *S. Ceylon Cardamom.*
833. *Zingiber Zerumbet*, *Rosc.* 315.
Z. Cassumunar, *Roxb.* 315.
Z. CYLINDRICUM, *Moon.* 315.
Wal-inguru, *S.*
Z. Wightianum, *Thw.* 315.
834. *Costus speciosus*, *Sm.* 320.
Tebu, *S.*
835. (*Alpinia Galanga*, *Sw.*) 319.
Kaluwála, *S. Great Galangal.*
A. Allughas, *Rosc.* 320.
Keleniya, *Alu-gas*, *S.*
A. nutans, *Rosc.*, var. *SERICEA*, *Moon.* (sp.) 320.
Raṅkiriya, *S.*
(*A. calcarata*, *Rosc.*) *Kaṭa-kiriya*, *S.* 320.
836. *Clinogyne virgata*, *Benth.* *Maranta.* 320.
Geṭa-oluwa, *S.*
837. *PHRYNIUM ZEYLANICUM*, *Benth.* *Maranta spicata.* 320.
Hulan-kiriya, *S.*
P. capitatum, *Willd.* 320.
Et-beṃi-kiriya, *S.*
838. *Canna indica*, *L.* 320.
But-saraṇa, *S. Indian Shot.*
839. *Musa paradisiaca*, *L.* 321.
Wal-kehel, *S. Wild Plantain.*

128. *Hæmodoraceæ.*840. *Ophiopogon intermedius*, *Don.* 339.841. *Sansevieria zeylanica*, *Willd.* 338.*Niyanda*, S. *Maral*, T.129. *Amaryllidæ.*842. *Curculigo orchioides*, *Gaertn.* 324.*Hin-bin-tal*, S.C. *Finlaysonian*, *Wall.* *Hypoxis trichocarpa.* 323.*Má-bin-tal*, S.var. *linearifolia*, *Thw.* 323.(C. *recurvata*, *Dryand.*) 324. *Wayá-pol*, S.843. *Crinum asiaticum*, *L.* 324.*Tolabó*, S. *Visha-mungil*, T.C. *zeylanicum*, *L.* C. *ornatum.* 324.*Goḍa-mánil*, S.var. *Herbertianum*, *Wall.* (sp.) ("C. P. 3735.")
324.C. *defixum*, *Gawl.* 324.C. *amœnum*, *Roxb.?*844. *Pancratium zeylanicum*, *L.* 324.*Wal-línu*, S.? P. *verecundum*, *Sol.*(Hymenocallis *tenuiflora*, *Herb.*) *Pancratium malabaricum.* 324. (C. P. 2339.)130. *Taccaceæ.*845. *Tacca pinnatifida*, *Forst.* 325.131. *Dioscoreaceæ.*846. *Dioscorea pentaphylla*, *L.* 326.*Kaṭu-wala*, S.D. *tomentosa*, *Koen.* 326.*Uyala*, S.D. *bulbifera*, *L.* 326.*Panu-kondol*, S.D. *oppositifolia*, *L.**Hiri-tala*, S.D. *INTERMEDIA*, *Thw.* 326.D. *spicata*, *Roth.* 326.847. *Trichopus zeylanicus*, *Gaertn.* *Trichopodium.* 291.*Bim-pol*, S.

132. *Roxburghiaceæ.*

848. *Stemona tuberosa*, *Lour.*, var. *miuor*, *Thw.* *Roxburghia gloriosoides.* 432.

133. *Liliaceæ.*

849. *Smilax ovalifolia*, *Roxb.* 338.
Maha-kabarasa, *S.*
S. zeylanica, *L.* 338.
Hin-kabarasa, *S.*
S. aspera, *L.*, var. *maculata*, *Roxb.* (sp.) 338.
850. *Asparagus falcatus*, *L.* 337.
Hátá-wáriya, *S.*
A. gonoclados, *Baker.* C. P. 2299 (part).
[A. sarmentosus, L.]
A. racemosus, *Willd.* *A. sarmentosus.* 337.
var. *ZEYLANICUS*, *Baker.* *A. racemosus.* (part). 337.
851. *Aloe vera*, *L.*, var. *littoralis*, *Koen.* (sp.)
Kattálai, *T.*
852. *DRACÆNA THWAITESII*, *Regel.* *D. elliptica.* 338.
853. *Chlorophytum laxiflorum*, *Br.* *C. parviflorum.* 339.
C. Heynei, *Baker.* *C. breviscapum.* 339.
854. *Dianella ensifolia*, *Réd.* 338.
Monara-petaṇ, *S.*
855. *Allium Hookeri*, *Thw.* 339.
856. *Dipcadi montanum*, *Baker.* *Uropetalum.* 443.
857. *Scilla indica*, *Baker.* *Ledebouria hyacinthina.* 432.
858. *Iphigenia indica*, *Kunth.* 339.
859. *Gloriosa superba*, *L.* 339.
Niyangalá, *S.* *Káddínchi*, *T.*
860. *Disporum Leschenaultianum*, *Don.* 338.

134. *Pontederiaceæ.*

861. *Monochoria hastæfolia*, *Presl.* 321.
Diya-habarala, *S.*
M. vaginalis, *Presl.* 321.
M. plantaginea, *Kunth.* 321.

135. *Xyrideæ.*

862. *Xyris indica*, *L.* 340.
Raṅ-moṭu, *Raṅ-manissa*, *S.*
X. Walkeri, *Wight.* 340.
X. schœnoides, *Mart.* 340.
X. pauciflora, *Willd.* 340.

136. Commelinaceæ.

863. *Pollia sorzogonensis*, *Endl.*, var. *indica*, *Wt.* (sp.) *P. indica*, 323.
864. *Commelina benghalensis*, *L.* 321.
Diya-menériya, *S.*
C. clavata, *Clarke.* *C. salicifolia*. 321.
Girápalá, *S.*
var. *attenuata*, *Vahl.* (sp.) Var. *angustata*. 321.
C. persicariæfolia, *Wight.* ("Reynaud.")
C. obliqua, *Ham.* 322.
C. Kurzii, *Clarke.* *C. longifolia* (part). 322.
C. appendiculata, *Clarke.*
C. ensifolia, *Br.* *C. longifolia* (part). 322.
865. *ANEILEMA GLAUCUM*, *Thw.* (in *Clarke Mon.*) C. P. 3977.
A. zeylanicum, *Clarke.* *A. dimorphum* & *A. montanum* (part). 322.
A. esculentum, *Wall.* *A. scapiflorum*. 322.
A. dimorphum, *Dalz.* *A. scapiflorum*, var. *minus*. 322.
A. spiratum, *Br.* *A. nanum*. 322.
A. nudiflorum, *Br.* 322.
var. *terminalis*, *Wight.* (sp.)
A. giganteum, *Br.* *A. ensifolium*. 322.
A. vaginatum, *Br.* 322.
A. montanum, *Wight.* 322.
A. protensum, *Wall.* 322.
866. *Cyanotis axillaris*, *R. & S.* 323.
C. cristata, *R. & S.* 323.
C. tuberosa, *R. & S.*, var. *adscendens*, *Dalz.* (sp.)
C. arachnoidea, *Clarke.*
var. *obtusá*, *Trim. ms.*
C. pilosa *R. & S.* 323.
C. villosa, *R. & S.* *C. lanceolata* (part). 323.
C. ZEYLANICA, *Hassk.* *C. lanceolata* (part). (C. P. 3223). 323.
C. fasciculata, *R. & S.* 323.
var. *Thwaitesii*, *Hassk.* (sp.)
867. *Floscopa scandens*, *Lour.* *F. paniculata*. 323.

137. Flagellariaceæ.

868. *Flagellaria indica*, *L.* 340.
Goyi-wel, *S.*

- .869. *Susum anthelminticum*, *Bl.* 340.
Induru, S.

138. Juncaceæ.

870. *Juncus glaucus*, *Ehrh.* 340.
J. Leschenaultii, *J. Gay.* 340.

139. Palmæ.

871. † *Areca Catechu*, *L.* 327.
Puwak, S. *Kamuka*, T. *Areca-nut Palm.*
A. CONCINNA, *Thw.* 328.
Lén-teri, S.
872. *LOXOCOCCUS RUPICOLA*, *Wendl. & Dr. Ptychosperma.* 328.
Dótalú, S.
873. *ONCOSPERMA FASCICULATA*, *Thw.* 328.
Katu-kitul, S.
874. *Caryota urens*, *L.* 329.
Kitul, S. *Tippili-pana*, T.
875. *Nipa fruticans*, *Thunb.* 327.
Gin-pol, S.
876. *PHŒNIX ZEYLANICA*, *Trim. ms. P. sylvestris.* 329.
Indi, S.
P. pusilla, *Gaertn.*
877. † *Corypha umbraculifera*, *L.*
Tala, S. *Kanda-pana*, T. *Talipot Palm.*
878. *Calamus longisetus*, *Griff.* 330.
C. rudentum, *Lour.?* 330.
Tudarena-wéwél, *Má-wéwél*, S.
C. Roxburghii, *Griff.* 330.
Wéwél, *Ela-wéwél*, S.
- C. PACHYSTEMONUS*, *Thw.* 431.
Kukula-wél, S.
- C. RADIATUS*, *Thw.* 431.
C. tenuis, *Roxb.* 330.
C. RIVALIS, *Thw. ms. C. P.* 3914.
Ela-wél, S.
- C. DELICATULUS*, *Thw.* 330 & 431.
C. OVOIDEUS, *Thw. ms. C. P.* 3925.
Tambutu-wél, S.
879. † *Borassus flabelliformis*, *L.* 329.
Tal, S. *Punai*, T. *Palmyra Palm.*
(Cocos nucifera, L.) 330.
Pol, S. *Tennai*, T. *Coco-nut Palm.*

140. Pandanaceæ.

880. *Pandanus fascicularis*, Lam. *P. odoratissimus*. 327.
Múdu-keyiyá, S. *Thále*, T. *Screw-pine*.
P. foetidus, Roxb., var. *RACEMOSUS*, Kurz. *P. humilis*.
 327.
Dunu-keyiyá, S.
P. ZEYLANICUS, Solms. *P. furcatus*. 327.
O'-keyiyá, S.
 † *P. Kaida*, Kurz.

881. *FREYCINETIA WALKERI*, Solms. *F. radicans*. 327.
F. PYCNOPHYLLA, Solms. *F. angustifolia*. 327.

141. Typhaceæ.

882. *Typha angustifolia*, L. 331.
Hambu-pañ, S.

142. Araceæ.

883. *CRYPTOCORYNE THWAITESII*, Schott. 334.
C. BECKETTII, Thw. ms. C. P. 3868.
 [C. *spiralis*, Fisch.] 334.
C. WALKERI, Schott.
884. *Lagenandra toxicaria*, Dalz. *L. ovata*. 334.
Ketala, S.
L. INSIGNIS, Trim. ms.
L. LANCIFOLIA, Thw. 334.
Ati-udayan, S.
L. THWAITESII, Schott. *L. lancifolia* (part). 334.
L. KOENIGII, Thw. 334.
885. *Pistia stratiotes*, L. 331.
Diya-parandella, S.
886. [Arisæma *curvatum*, Kunth.] 335.
A. NEGLECTUM, Schott. *A. filiforme*. 335.
A. Leschenaultii, Bl. *A. papillosum*. 335.
Wal-kidáran, S.
A. FILICAUDATUM, N. E. Br. C. P. 3980.
887. *Typhonium trilobatum*, Schott. *Arum*. 334.
Panu-ala, S.
T. divaricatum, Decaisne. *Arum Roxburghii*. 432.
Polon-ala, S.
888. *THERIOPHONUM ZEYLANICUM*, N. E. Br. *Arum divaricatum*. 334.
889. *Amorphophallus campanulatus*, Bl. 335.
Kidáran. S.

- A. dubius*, *Bl* 335.
 [*A. giganteus*, *Bl.*]
A. zeylanicus, *Bl.* ("Koenig.") 335.
890. *Synantherias sylvatica*, *Schott.* *Amorphophallus zeylanicus* (part). (C. P. 3733.) 443.
891. *Remusatia vivipara*, *Schott.* *Colocasia*. 336.
892. *Colocasia antiquorum*, *Schott.* 335.
Gahala (*Kandala*, *Tadala*. &c., cultivated vars)
 var. *nymphæifolia*, *Vent.* (sp.)
Wel-ala, *Fakutala*, *S.*
893. *Alocasia cucullata*, *Schott.* 336 *Colocasia*.
Panu-habarala, *Nagi-habarala*. *S.*
A. ALBA, *Schott.* ("Burmaun.")
 (*A. indica*, *Schott.*) *Rata-ala*, *Désa-ala*. *S.*
A. macrorrhiza, *Schott.* 336. *Colocasia*.
Habarala, *S.*
A. fornicata. *Schott.* 432. *Colocasia*.
894. *Raphidophora Peepla*, *Schott.* *Scindapsus* 336.
 (*R. pertusa*, *Schott.*)
R. decursiva. *Schott.* *Scindapsus*. 336.
Dada-kehel, *S.*
895. *Lasia spinosa*, *Thw.*, var. *HERMANNI*, *Sch.* (sp.) 336.
Kohila, *Maha-kohila*, *S.*
896. *Pothos scandens*. *L.* 336.
Pôtá-wel, *S.*
 var. *HOOKERI*. *Engler.*
P. ELLIPTICA, *Moon.* *P. remotiflora*. 337.
897. † *Acorus Calamus*, *L.* 337.
Wada-kaha, *S.*
 var. *terrestris*, *Engl.*

143. Lemnaceæ.

898. *Lemna paucicostata*, *Hegelm* *L. minor* 331.
L. polyrrhiza, *L.* 331.
899. *Wolffia arrhiza*. *Wimm.*

144. Triurideæ.

900. *SCIAPHILA SECUNDIFLORA*, *Thw.* 294.
S. ERUBESCENS, *Miers.* 294.
S. IANTHINA, *Thw.* 294.

145. Alismaceæ.

901. *Alisma oligococcum*, *F. Muell.* *A. glandulosum*. 332.
902. *Limnophyton obtusifolium*, *Miq.* *Alisma*. 332.

146. Naiadaceæ.

903. *Aponogeton monostachyum*, *L. f.* 333.
A. crispum, *Thunb.* 333.
Kekatiya, *S.*
904. *Potamogeton indicum*, *Roxb.* *P. natans.* 333.
P. pectinatum, *L.* (Inc. *Ruppia subsessilis*.) 333.
905. *Najas graminea*, *Del.* C. P. 3887.
906. ? *Cymodocea ciliata*, *Ehrenb.*
 ? *C. serrulata*, *Asch. & Magn.*
C. isoetifolia, *Asch.* *C. æquorea.* 333.
C. (Halodule) australis, (*Miq.*)

147. Eriocauloneæ.

907. *Eriocaulon setaceum*, *L.* 341.
E. Wallichianum, *Mart.* 341.
E. sexangulare, *L.* 341.
E. truncatum, *Ham.* 341.
E. Brownianum, *Mart.* 341.
E. quinquangulare, *L.* 341.
Kok-mota, *S.*
 var. *argenteum*, *Mart. (sp.)* 341.
E. luzulæfolium, *Mart.* 341.
E. Wightianum, *Mart.* 341.
E. cristatum, *Mart.* 341.
E. atratum, *Koen.* 341.
 var. *major*, *Thw.* 341.
E. FLUVIATILE, *Trim. ms.* (C. P. 3057 ?)

148. Cyperaceæ.

908. *Cyperus cephalotes*, *Vahl.* *C. Hookerianus.* 342.
C. stramineus, *Nees.* 432.
C. pumilus, *L. (non Nees.)* *C. pulvinatus.* 342
Gó-hiri-pay. *S.*
C. hyalinus, *Vahl.* *C. pumilus.* 432.
C. globosus, *All.*, var. *nilaguica*, *Hochst* *C. flavescens.*
 342.
C. polystachyus, *Rottb.* 342.
 var. *laxiflorus*, *Benth.*
C. Eragrostis, *Vahl.* *C. sanguinolentus.* 342.
C. puncticulatus, *Vahl* 342 & C. P. 4019.
C. alopecuroides, *Rottb.* 342.
C. pygmaeus. *Rottb.* C. P. 3947

- C. castaneus*, Willd. 343.
C. cuspidatus, H. B. K. ("Beckett.") C. P. 803 (part).
C. aristatus, Rottb. 343.
C. squarrosus, Rottb. C. P. 803 (part).
C. compressus, L. 342.
C. lucidulus, Klein. *C. compressus*, var. 342.
C. arenarius, Retz. 342.
 Müdu-kalánduru, S.
C. pachyrrhizus, Nees. *C. conglomeratus*. 343.
C. platystylis, Br. *C. pallidus*. 343.
C. Haspan, L. 343.
C. flavidus, Retz. (C. P. 805.) *C. Haspan* (part.) 343.
C. elegans, L. *C. nigro-viridis*. 344.
C. diffusus, Vahl. C. P. 3931.
C. pulcherrimus, Willd. *C. silhetensis*. 343.
C. difformis, L. 344.
C. Iria, L. 344.
 Wel-hiri, S.
C. eleusinoides, Kunth. *C. xanthopus*. 344.
C. nutans, Vahl. *C. distans*, var. *major*. 432.
C. distans, L. f. 344.
C. dehiscens, Steud. *C. Pangorei*. 344.
 Hewan-paṇ, S.
C. pilosus, Vahl. 344.
C. procerus, Rottb. 343.
C. articulatus, L. 342.
C. corymbosus, Rottb. 344.
 Gal-ḥi, S.
 var. *Pangorei*, Rottb. (sp.)
C. rotundus, L. 343.
 Kalánduru, S. *Kórai*, T.
 var. *procerula*, Nees. (sp.) *C. Retzii*. 343.
C. stoloniferus, Retz. ("Koenig.")
C. tenuiflorus, Rottb. C. P. 3966.
C. bulbosus, Vahl.
 Silandi-arisi, T.
C. exaltatus, Retz. 343.
 var. *amœnus*, Clarke. *C. venustus*. 432.
C. auricomus, Sieb. *C. Neesii*. 344 & C. P. 3940.
C. PLATYPHYLLUS, R. & S. *C. Roxburghii*. 343.
C. dilutus, Vahl. 344.
C. pennatus, Lam. 343.

- C. dubius*, *Rottb.* 344.
C. biglumis, *Clarke.* *C. umbellatus* (part). 345.
C. umbellatus, *Benth.* 345.
 var. *laxata*, *Clarke.* (C. P. 817.)
 var. *panicea*, *Rottb.* (sp.) (C. P. 2878.)
909. *Kyllinga monocephala*, *Rottb.* 345.
 K. brevifolia, *Rottb.* 345.
 K. melanosperra, *Nees.* 345.
 K. cylindrica, *Nees.* 345.
 K. triceps, *Rottb.* 345.
910. *Heleocharis spiralis*, *Br.* 352.
 H. plantaginea, *Br.* 352, 434.
 Boru-paṇ, *S.*
 H. LAXIFLORUS, *Thw.* 435.
 H. fistulosa, *Schult.* 351.
 H. capitata, *Br.* 351.
 H. ovata, *Br.* 351.
 H. multicaulis, *Sm.*
 H. tetraquetra, *Nees.* 351.
 H. chætaria, *R. & S. Scirpus.* 435.
911. *Fimbristylis polytrichoides*, *Br.* 348.
 F. nutans, *Vahl.* 348.
 F. schœnoides, *Vahl.* 348.
 F. acuminata, *Vahl.* 348.
 F. tetragona, *Br. F. Arnottii.* 348.
 Dara-hál-paṇ, *S.*
 F. monostachya, *Hassk.* 347 & 434.
 F. tristachya, *Thw.* 347 & 434.
 F. fusca, *Nees. F. fulvescens.* 434.
 F. cyperoides, *Br. F. cinnamomctorum.* 434.
 F. TENUIFOLIA, *Thw.* 434.
 F. salbundia, *Kunth.* 349.
 F. CONNECTENS, *Thw.* 349.
 F. NIGRO-BRUNNEA, *Thw.* 434.
 F. diphylla, *Vahl.* 348.
 var. *major*, *Thw.* 433.
 F. ovalis, *Nees.* 348.
 F. ferruginca, *Vahl.* 348.
 F. dichotoma, *Vahl. F. pallescens* 348
 F. æstivalis, *Vahl. C. P. 3943.*
 var. *major* (*F. dichotoma*, *Nees.*)
 F. argentea, *Vahl.* 348.

- F. miliacea*, *Vahl.* 318.
Mûdu-hâl-paṇ, S.
F. globulosa, *Wall.* 349.
Hâl-paṇ, S.
F. quinquangularis, *Kunth.* 349.
F. insignis, *Thw.* 349.
F. complanata, *Link.* 349.
F. chætorhiza, *Kunth.* 349.
F. Wightiana, *Nees.* 349.
var. *congesta*.
F. RETUSA, *Thw.* 349.
F. trifida, (*Nees.*) *Isolepis.* 350.
F. gracilis, (*Nees.*) *Isolepis.* 350.
F. PULCHELLA, (*Thw.*) *Isolepis.* 350.
F. barbata, *Benth.* *Isolepis.* 350.
F. dipsacea, *Benth.* *Isolepis.* 350.
912. *Scirpus squarrosus*, *L.* *Isolepis.* 350.
S. articulatus, *L.* *Isolepis.* 350.
Maha-gêta-paṇ, S.
S. supinus, *L.* *Isolepis.* 350.
S. fluitans, *L.* *Isolepis.* 350.
S. grossus, *L.* 351.
S. pectinatus, *Roxb.* 351.
S. SUBCAPITATUS, *Thw.* 351.
S. debilis, *Pursh.* *S. juncooides.* 351.
S. mucronatus, *L.* 351.
913. *Fuirena ciliaris*, *Roxb.* 347.
F. glomerata, *Lam.* 347.
F. umbellata, *Rottb.* 347.
F. uncinata, *Wall.* 347.
914. *Lipocarpus argentea*, *Br.* 347.
L. sphacelata, *Kunth.* 347.
915. *Hypolytrum latifolium*, *Rich.* 346.
var. *minor*, *Thw.*
H. LONGIROSTRE, *Thw.* 346.
916. *Mapania zeylanica*, (*Thw.*) *Pandanophyllum.* 345.
M. IMMERSA, (*Thw.*) *Pandanophyllum.* 433.
917. *Scirpodendron costatum*, *Kurz.* *Hypolytrum* 346.
918. *Lepironia mucronata*, *Rich.* 346.
Êta-paṇ, S.
919. *Remirea maritima*, *Aubl.*, var. *pedunculata*, *Br.* (F)
345.

920. ACTINOSCHÆNUS FILIFORMIS, *Benth* *Arthrostylis*. 352.
 921. Rhynchospora Wallichiana, *Kunth*. 352.
 R. aurea, *Vahl*. 352.
 R. zeylanica, *Kunth*. 352.
 R. laxa, *Br.* 352.
 var. *minor*, *Thw.* 352.
 R. GRACILLIMA, *Thw.* 435.
 R. ruppioides, *Benth.* C. P. 3936.
 922. TRICOSTULARIA ZEYLANICA, *Benth.* *Cladium*. 353
 923. CLADIUM CRASSUM, (*Thw.*) *Baumca.* 353.
 924. Scleria caricina, *Benth.* *Diplacrum*. 354
 S. HIRSUTA, *Moon.* *S. junciformis*. 354.
 S. NEESII, *Kunth.* 354.
 Baka-mānu-tana, *S.*
 S. pergracilis, *Kunth.* 354.
 S. tessellata, *Willd.* 354.
 S. ZEYLANICA, *Poir.* 435 & 354.
 S. lithosperma, *Willd.* 354.
 S. lævis, *Retz.* 354.
 Hin-kerewu, *S.*
 S. androgyna, *Nees.* 353.
 S. elata, *Thw.* 353.
 Maha-kerewu, *S.*
 S. HEBECARPA, *Nees.* 435 & 353.
 S. sumatrensis, *Retz.* 353.
 S. oryzoides, *Presl.* 353.
 Potu-kola, *Potu-pay.* *S.*
 925. Carex rara, *Boott.* 354.
 C. nubigena, *Don.* 355.
 C. SPICIGERA, *Nees.* 355.
 var. *minor*, *Boott.* 355.
 var. *rubella*, *Boott.* (sp.) 355
 C. leucantha, *Arn.* 355.
 C. gracilis, *Br.* 355.
 C. longipes, *Don.* 355.
 C. bengalensis, *Roxb.* 355
 C. cruciata, *Wahlenb.* 355.
 C. baccans, *Nees.* 355.
 C. WALKERI, *Arn.* 355.
 C. maculata, *Boott.* 355
 C. phacota, *Spr.* 356.
 C. Arnottiana, *Drej.* 356.

- C. lobulirostris*, *Drej.* 356.
C. Jackiaua, *Boott.* 356.
 var. *breviculmis*, *Thw.* 356.
C. THWAITESII, *Hunce.* *C. breviculmis.* 356.

149. Gramineæ.

926. *Paspalum serobiculatum*, *L.* 357.
 Amu, *S.* *Waragu*, *T.*
 * *P. conjugatum*, *Berg.*
P. filiculme, *Nees.* 358.
P. Royleanum, *Nees.* 358.
927. *Eriochloa polystachya*, *H. B. & K.* *E. annulata.* 358.
928. *Isachne pulchella*, *Roth.* 362.
I. Kuuthiana, *W. & A.* 362.
I. australis, *R. Br.* 361.
 var. *effusa*, *Trim. ms.*
I. MULTIFLORA, *Thw.* (var.) *I. australis* var. 361.
I. WALKERI, *W. & A.* 361.
I. nilagirica, *Hochst.* *Panicum Gardneri.* 359.
929. *Panicum sanguinale*, *L.* 358.
 var. *australe*, *Thw.* 358.
 var. *ciliare*, *Retz.* (sp.) *P. ciliare.* 358 & *C. P.* 3976.
P. corymbosum, *Roxb.* 436.
P. Wallichianum, *W. & A.* 358.
P. cimicinum, *Retz.* 358.
P. semialatum, *Br.* 358.
P. fluitans, *Retz.* 359.
P. brizoides, *L.* 359.
P. eruciforme, *Sibth.* 359.
P. distachyum, *L.* 359.
P. infidum, *Steud.?* *P. javanicum.* 358.
P. Helopus, *Trin.* 436.
 var. *glabra*, *Trim. ms.* Var. β . 358.
P. Colonum, *L.* *P. Crus-galli*, var. *minor.* 359.
P. Crus-galli, *L.* 359.
 Wēl-marukku, *S.*
 * var. *frumentaceum*, *Roxb.* (sp.)
P. Myurus, *Lam.* 361.
P. interruptum, *Willd.* 361.
P. indicum, *L.* 361.
P. Petiveri, *Trin.* 359.

- P. prostratum*, *Lam.* 359.
 var. *horizontale*, *Trim. ms.* *P. prostratum*, forma.
 359.
- * *P. molle*, *Sw.* (C. P. 899.) *P. barbinode.* 361.
Diya-tana-kola, *S. Mauritius-Grass, Water-Grass.*
- P. antidotale*, *Retz.* 360.
Krimisastru, *S.*
- P. plicatum*, *Lam.* 360.
- * *P. maximum*, *L.* *P. jumentorum.* 361.
Raṭa-tana, *S. Guinea Grass.*
- P. reticulatum*, *Thw. ms.* C. P. 3890.
- * *P. miliaceum*, *L.*
Varagu, *T.*
- P. miliare*, *Lam.* *P. miliaceum.* 360.
Menéri, *S. Chámai*, *T.*
- P. psilopodium*, *Trin.* 360.
Menéri, *S.*
- P. humile*, *Nees.* 360.
- P. Leptochloa*, *Nees.* 360.
- P. BLEPHARIPHYLLUM*, *Trim. ms.*
- P. auritum*, *Presl.* 361.
- P. repens*, *L.* 360.
Etórá, *S.*
- P. decompositum*, *Br.*, var. *paludosum*, *Roxb. (sp.)* C. P.
 4020.
- P. nodosum*, *Kunth.* 360.
- P. stenostachyum*, *Thw.* 436.
- P. curvatum*, *L.* 360.
- P. uncinatum*, *Raddi.* 359.
- P. coccospermum*, *Steud.* 359.
- P. ovalifolium*, *Poir.* 359.
- P. trigonum*, *Retz.* 359.
- P. pilipes*, *Wight Hb.!* (? *Nees.*) (C. P. 100.) *P. tri-*
gonum (part). 359.
- P. montanum*, *Roxb.* 360.
930. *Ichnanthus pallens*, *Munro.* 361.
931. *Oplismenus compositus*, *R. & S. Panicum.* 353 & C. P.
 3963 & 3964.
 ? *O. Burmanni*, *Beauv.* 353. *Panicum.*
932. *Setaria glauca*, *Beauv. Panicum.* 361.
Kawálu, *S.*
- S. verticillata*, *Beauv. Panicum.* 361.
- S. intermedia*, *R. & S. Panicum.* 361.

- (*S. italica*, *Beauv.*)
Tana-hál, *S. Tinai*, *T. Millet.*
 (Pennisetum typhoideum, *Pers.*) (C. P. 946.) *Kumba*, *T.*
933. *Chamaraphis spinescens*, *Poir.* *Panicum asperum*. 436.
 var. *subglabra*, *Thw. ms.* C. P. 3877.
 C. depauperata, *Nees.* *Panicum sordidum*. 443.
934. *Stenotaphrum complanatum*, *Schrank.* 361.
935. *Thuarea sarmentosa*, *Pers.* 362.
936. *Spinifex squarrosus*, *L.* 362.
 Maha-rawana-réwula, *S.*
937. *Leptaspis nrceolata*, *Br. & Benn.* 357.
 L. cochleata, *Thw.* 357.
 * *Coix Lacryma*, *L.* 357.
 Kirindi-mánd, *S.*
938. *Chionachne barbata*, *Br. & Benn.* *C. Koenigii*. 357.
939. *Hygroryza aristata*, *Nees.* 356.
 Go-jabbá, *S.*
940. *Oryza sativa*, *L.* 357.
 Uru-wi, *S.* *Wild Paddy.*
941. *Leersia hexandra*, *Sw.* 356.
 Lew, *S.*
942. *Garnotia stricta*, *Brongn.* 363.
 G. SCOPARIA, *Thw.* 363.
 G. micrantha, *Thw.* 363.
 G. patula, *Munro.* C. P. 3967.
 G. FUSCATA, *Thw.* 363.
 G. courtallensis, *Thw.* 363.
943. *Arundinella avenacea*, *Munro.* 362.
 A. nervosa, *Nees.* 362 & C. P. 4019.
 A. villosa, *W. & A.* 362.
944. *Trachys mucronata*, *Pers.* 362.
945. *Tragus racemosus*, *Hall.* *Lappago*. 362.
946. *Perotis latifolia*, *Ait.* 369.
947. *Zoysia pungens*, *Willd.* 370.
948. *Imperata arundinacea*, *Cyr.* 369.
 Iluk, *S.*
949. *Saccharum spontaneum*, *L.* 369.
 S. procerum, *Roxb.* C. P. 3939.
 Rambuk, *S.*
950. *Pollinia tristachya*, *Thw.* 368.
 var. *distachya*, *Trim. ms.* *Forma.* 368.
 P. lancea, *Nees.* (C. P. 411 (part).)
 P. Cumingii, *Nees.* 368.

- P. Wallichiana*, *Nees*. 369.
951. *Pogonatherum saccharoideum*, *Beauv.* 365.
952. *Apocopsis Wightii*, *Nees*. 365.
var. *BECKETTII*, *Thw. ms.* (sp.) 3959.
953. *DIMERIA PUSILLA*, *Thw.* 369.
var. *pallida*, *Thw. ms.* C. P. 3965.
D. pilosissima, *Trin.* 369.
D. LAXIUSCULA, *Thw. ms.* 3863.
D. ornithopoda, *Trin.* 369.
D. fuscescens, *Trin.* *D. ornithopoda*, var. β . 369.
954. *Rottboellia exaltata*, *L.* 364.
R. nigrescens, *Thw.* 364.
955. *Ophiurus lævis*, *Benth.* *Mnesithea*. 364.
956. *Manisuris granularis*, *Sw.* 364.
957. *Hemarthria compressa*, *Br.* 363.
958. *Ischæmum muticum*, *L.* 364.
I. rugosum, *Salisb.* 364.
I. barbatum, *Retz.* 364.
* *I. conjugatum*, *Roxb.* 365.
I. COMMUTATUM, *Hack. ms.* *I. semisagittatum*. 365.
I. laxum, *Br.* *I. nervosum*. 365.
I. ciliare, *Retz.* *Spodiopogon obliquivalvis*. 365.
Rat-tana, *S.*
I. timorensis, *Kunth*, var. *petiolatum*, *Hack. ms.* (C. P. 3168.)
I. pilosum, (*Nees*.) C. P. 3871.
I. ZEYLANICUM, *Hack. ms.* *I. falcatum*. 365.
I. pectinatum, *Trin.* 436.
959. *Heteropogon insignis*, *Thw.* 437.
H. hirtus, *Pers.* 368.
I-tana, *S.*
960. *Andropogon zeylanicus*, *Arn. (ex Benth.)* 365.
A. Nardus, *L.* *A. Martini*. 367.
Mána, *S.* (*Pengiri-mána*, *S.*, *Citronella Grass*, a cult. var.)
var. *distans*, *Nees* (sp.) *A. distans*. 367.
A. Schœnanthus, *L.*, var. *versicolor*, *Nees* (sp.) *A. versicolor*. 367.
A. lividus, *Thw.* 367.
A. filipendulus, *Hochst.*, var. *THWAITESII*, *Hack. ms.*
Anthistiria fasciculata. 366.
A. scandens, *Roxb.* 368.
A. rudis, *Steud.* 368.

- A. lancifolius*, *Trin.* 365.
A. caricosus, *L.* *Heteropogon concinnus*, 368.
A. POLYPTYCHOS, *Steud.* 367.
A. pertusus, *Willd.* 367.
A. punctatus, *Roxb.* *A. fascicularis*. 437.
A. VENUSTUS, *Thw.* 367.
A. muricatus, *Retz.* 368.
Seṇḍarā, *S.* *Vetti-vær*, *T.* *Cuscus Grass*.
961. *Chrysopogon aciculatus*, *Trin.* 366.
Tuttiri, *S.*
C. Wightianus, *Thw.* 366.
var. *LEUCANTHA*, *Thw.* 366.
C. montanus, *Trin.*
C. zeylanicus, *Thw.* 366.
962. *Sorghum halepense*, *Pers.* *Andropogon*. 366.
S. fulvum, *Beauv.* *Andropogon tropicus*. 366.
963. *Anthistiria Cymbaria*, *Roxb.* 436.
Karavuta-máná, *S.*
A. arguens, *Willd.* *A. ciliata*, var. *major*. 366.
A. ciliata, *Retz.* 366.
A. tremula, *Nees.* 366.
Pini-baru-tana, *S.*
A. heteroclita, *Roxb.* 366.
A. prostrata, *Willd.*
964. *Apluda aristata*, *L.* 364.
965. *Aristida adscensionis*, *L.* *A. cærulescens*. 370.
Et-tuttiri, *S.*
A. depressa, *Retz.* 370.
966. *Sporobolus indicus*, *Br.* 370.
S. virginicus, *Kunth.*
S. humifusus, *Kunth.*
S. orientalis, *Kunth.*
S. diander, *Beauv.* 370.
S. coromandelianus, *Kunth.*
967. † *Polypogon monspeliensis*, *Desf.* 370.
968. *Deyeuxia Royleana*, (*Trin.*) *Agrostis*. 370.
969. *ERIACHNE TRISETA*, *Nees.* 444 & 372.
Pini-tuttiri, *S.*
970. *Zenkeria elegans*, *Trin.* *Amphidonox Heynei*. 370.
Z. OBTUSIFLORA, *Benth.* *Amphidonax*. 370.
971. *Cœlachne brachiata*, *Munro.* *C. pulchella*. 373.
C. PERPUSILLA, *Thw.* 373.

972. *AVENA ASPERA*, *Munro*. 372.
973. *Cynodon Dactylon*, *Pers.* 371.
Arugam-pillu, T.
974. *Enteropogon melicoides*, *Nees*.
975. *Chloris barbata*, *Sw.* 371.
Mayuru-tana, S.
var. *decora*. *C. decorata*. 371.
C. digitata, *Steud.* 371.
976. *GYMNOPOGON RIGIDUS*, *Thw.* 372 & 444.
977. *TRIPOGON ZEYLANICUS*, *Nees*. 374.
* *Dinebra arabica*, *Jacq.*
978. *Eleusine indica*, *Gaertn.* 371.
Wal-kurakkan, *Bela-tana*, S.
(*E. coracana*, *Gaertn.*) *Kurakhan*, S. *Kaivaru*, *Kel-varagu*, T.
E. ægyptiaca, *Pers.* *Dactyloctenium*. 371.
Putu-tana, S.
979. *Leptochloa Neesii*, *Benth.* *Cynodon*. 371.
L. uniflora, *Hochst.* *Cynodon gracilis*. 371.
L. chinensis, *Nees*. 371.
* *L. filiformis*, *R. & S.*
[*Pommereula Cornucopiæ*, *L. f.*]
980. *Diplachne fusca*, *Beauv.* *Uralepis*. 372.
981. *Phragmites Roxburghii*, *Kunth.* 370.
Nala-gas, S.
982. *Elytrophorus articulatus*, *Beauv.* 374.
983. *Eragrostis brevifolia*, *Benth.* (C. P. 3250.)
E. unioides, *R. & S.* 373.
E. Brownii, *Nees*. 373.
E. zeylanica, *Nees*. 373.
E. orientalis, *Trin.* 373.
E. pilosa, *Beauv.* 373.
E. megastachya, *Link.* 373.
E. poæoides, *Beauv.* C. P. 3944.
E. paniculata, *Steud.* 373.
E. nutans, *Steud.* 373.
E. plumosa, *Link.* 373.
var. *maritima*, *Trim. ms.* (C. P. 927.)
? *E. viscosa*, *Trin.*
E. bifaria, *W. & A.* 373.
E. mucronata, *R. & S.* *Triticum repens*. 376.
984. *Centotheca lappacea*, *Desv.* 374.
985. *Lophatherum gracile*, *Brongn.* 374.

986. *Streptogyne crinita*, *Beauv.* 374.
 987. *Æluropus lagopoides*, *Trin.* 374.
 (*Dactylis glomerata*, *L.*)
 988. *Poa annua*, *L.* 372.
 989. *Brachypodium sylvaticum*, *R. & S.* 374.
 990. *Lepturus repens*, *Br.*
 991. *Oropetium Thomæum*, *Trin.* 373.
 992. *ARUNDINARIA DEBILIS*, *Thw.* 375.
A. FLORIBUNDA, *Thw.* 375 & *C. P.* 4023.
A. WALKERIANA, *Munro. A. Wightiana.* 444. (& *C. P.* 429.)
A. DENSIFOLIA, *Munro. C. P.* 3956.
 993. *Bambusa vulgaris*, *Wendl. B. Thouarsii.* 375.
Una, *S. Common Bamboo.*
B. spinosa, *Roxb. B. arundinacea.* 375.
Kaṭu-una, *S. Moongil, T. Spiny Bamboo.*
(B. nana, Roxb.) Chinese Bamboo. C. P. 4022.
 994. *Oxytenanthera Thwaitesii*, *Munro. Dendrocalamus mon-*
adelphus. 376.
 995. *TEINOSTACHYUM ATTENUATUM*, *Munro. Bambusa.* 375.
T. ? MACULATUM, *Trim. ms.*
Rana-baṭa-lī, *S.*
 996. *OCHLANDRA STRIDULA*, *Thw.* 376.
Baṭa-lī, *S.*
-

VASCULAR CRYPTOGRAMS.

150. Equisetaceæ.

997. *Equisetum debile*, *Roxb.* (C. P. 2577.)

151. Filices.

998. *Gleichenia linearis*, *Clarke.* *G. dichotoma.* 379.
Kekilla, S.
999. *CYATHEA SINGATA*, *Hk. & Grev.* 396.
C. HOOKERI, *Thw.* 396.
1000. *AMPHICOSMIA WALKERÆ*, *Moore.* *Cyathea.* 396.
1001. *Alsophila crinita*, *Hk.* 396.
A. glabra, *Hk.* *A. gigantea.* 396.
1002. *Diacalpe aspidioides*, *Bl.* 396.
1003. *Dennstædtia scabra*, *Moore.* *Dicksonia deltoidea.* 389.
1004. *Hymenophyllum tenellum*, *Kuhn.* *H. polyanthos* (part.)
(C. P. 3360.) 397.
H. exsertum, *Wall.* 397 & C. P. 4004.
H. polyanthos, *Sw.* (C. P. 3279.) 397.
H. Blumeum, *Spreng.* 397.
H. javanicum, *Spreng.* *H. crispatum.* 397.
H. Neesii, *Hk.* *H. tunbridgense.* 397.
1005. *Tricomanes Mottleyi*, *V. den Bosch.* C. P. 3972.
T. WALLII, *Thw. ms.* C. P. 3989.
T. exiguum, *Baker.* C. P. 3957.
T. neilgherrense, *Bedd.* *T. muscoides.* 397.
T. parvulum, *Poir.* C. P. 3991.
T. proliferum, *Bl.* 397.
T. digitatum, *Sw.* *Hymenophyllum corticola.* 397.
T. intramarginale, *Hk. & Grev.* 397.
T. pallidum, *Bl.* *T. glauco-fuscum.*
T. bipunctatum, *Poir.* *T. Filicula.* 397.
T. pyxidiferum, *L.* *T. proliferum* (part.) 397.
T. rigidum, *Sw.* 397.
1006. *Humata pedata*, *J. Sm.* *Davallia.* 388.
var. *vestita*, *Bl. (sp.) D. vestita.* 388.
1007. *Leucostegia pulchra*, *J. Sm.* *Dvallia.* 388.
L. hymenophylloides, *Bedd.* *Davallia affinis.* 389.
1008. *Prosaptia Emersoni*, *Presl.* *Davallia.* 389.
P. contigua, *Presl.* *Davallia.* 389.
1009. *Davallia elegans*, *Sw.* 389.
D. bullata, *Wall.* C. P. 3927.

1010. *Microlepia platyphylla*, *J. Sm.* *Davallia*. 389.
M. MAJUSCULA, *Moore.* *Davallia proxima*. 389.
M. Speluncæ, *Moore.* *Davallia polypodioides*. 389.
M. hirta, *J. Sm.* *Davallia*. 389.
M. strigosa, *Presl.* *Davallia*. 389.
1011. *Stenoloma chinense*, *Bedd.* *Davallia tenuifolia*. 389.
1012. *Lindsæa cultrata*, *Sw.* 388.
L. repens, *Thw.* 388.
var. *minor*, *Thw.* 388.
L. orbiculata, *Bedd.* *L. flabellulata*. 388.
var. *tenera*, *Bedd.* *L. tenera*. 388.
var. *SCHIZOPHYLLA*, *Baker* (sp., sub *Davallia*.)
C. P. 3903.
L. Lancea, *Bedd.* *L. caudata*. 388.
L. Walkeræ, *Hk.* 388.
1013. *Schizoloma lobata*, *J. Sm.* *Lindsæa nitens*. 388.
S. ensifolia, *J. Sm.* *Lindsæa*. 388.
var. *heterophylla*, *Dryand.* (sp.) C. P. 3861.
1014. *Adiantum lunulatum*, *Burm.* 387.
A. caudatum, *L.* Includes *A. rhizophorum*. 387.
A. Capillus-Veneris, *L.* 387.
† *A. æthiopicum*, *L.*
A. hispidulum, *Sw.* 387.
A. flabellulatum, *L.* 387.
1015. *Cheilanthes mysurensis*, *Wall.* 387.
C. LAXA, *Moore.* *C. varians*. 387.
C. tenuifolia, *Sw.* 387.
C. farinosa, *Kaulf.* 387.
1016. *Pellæa concolor*, *Bedd.* *Pteris geraniifolia*. 386.
P. Boivini, *Hk.* *Pteris*. 386.
P. falcata, *Fée.* C. P. 3933.
1017. *Pteris longifolia*, *L.* 386.
P. cretica, *L.* 386.
P. HOOKERIANA, *Agardh.* *P. cretica*, var. β . 386.
P. ensiformis, *Burm.* *P. crenata*. 386.
P. quadriaurita, *Retz.* 386.
var. *ludens*, *Thw.* 386.
P. biaurita, *L.* 387.
var. *argyræa*, *Thw. ms.* C. P. 3992.
P. patens, *Hk.* 386.
P. longipes, *G. Don.* C. P. 3945.
P. aquilina, *L.* 386.
Bracken.

1018. *Litobrochia marginata*, *Bedd.* *Pteris tripartita*. 387.
L. incisa, *Presl.* *Pteris aurita*. 387.
1019. *Ceratopteris thalictroides*, *Brongn.* 379.
1020. *Lomaria Patersoni*, *Spr.* *L. elongata*. 381.
1021. *Blechnum orientale*, *L.* 381.
1022. *Doodia dives*, *Kunze*, var. *ZEYLANICA*, *Hk.* 382.
1023. *Thamnopteris Nidus*, *Presl.* *Asplenium*. 383.
1024. *Asplenium ensiforme*, *Wall.* 383.
A. normale, *Don.* 384.
A. Wightianum, *Wall.* 383.
var. *vulcanicum*, *Bl.* (sp.)
A. tenerum, *Forst.* *A. elongatum*. 383.
A. lunulatum, *Sw.* *A. erectum*, and *A. resectum* (part)
(C. P. 1336.) 383.
var. *campitorachis*, *Kunze* (sp.)
A. Zenkerianum, *Kunze.* *A. persicifolium*. 383.
A. Gardneri, *Baker.* *A. macrophyllum* (C. P. 1340)
384.
A. falcatum, *Lam.* *A. caudatum* (C. P. 1339), *A.*
spathulinum (part) (C. P. 1341). 384, and C. P.
3891.
var. *caudatum*, *Forst.* (sp.) *A. falcatum* (C. P. 3140.)
384.
var. *macrophyllum*, *Sw.* (sp.)
A. furcatum, *Thunb.* 384.
var. *affine*, *Sw.* (sp.)? *A. spathulinum* (part) (C. P.
2905.) 384.
var. *planicaule*, *Wall.* (sp.) 384.
A. nitidum, *Sw.* 384.
var. *laserpitiifolium*, *Lam.* (sp.) 384.
A. formosum, *Willd.* 384.
A. unilaterale, *Lam.* *A. resectum* (part.) 383.
A. heterocarpum, *Wall.* 383.
A. varians, *Hk. & Grev.* 384.
A. tenuifolium, *Don.* 384.
A. rutæfolium, *Kunze.* *A. prolongatum*. 384.
1025. *Diplazium lanceum*, *Presl.* *Asplenium*. 385.
D. ZEYLANICUM, *Moore.* *Asplenium*. 385.
D. sylvaticum, *Sw.* *Asplenium*. 385.
var. *dentatum*, *Thw. ms.* C. P. 3892.
D. japonicum, *Bedd.* *Asplenium Thwaitesii*. 385.
D. POLYRRHIZON, (*Baker.*) C. P. 3951.
D. SCHKUHRII, *Bedd. (non J. Sm.) Asplenium.* 385.

- D. polypodioides, *Bl. Asplenium*. 385.
 var. asperum, *Bl. (sp.) (C. P. 1353.)*
 D. DECURRENS, *Bedd. A. polypodioides*, var. 385.
 D. latifolium, *Moore. Asplenium dilatatum*. 385.
 D. Smithianum, (*Baker.*) C. P. 3990.
 D. esculentum, *Sw. Asplenium*. 385.
 Miwana-kola, S.
 D. assimile, *Bedd. Asplenium australe*. 385.
 1026. *Athyrium Hohenackerianum*, *Moore. C. P. 3867.*
 A. macrocarpum, *Bedd. (non Fée). Asplenium*. 384.
 A. gymnogrammoides, *Bedd. Asplenium*. 385.
 A. stramineum, *J. Sm. (in Moore.) Asplenium nigripes*.
 384.
 A. Solenopteris, *Moore. Asplenium aspidioides*. 385.
 1027. *Allantodia javanica*, *Bedd. A. Brunoniana*. 385.
 1028. *Actiniopteris dichotoma*, *Bedd. A. radiata*. 386.
 1029. *Polystichum auriculatum*, *Presl. Aspidium*. 389.
 P. aculeatum, *Roth. Aspidium*. 390.
 var. angulare, *Presl. (sp.)*
 var. biaristatum, *Bl. (sp.) Asp. biaristatum*. 390.
 var. ANOMALUM, *Hk. & Arn. (sp.) Asp. anomalum*.
 390.
 P. amabile, *Bl. Aspidium*. 390.
 P. aristatum, *Presl. Asp. aristatum (part.)* 390. C. P.
 3937.
 P. conifolium, *Presl. Asp. aristatum (part.)* 390. C. P.
 3938.
 1030. *Aspidium subtriphyllum*, *Hk. 390.*
 A. polymorphum, *Wall. 390.*
 A. decurrens, *Presl. A. pteropus*. 390.
 A. REDUCTUM, *Baker ms. A. pteropus*, var. 433.
 A. cicutarium, *Sw. 390.*
 A. THWAITESII, (*Bedd.*) *A. cicutarium*, var. 390.
 A. Trimeni, (*Bedd.*) *A. giganteum*. 390.
 A. membranaceum, *Hk. A. giganteum*, var. *minor*. 390.
 1031. *Lastrea hirtipes*, *J. Sm. Aspidium*. 392.
 [*L. cuspidatum*, (*Baker.*)]
 L. WALKERÆ, *Hook. Polypodium*. 444.
 var. macrocarpa, *Bedd.*
 var. pinnatifida, *Bedd.*
 var. bipinnata, *Bedd.*
 L. calcarata, (*Bl.*) *Aspidium*. 391.
 var. MOONII, *Trim. ms. Var. β.* 391.

- L. Beddomii*, *J. Sm. Asp. gracilescens*. 391.
 [*L. ochthodes*, (*Kunze*).]
L. tylodes, *Moore. Aspidium*. 391.
L. syrmatica, (*Willd.*) *Asp. spectabile*. 392.
L. flaccida, *J. Sm. Aspidium*. 391.
L. Filix-mas, *Presl. Aspidium*. 392.
 var. *elongata*, *Sw. (sp.)*
L. sparsa, *Moore. Aspidium*. 392.
 var. *purpurascens*, *Bl. (sp.)* (C. P. 1370.)
 var. *undulata*, *Bedd. Asp. undulatum*. 444.
 var. *DELTOIDEA*, *Bedd.* (C. P. 1368.)
 var. *obtusissima*, *Mett. (sp.)* (C. P. 1369.)
 var. *MINOR*, *Bedd. Asp. undulatum* (part.) 444.
 var. *ZEYLANICA*, *Bedd.* C. P. 4007.
L. deparioides, *J. Sm. Aspidium*. 393.
L. THWAITESII, *J. Sm. Aspidium concinnum*. 392.
L. crenata, *Bedd.* C. P. 3888.
L. Blumei, *J. Sm. Aspidium*. 392.
L. recedens, *J. Sm. Aspidium*. 393.
L. dissecta, *Forst. Asp. membranifolium*. 390.
L. OBTUSILOBA, *J. Sm. Asp. Blumei*, var. 392.
L. Boryana, (*Willd.*) *Asp. divisum*. 392.
L. tenericaulis (*Wall.*) *Aspidium*. 393.
 1032. *Nephrodium Otaria*, *Baker. Aspidium*. 390.
 N. unitum, *Schott. Aspidium propinquum*. 391.
 N. pteroides, *J. Sm. Aspidium terminans*. 391.
 N. extensum, *Hook. Aspidium ochthodes*. 392.
 N. cucullatum, *Baker. Asp. unitum*. 391.
 ? *N. aridum*, *Baker.* C. P. 3271 (part).
 N. urophyllum, *Bedd. Polypodium granulosum*. 394.
 [*N. moulmeinense*, *Bedd.*] *Polypodium lineatum*. 439.
 & C. P. 3866.
 N. Arbuscula, *Schott. Aspidium*. 391.
 N. pennigerum, *Hk. Asp. abruptum* (part). 391.
 N. molle, *Schott. Aspidium*. 391.
 N. amboinense, *Presl. Aspidium extensum*. 391.
 N. truncatum, *Presl. Aspidium eusorum*. 391.
 1033. *Nephrolepis cordifolia*, *Presl. N. tuberosa*. 393.
 N. exaltata, *Schott.* 393.
 N. acuta, *Presl.* 393.
 N. ramosa, *Moore. N. obliterata*. 393.
 1034. *Oleandra musæfolia*, *Kunze. O. neriiformis*. 393.
 1035. *Phegopteris distans*, (*Don.*) *Polypodium paludosum*. 394.

- P. rufescens*, *Mett. Polypodium.* 394.
P. punctata, (*Thunb.*) *Polypodium rugulosum.* 394.
 1036. *Goniopteris prolifera*, *Presl. C. P.* 3916.
 1037. *Polypodium pilosiusculum*, *Hk.* (Includes *P. Wallii*, *Bedd.*) *C. P.* 3921.
 var. GLABRUM, Trim. ms. P. parasiticum. 393.
P. MEDIALE, Baker.
P. ZEYLANICUM, Mett. 393.
P. hirtellum, Bl. C. P. 3902.
P. CORNIGERUM, Baker. C. P. 4005.
P. CUCULLATUM, Nees. 394.
P. GLANDULOSUM, Hook. 394.
P. THWAITESII, Bedd. C. P. 3900.
P. decorum, Brack. 439.
 [*P. fuscatum, Bl.*]
P. obliquatum, Bl. 394.
P. repandulum, Mett. P. parvulum (part). (*C. P.* 1290.) 394.
P. subfalcatum, Bl. P. parvulum (part). (*C. P.* 3073.) 394.
 [*P. minutum, Bl.*]
 1038. *Nipholobolus lanceolatus, (L.) Polypodium adnascens.* 395.
 N. pannosus, (Mett) Polypodium Lingua. 395.
 N. fissus, Bl. Polypodium porosum. 395.
 N. Gardneri, Kunze. Polypodium. 395.
 1039. *Pleopeltis linearis, (Thunb.) Polypodium Wightianum.* 394.
 P. lanceolata, Presl. C. P. 3988.
 P. membranacea, (Don.) Polypodium. 395.
 P. punctata, (L.) Polypodium irioides. 395.
 P. hastata, (Thunb.) Polypodium oxylobum. 395.
 P. Pteropus, Moore. Polypodium tridactylon. 395.
 var. minor, Bedd.
 P. phymatodes, Moore. Polypodium. 395.
 P. nigrescens, (Bl.) Polypodium. 395.
 P. dilatata, (Wall.) C. P. 3973.
 P. quercifolia, (L.) Polypodium. 395.
 [*P. Linnæi, (Bory.)*]
 1040. *Monogramme paradoxa, Bedd. Vaginularia Jung-*
 kuhnii. 381.
 1041. *Leptogramme totta, J. Sm. Grammitis.* 382.
 [*Stegnogramme aspidioides. Bl. Grammitis.* 383..

1042. *Gymnogramme leptophylla*, *Desv.* C. P. 3934.
 * *G. Calomelanos*, *Kaulf.*, var. *dealbata*, *Moore.* *Silver Fern.*
1043. *Syngamme fraxinea*, *Bedd.* *Grammitis serrulata.* 382.
1044. *Loxogramme lanceolata*, *Presl.* *Grammitis.* 382.
L. involuta, *Presl.* *Grammitis.* 382.
1045. *Meniscium triphyllum*, *Sw.* 382.
M. Thwaitesii, *Hook.* 382.
1046. *Antrophyum reticulatum*, *Kaulf.* *Hemionitis.* 382.
A. plantagineum, *Kaulf.* *Hemionitis.* 382.
1047. *Vittaria elongata*, *Sw.* 438 & C. P. 981 (part).
V. lineata, *Sw.* 381.
V. scolopendrina, *Schk.* 381.
V. SULCATA, *Kuhn.* (C. P. 3807.) 438.
1048. *Tænitis blechnoides*, *Sw.* C. P. 3922.
1049. *Drymoglossum heterophyllum*, (*L.*) *D. piloselloides.* 381.
Mas-wenna, *S.*
1050. *Hemionitis arifolia*, (*Burm.*) *H. cordata.* 382.
1051. *Elaphoglossum conforme*, *Schott.* *Acrostichum marginatum.* 380.
E. latifolium, *J. Sm.* *Acrostichum laurifolium.* 380.
E. squamosum, *J. Sm.* 380. *Acrostichum.*
E. spathulatum, *Moore.* 380. *Acrostichum.*
1052. *Stenochlæna palustre*, (*Burm.*) *Acrostichum scandens.* 380.
Wel-bënduru, *S.*
 var. (abnorm.) *achilleifolia*, *Wall.* (sp., sub *Davallia*.)
1053. *Polybotrya appendiculata*, *J. Sm.* *Acrostichum.* 380.
1054. *Gymnopteris variabilis*, *Bedd.* *Acrostichum decurrens.* 381.
 var. *laciniata*, *Hook.* (C. P. 1316.)
 var. *lanceolata*, *Hook.* (sp.) (C. P. 1316 part.)
 var. *METALLICA*, *Bedd.* (sp.)
 var. *WALLII*, *Baker.* (sp.)
G. spicata, *Presl.* *Acrostichum.* 381.
G. quercifolia, *Bernh.* *Acrostichum.* 381.
G. contaminans, (*Wall.*) *Acrostichum repandum.* 380.
G. subcrenata, *Bedd.* *Acrostichum Hookerianum.* 380.
1055. *Acrostichum aureum*, *L.* 380.
Kéré-koku, *S.*
1056. *Osmunda javanica*, *Bl.* 379.
1057. *Schizæa digitata*, *Sw.* 379.

1058. *Lygodium dichotomum* Sw. *L. circinatum*. 379.
Et-pamba, S.
L. scandens Sw. 279.
Maha-pamba, S.
L. flexuosum, Sw. 437.
Hin-pamba, S.
1059. *Angiopteris evecta*, Hoffm. 379 & C. P. 3904.
1060. *Marattia fraxinea*, Sm. *M. sorbifolia*. 379.
1061. *Ophioglossum lusitanicum*, L.
O. vulgatum, L. 378.
* *O. bulbosum*, Mich. C. P. 3993.
O. pendulum, L. 378.
1062. *Helminthostachys zeylanica*, Hook. 378.
1063. *Botrychium daucifolium*, Wall. 378.
B. virginianum, Sw., var. *lanuginosum*, Wall. (sp.) 378.

152. Rhizocarpeæ.

1064. *Marsilea quadrifolia*, L. 378.
Diya-embul-embiliya, S. *Ara-keeré*, T.
M. minuta, L. *M. erosa*. 378 & C. P. 3968.
1065. *Azolla pinnata*, Br. 378.

153. Lycopodiaceæ.

1066. *Psilotum nudum*, (L.) *P. triquetrum*. 378.
Et-hawari, S.
1067. *Lycopodium Phlegmaria*, L. 377.
Maha-hedayá, S.
L. Hookeri, Wall. 377.
Kuda-hedayá, S.
L. serratum, Thunb. 377.
L. zeylanicum, Spring. (C. P. 1415.) *L. serratum*,
var. 377.
L. clavatum, L. 377.
L. complanatum, L. 377.
L. cernuum, L. 377.
Wanassa, *Badal-wanassa*, S.
L. carolinianum, L. 377.

154. Isoeteæ.

1068. *Isoetes coromandelina*. L. f.

155. Selaginellaceæ.

1069. *Selaginella rupestris*, Spring. 377.
S. plumosa, Baker. ("C. P. 1275.").

- S. ornithopodioides*, *Spring.* (*p. max. part.*) *S. concinna*
 & *S. atroviridis* (part) (C. P. 1184.) 377.
- S. COCHLEATA*, *Spring.* ("Moon.")
- S. caulescens*, *Spring.* 377.
- S. latifolia*, *Spring.* *S. caudata.* 377.
- S. proniflora*, *Baker.* *S. stolonifera* (part). 377, & C. P.
 3975, 3978, 3979.
- ? *S. ciliaris*, *Spring.* ("Koenig.")
- S. zeylanica*, *Baker.* ("Gardner 1417.")
- S. tenera*, *Spring.* *S. stolonifera* (part), *S. atroviridis*
 (part) (C. P. 1417.) 377.
- S. crassipes*, *Spring.* *S. atroviridis* (part) (C. P. 1274
 = 1418.) 377.
- S. brachystachya*, *Spring.* *S. stolonifera* (part) (C. P.
 1412, 1413.) 377, & C. P. 3974.
-

156. Characeæ.

1070. *Chara corallina*, *Klein.*
C. zeylanica, *Klein.*
C. Thwaitesii, *A. Br. ms.* (C. P. 238.)
1071. *Nitella acuminata*, *A. Br.*
N. pseudo-flabellata, *A. Br.*
-



INDEX.

[Natural Orders in SMALL CAPITALS; Synonyms in *italics*.]

Abelmoschus	93	Agyneia	693	Aneilema	865
Aberia	54	Ailantus	133	Anemone	3
Abrus	226	Alangium	350	Angiopteris	1059
Abutilon	88	Albizzia	269	Angracum	803
Acacia	268	Alchemilla	274	Ania	780
Acalypha	716	Aleurites	p. 81	Aniseia	533
Acampe	798	Alisma	901, 902	Anisochilus	624
ACANTHACEÆ	98	ALISMACEÆ	145	Anisomeles	630
Acanthephippium	778	Allæanthus	738	Anisophyllea	289
Acanthonotus	210	Allæophania	362	Anodendron	484
Acanthus	588	Allantodia	1027	Anogeissus	291
Achyranthes	646	Allium	855	ANONACEÆ	4
Acmena	296	Altmania	638	Anotis	366
Acorus	897	Allophylus	186	Anstrutheria	288
Acranthera	369	Alocasia	893	Anthistiria	963
Acrorychia	123	Aloe	851	Anthocephalus	354
Acrostichum	1055,	Alphonsea	24	Antiaris	742
	1051-4	Alpinia	835	Antidesma	704
Acrotrema	8	Alseodaphne	669	Antrophyum	1046
Actephila	692	Alsodeia	50	Apaturia	817
Actinopteris	1028	Alsophila	1001	Aphyllorchis	817
Actinodaphne	670	Alstonia	475	Apluda	964
Actinoschoenus	920	Alternanthera	617	Apocopis	952
Adansonia	p. 11	Alucisia	775	APOCYNACEÆ	84
Adenanthera	266	Alysicarpus	224	Apodytes	160
Adenochlæna	713	Alyxia	471	Apollonias	666
Adenosma	544, 579	Amanoa	691	Aponogeton	903
Adenostemma	404	AMARANTACEÆ	103	Aporosa	702
Adhatoda	598	Amarantus	640	Apostasia	825
Adiantum	1014	AMARYLLIDÆÆ	129	Appendicula	805
Adina	355	Ameletia	305	ARACEÆ	142
Adinandra	75	Ammannia	305	ARALIACEÆ	64
Æceoclades	797	Amomum	830, 831	Ardisia	451
Æchmandra	330, 331	Amoora	146, 147	Areca	871
Ægiceras	452	Amorphophallus	889, 890	Argyrea	531, 532
Æginetia	560, 562	AMPELIDÆÆ	39	Arisæma	886
Ægle	p. 16	Amphicosmia	1000	Aristida	965
Æluropus	987	Amphidonax	970	Aristolochia	659
Aerides	795, 793, 796	ANACARDIACEÆ	42	ARISTOLOCHIACEÆ	108
Ærna	645	Anacardium	p. 21	Artabotrys	16
Æschynanthus	564	Anætochilus	812	Artanema	548
Æschynomene	218	Anagallis	p. 50	Artemisia	429
Ætheilema	583	Anamirta	28	Arthrocnemum	650
Aganosma	483	Anaphalis	417	Arthrostylis	920
Ageratum	p. 46	Anaxagorea	19	Artocarpus	744
Aglaia	145	ANCISTROCLADEÆ	21 bis.	Arum	887, 888
Agrimonia	275	Ancistrocladus	86	Arundina	785
Agrostis	968	Andrographis	593	Arundinaria	992
Agrostistachys	711	Andropogon	960, 962	Arundinella	943

ASCLEPIADEÆ	58	Bombax	95	Capsicum	p. 61.
Asclepias	p. 55	Bonnaya	552	Carallia	287
Asparagus	850	BOBAGINÆÆ	89	Caralluma	506
Aspidium. 1030, 1029,		Borassus	879	Carapa	149
1031, 1032		Borreria	363, 397	Cardamine	41
Asplenium. 1024, 1023,		Boswellia	p. 16	Cardanthera	579
1025, 1026		Botrychium	1063	Cardiospermum	184
Asystasia	591	Bohicerosia	507	Carex	925
Atalantia	131	Bouchea	607	Careya	298
Ate	822	Brachypodium	989	Carica	p. 37
Athyrium	1026	Brachyrhamphus	435	Carissa	469
Atriplex	649	Bragantia	658	Carum	p. 39
Atylosia	243	Brassica	p. 4	CARYOPHYLLACEÆ	14
Avena	972	Breweria	537	Caryota	874
Averrhoa	p. 14	Breynia	697	Casearia	315
Avicennia	617	Bridelia	690	Cassia	257
Axinandra	311	Brucea	p. 16	Cassytha	673
Azadirachta	141	Bruguiera	286	Casuarina	p. 86
Azima	467	Bryonia	326	CELASTRACEÆ	37
Azolla	1065	Bryophyllum	p. 31	Celastrus	169
Baissea	482	Buchanania	197	Celosia	637
Balanophora	837	Bulbophyllum	773	Celsia	543
BALANOPHORACEÆ	119	Bupleurum	344	Celtis	732
Balsamodendrum	137	BURMANNIACEÆ	125	Centipeda	428
Bambusa	993, 995	Burmanna	767	Centotheca	984
Barleria	589	BURSERACEÆ	32	Centranthera	557
Barringtonia	297	Bursinopetulum	351	Centrosæma	p. 26
Basella	653	Butea	236	Centrostachys	646
Bassia	457	CACTACEÆ	61	Cephalandra	325
Batatas	533	Cadaba	46	Cephalostigma	442
Bauhinia	263	Casalpinia	254, 255	Cerasiocarpum	331
Baumea	923	Cajanus	p. 26	Cerastium	61
Begonia	335	Calamintha	628	CERATOPHYLLACEÆ	121
BEGONIACEÆ	59	Calamids	878	Ceratophyllum	758
Beilschmiedia	666	Calanthe	784	Ceratopteris	1019
Benincasa	p. 38	Calceolaria	p. 62	Cerbera	473
BERBERIDEÆ	6	Callicarpa	610	Ceriops	285
Berberis	37	Callitriche	283	Ceropegia	505
Bergia	68	Calonyction	533	Chaetocarpus	724
Berrya	105	Calophanes	581	Chailletia	152
Bidaria	496	Calophyllum	71	CHAILLETIACEÆ	34
Bidens	427	Calosanthus	571	Chamabaina	754
BIGNONIACEÆ	96	Calotropis	491	Chamaraphis	933
Biophytum	117	Campanula	442	Chamissoa	638
Bixa	p. 5	CAMPANULACEÆ	73	Championia	567
BIXINEÆ	11	Campbellia	561	Chara	1070
Blachia	709	Camposperma	201	CHARACEÆ	156
Blainvillea	424	Canarium	138	Chasalia	392
Blechnum	1021	Canavalia	237	Chavica	660
Blepharis	587	Canna	838	Cheilanthes	1015
Blepharispermum	416	Canscora	515	CHENOPODIACEÆ	104
Blumea	412, 413	Cansjera	156	Chenopodium	648
Blyxa	762	Canthium	385	Chickrassia	150
Bocagea	26	CAPPARIDEÆ	9	Chierostylis	814
Boehmeria	753	Capparis	47	Chionachne	938
Boerhaavia	635	CAPRIFOLIACEÆ	66	Chionanthus	463
				Chirita	566

CHLORANTHACEÆ	110	CORNACEÆ	65	<i>Dactylis</i>	p. 109
<i>Chloranthus</i>	662	<i>Corymbis</i>	808	<i>Dactyloctenium</i>	978
<i>Chloris</i>	975	<i>Corypha</i>	877	<i>Dædalacanthus</i>	584
<i>Chlorophytum</i>	853	<i>Coscinium</i>	29	<i>Dæmia</i>	493
<i>Chloroxylon</i>	151	<i>Cosmos</i>	p. 48	<i>Dalbergia</i>	248
<i>Choucrumorpha</i>	481	<i>Cosmostigma</i>	499	<i>Dalechampia</i>	727
<i>Christisonia</i>	562	<i>Costus</i>	834	<i>Dalzellia</i>	655
<i>Chrozophora</i>	712	<i>Cottonia</i>	792	<i>Daphnidium</i>	672
<i>Chrysogonum</i>	420	<i>Covellia</i>	741	<i>Daphniphyllum</i>	703
<i>Chrysophyllum</i>	453	CRASSULACEÆ	47	<i>Dasygaulus</i>	457
<i>Chrysopogon</i>	961	<i>Cratæva</i>	45	DATISCEÆ	60
<i>Cinnamomum</i>	667	<i>Crawfordia</i>	516	<i>Datura</i>	542
<i>Gipadessa</i>	143	<i>Crepis</i>	434	<i>Davallia</i>	1006—1011
<i>Cirrhopetalum</i>	774	<i>Cressa</i>	538	<i>Debregeasia</i>	757
<i>Cissampelos</i>	34	<i>Crinum</i>	843	<i>Delima</i>	6
<i>Cissus</i>	182	<i>Crossandra</i>	590	<i>Deudrobium</i>	772
<i>Citrullus</i>	324	<i>Crotalaria</i>	208	<i>Dendrocalamus</i>	994
<i>Cladium</i>	923, 922	<i>Croton</i>	705	<i>Dendrocolla</i>	794
<i>Claoxylon</i>	714, 715	CRUCIFERÆ	8	<i>Dendrolobium</i>	225
<i>Clausena</i>	127	<i>Crudia</i>	260	<i>Dennstaëdia</i>	1003
<i>Cleghornia</i>	482	<i>Cryptocarya</i>	665	<i>Dentella</i>	360
<i>Cleidion</i>	721	<i>Cryptocoryne</i>	883	<i>Derris</i>	251
<i>Cleisostoma</i>	800	<i>Cryptolepis</i>	487	<i>Desmanthus</i>	p. 29
<i>Cleistanthus</i>	691	<i>Cryptostylis</i>	818	<i>Desmodium</i>	225
<i>Clematis</i>	1	<i>Ctenolepis</i>	332	<i>Desmostemon</i>	708
<i>Cleome</i>	42	<i>Cucumis</i>	323	<i>Detarium</i>	260
<i>Clerodendron</i>	614, 615	<i>Cucurbita</i>	p. 38	<i>Deyenzia</i>	908
<i>Cleyera</i>	74	CUCURBITACEÆ	58	<i>Diacalpe</i>	1002
<i>Clinogyne</i>	836	<i>Cudrania</i>	743	<i>Dialium</i>	259
<i>Clitoria</i>	241	<i>Cudranus</i>	743	<i>Dianella</i>	854
<i>Cnemidia</i>	809	<i>Cullenia</i>	97	<i>Dianthera</i>	p. 68
<i>Cocculus</i>	32	<i>Curculigo</i>	842	<i>Dicellostyles</i>	92
<i>Cochlospermum</i>	p. 5	<i>Curcuma</i>	829	<i>Dicerma</i>	225
<i>Cocos</i>	p. 96	<i>Cuscuta</i>	539	<i>Dichilanthe</i>	383
<i>Celachne</i>	971	<i>Cyanospermum</i>	246	<i>Dichopsis</i>	456
<i>Celodiscus</i>	717	<i>Cyanotis</i>	806	<i>Dichrocephala</i>	405
<i>Celogyne</i>	782	<i>Cyathæa</i>	999, 1000	<i>Dichrostachys</i>	267
<i>Coffea</i>	388	<i>Cyathocalyx</i>	15	<i>Dicksonia</i>	1003
<i>Coix</i>	p. 106	<i>Cyathula</i>	641	<i>Dicliptera</i>	603
<i>Coldenia</i>	523	CYCADEÆ	123	<i>Dicraea</i>	656
<i>Coleus</i>	623	<i>Cycas</i>	759	<i>Didymocarpus</i>	565
<i>Colocasia</i>	892, 891, 893	<i>Cyclea</i>	35	<i>Dienia</i>	769
<i>Colubrina</i>	180	<i>Cyclostemon</i>	700	<i>Digera</i>	639
COMBRETACEÆ	51	<i>Cylindrochilus</i>	794	<i>Dillenia</i>	11
<i>Combretum</i>	293	<i>Cymbidium</i>	787	DILLENIACEÆ	2
<i>Commelina</i>	864	<i>Cymodocea</i>	906	<i>Dimeria</i>	953
COMMELINACEÆ	136	<i>Cynanchum</i>	494	<i>Dimorphocalyx</i>	710
COMPOSITEÆ	70	<i>Cynoctonum</i>	494	<i>Dioclea</i>	238
CONNARACEÆ	43	<i>Cynodon</i>	973, 979	<i>Dioscorea</i>	846
<i>Connarus</i>	204	<i>Cynoglossum</i>	528	DIOSCOREACEÆ	131
<i>Conocarpus</i>	291	<i>Cynometra</i>	258	<i>Diospyros</i>	460
CONVOLVULACEÆ	90	CYPERACEÆ	148	<i>Dipcadi</i>	856
<i>Convolvulus</i>	535	<i>Cyperus</i>	908	<i>Diplachne</i>	980
<i>Conyza</i>	411, 409	<i>Cyphostigma</i>	831	<i>Diplacrum</i>	924
<i>Corallocarpus</i>	330	<i>Cyrtopera</i>	790	<i>Diplazium</i>	1025
<i>Corchorus</i>	108	<i>Cyrtopodium</i>	790	<i>Diplocentrum</i>	802
<i>Cordia</i>	521	<i>Cyrtosia</i>	806	<i>Diplospora</i>	379

DIPSACACEÆ	69	<i>Epistylum</i>	695	<i>Garcinia</i>	70
<i>Dipsacus</i>	401	<i>Epithema</i>	569	<i>Gardenia</i>	376
DIPTEROCARPACEÆ	21	<i>Epithimia</i>	380	<i>Garnotia</i>	942
<i>Dipterocarpus</i>	78	EQUISETACEÆ	150	<i>Gastrodia</i>	820
<i>Dischidia</i>	502	<i>Equisetum</i>	997	<i>Gaultheria</i>	444
<i>Discospermum</i>	379	<i>Eragrostis</i>	983	<i>Geissaspis</i>	p. 23
<i>Disperis</i>	824	<i>Eranthemum</i>	592, 601	<i>Gelonium</i>	725
<i>Disporum</i>	860	<i>Eria</i>	775	<i>Geniosporum</i>	619
<i>Dittelasma</i>	p. 20	<i>Eriachne</i>	969	<i>Gentiana</i>	517
<i>Dodonæa</i>	193	ERICACEÆ	75	GENTIANACEÆ	87
<i>Dolichandrone</i>	572	<i>Ericybe</i>	529	<i>Geodorum</i>	788
<i>Dolichos</i>	242	<i>Erigeron</i>	409	<i>Geophila</i>	393
<i>Doodia</i>	1022	<i>Eriocaulon</i>	907	GERANIACEÆ	28
<i>Doona</i>	83	ERIOCAULONÆÆ	147	<i>Geranium</i>	115
<i>Dopatrium</i>	547	<i>Eriochloa</i>	927	GESNERACEÆ	95
<i>Doritis</i>	793	<i>Eriodendron</i>	96	<i>GINALLOA</i>	684
<i>Doronicum</i>	433	<i>Eriosema</i>	245	<i>Girardinia</i>	747
<i>Dorstenia</i>	740	<i>Erythrina</i>	232	<i>Gironniera</i>	734
<i>Dracæna</i>	852	<i>Erythrospermum</i>	52	<i>Gisekia</i>	341
<i>Dregea</i>	500	<i>Erythroxylam</i>	112	<i>Givotia</i>	706
<i>Drosera</i>	280	<i>Engenia</i>	296	<i>Gleichenia</i>	998
DROSERACEÆ	48	<i>Eulophia</i>	786	<i>Gleniea</i>	188
<i>Drymispermum</i>	678	<i>Enonymus</i>	164	<i>Glinus</i>	340
<i>Drymoglossum</i>	1049	<i>Eupatorium</i>	p. 46	<i>Globba</i>	826
<i>Dumasia</i>	228	<i>Euphorbia</i>	688	<i>Glochidion</i>	695
<i>Dunbaria</i>	244	EUPHORBIACEÆ	120	<i>Gloriosa</i>	859
<i>Dysophylla</i>	626	<i>Eurya</i>	76	<i>Glossocarya</i>	615
<i>Dysoxylum</i>	144	<i>Euzolus</i>	640	<i>Glossostigma</i>	555
<i>Ebermaiera</i>	578	<i>Evodia</i>	120	<i>Glycine</i>	229, 230
EBENACEÆ	80	<i>Evolvulus</i>	536	<i>Glycosmis</i>	124
<i>Ecbolium</i>	601	<i>Exacum</i>	512	<i>Glyptopetalum</i>	165
<i>Eclipta</i>	423	<i>Excæcaria</i>	730	<i>Gmelina</i>	612
<i>Ehretia</i>	522	<i>Fagraea</i>	509	<i>Gnaphalium</i>	p. 47, 417, 418
ELÆAGNACEÆ	116	<i>Falconeria</i>	728	<i>Gomphandra</i>	159
<i>Elæagnus</i>	680	<i>Fergusonia</i>	363	<i>Gomphia</i>	136
<i>Elæocarpus</i>	109	<i>Feronia</i>	132	<i>Goniopteris</i>	1036
<i>Elæodendrum</i>	172	FICOIDEÆ	62	<i>Goniothalamus</i>	20
<i>Elaphoglossum</i>	1051	<i>Ficus</i>	741	GOODENOVIACEÆ	72
ELATINÆÆ	17	FILICES	151	<i>Goodyera</i>	815
<i>Elatostema</i>	751	<i>Filicium</i>	139	<i>Gordonia</i>	77
<i>Eleiotis</i>	220	<i>Fimbristylis</i>	911	<i>Gouania</i>	181
<i>Elephantopus</i>	403	<i>Firmiana</i>	98	GRAMINÆÆ	149
<i>Elettaria</i>	832, 830	<i>Flacourtia</i>	53	<i>Grammitis</i>	1041, 1043, 1044
<i>Eleusine</i>	978	<i>Flagellaria</i>	868	<i>Grangea</i>	406
<i>Ellipanthus</i>	205	FLAGELLARIACEÆ	137	<i>Graptophyllum</i>	p. 68
<i>Elytraria</i>	576	<i>Flemingia</i>	247	<i>Grewia</i>	106
<i>Elytrophorus</i>	982	<i>Fleurya</i>	745	<i>Griffithia</i>	375
<i>Embelia</i>	450	<i>Floscopa</i>	867	<i>Grisea</i>	306
<i>Emilia</i>	431	<i>Fluggea</i>	696	<i>Grumilea</i>	391
<i>Empusa</i>	771	<i>Freycinetia</i>	881	<i>Guatteria</i>	18
<i>Enhalus</i>	764	<i>Fuirena</i>	913	<i>Guazuma</i>	p. 12
<i>Enicostema</i>	514	<i>Gaertnera</i>	511	<i>Guettarda</i>	381
<i>Entada</i>	265	<i>Galactia</i>	234	<i>Guilandina</i>	254
<i>Enteropogon</i>	974	<i>Galeola</i>	806	GUTTIFERÆ	19
<i>Epaltes</i>	414	<i>Galium</i>	399	<i>Gymnema</i>	496
<i>Epipogum</i>	821				

Gymnogramme . . .	1042	Hugonia . . .	111	Kadsura . . .	13
Gymnopetalum . . .	320	Humata . . .	1006	Kaempferia . . .	827
Gymnopogon . . .	976	Humboldtia . . .	262	Kalanchoe . . .	279
Gymnopteris . . .	1054	Hunteria . . .	472	Kanilia . . .	286
Gymnosporia . . .	170	Hydnocarpus . . .	56	Kayea . . .	72
Gymnostachyum . . .	594	Hydrilla . . .	760	Kendrickia . . .	301
Gynandropsis . . .	43	Hydrobryum . . .	656	Kirganelia . . .	695
Gynostemma . . .	333	Hydrocera . . .	119	Klugia . . .	568
Gynura . . .	430	HYDROCHARIDÆE . . .	124	Knoxia . . .	384
Gyrinops . . .	679	Hydrocotyle . . .	342	Kokoona . . .	167
Gyrocarpus . . .	294	Hydrolea . . .	520	Kurrimia . . .	171
		Hydrophylax . . .	396	Kyllinga . . .	909
Habenaria . . .	822	HYDROPHYLLACEÆ . . .	88		
HÆMODORACEÆ . . .	128	Hygropyza . . .	939	LABIATÆ . . .	100
Halophila . . .	766	Hygrophila . . .	580	Lablab . . .	242
HALORAGÆE . . .	49	Hymenocallis . . .	p. 93	Lactuca . . .	435
Harpalosia . . .	64	Hymenophyllum . . .	1004,	Lagarosiphon . . .	761
Harpullia . . .	192		1005	Lagascea . . .	p. 48
Hedera . . .	348, 349	HYPERICACEÆ . . .	18	Lagenandra . . .	884
Hedychium . . .	828	Hypericum . . .	69	Lagenaria . . .	p. 38
Hedyotis 364, 363, 365-6		Hypolytrum . . .	915, 917	Lagenophora . . .	408
Hedysarum . . .	225	Hyopsis . . .	813	Lagerstrœmia . . .	309
Heleocharis . . .	910	Hyptianthera . . .	377	Laggera . . .	413
Helicia . . .	675	Hyrtanandra . . .	755	Lagunea . . .	93
Helichrysum . . .	418			Lantana . . .	605
Helicteres . . .	100	Ichnanthus . . .	330	Laportea . . .	746
Heligme . . .	478	Ichnocarpus . . .	485	Lappago . . .	945
Helophytum . . .	526	ILICINÆE . . .	36	Lasia . . .	895
Heliotropium . . .	526	Ilex . . .	163	Lasianthera . . .	158
Helminthostachys . . .	1062	Ilysanther . . .	551	Lasianthus . . .	394
Helosciadium . . .	345	Impatiens . . .	118	Lasiosiphon . . .	677
Hemarthria . . .	957	Imperata . . .	948	Lastrea . . .	1031
Hemicyclia . . .	699	Indigofera . . .	210	Launca . . .	436
Hemidesmus . . .	486	Ionidium . . .	49	LAURACEÆ . . .	113
Hemigyrosa . . .	185	Iphigenia . . .	858	Lawsonia . . .	308
Hemionitis . . .	1050, 1046	Ipomœa . . .	533	Lecanthus . . .	749
Heptapleurum . . .	349	Ipsœa . . .	777	Ledebouria . . .	857
Heracleum . . .	347	Isachne . . .	928	Leea . . .	183
Heritiera . . .	99	Isanthera . . .	570	Lcersia . . .	941
Hernandia . . .	674	Ischæmum . . .	958	LEGUMINOSÆ . . .	44
Herpestis . . .	546	ISOETÆE . . .	154	Lemna . . .	898
Heteria . . .	816	Isoetes . . .	1068	LEMNACEÆ . . .	143
Heteropogon . . .	959, 960	Isolepis . . .	911, 912	LENTIBULARIACEÆ . . .	94
Heterostemma . . .	501	Isonandra . . .	455, 456	Leonotis . . .	632
Hewittia . . .	534	Isotoma . . .	p. 49	Lepidagathis . . .	595
Heylandia . . .	207	Ixora . . .	386	Lepironia . . .	918
Hibiscus . . .	93, 94			Leptadenia . . .	504
Hippocratea . . .	173	Jambosa . . .	296	Leptaspis . . .	937
Hiptage . . .	113	Jasminum . . .	462	Leptochloa . . .	979
Holarrhena . . .	477	Jatropha . . .	p. 81	Leptogramme . . .	1041
Holoptelea . . .	731	Jonesia . . .	261	Lepturus . . .	990
Homalium . . .	317	Josephia . . .	781	Lettsomia . . .	532
Homonoia . . .	723	Julostylis . . .	91	Leucœna . . .	p. 29
Hopea . . .	82	JUNCACEÆ . . .	138	Leucas . . .	631
Hoppea . . .	413	Juncus . . .	870	Leucocodon . . .	370
Hortonia . . .	664	Jussiaea . . .	312	Leucostegia . . .	1007
Hoya . . .	503, 500	Justicia . . .	597, 598	Ligustrum . . .	465

LILIACEÆ . . .	133	Medinilla . . .	303	Mundulea . . .	212
Limacia . . .	31	Melanthesa . . .	697	Munronia . . .	140
Limnanthemum . . .	519	Melastoma . . .	300	Murraya . . .	126
Limnophila . . .	545	MELASTOMACEÆ . . .	53	Musa . . .	839
Limnophyton . . .	902	Melia . . .	142	Mussaenda . . .	368
Limonia . . .	128	MELIACEÆ . . .	33	Myniactis . . .	407
LINACEÆ . . .	25	Meliosma . . .	195	Myriogyne . . .	428
Lindenbergia . . .	544	Melochia . . .	102	Myriophyllum . . .	282
Lindera . . .	672	Melothria . . .	329	Myristica . . .	663
Lindsaea . . .	1012, 1013	Memecylon . . .	304	MYRISTICACEÆ . . .	111
Linociera . . .	463	Meniscium . . .	1045	Myrsine . . .	449
Linum . . .	110	MENISPERMACEÆ . . .	5	MYRSINEÆ . . .	78
Liparis . . .	771	Mentha . . .	627	MYRTACEÆ . . .	52
Lipocarpa . . .	914	Mesua . . .	73	Mystacidium . . .	803
Lippia . . .	606	Mezoneurum . . .	256		
Litobrochia . . .	1018	Michelia . . .	12	NAIADACEÆ . . .	146
Litsea . . .	671	Microcarpaea . . .	553	Naias . . .	905
Lobelia . . .	439	Micrococca . . .	715	Naravelia . . .	2
LOGANIACEÆ . . .	86	Microdesmis . . .	p. 81	Nargedia . . .	377
Logania . . .	1020	Microglossa . . .	410	Nasturtium . . .	40
Lophatherum . . .	985	Microlepia . . .	1010	Nauclea . . .	357, 353-6
LOBANTHACEÆ . . .	117	Micromelum . . .	125	Nechamandra . . .	761
Loranthus . . .	681	Microhynchus . . .	436	Nelsonia . . .	577
Loxococcus . . .	872	Microstachys . . .	729	Nelumbium . . .	39
Loxogramme . . .	1044	Microstylis . . .	769	NEPENTHACEÆ . . .	107
Ludwigia . . .	313	Microtropis . . .	166	Nepenthes . . .	657
Luffa . . .	321	Miliusa . . .	23	Nephelium . . .	190, 189
Lnisia . . .	791, 792	Millingtonia . . .	p. 64	Nephrodium . . .	1032
Lumnitzera . . .	292	Milnea . . .	145	Nephrolepis . . .	1033
Luvulga . . .	129	Mimosa . . .	p. 29	Neptunia . . .	264
LYCOPODIACEÆ . . .	153	Mimusops . . .	458	Nesaea . . .	p. 36
Lycopodium . . .	1067	Mirabilis . . .	p. 71	Neurocalyx . . .	361
Lygodium . . .	1058	Mischodon . . .	701	Nicandra . . .	p. 61
Lysimachia . . .	447	Mitrasacme . . .	508	Nipa . . .	875
LYTHACEÆ . . .	54	Mitrephora . . .	21	Niphobolus . . .	1038
		Mnesithea . . .	955	Nitella . . .	1071
Maba . . .	459	Modecca . . .	318	Nothopegia . . .	200
Macaranga . . .	722	Moesa . . .	448	Nothosærua . . .	644
Machilus . . .	668	Mohlana . . .	p. 73	Notonia . . .	432
Macreightia . . .	459	Mollugo . . .	340	Notothixos . . .	683
Mærua . . .	44	Momordica . . .	322	NYCTAGINEÆ . . .	102
MAGNOLIACEÆ . . .	3	MONIMIACEÆ . . .	112	Nyctanthes . . .	p. 53
Mallea . . .	143	Monocera . . .	109	Nymphæa . . .	38
MALPIGHIACEÆ . . .	26	Monochilus . . .	813	NYMPHÆACEÆ . . .	7
MALVACEÆ . . .	22	Monochoria . . .	861		
Malvastrum . . .	p. 10	Monogramme . . .	1040	Oberonia . . .	770
Mallotus . . .	720	Monoporandra . . .	85	Ochlandra . . .	996
Mangifera . . .	196	Monothecium . . .	596	OCNACEÆ . . .	31
Manisuris . . .	956	Moonia . . .	420	Ochna . . .	135
Mapania . . .	916	Morinda . . .	389	Ochrosia . . .	474
Mappia . . .	161	Moringa . . .	p. 21	Ocimum . . .	618
Maranta . . .	836, 837	MORINGÆ . . .	p. 21	Octarrhena . . .	794, bis.
Marattia . . .	1060	Morocarpus . . .	757	Odina . . .	198
Marsdenia . . .	497	Moschosma . . .	620	OLACINEÆ . . .	35
Marsilea . . .	1064	Mucuna . . .	231	Olax . . .	154
Martynia . . .	p. 64	Mukia . . .	327	Oldenlandia . . .	365
Mastixia . . .	351	Muldera . . .	660	Olea . . .	464

OLIFACEÆ	82	Pellaea	1016	Podadenia	718
Oleandra	1034	Pellionia	750	Podochilus	804
ONAGRACEÆ	65	Peltophorum	255	PODOSTEMACEÆ	106
Oncosperma	873	Pemphis	307	Podostemon	656
<i>Ophelia</i>	518	Pennisetum	p. 106	Pogonatherum	951
Ophioglossum	1061	Pentatropis	492	Pogonia	819
Ophiopogon	840	Peperomia	661	<i>Pogonotrophe</i>	741
Ophiorrhiza	367	Peplidium	554	Pogostemon	625
<i>Ophioxylon</i>	470	Pericopsis	253	<i>Polanisia</i>	42
Ophiurus	955	Peristrophe	604	Pollia	863
Opilia	157	<i>Peristylus</i>	822	Pollinia	950
Oplismenus	931	Perotis	946	Polyalthia	18
Opuntia	p. 39	Persea	669	Polyhotrya	1053
ORCHIDEÆ	126	Pestalozzia	333	Polycarpæa	65
<i>Oreocnide</i>	756	Peucedanum	346	Polycarpon	64
Ormocarpum	219	Phaius	779	Polygala	58
OROBANCHACEÆ	93	Phaleria	678	POLYGALACEÆ	13
Oropetium	991	<i>Pharbitis</i>	533	POLYGONACEÆ	105
Orophea	25, 26	Phaseolus	239	Polypodium	1027, 1032
Oroxylum	571	Phaylopsis	583	1035, 1038, 1039	
Orthosiphon	621	Phegopteris	1035	Polypogon	967
Oryza	940	Phoenix	876	Polyscias	348
Osebeckia	299	Pholidota	783	Polystachya	789
Osmelia	316	Photinia	277	Polystichum	1029
Osmunda	1056	Phragmites	981	Pometia	191
Ostodes	708	Phreatia	776	Pongamia	250
Osyris	685	Phrynium	837	PONTERIACEÆ	134
Ottelia	763	Phyllanthus	695	Portulaca	66
Oxalis	116, 117	Phyllocllamys	736	PORTULACACEÆ	15
Oxystelma	490	<i>Phyllodium</i>	225	<i>Posidonia</i>	765
Oxytenanthera	994	Physalis	p. 61	Potamogeton	904
		Physurus	811	Potentilla	273
<i>Pachycentria</i>	301	Phytolacca	p. 73	Poterium	276
Pachygone	36	PHYTOLACCACEÆ	p. 72	<i>Pothomorphe</i>	660
Pachystoma	777	Pilea	748	Pothos	896
Polenga	698	Pimpinella	345	Pouzolzia	755
<i>Palmbia</i>	346	Piper	660	Premna	611
PALMÆ	139	PIPERACEÆ	109	PRIMULACEÆ	77
<i>Panax</i>	p. 40	Pisonia	636	Prismatomeris	390
Pancratium	844	Pistia	885	Priva	609
PANDANACEÆ	140	Pithecolobium	270	Procris	752
<i>Pandanophyllum</i>	916	PITTOSPORACEÆ	12	Prosaptia	1008
Pandanus	880	Pittosporum	57	<i>Prosorus</i>	695
Panicum	929, 928, 931, 932, 933	Pityranthe	104	PROTEACEÆ	114
Paramignya	130	<i>Pladera</i>	513	Pseudarthria	222
<i>Paritium</i>	93	PLANTAGINEÆ	101	Pseudocarapa	147
Parochetus	209	Plantago	634	Psidium	p. 32
Parsonsia	478	<i>Platanthera</i>	822	Psilotrichum	643
Paspalum	926	<i>Platea</i>	159	Psilotum	1066
Passiflora	p. 37	Plecosperrum	739	Psoralea	211
PASSIFLORACEÆ	57	Plectranthus	622	Psychotria	391
Pavetta	387	Pleopeltis	1039	Pteris	1017, 1016
Pavonia	90	Pleurostylia	168	1018	
PEDALIACEÆ	97	PLUMBAGINEÆ	76	Pterocarpus	249
Pedalinm	574	Plumbago	446	<i>Pteroloma</i>	225
Pedicularis	559	Plumeria	p. 54	Pterospermum	101
		Poa	988	<i>Pterostigma</i>	544

<i>Pterygota</i>	98	<i>Sageretia</i>	179	<i>Sebastiana</i>	729
<i>Ptilotus</i>	643	<i>Sagina</i>	p. 6	<i>Secamone</i>	488
<i>Ptychosperma</i>	872	<i>Salacia</i>	173, 174	<i>Selaginella</i>	1069
<i>Ptyssiglottis</i>	600	<i>Salicornia</i>	651	<i>SELAGINELLACEÆ</i>	155
<i>Pnpalia</i>	642	<i>Salmalia</i>	95	<i>Semecarpus</i>	199
<i>Putranjiva</i>	698	<i>Salomonina</i>	59	<i>Senecio</i>	433, 432
<i>Pycnospora</i>	221	<i>Salvadora</i>	466	<i>Serissa</i>	395
<i>Pygeum</i>	271	<i>SALVADORACEÆ</i>	83	<i>Serpicula</i>	281
<i>Pyrenacantha</i>	162	<i>Samadera</i>	134	<i>Sesamum</i>	p. 65
<i>Pyrularia</i>	686	<i>Samara</i>	450	<i>Sesbania</i>	214
<i>Randia</i>	375	<i>SAMYDACEÆ</i>	56	<i>Sesuvium</i>	338
<i>RANUNCULACEÆ</i>	1	<i>Sanicula</i>	343	<i>Setaria</i>	932
<i>Ranunculus</i>	5	<i>Sansevera</i>	841	<i>Sethia</i>	112
<i>Raphidophora</i>	894	<i>SANTALACEÆ</i>	118	<i>Shorea</i>	81
<i>Rauwolfia</i>	470	<i>Santalum</i>	p. 77	<i>Shuteria</i>	227
<i>Remirea</i>	919	<i>SAPINDACEÆ</i>	40	<i>Shuterea</i>	534
<i>Remusatia</i>	891	<i>Sapindus</i>	189	<i>Sida</i>	78
<i>Rhabdia</i>	524	<i>Sapium</i>	728	<i>Sideroxylon</i>	454
<i>RHAMNACEÆ</i>	38	<i>Sapota</i>	454	<i>Siegesbeckia</i>	422
<i>Rhamnus</i>	177	<i>SAPOTACEÆ</i>	79	<i>SIMARRUBACEÆ</i>	30
<i>Ramphidia</i>	816	<i>Saprosma</i>	395	<i>Slevogtia</i>	514
<i>Rhinacanthus</i>	599	<i>Saraca</i>	261	<i>Smilax</i>	849
<i>Rhipsalis</i>	337	<i>Sarcanthus</i>	799	<i>Smithia</i>	217
<i>RHIZOCARPEÆ</i>	152	<i>Sarcocephalus</i>	353	<i>Soja</i>	229
<i>Rhizophora</i>	284	<i>Sarcochilus</i>	794	<i>SOLANACEÆ</i>	91
<i>RHIZOPHORACEÆ</i>	50	<i>Sarcoclinium</i>	711	<i>Solanum</i>	540
<i>Rhododendron</i>	445	<i>Sarcococca</i>	689	<i>Nonchus</i>	p. 49
<i>Rhodomyrtus</i>	295	<i>Sarcostemma</i>	495	<i>Sonerila</i>	302
<i>Rhynchosia</i>	246	<i>Sarosanthera</i>	75	<i>Sonneratia</i>	310
<i>Rhynchospora</i>	921	<i>Satyrrium</i>	823	<i>Sophora</i>	252
<i>Ricinus</i>	p. 82	<i>Sauropus</i>	694	<i>Sopubia</i>	558
<i>Rivea</i>	530, 531	<i>SAXIFRAGACEÆ</i>	46	<i>Sorghum</i>	962
<i>Rivina</i>	p. 72	<i>Scævola</i>	438	<i>Soymdia</i>	p. 17
<i>ROSACEÆ</i>	45	<i>Schizæa</i>	1057	<i>Spathiostemon</i>	723
<i>Rostellularia</i>	597	<i>Schizoloma</i>	1013	<i>Spathodea</i>	572
<i>Rotula</i>	305	<i>Schizostigma</i>	372	<i>Spatholobus</i>	235
<i>Rothia</i>	206	<i>Schleichera</i>	187	<i>Spergula</i>	p. 6
<i>Rotthoellia</i>	954	<i>Schmidelia</i>	186	<i>Spermacoce</i>	397
<i>Rottlera</i>	720, 722	<i>Schenorchis</i>	797	<i>Sphaeranthus</i>	415
<i>Rourea</i>	203	<i>Schumacheria</i>	9	<i>Sphenoclea</i>	441
<i>Roxburghia</i>	848	<i>Sciaphila</i>	900	<i>Spilanthus</i>	426
<i>ROXBURGHACEÆ</i>	132	<i>Scilla</i>	857	<i>Spinifex</i>	936
<i>Rubia</i>	398	<i>Scindapsus</i>	894	<i>Spiranthes</i>	810
<i>RUBIACEÆ</i>	67	<i>Scirpodendron</i>	917	<i>Spodiopogon</i>	958
<i>Rubus</i>	272	<i>Scirpus</i>	912, 910	<i>Spondias</i>	202
<i>Ruellia</i>	582	<i>SCITAMINEÆ</i>	127	<i>Sponia</i>	733
<i>Rumex</i>	p. 73	<i>Scleria</i>	924	<i>Sporobolus</i>	966
<i>Rungia</i>	602	<i>Scleropyron</i>	686	<i>Stachys</i>	p. 71
<i>Ruppia</i>	904	<i>Scolopia</i>	51	<i>Stachytarphet</i>	608
<i>RUTACEÆ</i>	29	<i>Scoparia</i>	p. 63	<i>Stellaria</i>	62
<i>SABIACEÆ</i>	41	<i>SCROPHULARIACEÆ</i>	92	<i>Stemona</i>	848
<i>Saccharum</i>	949	<i>Scutellaria</i>	629	<i>Stemonoporus</i>	84, 79
<i>Saccolabium</i>	797, 799, 800	<i>Scutia</i>	178	<i>Stenochlæna</i>	1052
<i>Sageræa</i>	26	<i>Scutinanthe</i>	138	<i>Stenoloma</i>	1011
		<i>Scyphellandra</i>	50	<i>Stenosiphonium</i>	585, 586
		<i>Scyphiphora</i>	380	<i>Stenotaphrum</i>	934
		<i>Scyphostachys</i>	378	<i>Stephania</i>	33

Stephegyne . . .	356	Thuarea . . .	935	Vahlia . . .	278
Sterculia . . .	98	Thunbergia . . .	575	Valeriana . . .	400
STERCULIACEÆ . . .	23	THYMELÆACEÆ . . .	115	VALERIANACEÆ . . .	68
Stereospermum . . .	573	TILIACEÆ . . .	24	Vallaris . . .	479
Streblus . . .	737	Tiliacora . . .	30	Vanda . . .	796, 792
Streptogyne . . .	986	Timonius . . .	382	Vandellia . . .	550
Striga . . .	556	Tinospora . . .	27	Vanilla . . .	807
Strobilanthes . . .	586	Tithonia . . .	p. 48	Vateria . . .	84, 79
Strombosia . . .	155	Toddalia . . .	122	Vatica . . .	80
<i>Strongylocalyx</i> . . .	296	Torenia . . .	549	Ventilago . . .	175
Strongylodon . . .	233	Tournefortia . . .	525	Verbascum . . .	p. 61
Strychnos . . .	510	Toxocarpus . . .	489	VERBENACEÆ . . .	99
STYLIDIACEÆ . . .	71	Trachys . . .	944	Vernonia . . .	402
Styldium . . .	437	Tragia . . .	726	Veronica . . .	p. 63
<i>Styllocoryne</i> . . .	373, 374	Tragus . . .	945	Viburnum . . .	352
Stylosanthes . . .	216	Trapa . . .	314	Vicoa . . .	419
STYRACEÆ . . .	81	Trema . . .	733	Vigna . . .	240
Suæda . . .	652	Trewia . . .	719	Villebrunea . . .	756
Sunaptea . . .	79	Trianthema . . .	339	Vinca . . .	p. 54
Susum . . .	869	Tribulus . . .	114	Viola . . .	48
Swertia . . .	518	Trichadenia . . .	55	VIOLACEÆ . . .	10
Symphorema . . .	616	Trichodesma . . .	527	Viscum . . .	682
Symplocos . . .	461	<i>Trichopodium</i> . . .	847	Vitex . . .	613
Synantherias . . .	890	Trichopus . . .	847	Vitis . . .	182
Synedrella . . .	p. 48	Trichosanthes . . .	319	Vittaria . . .	1047
Syngamme . . .	1043	Tricomanes . . .	1005		
<i>Syzygium</i> . . .	296	Tricostularia . . .	922	Wahlenbergia . . .	440
		Tridax . . .	p. 48	Walsura . . .	148
Tabernæmontana . . .	476	Trifolium . . .	p. 22	Waltheria . . .	103
Tacca . . .	845	Trigonostemon . . .	707	Webera . . .	373
TACCACEÆ . . .	130	Tripogon . . .	977	Wedelia . . .	425
Tæniophyllum . . .	801	<i>Triticum</i> . . .	983	Weibea . . .	288
Tænitis . . .	1048	Triumfetta . . .	107	Wendlandia . . .	359
Tainia . . .	780	TRIURIDEÆ . . .	144	Wikstrœmia . . .	676
Tajetes . . .	p. 48	Tropidia . . .	809	Willughbeia . . .	468
Tamarindus . . .	p. 29	Turnera . . .	p. 37	Wissadula . . .	p. 10
TAMARISCINEÆ . . .	16	Turpinia . . .	194	Withania . . .	541
Tamarix . . .	67	Tylophora . . .	498	Woffia . . .	899
Taxotrophis . . .	735, 736	Typha . . .	882	Wollastonia . . .	425
Tectona . . .	p. 68	TYPHACEÆ . . .	141	Woodfordia . . .	306
Teinostachyum . . .	995	Typhonium . . .	887	Wormia . . .	10
Tephrosia . . .	213	<i>Ulmus</i> . . .	731	Wrightia . . .	480
Teramnus . . .	230	UMBELLIFERÆ . . .	63		
Terminalia . . .	298	Uncaria . . .	358	Xanthium . . .	421
Terniola . . .	655	Unona . . .	17	<i>Xanthochymus</i> . . .	70
Ternstroemia . . .	74	Uraria . . .	223	Xanthophyllum . . .	60
TERNSTROEMIAEÆ . . .	20	Urena . . .	89	<i>Ximenesia</i> . . .	p. 48
Tetracera . . .	7	<i>Uropetalum</i> . . .	856	Ximenia . . .	153
Tetrameles . . .	336	Urophyllum . . .	371	Xylocarpus . . .	149
<i>Tetranthera</i> . . .	671	<i>Urostigma</i> . . .	741	Xylopia . . .	22
Teucrium . . .	633	URTICACEÆ . . .	121	XYRIDEÆ . . .	135
Thalassia . . .	765, 766	Utricularia . . .	563	Xyris . . .	862
Thalictrum . . .	4	Uvaria . . .	14		
Thamnopteris . . .	1023	VACCINIACEÆ . . .	74	Youngia . . .	434
Therophonum . . .	888	Vaccinium . . .	443		
Thespesia . . .	94	Vaginularia . . .	1040	Zanonia . . .	334
Thismia . . .	768			Zanthoxylum . . .	121

Zehneria	328, 332	Zingiber	833	Zosterostylis	818
Zenkeria	970	Zizyphus	176	Zoysia	947
Zeuxine	813	Zornia	215	ZYGOPHYLLACEÆ	27

INDEX TO SINHALESE NAMES.

Aba	p. 4	Balu-dap	451	Bú-pila	213
Acháriyá-palu	231	Balu-nakuṭa	152, 608	Burulla	183
Agaládára	598	Bambara-wel	248	Buruta	151
Aga-mula-neṭi-wel	539	Bándurá-wel	657	Bu-séru	611
Agu-karuni	393	Bāta-domba	296	Bú-tóra	257
Ahu	389	Bāta-kirilla	112	But-saraṇa	838
Akká-pána	p. 31	Bāta-li	996	Chanchala	225
Akmella	426	Beḷa-tana	978	Dada-kaha	829
Alandu	738	Beli	p. 16	Dada-kehel	894
A'lapgá	533	Beli-paṭṭá	93	Dada-kiriya	688
A'laríya	p. 54	Beraliya	83	Daluk	688
Alubó	296	Bériya	292	Daminiya	106
Alu-gas	835	Béru	711	Dap	296
Alu-pila	213	Béru-diyanilla	312	Dara-hál-pap	911
Alu-puhul	p. 38	Bevila	87	Dára-veṭa-kolu	321
Amba	196	Bilin	p. 14	Dat-keṭiyá	22, 367
Amba-kaha	827	Bim-pol	847	Dawata	287
Ambala	519	Bindara	512	Dawu	291
Amu	926	Biḡ-karal-heba	641	Dawul-kurundu	671
Amukkará	541	Biḡ-kohomba	140	Dedi-kaha	304
Anāna-híriya	208	Bin-mé	239	Del	744
Andara	267	Bin-nuga	498	Demata	612
Andun-weṇna	163	Bin-ólu	519	Désa-ala	893
Angana	382	Bin-siyambalá	257	Divi-aḍiya	533
Anitta	599	Bin-tal	842	Divi-kaduru	476
Ankenda	123	Bin-tamburu	533	Divi-pahuru	533
Anódá	88	Bó	741	Diwul	132
Aralu	290	Bó-kéra	136	Diya-béru	711
Aramaná	257	Bómbu	461	Diya-dangá	572
Arida	201	Bó-mi	671	Diya-embul-embiliya	1064
As-wel	484	Boru-pap	910	Diya-habarala	861
Asweṇna	224	Bówiṭiya	299	Diya-hawari	762
Atakeṭiyá	375	Bú-dada-kiriya	688	Diya-kirilla	520
Ati-uḍayan	884	Bú-embilla	704	Diya-kirindi-wel	173
Attana	542	Bú-geṭiya	111	Diya-kúdal	119
Attikka	741	Bú-hora	78	Diya-labu	p. 38
Awari	210	Bú-hunu-kirilla	695	Diya-menériya	864
Badal-wanassa	1067	Bu-kattu-henda	528	Diya-midella	297
Badulla	199	Bú-kenda	720	Diya-mitta	34
Baka-múnu-tana	924	Bú-kinda	27	Diya-ná	73
Bak-mí	353	Bulat-wel	660	Diya-nilla	568
Bala	200	Bulu	290		
Báloiyá	225	Bú-nelu	585		
		Bú-nuga	741		

Diya-para . . .	10	Eṭórá . . .	929	Gop-kaduru . . .	473
Diya-parandella . . .	885	Ēt-pamba . . .	1058	Gop-kekiri . . .	323
Diya-ratambalá . . .	261	Ēt-pitawakká . . .	693	Go-palangá . . .	330
Diya-ratmal . . .	261	Ētṭériya . . .	126	Goraka . . .	70
Diya-siyambalá . . .	218	Ēt-tóra . . .	243	Goṭu-kola . . .	342
Diya-taliya . . .	351	Ēt-tuttiri . . .	965	Goyi-wel . . .	868
Diya-tana-kola . . .	929	Ēṭuna . . .	99	Gurenda . . .	732
Diya-wawuleṭiya . . .	254			Guru-kína . . .	71
Doḍaṇ-kaha . . .	304	Gahala . . .	892	Gurulla . . .	183
Doḍaṇ-paná . . .	124	Gal-demata . . .	118		
Doḍaṇ-wenna . . .	304	Gal-ehi . . .	908	Habarala . . .	893
Domba . . .	71	Galis . . .	376	Hal . . .	84
Domba-kína . . .	71	Gal-kappra-walliya . . .	624	Hál-bembiya . . .	143
Dorana . . .	78	Gal-karanda . . .	262, 385	Hal-milla . . .	105
Dótalú . . .	872	Gal-mendóra . . .	258	Hál-paṇ . . .	911
Duhudu . . .	169	Gal-mora . . .	191, 665	Hambu-paṇ . . .	882
Dúl . . .	484	Gal-siyambalá . . .	259	Hampilla . . .	247
Dummélla . . .	319	Gal-weralu . . .	109	Hampinna . . .	225
Dún . . .	83	Gammalu . . .	249	Hampirila . . .	720
Dunu-keyiyá . . .	880	Gammiris-wel . . .	660	Hana . . .	208
Duṭu-satuṭu . . .	557	Gandapána . . .	161, 605	Happalandá . . .	290
		Ṭaṇ-kollaṇ-kola . . .	625	Harap-kaha . . .	829
Eheḷa . . .	257	Ḡaṇ-mi . . .	457	Hátá-wáriya . . .	850
Ēheṭu . . .	741	Gas-dúl . . .	757	Hawari-madu . . .	533
Ēkáwériya . . .	470	Gas-kahambiliyá . . .	747	Hédawaka . . .	724
Ela-baṭu . . .	540	Gas-karal heba . . .	646	Heḍayá . . .	1067
Ela-dadakiriya . . .	688	Gas-kayila . . .	697	Heḍóka . . .	724
Ela-gokatu . . .	70	Gas-kéla . . .	236	Heḱarilla . . .	540
Ela-imbui . . .	p. 5	Gas-keppiṭiyá . . .	705	Heḷamba . . .	356
Ela-mal . . .	828	Gas-neṭul . . .	741	Heṃanilla . . .	626
Ela-midella . . .	297	Gas-nidi-kumba . . .	117, 264	Heri-mena-deṭta . . .	606
Ela-neṭul . . .	446	Gas-pichcha . . .	388	Heṃan-paṇ . . .	908
Ela-nuga . . .	741	Gas-pinna . . .	614	Hik . . .	198
Ela-rat-mal . . .	384	Geḍumba . . .	733	Hima . . .	294
Ela-wel . . .	878	Genda-kola . . .	66	Himbuṭu-wel . . .	174
Ela-wéwel . . .	878	Geṭa-kola . . .	364	Hín-badulla . . .	199
Ēlbedda . . .	195	Geṭa-neṭul . . .	737	Hín-biṇ-kohomba . . .	593
Ēmbarella . . .	202	Geṭa-oluwa . . .	836	Hín-bin-tal . . .	842
Enḍaru . . .	p. 82	Geṭa-tumba . . .	631	Hín-bówiṭiyá . . .	299
Ensál . . .	832	Geṭiya . . .	111	Hín dap . . .	296
Ēpala . . .	107	Gherriata-gas . . .	463	Hín-embilla . . .	704
Erabadu . . .	232	Gin-pol . . .	875	Hín-embul-embiliya . . .	116
Eraminiyá . . .	176	Girá palá . . .	864	Hín-epala . . .	89
Ēt-adi . . .	403	Giri-tilla . . .	531	Hín-eraminíyá . . .	176
Ēṭa-kirilla . . .	194	Goḱa-itta . . .	349	Hín-genda-kola . . .	76
Ēṭa-kirinda-wel . . .	510	Goḱa-kaduru . . .	510	Hín-goṭu-kola . . .	342
Ēṭamburu . . .	509	Goḱa-kirilla . . .	731	Hingul . . .	146
Ēṭa-míriya . . .	529	Goḱa-mánil . . .	843	Hinguru . . .	268
Ēṭa-paṇ . . .	918	Goḱa-para . . .	11	Hinguru-piyali . . .	827
Ēṭa-weṛella . . .	193	Goḱa-wawuleṭiya . . .	256	Hín-himbuṭu-wel . . .	174
Ēt-bemi-kiriya . . .	837	Gó-hiri-paṇ . . .	908	Hín-kabarasa . . .	849
Ēt-demata . . .	612	Go-jabbá . . .	939	Hín-kaḍol . . .	452
Ēt-hawari . . .	1066	Gokaṭn . . .	70	Hín-karamba . . .	469
Ēt-heraliya . . .	171	Golu-mora . . .	271	Hín-kaṭu-pila . . .	696
Ēt-korasa-wel . . .	7	Gona . . .	460	Hín-kebella . . .	702
Ēt-kukurumán . . .	375	Góna-kola . . .	544	Hín-kekiri . . .	327
Ēt-nerenchi . . .	574	Góna-wel . . .	86	Hín-keṛewu . . .	924

Hin-madu . . .	533	Kakkuṭu-palá . . .	48	Keḥi-pittag . . .	35
Hin-muda-mahana .	414	Kalaha . . .	741	Keḥala . . .	15
Hin-nápiritta . . .	93	Kalamaduwa . . .	741	Kekatiya . . .	903
Hin-pamba . . .	1058	Kalánduru . . .	908	Keḥilla . . .	998
Hin-sárana . . .	339	Kalaṭi . . .	18	Keḥiri . . .	327, 328
Hin-takkaḍa . . .	438	Kalaṭiya . . .	270	Keḥiriwará . . .	9, 311
Hin-talá . . .	618	Kala-wel . . .	251	Keku . . .	26
Hin-tambala . . .	522	Kalos-wáranīya . . .	597	Keḥuna . . .	138
Hin-undu-piyali . . .	225	Kalu-habaraliya . . .	459	Keleniya . . .	835
Hiressa . . .	182	Kalu-kaḍumbériya . . .	460	Keḥiya . . .	106
Hiri-tala . . .	846	Kalu-kan-wériya . . .	540	Keḥa . . .	722
Hó-meḍiriya . . .	460	Kalukéra . . .	20	Keḥ-henda . . .	614
Honda-beraliya . . .	83	Kalu-meḍiriya . . .	460	Keḥpiṭiyá . . .	705
Hondala . . .	318	Kaluwála . . .	835	Keḥ-koku . . .	1055
Hondapara . . .	11	Kámaranga . . .	p. 14	Kesi-pissan . . .	35
Hora . . .	78	Kampottá . . .	702	Keṭa-kála . . .	690
Hulaḡ-hik . . .	150	Kana-gouna . . .	744	Keṭala . . .	884
Hulaḡ-kiriya . . .	837	Kana-goraka . . .	70	Keṭ-embilla . . .	54
Hulaḡ-mará . . .	269	Kandala . . .	892	Keṭiya . . .	57
Hulaḡ-talá . . .	404	Kaudu-bó . . .	741	Keṭiya-kéra . . .	304
Hunu-kirilla . . .	695	Kandu-lessa . . .	280	Keyiyá . . .	880
Hurukandu . . .	171	Kaḡkumbalá . . .	194, 494	Kiḍaran . . .	889
		Kankumbal-koṭiya . . .	271	Kikirindi . . .	423
Ikili . . .	588	Kaḡ-kug . . .	533	Kimbulwenna . . .	654
Ikiliya . . .	314	Kappa-walliya . . .	623	Kina . . .	71
Ila . . .	610	Kapu-kinissa . . .	93	Kini-hiriya . . .	p. 5
Iluk . . .	948	Kapuru . . .	20, 444	Kiri-anguna . . .	550
Imbul . . .	96	Kara . . .	385	Kiri-badn . . .	533
Indi . . .	876	Karapincha . . .	127	Kiri-hembiliya . . .	456
Induru . . .	869	Karavuta-máná . . .	963	Kiri-henda . . .	637
Ingini . . .	510	Karawala-keḥella . . .	704	Kiri-hiriya . . .	512, 456
Innala . . .	622	Karawu . . .	695	Kiri-kaju . . .	p. 10
I'petta . . .	15	Kariwila . . .	322	Kiri-kop . . .	148
Iramusu . . .	486	Karon . . .	525	Kirilla . . .	310
Iri-wériya . . .	622	Kása . . .	p. 86	Kiri-maḡu . . .	533
I'riya . . .	663	Kaṭu-andara . . .	268	Kiri-makulu . . .	728
Iru-rája . . .	813	Kaṭu-boda . . .	97	Kirindi-máná . . .	p. 106
I'-tana . . .	959	Kaṭu-embilla . . .	680	Kirindi-wel . . .	203
Itta . . .	349	Kaṭu-ikili . . .	588	Kiri-pella . . .	741
		Kaṭu-ikiri . . .	580	Kiri-walla . . .	477
Jaya-pála . . .	705	Kaṭu-imbul . . .	95	Kiri-warala . . .	455
		Kaṭu-karandū . . .	589	Kiri-wel . . .	389, 485
Kabal-mará . . .	269	Kaṭu-kenda . . .	51	Kitul . . .	874
Kabarasa . . .	849	Kaṭu-kina . . .	121	Kobbé . . .	186
Kaḍol . . .	284	Kaṭn-kiriya . . .	835	Kobo-mal . . .	296
Kaḍumbériya . . .	460	Kaṭu-kitul . . .	873	Kohila . . .	895
Kaduruketiya-wel . . .	293	Kaṭu-kurundu . . .	51	Kohomba . . .	141
Kaha . . .	p. 5, 829	Kaṭu-pamburu . . .	686	Kokaṭiya . . .	70
Kaha-andana-hiriya . . .	208	Kaṭu-patuk . . .	p. 39	Kok-moṭa . . .	907
Kaha-góna-kola . . .	544	Kaṭuru-murungá . . .	p. 23	Kokun-potu . . .	167
Kaha-kála . . .	460	Kaṭu-tam-palá . . .	640	Kollu . . .	242
Kahambiliyá . . .	745, 747	Kaṭu-timbol . . .	739	Kolog . . .	355
Kaha-penela . . .	189	Kaṭu-una . . .	993	Komaḡu . . .	324
Kaha-petaḡ . . .	263	Kaṭu-wala . . .	846	Kón . . .	187
Kahaṭa . . .	298	Kaṭu-wel-baṭu . . .	540	Kora-kaha . . .	304
Kaha-tel-kola . . .	533	Kawálu . . .	932	Korasa-wel . . .	6
Kaju . . .	p. 21	Keḥella . . .	702	Kos . . .	744

Kosatta	709	Maha-diya-siyambalá	218	Midi	611, p. 29
Kos-bađa	671	Maha-dumudu	531	Mi-hiriya	456
Koťa-dimbulá	741	Maha-eramiñiyá	176	Milila or Milla	613
Kotalá-wel	549	Maha-geťa-pağ	912	Miwana-kola	1025
Koťikan-bevila	87	Maha-geťiya	111	Monara-kuđimbiya	402
Koťtambá	290	Maha-goťu-kola	342	Monara-petağ	854
Kówakká	325	Maha-hakambalá	335	Mora	190
Krimisastru	929	Maha-heďayá	1067	Mottu	p. 61
Kúďalu-mal	118	Maha-kabarasa	849	Muđa-mahana	415
Kudu-dawulu	671	Maha-karamba	469	Múdilla	297
Kudu-hedayá	1067	Maha-keřewu	924	Múdu-bin-nuga	498
Kuđu-keķiri	328	Maha kiri-wel	389	Múdu-bin-tamburu	533
Kudu-miris	122	Maha-kohila	895	Múdu-dađa-kiriya	688
Kađu-pára	431	Maha-madu	533	Múdu-geťa-kola	396
Kukula-wel	878	Mahamidi	611	Múdu-hál-pağ	911
Kukurumán	375	Maha-nuga	741	Múdu-kaduru	474
Kumatiya	638	Maha-pamba	1058	Múdu-kalánduru	908
Kumbalu	133	Maha-ratambalá	386	Múdu-keyiyá	880
Kumbuk	290	Maha-rawana-réwula	936	Mudu-murungá	252
Kumburu-wel	254	Maha-sárana	339	Muku-nu-wenna	647
Kuppa-méniya	716	Maha-undu-piyali	225	Múnamal	458
Kurakkan	978	Maha Yak-wanassa	632	Mun-eťa	239
Kuriññağ	496	Makulu	56	Murungá	p. 21
Kúreťiya	304	Malabaťu	540	Muruta	309
Kurundu	667	Malabođa	663	Muruvá-dúl	497
		Mala-labu	660	Mussenda	368
		Malamiris-wel	660	Muwa-kiriya	495
		Malita	306		
Lá-wulu	453	Mal-kéra	135	Ná	73
Lén-teři	871	Malu	249	Naha	677
Lew	941	Mána	960	Ná-imbul	192
Lí-kola-palá	611	Manda-madini-wel	398	Nala-gas	981
Líniya	100	Máuel	38	Nápiritta	93
Liyag	317	Mani	597	Nara-wel	1
Lolu	521	Má-pat-keřella	702	Nává	98
Lunu-ankenda	120	Mára	269	Nawa-handi	688
Lunu-dağ	451	Marag	296	Náyan	402
Lunu-keťiya-wel	33	Maranda	296	Nayi-habarala	893
Lunu-maďalá	573	Má-ratmal	445	Nayi-miris	p. 61
Lunu-miďella	142	Masağ	176	Nebedđa	613
Lunu-warana	45	Mas-mora	266	Neďun	253
Lunu-wila	546	Mas-wenna	1049	Nelli	695
		Maťu-bimbiya	448	Nelu	586
Má-bandá	531	Má-ussá	746	Nelun	39
Má-bin-tal	842	Má-wewel	878	Neralu	172
Madará	691	Mayila	263	Neťawu	22
Maďatiya	266	Mayuru-tana	975	Neya-dasse	76
Maďol	70	Međa-hangu	493	Nil-aďana-hiriya	208
Mađu	759	Meďiya	472	Nil-awari	210
Maduru-talá	618	Meďiya-jáwála	767	Nil-góna-kola	544
Magul-karanda	250	Meďiya-wel	182	Nil-kaťarolu	241
Maha-andara	268	Meřla	154	Nil-monareřsa	563
Maha-badulla	199	Mímiñi-mára	270	Nil-nika	613
Maha-béru	711	Meňďóra	80	Niri-wel	31
Maha-bówiťiyá	300	Menéri	929	Niviti	653
Maha-bulu-mora	138	Mí	457	Niyanda	841
Maha-dağ	296	Midella	297	Niyangalá	859
Maha-debara	176				
Maha-diya-dúl	753				

Niyan-veṭa-kolu	321	Potu-kola	924	Sewana-meḍiya	741
Nuga	741	Potu-palá	533	Síniya	268
Odn-tulan	627	Potu-paṇ	924	Sínuk	688
O'-keyiyá	880	Pulila	741	Siribó	660
O'kuru	721	Pupula	402	Siwiya-wel	660
Olinda-wel	226	Puruk	591	Sudu-idda	480
O'lu	38, 519	Pus-wel	265	Sudu-kimbulwenna	654
Olupetta	708	Putu-tana	978	Sudu-liyaṇ	695
Oṭa	722	Puwak	871	Sudu-nika	613
		Puwak-geḍiya-wel	113	Sudu-pareyimal	772
Palu	458	Radaliya	204	Sudu-puruk	597
Palu-kaṇ	14	Rambuk	949	Sudu-tam-palá	640
Paluṭu	674	Rana-bata-lí	995	Sudu-tumba	631
Pamba	1058	Rana-tam-palá	640	Sulu-neyi	602
Pamburu	131	Raṇawará	257	Súriya	94
Panu-ala	887	Raṇkíriya	835	Súriya-mará	269
Panu-habarala	893	Raṇ-manissa	862	Suwanda	72
Panu-kéra	296	Raṇ-motu	862	Taḍala	892
Panu-kondol	846	Raṇ-waṇ-kirinda	425	Takkaḍa	438
Pat-kála	690	Rasa-kinda	27	Tal	879
Pat-kenda	722	Rasa-tel-kola	533	Tala	877
Patóla	319	Ras-ni	439	Tambuṭu-wel	878
Pattá-ḍpala	89	Rata-ala	893	Tammanná	701
Pattangi	254	Raṭa-attana	542	Tampalá	644
Pattá-wallá	679	Raṭa-bulat-wel	660	Tana-hál	932
Páwattá	387	Raṭa-del	744	Tarana	373
Peddi-méla	382	Raṭa-eṇḍaru	p. 81	Tebu	834
Pehimbiya	139	Raṭa-gówá	p. 31	Tela-kíriya	730
Pelaṇ	171, 698	Raṭa-hinguru	605	Telambu	98
Penela	189	Raṭa-labu	p. 38	Tel-híriya	180
Penela-wel	184	Ratambalá	386	Tel-kekuna	p. 81
Pengiri-kurundu	667	Raṭa-tana	929	Tel-nuga	741
Pengiri-máná	960	Raṭa-tóra	257, p. 26	Tel-tala	p. 65
Pepiliya	702	Raṭa-uguressa	53	Tembiliya	296
Pepol	p. 37	Rat-keḷiya	671	Tibbatu	540
Péra	p. 32	Rat-kírii	268	Timbiri	460
Péra-tambala	511	Rat-piṭawakká	695, 729	Tiniya	83
Petaṇ	263	Ratu-kimbulwenna	654	Tippili	660
Petiká-wel	16	Ratu-wá	257	Titta-gas	55
Peti-tóra	257	Rawan-idala	359	Titta-hondala	319
Pichcha	462	Rénu-ólu	519	Titta-kinda	27
Pila	213	Riṭa-bulat-wel	182	Titta-wel	28
Pilila	681	Riṭi	742	Tolabó	843
Pinibaru	296	Ruk	663	Tolol	55
Pini-baru-tana	963	Ruk-attana	475	Toṭila	571
Pini-tuttiri	969	Sámadána	587	To-wel	182
Piṭa-sudu-palá	364, 635	Samadará	134	Trasta-wálu	533
Piṭa-wakká	693, 695	Sanní-náyan	402	Tudarena-wéwel	878
Piyari	168	Sap-sanda	659	Tumba-karivila	322
Pol	p. 96	Sapu	12	Tumpat-kurundu	128
Pol-kuḍu-palá	645	Sapu-milila	613	Tuttiri	961
Poloṇ-ala	887	Saya-mul	365	Ubbériya	287
Porawa-mará	385	Sembu-nereuchi	114	Uguressa	53
Porua-malla	460	Sépála or Sépáliká	p. 53	Ululu	668
Pótá-wel	896	Seṇḍará	960	Una	993
Potu-honda	318				

Undu-piyali . . .	225	Wal-kidáran . . .	886	Wel-buté . . .	272
Unumu . . .	271	Wal-kinda . . .	27	Wel-but-saraṇa . . .	368
U'ru-genda . . .	66	Wal-kollu . . .	243	Wel-dehi . . .	467
U'rukanu . . .	158	Wal-kolondú . . .	429	Wel-ēḥeṭu . . .	741
U'ru-tóra . . .	257	Wal-kópi . . .	378	Wel-ēmbilla . . .	450, 680
U'ru-wí . . .	940	Wal-kurakkan . . .	978	Wel-híri . . .	908
Uyala . . .	846	Wallá . . .	679	Weli-kaha . . .	304
		Wal-lúnu . . .	844	Weli-penna, Weli-	
Velanga . . .	101	Wal-mé . . .	239	piyáná . . .	289
Veṭa-kolu . . .	321	Wal-mēdiriya . . .	460	Weli-wenna . . .	710
Visnu-kránti . . .	536	Wal-murungá . . .	697	Wel-kahambiliyá . . .	726
		Wal-patpádagam . . .	365	Wel-kayila . . .	695
Wá . . .	257	Wal-pichecha . . .	381, 462	Wel-keppitiyá . . .	705
Wada-kaha . . .	897	Wal-rasakinda . . .	334	Wellangiriya . . .	47, 130
Wal-aba . . .	42	Wal-rat-diya-labu . . .	182	Wel-marukku . . .	929
Wal-amba . . .	196	Wal-sapu . . .	12	Wel-moṭṭu . . .	505
Wal-asamódagan . . .	345	Wal-té-kola . . .	427	Wel-nánu . . .	216
Wal-awara . . .	237	Wal-tibbaṭu . . .	540	Wel-radaliya . . .	204
Wal-bilin . . .	133	Wal-trasta-wálu . . .	534	Weni-wel . . .	29
Wal-bómbu . . .	461	Walú-kína . . .	71	Weni-wella . . .	638
Wal-buruta . . .	12	Walú-tam-palá . . .	640	Weralu . . .	109
Wal-del . . .	744	Wal-waraká . . .	315	Weraniya . . .	364
Wal-diya-labu . . .	182	Wam-para . . .	11	Wesak-mal . . .	772
Wal-ēḥeṭu . . .	741	Wana-mí . . .	457	Wéwarani . . .	669
Wal-endaru . . .	344, 346	Wana-potu . . .	167	Wéwēl . . .	878
Wal-gammiris-wel . . .	660	Wana-rája . . .	812	Wila . . .	552
Wal-goniká . . .	391	Wanassa . . .	1067	Wira . . .	699
Wal-gonna . . .	741	Wará . . .	491	Wisa-d úli . . .	787
Wal-gureṇda . . .	614	Wasa-kaduru . . .	471		
Wal-idda . . .	480	Waṭa-ressa . . .	280	Yaka-halu . . .	83
Wal-inguru . . .	833	Wáwiya . . .	664	Yakbériya . . .	208
Wal-jambu . . .	296	Wawuleṭiya . . .	254, 256	Yak-erabadu . . .	232
Wal-jayapála . . .	708	Waya-pol . . .	842	Yakináran . . .	131
Wal-kaha . . .	829	Weideya . . .	375	Yak-komaḍu . . .	324
Wal-kahambiliyá . . .	745	Wéla . . .	43	Yak-wanassa . . .	630
Wal-karapincha . . .	125	Wel-ala . . .	892	Yakuṭala . . .	892
Wal-kehel . . .	839	Wel-bénduru . . .	1052	Yawakenda . . .	827
Wal-kekuna . . .	708				

INDEX TO TAMIL NAMES.

Acha . . .	460	Amkulang . . .	541	Attunetta . . .	218
Achi . . .	571	Ampallai . . .	202	Avarai . . .	257
Adampu . . .	297	Ani-kundumani . . .	266		
A dátódai . . .	598	Ani-mullu . . .	268	Bandakai . . .	93
A' du-thinnápálé . . .	659	Ara-keéré . . .	1064		
Aglai . . .	150	Arasa or Arasu . . .	741	Chadachi . . .	106
Ail or Aiyilli . . .	731	Ari-maru . . .	298	Chadda-vakku . . .	148
A'l . . .	741	Arugam-pillu . . .	973	Chámai . . .	929
Alangi . . .	350	Atti . . .	741	Chamandalé . . .	105

Chara	460	Kilivai	137	Nannári	486
Chemel-paniché	460	Kirri-pálai	698	Naruvili	521
Chenu-kla	469	Klakái	469	Nával	296
Chiru-punnai	71	Koddi-thuvattai	106	Navala	45
Chivanár-vémbu	210	Kokatai	70	Nedunárai	18
Chowkku	p. 86	Kolkutti	611	Nir-kadamba	356
Churai	176	Kollu	242	Né-kurundu	131
Elam-purukki	461	Kona	269	Nérválum	705
Ellu	p. 65	Konji	97	Netavil	742
Elumburiki	671	Konnai	171	Nila-vémpu	593
Enné-kannai	457	Kórai	908	Nir-mulli	580
Errukum	491	Korukkai-puli	70	Nir-nochi	613
Iddu-mullai	686	Kottai	290	Nochi	613
Ilanthai	176	Kovani	257	Odái-velam	268
Iuppai	457	Kúlá	187	Othi	198
Ir-ellipalai	475	Sulla-pannai	124	Pachalai	653
Irum-palai	459	Kulli	688	Pakala-mullai	462
Kadalipuva	309	Kulothi	150	Pálai	458
Kada-manakku 105, 704		Kumbai	376	Palakuna	724
Kadaralai	473	Kumil	612	Palpirái	737
Káddinchi	859	Kundumani	226	Panai	879
Káddu-má	196	Kuppaimáni	716	Panap-kattáli	787
Kaddu-monthera	182	Kuri-kurité	706	Pandi-káyán	296
Kaditeni	98	Kurivuppu	126	Paneer	381
Kadu	473	Kurundu	131	Panichai	298
Kadukkái	290	Ma	196	Panichekai	460
Kaivaru	978	Mailai	613	Paparu-pulli	p. 11
Kaiya or Káyán	296	Malai-vempu	142	Pappalai	498
Kakai-palé	725	Mana-takkáli	540	Paritti	93
Kalli	688	Manchadi	269	Parutti	95
Kamuka	871	Manchavarna	304	Pasu	11
Kanchá	731	Manjal-kadambu	355	Pátiri	573
Káanchúrai	510	Manjel	829	Patpadágam	340
Kandá-pana	877	Marai-thinni	720	Patti-parutti	p. 12
Kandol	284	Maral	841	Pémarutti	630
Kannákampu	148	Maruthondí	308	Perukla	469
Kannu	288	Marukai	p. 21	Perumarandu	659
Kapila-podi	720	Marutu	290	Perum-kurundu	131
Kárai	385	Méladi-kurundu	182	Peru-nával	296
Kari-velam	268	Milagu	660	Perun-tutti	88
Karruvá	667	Mínachi	613	Pieri	172
Karukkuváchchi	172	Moongil	993	Pilá	744
Karupkáli	460	Moreli	190	Pinai	84, 614
Karuvakái	269	Morthiré-kuma	111	Pinari	98
Kassaddai	298	Muchalai	458	Pir-amati	93
Kata-manaku	613	Mukkarati	635	Pisukkap-kái	321
Katapuli	259	Mul-kilivai	137	Podivilángu	319
Kat-atti	263	Mullu-venké	690	Púkarupkáli	460
Kat-siragam	402	Mul-múkil	454	Puli	p. 29
Kattálai	851	Murukku	232	Pum-pullu	p. 46
Katti-kaiya	304	Murungi	296	Punai	11
Kavali	98	Mutirai	151	Pungai	250
Kelvaragu	978	Naka	73	Puṇku	250
Kethi-kanni	460	Náka-táli	p. 64	Punnai	71
		Nani-ilanthai	176	Purunké-nurai	127

Púsaní-kái . . .	p. 38	Thuvattai . . .	106	Velam . . .	268
Puttalai . . .	706	Tilai . . .	728	Vellai-kadamba . . .	354
Púvanti . . .	189	Tinai . . .	932	Vellai-karupkali . . .	460
Pu-varasu . . .	94	Tippili . . .	660	Vellai-nochu . . .	613
Puvu . . .	187	Tippili-pana . . .	874	Véli-paritti . . .	493
Radami . . .	297	Tírtu-kallí . . .	688	Vel-urruvai . . .	248
Ranai . . .	669	Tirukkondai . . .	257	Vel-velam . . .	268
Sadavaku . . .	724	Tiruvatti . . .	263	Vempu . . .	141
Saya . . .	365	Toddi . . .	101	Vengai . . .	249
Seenthil . . .	27	Tombu-kata . . .	71	Véré . . .	699
Sembu-nerenchi . . .	114	Tópu-nelli . . .	695	Vet-palai . . .	480
Senpakam . . .	12	Tumbika . . .	460	Vetti-vair . . .	960
Serappadi . . .	523	Tumpalai . . .	80	Vidi . . .	521
Sira-pulichul . . .	522	Udida-vengai . . .	249	Vid-puné . . .	705
Siru-chenumutthi . . .	112	Ughai . . .	466	Vinnaku . . .	101
Sittá-manaku . . .	p. 82	Ughil . . .	269	Virali . . .	193
Taintukki . . .	710	Ulavintai . . .	18	Visha-mungil . . .	843
Tamarai . . .	39	Vadatara . . .	267	Vitli-kanua . . .	452
Tammanná . . .	701	Vaimbadam . . .	175	Vukkana . . .	460
Tándi . . .	290	Vákai . . .	257	Vullum-puri . . .	100
Tanukku . . .	294	Vallárai . . .	342	Wadamadichi . . .	614
Taranai . . .	373	Vallarugu . . .	514	Wagé . . .	257
Tekku . . .	p. 68	Vammi . . .	353	Walsurai . . .	148
Termalái . . .	270	Vanni . . .	268	Wara . . .	267
Téttán . . .	510	Varagu . . .	929	Waragu . . .	926
Tevaturam . . .	112	Varit-thulai . . .	725	Waṭṭak-kai . . .	p. 38
Thain . . .	611	Vátham-addakki . . .	614	Yávaranai . . .	669
Thálé . . .	880	Vedú-kunari . . .	460	Yerkoli . . .	385
Thavarai . . .	p. 26	Vekandé . . .	460	Yerkum . . .	491
Thuvarai . . .	459	Vekkali . . .	291	Yetti . . .	510

the species, the new acquisitions are worked out and duly inserted in their proper places, various errors of nomenclature get corrected, doubts are cleared up, and the whole if thoroughly done gives a fair *résumé* of the progress effected. In the 20 years which have elapsed since the completion of the late Dr. Thwaites's valuable "Enumeratio" much has been published bearing more or less directly upon the Ceylon flora, among which may be specially mentioned Beddome's useful illustrated works on the Botany of Southern India, and that important summary of Indian Botany, the "Flora of British India." This very extensive undertaking by Sir J. D. Hooker and numerous fellow-workers, has proceeded through more than half of the Natural Orders, and is in active progress at Kew. By this invaluable book I have, of course, been mainly guided so far as it extends—i.e., to the order *Acanthaceæ*; in the subsequent Orders, so far as Genera are concerned, I have followed the standard "Genera Plantarum" by the lamented Bentham and Sir J. D. Hooker.

In Ceylon itself, though little has been published, practical exploration and investigation have not been intermitted. My predecessor's (Dr. Thwaites) plant-collectors brought in to him from the jungle many novelties, and our few resident botanists have also been very successful in adding to the flora. Mr. T. N. Beckett, lately of Matulé but now in New Zealand, Mr. William Ferguson, F.L.S., who lets no opportunity escape him, Mr. H. Nevill, C.C.S., a very acute observer in the field, and Mr. G. Wall, F.L.S., a keen hunter after ferns (to which group unfortunately he restricts his energies), have all contributed to swell this Catalogue of the Plants of the Island. Much of my own time since my arrival in Ceylon has also naturally been devoted to exploration, though far less than I could wish. As a result, the present Catalogue contains, I suppose, not far from 200 species additional to that of 1864, whilst the whole of the flora has undergone a critical revision, and is re-arranged according to the best available system. In the nomenclature and determinations, I have been often assisted by the botanists at Kew and at the British Museum, to whom my thanks are due. Even with this I am fully aware that not a few errors will be detected by botanists working with access to type specimens,

large herbaria, and full libraries: without these advantages it is often impossible to come to decision on doubtful points.*

The list contains about 3,250 species, of which the odd 250 may be reckoned to consist of the ferns and their allies, and the remaining 3,000 of the Phanerogams or Flowering Plants. In the remarks and comparisons which I now proceed to make, it is in general these latter—the Phanerogams—only that are taken into consideration.

2. Now the first thing to be observed with regard to these 3,000 species is that a very considerable number of them are no more natives of Ceylon than are the great majority of the Members of this Society. Like them they are aliens, settled colonists or denizens, or casual waifs and strays from other lands. This fact is always rather a surprize to those who see the vegetation of this country for the first time; for many of the plants which seem to them most characteristic really come under the category of foreigners. Such familiar trees as the Cashew Nut, the Mango, the Guava, the Country Almond (*Terminalia Catappa*), the Blimbing, the Papaw, and even the Horse-radish tree (*Moringa*), the Jak, and the Tamarind, are all of exotic origin, and introduced by man. Many of them are, no doubt, very ancient introductions, and from no greater distances than the adjacent Indian Peninsula, as the Jak, or the Malay Peninsula, as the Arecanut Palm; but many were brought from the W. Indies or Tropical America, much more recently. So, too, with the common garden plants and weeds which line our roadsides and cover waste ground; the *Opuntia* or Cactus, the Sensitive plant (*Mimosa pudica*), the yellow *Turnera*, the Castor-oil plant, the Marvel of Peru, the blue Vervain (*Stachytarpheta*), the white yellow or orange *Thunbergia alata*, the great white Trumpet-flower (*Datura suaveolens*), the pink or white *Vinca*, the Temple Tree (*Plumeria acutifolia*), the Allamanda, and many others; not to mention the too familiar *Lantana* and the nearly as abundant and much handsomer “Sun-flower” (*Tithonia diversifolia*). All

* Notes on the more important of the additions, and descriptions of the new species, will be found in my paper published in the “Journal of Botany” for 1885, commencing in the May number (p. 138).

are foreigners, and by far the greater number are from the New World, and therefore comparatively lately introduced, i.e. within the last three centuries.

This invasion of the Eastern Tropics by an army of herbaceous or half-shrubby weeds from the W. Indies is a remarkable fact.* It has had the effect of causing a very uniform character in the vegetation of the cultivated coast regions of the whole tropical belt, and it would not now be possible in many cases to even guess the origin of many species from their present distribution ; generally, however, their origin and history can be traced without much difficulty through the botanical treatises of the 16th and 17th centuries.†

Some of these plants, however, appear to inhabit naturally all the three tropical areas of Africa, Asia, and America, these are mostly such as are capable of having been transported by ordinary natural means of dispersion in past times.

3. In temperate zones the opposite state of things has held good, and the interchange of such plants between Europe and N. America has been all in favour of the Old World. English weeds have largely established themselves in the United States, &c., whilst few, very few N. American ones have succeeded in getting a permanent footing in Europe, those which have done so being a few annual species exceptionally provided with means for copious dispersion of seed, or aquatics. The same readily colonizing English weeds have also spread themselves over the cool mountain districts of the East, and as regards Ceylon a fair proportion of our introduced plants belong to this category. These, of course, are found chiefly about

* It is the clearing of land for cultivation that gives these alien plants their opportunity. A country naturally covered with forest has no native species able to compete with these foreign inhabitants of open country and plains, which, when once introduced, are thus able to spread without hindrance.

† The rapidity with which some useful or ornamental species were transported from the New World to the Old is very striking. The Portuguese came first to Java in 1496, four years after the discovery of America ; and in 1520 Magellan sailed direct from S. America to the Philippines. It was from these islands that the other Eastern tropics obtained many of the American plants now so abundant.

Nuwara Eliya, and have all been imported within the last 50 years, mostly with grass seed. The great Mullein (*Verbascum Thapsus*) now looks as thoroughly native as the tall *Lobelia excelsa* along with which it grows, and in several respects resembles; and such homely plants as the Chickweed, the Spurrey, the narrow-leaved Plantain (*Plantago lanceolata*), the Dutch clover, the Dock (*Rumex obtusifolius*), and the Yarrow, have quite established themselves as factors in the roadside vegetation.

Thus we have two very distinct classes of exotic naturalized plants in Ceylon, tropical and temperate; to which may perhaps be added a third intermediate one, comprehending the weeds of the Coffee and other estates in the hills, which are principally annual wide-spread *Compositæ* of uncertain origin, and occur in vast abundance; as the White weed (*Ageratum conyzoides*), *Gnaphalium indicum* (absurdly called in some places "Wild Mignonette"), *Erigeron linifolius*, and others.

The whole number of the various sorts of foreigners sufficiently well established to find a place in this Catalogue is, including those commonly cultivated and often appearing as if wild, no less than 194. After clearing these out of the way we find 2,729 Phanerogamic Plants remaining, and it is with this, the truly native flora, that we are now concerned.*

4. Considering the variety of aspect, climate, and elevation of this tropical island and its notoriously luxuriant vegetation, it might be expected to contain a larger number of species than that above given, and indeed before the flora had been well worked out a very much larger estimate was formed. Thus, Gardner in 1845 thought there would prove to be between 4,000 and 5,000 species in Ceylon, but it must be remembered that estimates of this sort greatly depend on the individual botanist's views as to specific limitations. Perhaps that number of Ceylon "species" has actually been *described* in books, but many are here considered as varieties. And I ought to say that the course followed here

* A suspicion of artificial introduction attaches to a few also of these—such are marked in the Catalogue by a †—whilst the certainly introduced and naturalized ones have * prefixed, and those half wild from cultivation are in ().

in this matter is a mean between "splitting" and "lumping;" such as is kept up with more or less consistency in the "Flora of British India," and the other Colonial Floras issued by the Kew botanists: it is at least convenient to be in accord with these for the sake of comparisons.

Let us then now compare in this respect of numbers, our flora with that of a few other countries. An island area near in size (about one-sixth larger) to Ceylon is Ireland (32,524 square miles). This lies in a cool temperate, very equable climate, uniformly humid, and with no great elevations of surface; the Phanerogamic flora is very poor in species, 972, and even this estimate would be somewhat reduced if the specific limits were drawn as broadly as in this Catalogue. At the Antipodes, New Zealand presents us with another but totally different temperate flora. Though the area of these islands nearly equals Great Britain and Ireland combined, only 935 species of Flowering Plants are recorded in the latest published Flora. It must not be supposed that temperate regions are less rich in species than tropical ones; on the contrary, the richest floras of the world in point of numerical strength of species are those of the Cape of Good Hope and West Australia, both in the South temperate zone.

When we attempt to compare Ceylon with other *tropical* regions, the difficulty meets us that there is scarcely any definite area of which the flora has as yet been so thoroughly worked out. We may take, however, that of the oceanic island of Mauritius, which is well-known, and is still very rich, though it is believed that many species have quite recently become extinct. This isolated island, however, is only 850 square miles in area; it possesses 1,058 native species. The flora of the great Philippine Archipelago (the collective area of which is 53,299 square miles, or more than double that of Ceylon) has been recently estimated at 3,466 species of Flowering Plants, and the vegetation is as yet but partially known. This shows a very rich flora, no doubt. A comparison of greater interest would be with the vast equatorial island lying to the south-east of us, Sumatra, which possesses a very similar climate to our own; but too little is accurately known to render this possible. A Flora published in 1860 gives the number of known species at

2,642, which must be much below the actual number. Thus then, when it is remembered that Ceylon is situated in that part of the Oriental area—the *Indian*—which is poorest in species, its total of native plants—including Ferns, &c., nearly 3,000 species—shows decided richness, and is probably greater than that of any part of Peninsular India of the same area.

5. In one of his admirable Presidential addresses to the Linnean Society of London, the late Mr. Bentham, remarking on the fact that no Flora of a tropical country of large extent had yet been completed, added, with regard to Thwaites's enumeration of the plants of Ceylon—then (in 1869) lately published, and the only completed Flora of any tropical region—that the chief interest of this isolated district “would lie in the comparison of its very rich vegetation “with that of other portions of the Tropical Asiatic flora, “which,” he added, “has not yet been made.” In the following remarks I purpose to make some progress towards such a comparison, though I have not at present the opportunity or the leisure to do so in detail, or as fully as the subject requires. Let us then endeavour to ascertain the elements of which our flora consists.

The most interesting portion of the vegetation of any country, and especially of islands, is that composed of the plants peculiar to it and not found elsewhere, or as it is called *endemic*. The proportion of such species is found to vary remarkably in different places, and on this to a chief extent the individuality and interest of any flora depends. In the British Isles, among over 1,400 native species there is probably not one which is peculiar or endemic, though four or five strongly marked local varieties are considered specifically distinct by some British botanists. As a contrast, in New Zealand more than 72 per cent. of the species found there are found nowhere else. Between such extremes there is every gradation. It has long been observed that oceanic islands—that is *small* islands (usually volcanic) widely isolated from continents in the deep ocean—possess a large proportion of endemic species. Thus in Mauritius (including Seychelles and Rodriguez) 29 per cent. are peculiar, and 22 per cent. more do not extend beyond the other Mascarene

Islands. In that little speck of land in mid ocean, St. Helena, nearly 78 per cent. of the small remnant of its once remarkable flora (i.e., 53 species out of 68) are found nowhere else in the world. Of greater interest and significance is it when *Genera*, and not merely species, are endemic; this, of course, indicates a still further specialization, and here oceanic islands are particularly remarkable. Thus in Mauritius 11 per cent. of the genera are peculiar, and in St. Helena a still larger proportion.

Now Ceylon, though an island, is by no means an oceanic one; rather it is what is termed a *continental* island, being separated from the adjacent continent by the very shallow and narrow piece of sea in Palk Straits. Yet the remarkable fact presents itself that while in Britain probably not a single species is peculiar, here in Ceylon no less than about 800, or more than 29 per cent. of the Phanerogams, are strictly endemic to the island. Indeed, to these would be added by many botanists some 50 more well-marked insular sub-species or varieties of continental species, which would raise the proportion to over 31 per cent.* We do not possess many endemic *genera*, however—only about 20, or little over 2 per cent.—but here also may be added, as of similar significance, some groups peculiar to the island which are here ranked as sub-genera only.

How are we to account for this large element of specialization in our flora?

6. The opinions and theories now generally held by naturalists to explain the present distribution of animals and plants over the globe have been expressed and explained in the writings of E. Forbes, Darwin, Bentham, Wallace, J. Hooker, and others. I may remind you of some leading points. Widely distributed as are some species over the world, it is held that each has spread from some single centre where it had its origin, and in cases where a species now exists, not over an unbroken area, but at two or more spots not continuous, and even it may be widely separated from one another, it is considered (when there is no evidence of transport by men or animals) either that these points

* This is perhaps a larger endemic proportion than is possessed by any other continental island with the exception of Madagascar.

were formerly in connection, or more often that each of them has been in connection with some common point of origin in the past. Thus, the floras of continental islands have, as a basis, the plants of the mainland. All but the whole of the English species are also European (the two exceptions being American), and it is reasonable to suppose that their passage was effected at a time or times when the land was in part continuous. The English Channel is nowhere over 100 fathoms deep, and in most places not half that depth. So too in Ceylon; *after deducting the endemic ones*, we have left about 1,929 species, all of which except about 130* are also found in the adjacent Peninsula of India. No doubt the separation of the northern portion of Ceylon from the opposite mainland is geologically recent, and the species crossed over hither before it occurred.

When, however, the localities in which a particular species or group is found are widely separated (i.e., its area is *discontinuous*) we have to assume often great changes of level, producing, in present continental areas, various and different arrangements of sea and land at different periods, and also extreme changes of climate. For the operation of these is required also a vast extent of time, but the revelations of palæontology and physical geology fully warrant the botanist as well as geologist in forming such speculations.

It frequently happens that the floras of two districts show their affinity not by identity of species, but, less intimately, by community of *genera* only, the *species* being different. A good example is found in comparing our mountain district with that of Southern India, say in both cases the flora of the hills above 5,000 feet. A large, varied, and beautiful vegetation characterizes both these regions, and they are evidently very similar. Less than 400 miles separates the summits of Pidurutalágala and Dodabetta (and there are half-way houses in the Pulnis and Anamalais). Yet the curious fact presents itself that more than half the species of our hills are not found in the Nilgiris or other hills of the Indian Peninsula, but are endemic here, and probably an even larger proportion of Nilgiri species do not extend to us. The number common to both ranges is only about

* This estimate is an approximation only.

200. Yet very nearly all belong to the same genera, which are almost identical for both regions. It is thus possible to make the contradictory assertions that the floras are very similar and very different.

Let us take some illustrative examples. Of the genus *Strobilanthes*, consisting of the well-known "Nillus," the Ceylon hills possess 22 peculiar species, and the Nilgiris, &c., about 29, whilst only 2 are found in both regions; of the mountain species of Balsam, genus *Impatiens*, there are also 2 species common to both ranges, whilst Ceylon has 10 others endemic, and the Nilgiris 30; and other examples could be easily given.

These representative species of one genus in different areas were a great puzzle to naturalists until the derivative theory of the origin of species became generally accepted, when it became evident that scientific "affinity" really meant relationship by descent. If we suppose a common origin for both these Hill-floras in the past, or derive the Ceylon one from the Peninsular, the differences now seen in the two districts indicate a sufficient lapse of time since their separation to allow of the evolution under different surroundings of new forms of the rank of species, but not of the superior rank of genera. In the case in question the energy with which this differentiation of specific forms has gone on is highly remarkable.

There are cases where the relationship of distinct floras is less intimate still, where it is traceable only in the larger groups (of genera) called *Natural Orders*. The two richest and most specialized floras in the world, as already noticed, are those of the Cape and Australia; probably, scarcely a single genus is common to them, yet the large and well-marked Natural Orders *Proteaceæ* and *Restiaceæ* are abundant in each of these far distant regions, and are almost confined entirely to them. This, according to present views, implies a common focus of origin in a remote past.

7. To return to the Ceylon flora. Of our *endemic species* the great mass, fully five-sixths,* belong, as would be

* The numbers given in this paragraph must not be regarded as more than fairly close approximations. I am not able to make the investigations here which are necessary to ensure close accuracy.

expected from what has just been said as to the Hill-flora, to *genera* which are more numerous represented on the opposite continent, whence our flora was for the most part derived. As to the remaining species, there are of course those (48) which go to make up our endemic *genera*, and there are others (about 73) which are members—usually solitary and isolated ones—of *genera* which, though not endemic here, yet have no representatives in Peninsular India. Such *non-Peninsular* *genera* are also represented in Ceylon, not by endemic species, but by discontinuous ones identical with those in other countries than India (about 35). These few (108) non-Peninsular species belong to almost as many (86) *genera*, very many more indeed than I had expected to find before making this comparison. It is, indeed, a very striking fact that this little island, so closely connected with the peninsula of India, should possess over 100 *genera* of Phanerogams (i.e., over 11 per cent.) which are not found on the mainland, and of which only 20 are endemic.*

We will first examine our comparatively few endemic *genera*. They are, counting in two sub-*genera*, 21 in number, as follows :—

Schumacheria (Dilleniaceæ) sp. 3. Straggling shrubs.

Trichadenia (Bixaceæ) Monotypic. A large tree.

Doona (Dipterocarpaceæ) sp. 11. Large timber trees.

Monoporandra (id.) sp. 2. Trees.

Stemonoporus (*Vateria* sect.) (id.) sp. 13. Large trees.

Julostylis (Malvaceæ) Monotypic. Tree.

Pityranthe (Tiliaceæ) Monotypic. Tree.

Scutinanthe (*Canarii* sect.) (Burseraceæ) Monotypic. Large tree.

Pseudocarapa (Meliaceæ) Monotypic. Large tree.

Gleniea (Sapindaceæ) Monotypic. Tree.

Pericopsis (Leguminosæ) Monotypic. Large tree (Nédun, Singh.)

Leucocodon (Rubiaceæ) Monotypic. Climbing shrub.

Schizostigma (id.) Monotypic. Herbaceous perennial.

Nargedia (id.) Monotypic. Shrub.

Scyphostachys (id.) sp. 2. Shrubs.

Championia (Gesneraceæ) Monotypic. Herbaceous perennial.

Hortonia (Monimiaceæ) sp. 2. Large shrubs.

* One of the endemic *genera*, *Hortonia* belongs to a *Family*, the *Monimiaceæ*, of which no member occurs in India proper.

Mischodon (Euphorbiaceæ) Monotypic. Tree. (Tammana Singh.)

Podadenia (id.) Monotypic. Large tree.

Cyphostigma (Scitamineæ) Monotypic. Herbaceous perennial.

Loxococcus (Palmae) Monotypic. Small Palm.

One or two species of *Stemonoporus* are mountain plants ; the remainder are all from the low country, and with the exception of three monotypic genera—*Pityranthe*, *Glenicia*, and *Mischodon*—which are found in the dry north and east, the whole are natives of the damp luxuriant districts in the south-western quarter of our island.

Next as to the non-endemic but yet non-Peninsular genera. The following is a list of them :—*

With species endemic.—56.

Wormia (1), Xylopia (3), Erythrospermum (1), Aberia (1), Kayea (1), Adinandra (1), Dipterocarpus (5), Sunaptea (2), Dicellostyles (1), Campnosperma (1), Ellipanthus (1), Dialium (1), Crudia (1), Agrimouia (1), Poterium (1), Anisophyllea (1), Axiuandra (1), Osmelia (1), Melothria (1), Allæophania (1), Urophyllum (2), Dichilanthe (1), Prismatomeris (1), Willughbeia (1), Alyxia (1), Baissca (1), Gaertnera (4, one non-endemic), Chirita (3), Ptyssiglottis (1), Glossocarya (1), Nepenthes (1), Lindera (1), Phaleria (1), Gyrinops (1), Norothixos (1), Ginalloa (1), Trigonostemon (2), Chætocarpus (2), Allæanthus (1), Acanthephippium (1), Phajus (2), Tæniophyllum (1), Mystacidium (1), ? Hetæria (1), Aphyllorchis (1), ? Dracæna (1), Oncosperma (1), Freycinetia (2), Sciaphila (3), ? Hypolytrum (2, one non-endemic), Mapania (2, one non-endemic), Tricostularia (1), Cladium (1), ? Eriachne (1), Gymnopogon (1).

With species non-endemic.—31.

Delima (1), Anaxagorea (1), Limacia (1), Pometia (1), Strongylodon (1), Dioclea (1), Peltophorum (1), Gynostemma (1), Rhipsalis (1), Uncaria (1), Stylidium (1), Chrysophyllum (1), Ochrosia (1), Dischidia (1), Crawfordia (1), ? Avicennia (1), Hernandia (1), Wikstrœmia (1), Taxotrophis (1), ? Appendicula (1), ? Galcola (1), Physurus (1), Cryptostylis (1), Gastrodia (1), Susum (1), Scirpodendron (1), ? Thuarea (1), Leptaspis (2), ? Lophatherum (1), ? Streptogyne (1), Lepturus (1).

* I am in doubt as to whether some of these may not extend into India ; those marked with a ? are possibly Peninsular. The figures in brackets refer to the number of Ceylon species.

The same remark applies here that was made with regard to the endemic genera. Nearly the whole are low-country plants of the wet south-west (several being sea-shore species). There are a few mountain types among them, in *Agrimonia*, *Poterium*, *Gynostemma*, *Cranfordia*, and *Wikstræmia*, which are thus especially interesting as not occurring in the Nilgiris.

It is then clear that this non-Peninsular element of our Flora is mainly concentrated in the south-west part of the Island; that is, between the high mountains and that part of the coast of the Indian Ocean fairly bounded by the towns of Colombo and Mátara. Let us now endeavour to ascertain whence it was derived.

I may say at once that the affinity of the great majority of the genera in the above lists is distinctly *Malayan* as opposed to Indian. By this geographical expression, I intend to indicate that type of vegetation characteristic of the whole of the Eastern or Malay Peninsula down to Singapore; of the great Archipelago stretching from the Andamans, Nicobars, and Sumatra eastward to, but not including, New Guinea; and also that extending northwards from Burmah through Tenasserim, Silhet, and the plains of Assam up to the foot of the Eastern Himalaya, which may be termed generally East Bengal. It is to this very rich and luxuriant flora that these plants of south-west Ceylon characteristically belong, though so completely discontinuous with it.

This would be readily seen in detail if we were to examine the distribution of the genera, both endemic and non-endemic, in the three foregoing lists. Fully three-fourths of them show this affinity unmistakably. In the non-endemic ones we find in many cases identical species occurring in Ceylon and in Malacca, or Burmah, or Borneo, or over a wide range of the Malay Peninsula and islands. In other cases the species are peculiar and confined to Ceylon, whilst their congeners inhabit these Malayan regions. Further examination of our flora would show us yet other species with the same affinity, although the genera to which they belong are not wholly absent from Peninsular India, as is the case with all those above enumerated.

A few striking examples are all that can be given here.

We may take 2 or 3 Natural Orders for analysis. Of *Dilleniaceæ* we possess 6 genera and 15 species; 1 genus *Schumacheria*, with 3 species, is endemic, but allied to Malayan ones; another, *Acrotrema*, has 7 species all endemic, and one very variable (of which many more species could be manufactured). Of this genus, which may be said to have its centre in Ceylon, there is one other species in the Malay Peninsula, and another occurs in Malabar (thus just excluding the genus from the above lists of non-Indian genera). The third genus, *Wormia*, is entirely Malayan, with the exception of our single endemic species (and one in Madagascar). The fourth, *Dillenia*, is mainly also Malayan; of our 2 species, one is endemic, the other also occurs in the Indian Peninsula as well as widely through Malaya. We have but a single species each of the remaining two genera, *Delima* and *Tetracera*, both of which are identical with Malayan ones, one also reaching Malabar. Of another family, *Anonaceæ*, Ceylon contains 13 genera and 39 species, and is too extensive to go through seriatim. But two of the genera, *Xylopia* with 3 endemic species, and *Anaxagorea* with one discontinuous, are Malayan and not Indian; whilst of *Ucaria*, with 6 species, 2 are identical with Malayan ones and 2 are endemic; and *Goniothalamus* has 7 species (6 of them endemic) against only 3 in Peninsular India and 7 in Malaya. But the most remarkable example of this western extension of the Malay flora to Ceylon is seen in the Nat. Order *Dipterocarpaceæ*, which is pre-eminently characteristic of the Archipelago. This family is a large one, and destined to be largely added to as investigation of the less-known Malay islands is further carried out; its members are all forest trees, and each species appears to be somewhat restricted in its range. Thus the 24 species recorded from Sumatra (under 4 genera) are all different from the far more numerous ones from Java. In the south-west of Ceylon we have no less than 8 genera of this Order, containing 46 species (i.e., 1·7 per cent. of the Phanerogamic flora and equal to the *Myrtaceæ*). Of the genera, 2—*Monoporandra* with 2 species, and *Doona* with no less than 11 species—are strictly endemic, and so is the well-marked sub-genus of *Vateria*, *Stemonoporus*, with 13 species. Of the remaining genera, *Dipterocarpus*, with 5

endemic species, and *Sunaptea* with 2, are entirely Malayan, whilst the last four—*Vatica*, *Shorea*, *Hopea*, and *Vateria*, sect. *Hemiphractum*—are chiefly so, though each is also sparingly represented in Southern India. All the *species*, however, are endemic in Ceylon with one exception, *Vatica Roxburghiana*, the “Mendora,” which is also found in many parts of the south of the Peninsula.

Before going further I must direct attention to the important fact which will now have become obvious, that this Malayan type is also present in the flora of the Indian Peninsula. It is in the hot, moist regions along the Malabar coast on the slopes of the western mountain range, and between that and the sea, that there is found a rich Forest-flora, containing numerous genera and species of great interest, some also Sindhalese, but others strictly endemic or at least not found in Ceylon, and many of which have clear Malayan relationships.* The order *Dipterocarpeæ* itself is represented by 9 or 10 species, and recently a new endemic genus of this family, *Balanocarpus*, with 2 species, has been found near Tinnevely. Other examples may be instanced in the genera *Xanthophyllum* (also in Ceylon), *Sarcostigma*, *Lophopetalum*, *Holigarna*, *Pterolobium*, *Acrocarpus*, *Xylia*, *Antistrophe*, and *Myxopyrum*.

This Malayan element is, however, much less striking in Malabar than in Ceylon, and forms a far less important factor of its flora. Proceeding northward it rapidly runs out, and has disappeared before the latitude of Bombay.

8. We return to the question, How did this Malayan flora reach Ceylon and S.W. India? I am not aware that this has been discussed from the botanical point of view, but naturalists generally have apparently been content with the theory of Wallace proposed to explain a similar representation of certain Malay types in our *fauna*. The representation in the animal world is, however, very feeble compared with that of the flora, and the botanical facts above remarked upon were probably not fully known to the eminent

* Recent explorations of the moist forests of Malabar, &c., have added to the Peninsular flora many plants previously thought to be peculiar to Ceylon.

zoologist quoted.* The principal Malayan affinities among animals are, I believe, found in two genera of Birds, *Phœnicophæus* and *Myrophœneum*, several genera of Longicorn Beetles, and the beautiful genus of Butterflies, *Hestia*; but I believe there is no large accumulation of such types in the south-west among the animals as among the plants of Ceylon.

Wallace's theory is to the effect that the shallow northern part of the Bay of Bengal has been elevated during the late Miocene and Pliocene periods,† and thus a few Malayan types were able to migrate to the Indian Peninsula, where they have been preserved only in the Nilgiris and Ceylon, where alone a suitable climate now prevails.

This would derive our Malayan plants, like the great bulk of our flora, from India. No doubt can be entertained of an ancient continuity of the south-west coasts of India and Ceylon, either directly or by their union with some intermediate or neighbouring land,‡ but the numerous cases among the plants of Ceylon where the closest affinities are seen to be with the flora of the Malay Peninsula and Archipelago, rather than with its extension into East Bengal,§ would rather lead one to endeavour to trace a former means of communication and transfer in a lower latitude, e.g., by the Andamans or Sumatra. Both districts were of course supplied from one and the same source, but it would seem more in accordance with present facts to derive the feebly

* It is singular that in Mr. Wallace's latest and very valuable book "Island Life" (1880), he does not once allude to Ceylon or the problems it presents for solution.

At this time geologists believe Peninsular India to have been cut off as an island from the countries to the north, the Gangetic plain being occupied by the sea.

‡ I am indebted to Captain Donnan for the information, which is important and somewhat unexpected, that the sea in the Gulf of Mannar is over 1,000 fathoms deep, and perhaps as much as 1,450 fathoms, half way between Kalpitiya and Cape Comorin.

§ For instance, *Dichilanthe*, a very isolated genus in structure, with one species in Ceylon and one in Borneo; *Azinandra*, *Prismatomeris*, and *Allæophania*, all in the same case; *Ptyssiglottis* with a second species in Java; *Gyrinops* with a second species in the Moluccas, and many similar cases; besides the identical species to which attention has already been called.

represented Malayan element existing in Malabar from the rich one in Ceylon, rather than to trace the migration in the opposite direction. I do not, however, venture to put forward any speculations on the matter; such should be supported by evidence, from sea-soundings, of the existence of banks or shoals indicating areas of submergence and the position of sunken lands near the Equator in the ocean intervening between Sumatra and the Maldives to the south-west of Ceylon; and I have no such data, and am not aware that any such exist.

9. Wallace is inclined to regard the occurrence of certain endemic animals in Ceylon and in S. India—as the *Loris*, several monkeys, a genus of Rats, *Elaphrornis* among birds, the *Uropeltidæ* among snakes, and certain Lizards and Batrachians—as indicating a separate *Indo-Ceylonese* zoological sub-region. In a general sense this may be also said of the flora, but in the rich moist regions of our island—the Western Province and parts of the Central and Southern Provinces—and the Malabar coast of India, I find it difficult to clearly distinguish any peculiar element characteristic of both, apart from the Malayan one already so strongly dwelt upon. There are, however, a few endemic genera which do not present any specially Malayan affinities. Thus, *Mischodon*, a Euphorbiaceous tree valuable for its timber, the “Tamma” of the Sinhalese, is very isolated in structure and confined to Ceylon. Three other Euphorbiaceans genera are common to both Ceylon and South India, *Ostodes*, *Adenochlæna*, and *Givotia*; in *Malvaceæ* *Julostyles* in Ceylon and *Decaschistia* in India are respectively endemic and closely allied; and there are also a few other genera common to both parts of the Indo-Ceylon region but not occurring elsewhere, as *Kendrickia* and *Fergusonia*. All of these have no marked relationship to Malayan types, and may be perhaps evidence of the existence of a special element apart from them.

As to the flora of our dry region—fully four-fifths of the area of Ceylon, and for the most part covered with low forest composed of a very uniform and monotonous vegetation—it is the Carnatic flora essentially. This is very much more fully represented in continental India than here, though

exploration of the north and east of the Island is continually lessening the disparity. To this type a moderate number of our endemic species belong, all closely related to continental ones, and clearly derivable from them or from common ancestors. Of our endemic genera, *Gleniea*, closely related to *Sapindus* and *Nephelium*, may be referred to this element, and possibly also *Podadenia*, more slightly allied to *Mallotus* in Euphorbiaceæ.

It would at first appear that in the high Hill-flora of the two countries stronger grounds for the establishment of a separable Indo-Ceylon Floral region might be found. Yet, in spite of the great development of species to which attention has already been called, we do not find any features which mark off these hill-districts as an area of preservation of ancient or special types. There is not, I think, a single endemic genus in either district or in both combined. The Ceylon hills certainly contain a few genera not met with in the Nilgiris, as *Agrimonia*, *Gynostemma*, and *Cranfordia*; and some species, as *Potentilla Mooniana*, *Anaphalis cinnamomea*, and *Lysimachia ramosa*; so, too, the Nilgiris have several genera wanting here, as *Fragaria*, *Rosa*, *Circæa*, *Passiflora*, *Lonicera*, *Carduus*, *Salix*, *Gnetum*, *Cypripedium*, and *Lilium*; but all of these are Himalayan, as is also, I believe without exception, every genus of these Indo-Ceylon highlands. Their flora, therefore, may be regarded as simply a southward extension of the Himalayan without any other admixture.

10. There remain now but a few anomalous factors of our Ceylon flora to be alluded to. The most interesting are a very small number which link us with Tropical Africa, or at least with Mauritius and the other Mascarene Islands.

Thus, *Erythrospermum phytolaccoides*, a beautiful ever-green tree of the south, is one of a genus of 6 species, all the others being natives of the Mascarene Islands. *Eugenia lucida* grows in the Mátalé District, but is elsewhere known only in Mauritius and Bourbon.

A very interesting plant is *Rhipsalis Cassytha*, a common epiphyte on old trees in the Central Province, which is found also only in Mauritius and Tropical Africa and

America. This is also the only member* of the large order of *Cactaceæ*, which grows naturally outside of the American continent. A few other examples of this connection with the West might be given,† though they are very few compared with the large number which Asia has given to Mauritius. But they equally point to a means of communication, which, it appears almost certain, once permitted the passage of organisms across the Indian Ocean.‡ The hypothetical continent of “Lemuria” invented to account for the distribution of that curious group the Lemurs, of which our *Loris* is a member, has been found unnecessary in the light of palæontological discoveries, but the existence of the very extensive shoals, coral reefs, and islands which are known under the names of the Carcados, the Chagos, and the Maldives, show the former existence of a series of very large islands in the deep ocean, and bridging the distance at intervals.

The Maldives possess a special interest for us. The sunken land upon which the “12,000 isles” have been built up by the coral-makers must at the lowest computation have been 500 miles long and 100 broad; another Sumatra must then have approached close to our shores. Now, the nearest atoll is 350 miles from Cape Comorin, and 400 from Ceylon, and the wild vegetation consists merely of a few sea-shore plants brought by the waves, and some weeds of cultivation. But in the past which has made the present,

* A second species of *Rhipsalis* has lately been found in Madagascar.

† There are also similar cases in the Peninsula in the genera *Naregamia*, *Calpurnia*, *Hardwickia*, *Droguetia*, &c.

‡ Several botanists have remarked that the main direction of the migrations of plants is from east to west, and it has been suggested that this is connected with the earth's rotation. We are also led from many considerations to the inference that the world has been originally stocked with plants from the north. Migration generally, then, when unchecked by insurmountable barriers may take an average course of from north-east to south-west. This consideration may tend to explain the fact that the great accumulations of endemic species are so often found crowded together in the south-west extremities of continental areas. The neighbourhood of Cape Town in South Africa and West Australia are striking examples; the Indo-Ceylonese flora under examination may perhaps afford another less marked one, and similar phenomena in a smaller scale are to be seen in Europe and its Islands.

the flora of Maldivia, doubtless, had its part to play in the great progressive drama of Nature. We can only guess at what it may have been, part apparently of the great bridge between Africa and Asia; but we may feel sure that this sunken land was intimately connected with the events and changes which contributed in their time to the formation of the existing flora of Ceylon.

APPENDIX.

I APPEND a few tabular statements bearing upon the composition of the Ceylon Flora, considered from a systematic point of view.

I.—*Number of Native Genera and Species.*

		Genera.		Species.
Dicotyledons	...	759	...	2,019
Monocotyledons	...	237	...	710
Phanerogams	...	996	...	2,729
Vascular Cryptogams	...	75	...	260
Total	...	1,071		2,989

II.—*Preponderant Natural Families.*

The following seven Orders, each containing over 4 per cent. of the species native to Ceylon, collectively comprise over two fifths of the whole Flora :—

		Number of species.		Per cent.
1. Filices	...	228	...	7·63
2. Leguminosæ	...	205	...	6·96
3. Gramineæ	...	198	...	6·62
4. Orchideæ	...	155	...	5·18
5. Cyperaceæ	...	152	...	5·08
6. Rubiaceæ	...	137	...	4·58
7. Euphorbiaceæ	...	132	...	4·41

Followed by *Acanthaceæ* (95), *Compositæ* (76), *Urticaceæ* (67), *Melastomaceæ* (52), and *Dipterocarpaceæ*, *Myrtaceæ*, and *Convolvulaceæ*, (each 46).

The average number of species to each Natural Order in Ceylon is 18.

III.—*Preponderant Genera.*

Genera containing over 20 species are:—

1. Cyperus	... 46	7. Ficus	... 24
2. Eugenia	... 40	8. Memecylon	... 23
3. Panicum	... 38	9. {	Crotalaria ... 21
4. Fimbristylis	... 34		Desmodium ... 21
5. Phyllanthus	... 30		Hedyotis ... 21
6. Strobilanthes	... 27		

The average number of species to a genus in Ceylon is 2.77.

IV.—*Endemic Species.*

The leading Natural Families (II.) which also contain a large proportion of Endemic Species, are:—

	Number of Endemic species.	Per cent.
Dipterocarpaceæ ...	45	97.8
Melastomaceæ ...	38	74.5
Myrtaceæ ...	26	56.5
Rubiaceæ ...	72	52.5
Orchideæ ...	74	47.7
Euphorbiaceæ ...	53	40.1

The average proportion of endemic species in a Nat. Order in Ceylon is 5.27 per cent., but over one-third of the Orders contain no endemic Ceylon species at all.

Leading Genera (III.) with a large proportion of endemic species are:—

	Number of Endemic species.	Per cent.
Strobilanthes ...	25	92.5
Memecylon ...	17	73.8
Hedyotis ...	15	71.4
Eugenia ...	25	62.5
Phyllanthus ...	16	53.3

The average to each genus is 0.76 per cent. in the whole Flora.

V.—The following Natural Orders are quite absent from the Ceylon Flora, though all possess species in some other parts of the Eastern tropics:—

Hamamelideæ, Epacrideæ, Myoporaceæ, Illecebraceæ, Cytinaceæ, Juglandæ, Myricaceæ, Casuarineæ, Cupuliferæ, Salicaceæ, Gnetaceæ, Coniferæ, Irideæ, Philhydraceæ, Restiaceæ.

RICE CULTIVATION UNDER IRRIGATION IN CEYLON.

By E. ELLIOTT, Esq., C.C.S.

(Read 11th August, 1885.)

FOR many years there has been a widely accepted idea that rice cultivation in Ceylon does not pay. A dictum of Sir C. P. Layard has been generally quoted in support of this, and two writers many years ago* published certain statistics which appeared confirmatory of this unfavourable view; and these were, I believe, allowed to pass unchallenged, though they contained errors which materially affect the result. However, whether erroneous or not, these opinions and figures referred to a time and to districts where the attempt had not then been made to provide irrigation. This fact has been overlooked in recent discussions; indeed, both writers and speakers have gone further, and have asserted that it would probably pay better to import nearly all the rice required in the Island, as it is doubtful whether Ceylon can economically compete with India in the production of paddy.

For many years past I have been unable to accept the low estimate made as to the small profit to be derived from paddy cultivation; but whatever doubts I may have had on this point have been entirely removed by my

* Mr. Ludovici's "Paddy Cultivation" and "Speculum's" letters. In "Speculum's" estimate, outlay in labour is excessive, especially for watching, reaping, threshing, and husking; while Ludovici takes too high a rate of wages—7*d.* as the value of a day's labour in a district where no agricultural labour was at the time remunerated in money. Other points in his calculation are also open to question.

observation of the effects of irrigation, where that has been provided on a satisfactory basis.

Since the question has been so prominently revived, I have taken considerable trouble to further investigate the subject ; and I have been able to collect a very large and varied mass of data as to the yield of paddy, as well as to the actual outlay necessary to bring a crop to maturity, in the irrigated lands of the Mátara and Batticaloa Districts.

The results proved so far more favourable to Ceylon than I had ventured to anticipate, that when invited by the Committee of this Society to contribute a Paper, I readily accepted the opportunity for making my researches public, in the hope of being able to remove doubts which might exist as to the possibility of growing paddy in Ceylon at a cheaper rate than it can be imported from India.

In discussing this question, it is convenient first to review shortly the information available, especially as regards the superior fertility of rice land in India. I have been unable to meet with any reliable returns of the yield of grain in North India, but I recently saw it stated in the newspapers that the average crop in Burmah was 42 bushels per acre, and that 1,500 pounds weight of paddy had been harvested from an acre of land in Bengal. The latter is equal to 30 English bushels by measurement, or a return of 12-fold according to the ordinary Ceylon rate of sowing. Much reliance cannot be placed on such casual notices as indicating the regular returns from an extended area ; but fortunately I have had access to the transactions of the Revenue Settlement of parts of the Madras Presidency, in which very elaborate statistics are given of the yield of various soils in the irrigated and rich districts, served by the works on the Godavery and Cavery rivers.

In these publications I find it recorded that in the Godavery delta, soil of good quality will produce, under irrigation, about two pooties of 800 seers of paddy per acre, and the next sort about one and a-half pooty. For the inferior soil about one pooty per acre may be assumed. As the pooty of paddy weighs 1,200 to 1,400 pounds, this yield is equivalent to 50, 40, and 26 bushels per acre.

In South Arcot, in the doab of the Coleroon and Vellar,

which is irrigated by the lower Coleroon anicut, it is stated that 300 experiments gave the following results:—

			Per Acre.	
			Harris Collums.*	English Bushels.
Island and other alluvial deposits	...		45	= 47 $\frac{3}{4}$
Permanently improved lands near village			40	= 42 $\frac{1}{2}$
Best lands with vandel or sandel†	...		35	= 38
Ordinary do. do.	...		30	= 32
Best ordinary, rich in sandel	...		40	= 42 $\frac{1}{2}$
Good ordinary	35	= 38
Ordinary	30	= 32
Ordinary red earth	25	= 26 $\frac{1}{2}$

Col. Baird Smith, in writing of the irrigation works on the Cavery and Coleroon, gives the average yield in the irrigated lands at 40 bushels per acre; and in his work on Italian Irrigation expresses no surprise on learning that in the permanent rice lands of Mantua and Verona the average produce per acre was estimated at 30 to 35 bushels of uncleaned grain, while the temporary land in the same and adjoining provinces yield about one-fifth more, or 40 bushels an acre. He adds: "The process of cleaning reduces the rice to about one-third its bulk, so that for permanent land the produce would be nearly 13 bushels of rice."

In a recent Order of the Madras Government reviewing the working of the Saidapet Farm, it is recorded that in the reply given by the Director of the Revenue Settlements to the Famine Commission, the average yield per acre of rice lands in this Presidency is stated to be 1,884 pounds, and in some localities it exceeds 2,500 pounds. These figures represent 35 and 50 English bushels of paddy, and would, in the agricultural parlance of Ceylon, be spoken of as equivalent to a yield of 15- to 20-fold on a sowing of 2 $\frac{1}{2}$ bushels per acre.

It must be remembered that these data are drawn from the hurried trial measurements of the Settlement Officers, and it has been recently urged that, as these results are

* One Harris collum = 24 Madras standard seers of 100 cubic inches = 1.06 English bushel.

† Fine mud deposited by the floods.

deduced from experiments on a limited scale, the tendency is to exaggerated results.

Nor must it be overlooked that there is in India a system of cultivation which is decidedly superior in many respects to that followed in this Island; and I have been also assured that in the Madras Presidency much more manuring is done than in Ceylon, though there is still room for improvement in this respect.

Turning to Ceylon, the first matter to be dealt with is the *cost of cultivation*; and on this point I am able to give very full information, the result of personal inquiry in the Mátara and Batticaloa Districts. As the details of cultivation differ in many respects in these Districts, it is necessary to give a short outline of the practice in each.

In Mátara, one or more cultivators jointly undertake the tillage of a field. One at least of these men has generally a proprietary interest in the land. There is no hiring of coolies or money payments for any additional requirements. The work is done on the co-operative or bee system, neighbours mutually assisting each other without any special remuneration beyond a good meal provided by the individual whose land is being tilled.

The cultivation of paddy has been so extended in the Mátara District, and the available land is so incessantly under crop (two harvests being almost invariably taken from the same land in the irrigated villages), that there is little or no grazing ground left for cattle, and the buffaloes especially have to be driven long distances*—some beyond Tangalla, 15 miles away—for pasturage.

In consequence of this difficulty and the abundant supply of manual labour, cattle are very little used, and the fields are almost entirely tilled with the mamotie. The soil is dug up and turned three times and then sown, and this occupies a man about 40 days for an area of an amunam, or $2\frac{1}{2}$ acres.

As the cattle are folded or driven away, there is no

* In Mátara District in 1882 the number of buffaloes was only 10,162, and in the chief irrigated Pattu, the Gaggaboda, only 1,800, or one to every 8 acres. In Batticaloa the number was 36,630 in 1882, or about 1 to every 2 acres cultivated with paddy.

fencing to be done, and watching too has been nearly given up, as all the people live in gardens bordering the fields, and there are no wild animals, such as pigs or elephants, to be guarded against.

Reaping an amunam's extent occupies a man 16 days, and threshing and winnowing about 30 days for an average good crop. Allowing a margin for contingencies, the cultivation and harvesting of an amunam of land in the irrigated villages of the Mátara District require 90 days of a man's labour, or 36 days* per acre, besides an outlay of about four bushels of paddy for seed and tools.

I may here mention that Mr. Weeracoddy, in the report of his experiment in Kégalla, gives 34 days per acre as his outlay in labour, inclusive of certain permanent improvements he had to undertake.

In *Batticaloa*, the arrangements for cultivation are not so simple, while the lands are more extensive, and a smaller portion of proprietors cultivate their own lands. There are two extensive harvests in each year, known as the "munmári," which may be termed the winter crop, and the "kalawellámai," or spring crop.

For the "munmári" it is usual to engage cultivators, of whom one is termed the head field servant or mullakkáran, who has certain privileges, and supervises the other three field servants (or four in all) required for an extent of ten amunams. As the long drought which prevails during the South-West monsoon hardens the ground, it is usual to wait for the light rains of September to soften the soil before beginning to plough.

The object kept in view in ploughing with the small native implement (which is similar to that used in other parts of the Island) is by frequently going over the land to thoroughly pulverize the soil. The seed is then sown broadcast without being germinated, and left to spring up by itself under the influence of the first rains, ploughing and sowing going on until stopped by the heavy rains of October. A description of paddy which takes six

* I find Ludovici in his "Rice Cultivation" estimates the labour for cultivating an acre at very nearly the same number of days.

months to mature is sown at first, and latterly one which requires four months. By this means the most is made of the time favourable to sowing, while the rush at harvest is reduced by the crop not all ripening at the same time.

Cattle are hired for ploughing, and payment made in paddy, varying (for a ten-amunam extent) from six amunams in the southern districts to four amunams in the northern, where cattle are more plentiful in proportion to the arable area.

In October and November the field servants complete the fences and repair the ridges, &c. ; and, ordinarily, for three months after this they have but little to do, beyond sleeping at night in the watch-huts, though they are supposed at intervals to patrol the fences. Their days are practically free, and they can engage, if so inclined, in other occupations which will not take them too far away. As a fact, all grow plots of vegetables and tobacco on the higher portions which are to be found in every munmári land, besides shooting game, fishing, and collecting jungle products. In some localities they are able, in January, to undertake the cultivation of lands for kalawellámai, especially in the southern districts. In March the reaping begins, and the crop might be all threshed out by the end of April ; but in practice it is stacked and threshed out later at leisure, to admit of the field servants taking part in the cultivation for kalawellámai now going on.

For reaping extra assistance is taken on, though not invariably, and costs from three to five amunams (for ten amunams' extent) according to the locality and the demand for labour at the time. Threshing out the crop is done entirely with buffaloes, which have generally to be hired, and this operation costs from $2\frac{1}{2}$ to 4 per cent. of the crop in kind.

Other charges, also paid in kind, are the "kuruvikáran" or bird-boy, who is employed to frighten off the birds at the time of sowing and when the crop is in ear ; also the cost of ploughs and mamoties, Vattai Vitánai's fee, &c. : these charges may be put down at two amunams for every ten amunams' extent.

The cost of cultivation of an extent of ten amunams (or

say 25 acres)* with four or six months' paddy for the "munmári" thus amounts to an outlay (including seed paddy) of about 26 amunams in grain, and the services of four men for a period of 8 months, or 960 days of a man.

The kalawellámai is sown between February and May. The paddy generally used is of a kind which ripens in three months, and is germinated before sowing. The lands cultivated for this harvest invariably lie low, and have been generally flooded during the rainy weather of the North-East monsoon. They are consequently much softer and more muddy than munmári lands, and are trampled with buffaloes (costing six amunams) and tilled with the mamotie. The proportion of field servants required is also smaller, and three can undertake an extent of ten amunams; but, on the other hand, more additional aid is required in sowing and at harvest time; while the extra charge for reaping and threshing comes to nearly 50 per cent. more, viz., 11 amunams against 8 for munmári. Then there are the usual charges for bird-boy, tools, &c., amounting to $2\frac{1}{2}$ amunams more.

The crop is reaped and threshed between June and August. The cost of cultivating ten amunams' extent, or 25 acres, for kalawellámai, amounts to an outlay of 32 amunams in paddy, and requires the labour of three field servants for 5 months, or 450 days of a man.

In this District also no money wages are paid for agricultural operations, the regular cultivators being remunerated by certain shares and perquisites out of the crop. But if additional assistance is required for any purpose, the ruling rate is a "marakal" (a quarter of a bushel) of paddy a day. At this rate the expenses of cultivation in grain would average 13 bushels per acre.

This result agrees fairly, though worked out independently, with a reply furnished to a Committee of the Legislative Council by Mr. Crowther, a Proctor and landowner at Batticaloa, in which the cost of cultivating 75 bushels,

* In Batticaloa District it is usual, according to season, situation, &c., to sow from 2 to as much as $3\frac{3}{4}$ bushels of paddy in an area of an English acre. I have accordingly assumed 3 bushels to the acre as a fair average proportion in my calculations. This makes the amunam sowing extent the same as in the Singhalese districts.

extent by hired coolies is given at 350 bushels in grain, or about 13 bushels per acre. In another estimate for cultivating 10 amunams in the customary manner, Mr. Crowther provides for three field servants, and an outlay of $24\frac{1}{2}$ amunams of paddy (exclusive of ground share or rent, and consumption paddy which is an advance repaid at harvest time).

From the Indian reports I find that in the Godavery District, where agricultural services are remunerated in grain, the expenses of cultivation are very nearly the same, and are given in the revenue reports as $3\frac{1}{2}$ pooties of grain for 1 pooty extent, equivalent to 100 English bushels for 8 acres, or $12\frac{1}{2}$ bushels the acre. In other parts of the Madras Presidency the rate is very much the same.

Perhaps it is as well I should explain that I have throughout dealt with the case of a proprietor working his own land with his own capital, hiring at ready money prices any additional aid he requires in men or cattle, so as to avoid liability for the exorbitant rate of interest charged for deferred payment, which, in Batticaloa, is never less than 50 per cent.

All the information which I have collected (though obtained direct from practical working agriculturists) has, owing to my official position, been afforded under the impression that it was sought with a view of increasing their liabilities to Government. We may consequently, I think, safely conclude that the figures given are very outside estimates, rarely worked up to, and include charges not always incurred. For instance, I have made no deduction for the spare time on the cultivator's hands between sowing and reaping, which a European employer of labour would doubtless find some way of turning to account. Indeed, many natives do, to my own knowledge, utilize it for other purposes, as already explained, as the only call on them during this interval is that of watching by night, which is done alternately or by arrangement, so as to admit of at least half the men being absent at a time, and frequently by the substitution of mere children.

Again, as regards harvest operations, I found, when going round, that in many instances these are done by the regular field servants, sometimes aided by their female

relatives and children (who get no additional remuneration), and no extra aid is called in unless the crop is really a heavy one, and comes in with a rush; but I have allowed the full charge in all cases.

I will now pass to consider *the quantity of paddy that can be grown on an acre of land*. But I must first point out that the yield in Ceylon is generally spoken of by "fold," and, ordinarily, without reference to the amount of seed sown, or the mode of sowing adopted. In India the seed is, I believe, invariably sown in small beds, and the plants transferred when about a month old to the prepared land in which they are to be matured. Under this system 50 to 60 pounds weight of paddy, or about an English bushel by measurement, suffices to sow an acre of land.

In Ceylon (except, perhaps, in Jaffna on a small scale) this system is not followed. The seed is sown broadcast, and in the Batticaloa District for the *muumári* without being previously germinated, as usual in the Sinhalese districts. This leads, I believe, to great waste, as much as $3\frac{3}{4}$ bushels to the acre being, it is alleged, sown in some lands in Batticaloa, and nowhere less than two; while in the Sinhalese districts it takes six bushels to sow an *amunam's* extent, or about $2\frac{1}{2}$ bushels to the acre. A return, therefore, which might be termed one of 30-fold in India, would be equivalent to one of 12 in most parts of Ceylon, and in some parts to only $7\frac{1}{2}$ -fold. In examining the figures for Ceylon, therefore, it will be well for purposes of comparison to reduce the returns secured to the number of bushels of paddy per acre.

In Mannár, Baldæus speaks of a return of a 100-fold, and Mr. De Hoedt, late Head Clerk of the District Kachchéri, and a landowner and practical cultivator, assures me that in a favourable season (in the absence of proper irrigation) he has ordinarily obtained a return of 30-fold on a sowing of $3\frac{1}{2}$ bushels, or over 100 bushels an acre; and that 25-fold or 87 bushels is the usual return cultivating in the ordinary native way.

In Má tara, before irrigation was introduced, in favourable localities a return of 30-fold or 75 bushels an acre was admittedly obtained; and Mr. Dawson, in his reports as Grain Commissioner, speaks of a similar return being

secured in two villages near Hikkadnwa. These returns are exceptional, it is admitted, under existing circumstances; but they are mentioned to show what can be, and is being, secured in Ceylon without the stimulus of improved cultivation or regular irrigation.

It cannot be too emphatically insisted that the primary consideration in regard to paddy cultivation is a regular water-supply. In its absence the best lands give but an indifferent return, and where it is present the poorest lands give, I believe, a remunerative crop. In the irrigated districts of Mátara it is now freely admitted that a crop of 30 bushels to the acre is regularly secured frequently twice a year, and in Batticaloa there is ample evidence that the return varies from 30 to 60 bushels per acre, with a most slovenly and imperfect style of cultivation, in which very little is done by man and a great deal by Nature.

I see it stated in the report of the Irrigation Committee of 1867 that the return in Ceylon was at one time $17\frac{1}{2}$ -fold, according to an inscription in the Polonnáruwa tablet. This, I presume, refers to lands irrigated by the tanks erected by the Sinhalese Kings, and I have every reason to believe fairly represents the return now-a-days in the irrigated districts in the south and east of the Island. I need not here refer to the evidence on which this opinion is based, as I am content to rest my calculations as to rice cultivation on more moderate returns.

We will first take the case of a gross crop of 25 bushels of paddy to the acre, which would be spoken of as a return of 10-fold in the Sinhalese districts, and of 7-fold in South Batticaloa, where the acre is considered as equal to $3\frac{3}{4}$ bushels' sowing extent.

Dealing first with Batticaloa, we must, from the gross return, deduct the outlay in grain for seed, ploughing, &c., already detailed, and the Government tithe. These first charges amount to 10 bushels per acre for munmári, and leave a nett outturn of 15 bushels as the return for the 38 days' labour bestowed by the cultivator in the sowing and gathering of the munmári crop, or about $2\frac{1}{2}$ days' labour for the bushel of paddy.

This is an outside estimate of the most expensive cultivation I know of in Ceylon, and one, I believe, never

touched. In kalavellámai lands, in which a quicker-growing paddy is cultivated, after the usual deductions the cost falls to $1\frac{1}{2}$ day's labour to the bushel; and if a return of 30 bushels to the acre is secured, the proportion is still further reduced to 1 day's labour, while a return of 37 bushels would secure a bushel of paddy for $\frac{3}{4}$ day's labour.

In Mátara the proportion is as follows:—

For a 25-bushels' crop $1\frac{3}{4}$ day per bushel.

30-	„	$1\frac{1}{2}$	„
37-	„	$1\frac{1}{8}$	„

As I have already stated, the expenses of cultivation have erred on the side of liberality, while the return has been taken at a moderate rate. I feel, consequently, after a very careful consideration of the whole subject, I am by no means overstating the case in venturing to affirm broadly, that in a fair land, properly irrigated, on an average *a day's labour produces a bushel of paddy*.

As I have taken a low rate of yield, I have made no special deductions for unfavourable years, attacks of insects, &c. Flood and drought are the two great enemies of paddy cultivation. The former is not hurtful unless the plants are submerged for an excessive period, fluctuating according to age and variety, and can be guarded against by selection of land and timely sowing. On the other hand, these floods do good by the fertilizing matter deposited on the lands, and in every district I have found the best lands are those liable to be inundated at frequent intervals. When irrigation is provided, it is possible to choose the proper time to put in the seed; the cultivation is practically independent of the weather to a great extent, and the danger of drought reduced to a minimum. Caterpillars and flies (or more properly speaking a description of bug) are the next most important enemies of the paddy plant. Caterpillars can generally be got rid of with a good supply of water, and the damage by flies is, I believe, limited in extent. I recently saw some fields, about which there were loud complaints, and which were said to have suffered more than had ever been experienced in that locality. Inquiry showed the yield had been reduced by about 2-fold in fields which ordinarily return 7 to 9-fold. In Madras an allowance of 15 per cent. on *the full crop of a favourable*

year is considered sufficient to cover all adverse contingencies.

I have purposely worked out my figures so far in days' labour and grain, in keeping with native modes of estimating agricultural outlay. In addressing a European audience it is necessary to attach money equivalents to these results, based on the value of labour in each locality.

In Sonth Batticaloa the ordinary rate of pay on the cocoanut estates is 18 cents per diem, and the hire of an agricultural labourer is a marakal of paddy per diem, which generally changes hands at about the same rate. The road commutation tax in both Batticaloa and Mátara is Rs. 1.50 in lieu of six days' labour. In neither District is there any special demand for labour, except for paddy cultivation. Twenty-five cents a day is therefore an exceptional wage, and a very outside value of time in the local labour market of both Districts.

In my opinion, the most unfavourable view that can be taken of the situation is that paddy can be grown in Ceylon for $37\frac{1}{2}$ cents a bushel, and that it is probable a large proportion is raised at a cost of 25 cents (sixpence) a bushel; while it can be sold nearly everywhere for at least a rupee, leaving a profit of 75 cents per bushel to meet interest on capital invested, &c.

Turning to India again for a moment, I find that the average selling price of paddy in the Madras Presidency has been 94 cents per bushel during 1881 and 1882, against 96 cents for the three years previous to the famine. To this, on grain coming to Ceylon, has to be added Customs duties amounting on both sides to 26 cents per bushel, besides freight and other charges. So that it is not surprising the price of paddy is generally Rs. 1.50 in the Jaffna market, where alone Indian grain comes into competition with the surplus production of the Batticaloa District, and that surplus comes burthened with charges for transport of over 50 per cent. on the cost of production. In the Colombo bazaar Indian paddy generally sells at Rs. $1.37\frac{1}{2}$ per bushel, and the Customs valuation for statistical purposes has for some years been Rs. 1.50.

This brings me to the consideration of the cost of bringing Ceylon paddy to market. In Mátara not nearly enough

is yet grown to meet the demand of the resident population, and consequently there is a market on the spot.

In Batticaloa, on the other hand, an excess over local requirements is produced even in unfavourable years, and in 1883 over 350,000 bushels were exported to Jaffna coast-wise, besides what was sent inland to Badulla and Bintenna, of which no account can be obtained. As Jaffna ordinarily absorbs an annual import of about 900,000 bushels of paddy, there is still a considerable margin in this market so long as Batticaloa can undersell Indian paddy, as it does now.

Batticaloa is further favoured by possessing cheap transport to this market, owing to the facilities offered by the extensive backwaters, which are such prominent features on this side of the Island; and the fortunate circumstance that both harvests fall within the period when communication with Jaffna by sea is easy and rapid. A considerable number of native vessels engage in the trade, especially during the continuance of the South-West monsoon, and paddy can consequently be transported from the threshing-floors in the fields to any seaport market in the Jaffna Peninsula for about 20 cents per bushel.

A grower of paddy in Batticaloa can therefore, in my opinion, put his paddy into the Jaffna market for about 50 cents a bushel, and secure a profit of about 75 cents a bushel—possibly a little more.

In Mátara the extent of waste land is now very small, and as there is considerable wealth in the District, fields in favourable localities fetch fancy prices, running to as much as Rs. 200 to Rs. 250 per acre.

In Batticaloa the circumstances are very different, and the supply of land is still in excess of the demand. For a limited extent situate in a central locality, an alluvial well-watered plain, known as the Karaivákuppallam, the value rivals, if it does not exceed, that for the best lands in Mátara; but the usual price for ordinary paddy land in cultivation is Rs. 30 to Rs. 50 per acre, and at this rate a large proportion of the fields could be purchased. Waste land in this District can be procured at Rs. 10 per acre and survey fees, payable in four annual instalments. As the Batticaloa lands when sold are covered with jungle, after cutting out any timber available, purchasers hand over the property for a couple of

years to persons who undertake to clear and cultivate it, taking as remuneration the crops grown during the interval; no ground share is claimed, and the owner advances seed and maintenance paddy, which are repayable, but without interest. An expenditure of about Rs. 10 in cash is required to put up the dams and bridges, which are frequently of larger dimensions than is usual in the Sinhalese districts. It is difficult to say what the total cost of asweddumizing comes to in money, but, so far as I can judge, it is not more than Rs. 30 per acre, a portion of which is generally recouped by the timber.

The task I set myself is now finished, and I trust it will be considered that I have shown paddy can be locally grown, with the aid of irrigation, more economically than it can be imported. I have endeavoured to give a truthful, fair epitome of the information I have drawn from the lips of all classes, chiefly the practical fieldworkers, with whom I have been brought more directly in contact during the past two years, especially in the Batticaloa District. As regards expenses of cultivation, my inquiries are more than corroborated by the outside and independent testimony of others to which I have already referred.

The only point which is really open to discussion is the rate of yield. This I have purposely kept low, I believe below the truth, and I appeal to the gentlemen who have experience in such matters if I have not been most moderate in basing my calculations upon a yield in irrigated lands which would, in the Sinhalese districts, be spoken of as varying from 10 to 15-fold, and of 7 to 10-fold in the localities where $3\frac{3}{4}$ bushels to the acre are sown.

I have selected for the investigation of this question two districts in which the construction of irrigation works has introduced a considerable element of certainty in the cultivation of paddy, and it is practicable to judge results by pecuniary tests in accordance with European ideas. When a reliable water-supply is absent, and paddy-growing depends on the rainfall, it is probably liable to more vicissitudes than any other branch of agriculture in the Island, perhaps in the world. It would be a waste of time to consider its pecuniary capabilities under such conditions.

But, fortunately, the rainfall in some parts of the Island,

and in the more populous districts, is well distributed, and paddy cultivation is carried on with results only second to those ensured by irrigation. Where such favourable circumstances are wanting, there is really only one remedy, and that may be summed up in the single word "irrigation."

I know no other of equal efficacy. Improved modes of cultivation, new implements, and fresh seed, are all of secondary importance. Where necessary, make the water-supply tolerably secure, and we may and can rival India, if we do not do so already, in the economical production of paddy, though it may be a long day before we can entirely overtake the local demand. Still, the fact remains that while paddy cannot apparently be imported into Ceylon for much under Rs. 1.50 per bushel, we can produce it in the Island for one-third this sum at the very outside.

PLUMBAGO :

*With special reference to the Position occupied by the Mineral
in the Commerce of Ceylon ;*

*And the Question discussed of the alleged existence in the
Island of the Allied Substance, ANTHRACITE.*

BY A. M. FERGUSON, Esq., C.M.G.

(Read 28th August, 1885.)

THE mineral of which this paper treats is a form of carbon, the substance which constitutes so large a portion of organized nature, more especially of the vegetable world. Graphite is in truth vegetable matter mineralized by those various forces of moisture, heat, friction, pressure, and electricity or magnetism, which have so marvellously metamorphosed the primitive rocks in which the mineral is generally, if not exclusively found. In Geikie's Handbook of Geology, graphite is mentioned first in the list of rock-forming minerals, sulphur and iron following, before silica in its protean forms is specified. In a more or less definitely crystallized, foliated, columnar, needle-like, or massive shape, the mineral embodies the altered remains of some of the earliest plant forms which appeared on the earth, when the fiat was uttered in the far back ages of creation, "Let the earth put forth grass, herb yielding seed, and fruit tree bearing fruit." Those of you who entertain a vivid recollection of the fascinating paper by Dr. Trimen on the Flora of Ceylon, recently read in this hall, can imagine the delight it would afford that eminent naturalist and thousands of other scientists, could the brilliant steel-grey to jet-black ore we are considering reveal the secrets of its vegetable origin and show the fibres, the leaves, the flowers, and fruits of the earliest herbage of the morning of the times, from which it has been transformed, in like manner as ordinary coal also generally speaks of the early days of the geologic

ages. But graphite,* (so called from its earliest use in the formation of pencils for writing and sketching,) and which there can be little doubt is closely allied to coal, although generally older in origin, and the subject of more intense and long-continued metamorphic influence than the carbonaceous substance so valuable as fuel, is too highly mineralized (with the exception, perhaps, of the formations in Canada) to display a trace of the vegetable tissues from which it claims its descent.

To the seeker for fossil remains of ancient organic life, therefore, graphite like our other primitive rocks, gneiss and crystalline limestone, is less interesting than are the coal measures, with their wonderfully preserved specimens of plants and animals and shells, on which human eye probably never looked until the operations of the toiling miner revealed their, in some cases, almost perfect lineaments. Graphite seems, in truth, to be the most highly crystallized form of carbon next to the peerless diamond, which poetically, if not with perfect scientific accuracy, has been described as a drop of pure liquid carbon crystallized. If such were the case, the most brilliant rays which light can yield seem to have played on the drop and to have been captured by the agency, perhaps electricity in one of its multitudinous forms, which gave the gem its unrivalled hardness, in addition to unapproachable brilliance and beauty. Graphite (to which, when burnt, the diamond reverts) has a beauty of its own, and as small diamonds have actually been formed by artificial means, the time may possibly arrive when the form of carbon which mineralogists rank only next below the diamond, may, by means of the appliances of progressive science, be advanced from the second to the first place. Let us only attempt to imagine a mass of pure graphite equal to a quarter of a ton, such as that sent to Melbourne in 1880, and the still larger mass which will probably figure in the Court of the

* BLACKLEAD, PLUMBAGO, GRAPHITE, WAD; (DUTCH, *potlood*; FRENCH, *mine de plomb noir*, *plomb de mine*, *potelot*; GERMAN, *pottloth*, *reissbley*; ITALIAN, *miniera di piombo*, *piombagine*, *corezolo*; LATIN, *plumbago*; SPANISH, *pie dra mineral de plombo*.)—MACCULLOCH'S DICTIONARY OF COMMERCE.

Colonial and Indian Exhibition of 1886, metamorphosed into diamond "of purest ray serene," and try to conceive the thing of beauty it would be, even if shrinkage in the transformation process reduced its size to one-tenth or even one-hundredth of the original bulk. Meantime it seems curious that Ceylon, so rich in "precious stones," which with all their brilliancy are simply crystallized and coloured clays, should be utterly destitute of specimens of the king of all gems, seeing that diamonds are found close by us in Southern India, and in formations similar to those existing here: laterite, occasionally, and especially in association with corundum, which in Ceylon is so common and of which our most precious sapphires and rubies are but higher forms.

But of more value to Ceylon economically, beyond all comparison, would be the real discovery amidst its rocks of that form of carbon which ranks next to the diamond and graphite, and which seems to be graphite and perhaps diamond in a less altered form. It need scarcely be said that coal is referred to. The late Dr. Gardner, of the Peradeniya Royal Botanic Gardens who was eminently a geologist, expressed a strong opinion to the effect that where primitive rock—in our case gneiss—forms the surface formation, it is hopeless to look for coal beneath. It is true that in India coal has been discovered in formations or positions where it never would be expected to occur in Europe. But I am not aware that in any case coal has been found underlying, or near the surface of, primitive formations. The only important class of rock, so far as I am aware, which is associated with our Ceylon gneiss, is itself a primitive formation, and is to a certain extent a carboniferous rock—I refer to the crystalline magnesian limestone known as dolomite; this rock contains, in varying, sometimes in large proportion, carbonate of lime, but in that respect alone has it the remotest affinity to coal.

Were coal really, whether the so-called bituminous mineral or the more highly crystallized form called anthracite, to be found in association with this lime and with our abundant plumbago and fine clays, then indeed might the "millions of tons of iron" of which Dr. Gyax wrote nearly forty years ago, and which he said could be laid down at Colombo for little over £6 a ton (with native anthracite at only 18s.

per. ton) be utilized, so as rapidly to solve the problems of cheapening steam navigation and covering the surface of the island with iron highways. Much of our plumbago, now so largely exported to the Far West, might then be retained and used in the shape of crucibles for the manufacture of Ceylon steel, with more profit than the Sinhalese usually derive from their native iron, on the production of two shillings' worth of which, according to the Swiss geologist abovementioned, the natives spend nine shillings' worth of fuel and labour.

But nothing in my researches with regard to this paper has been to me so great a shock and disappointment as the apparent impossibility of verifying the existence in Ceylon of the valuable mineral—it would be doubly valuable now that planters will largely need just such a fuel as it would yield for preparing their tea—which, between 1847 and 1849, Dr. Gyax professed, with such a flourish of trumpets, to have discovered. He stated that it existed where stone or glance coal might be expected to occur (had “bituminous” coal ever been present), in juxtaposition with basaltic rock, and in such abundance that he estimated it could be delivered in Colombo at the very low price I have named, of 18s. per ton!

Specimens of anthracite which Dr. Gyax alleged he had collected in Ceylon were, with other minerals, deposited in the Museum of this Society, and in his report to the government of Lord Torrington, dated 30th June, 1848, Dr. Gyax remarked, speaking of the vast quantity of excellent iron and of its being easily smelted, “*But anthracite being easily found on the spot*, could be used in the proportion of three to one of English coal and much cost saved.” Again, in the same report there is a distinct heading for the coal he alleged he had discovered, and he wrote:—“*Anthracite may be found in precisely similar situations with plumbago. Indeed, whilst the latter is the metallic carbon, the former is a hydrate of carbon. Just as plumbago is found near the basaltic eruptions, so is anthracite found. It is my opinion that this substance exists as abundantly as does plumbago. I recommend exploring the country for it near the Bentota river, half way between Galle and Colombo, and I believe it might be produced for 18s. the ton.*” Writing, too, of the kaolin (*kirimeṭiya* of the Sinhalese), so plentiful in Ceylon, as

suitable for the manufacture of superior bricks and tiles, he referred to the great advantage of the vicinity of anthracite to burn them. He then went on to show the importance of his alleged discovery in view of the mail steamers touching at Galle, a consideration which, shifting the scene, would now, with the vastly increased resort of steam vessels to Colombo, tell with ten-fold force. Tennent, in his beautifully written and widely-read work on Ceylon, endorsed, by adopting, Gygax's statement of millions of tons of iron in one locality in Sabaragamuwa, with a flux in the shape of anthracite ready to hand;* and yet in all these years the inhabitants or colonists of Ceylon have neither bestirred themselves, nor been by outsiders reproached for their criminal apathy in neglecting such magnificent resources, while the island has been several times shaken from its propriety by alleged discoveries of gold in paying form and quantity. In the history of scientific exploration and report, and of colonial history and progress, there seems to be no greater fiasco.

The curious part of the matter is that in his first report of 1847, which is extant in the Colonial Secretary's Office, and the peculiar English of which is uncorrected, the Swiss geologist *said not one word about anthracite*, so prominently introduced into his later report of 1848 from which I have quoted, and the style of which is as purely idiomatic and graphic as that of the great writer on Ceylon who adopted and gave world-wide currency to statements of mineral finds which, if not apocryphal, have certainly not been confirmed by later explorers of our rocks. Any suspicion, however, which might be entertained of Tennent's sincerity in his avowed belief of Dr. Gygax's discovery, is removed by the fact that the latter included anthracite in a collection of the minerals he had personally collected during his official survey, and which, as already stated, he lodged in the Museum of this Society.

True, there was one man, a British merchant, the late Mr.

* Tennent's statement is: "The *anthracite* alluded to by Dr. Gygax is found in the southern range of hills near Nambápána, in close proximity to rich veins of plumbago." The rich veins of plumbago are a reality, but the anthracite seems to be as mythical as Sinbad the Sailor and his gems.

John Armitage, who previously to the advent of Dr. Gygax was stirred to action by the supposed existence of anthracite in Ceylon. But, curiously enough, Mr. Armitage, accompanied by Mr. Wm. Tindall, applied to the Emigration Commissioners in 1846 for concessions to mine for anthracite in Ceylon, not because of any specimens of the mineral he had seen in the island, whether in museums or cabinets, or *in situ*, but because the very finest specimen of anthracite in the British Museum, "presenting a flat surface of nine to twelve inches, and beautifully iridescent like some of the best descriptions of coal," was labelled as from Sabaragamuwa, Ceylon, and because, as Mr. Armitage was assured by the curator, it was genuine, it having come from the collection of a Col. Greville. The name of Greville does not to my knowledge occur, it is certainly not prominent, in the annals of Ceylon.

To show how confusion may arise, I need merely mention that through the dropping of a comma, plumbago is represented in successive works, including the *Encyclopædia Britannica*, as found in "Travancore Ceylon," as if the localities were one. There is the case of *columba* root, too, which received that name because ships touching last at Colombo brought the bitter root to Europe from India. But the crowning absurdity was that the Emigration Commissioners, who had in 1846 the ordering of such matters, instead of saying to Messrs. Armitage and Tindall, "We will refer to the Governor of the colony for information," or "You go and prospect and let us know what you find and under what circumstances, make your offers, and we will consider them," jumped instantly to the conclusion that anthracite of such quality, in such plenty, and in such circumstances of cheap acquirement, existed in Ceylon, that 40 per cent. would be a fair royalty to charge! The gentlemen who were prepared to embark capital in the enterprise were naturally disgusted and deterred, and, what is to be especially deplored, Mr. Armitage seems never subsequently to have practically tested, personally or by his agents, the actual existence of anthracite in Ceylon, although he was resident in the island when the discovery of this species of coal in quantity was authoritatively announced.

Dr. Gygax did not hazard a mere guess, but gave full scientific details of the existence of anthracite not only in

association with plumbago, but in juxtaposition with basaltic rocks, the friction and heat of which when irrupted would, as all acquainted with the principles of geology know, have supplied just the needed agency to convert ordinary gaseous coal into anthracite by the expulsion of the volatile portions. My limited knowledge of the mysteries of geology forbids me to dogmatize, but I have observed, read, and inquired to some extent, and until better advised I must confess to utter scepticism regarding the existence of anthracite in the formations at Nambápána, or anywhere amongst the granitic formations of Sabaragamuwa, or as at all existing in Ceylon.

The strange part of the matter is that Tennent, with his special opportunities of testing the reality of a discovery which he evidently deemed immensely important, never did more than take Dr. Gygax's statements for granted giving them the benefit of amplification and word-painting in his book, a book in regard to most subjects, as correct in statement as it is elegant in style. That Dr. Gygax was not infallible, we have had proof in the case of an assertion he made in a paper contributed to the earlier annals of this Society. He stated that the little land leech, which is such a pest in the damp forests of Ceylon and Southern India, cannot exist on volcanic soil. But travellers in Java and other portions of the Eastern Archipelago have told, from painful experience, a very different tale.

It is not, however, scientific accuracy, but personal veracity which seems at stake in the statement that anthracite not only exists but abounds in Ceylon; and to set this and other like questions at rest, I submit that this Society would do well to use its influence with Government to induce them to borrow an officer, if his services could be spared, from the Geological Survey staff of the Government of India, to examine and report, once for all and with authority, on the geology and mineralogy of our island. Such a man as Dr. Wm. King, with his experience acquired in India, could pronounce on all important points in a period of time probably not extending beyond a year. Dr. King has visited the island more than once, I believe, and is interested in its physical constitution and condition generally, while he is personally connected with Ceylon from the fact that he has a brother in our Civil Service. In regard to a discussion in the *Observer* regarding

the geological age of plumbago, started before the idea of my writing a paper on the subject was entertained, Dr. King wrote to assure me I was right in describing the mineral as one of the oldest formations extant, and in a note which I had the pleasure of receiving from him a short time ago Dr. King wrote :—

“Ancient a correspondent in the last *Overland Observer*, don't be led away with too much expectation of valuable minerals (ores) in your gneisses. Exploration is, of course, necessary, but it is often in the less highly metamorphosed rocks—of which you have none in Ceylon—that good mineral ores are found, at least in India. The gold is most disappointing : though you may get traces of gold in almost any region of our crystalline rocks (gneiss, &c.), you see what a failure Wainad has been ; and so was Mysore until lately. However, I yet believe that moderate returns will be got from some of the reefs in Wainad ; but not to pay for the awful charges on purchase of land and expenditure on machinery, or prices of promotion money, or extravagant preparation in highly paid officers, plant, bungalows, &c.”

Dr. King's opinion as to the improbability of the existence in any quantity of valuable mineral ores in our metamorphic rocks, is in entire consistency with the previous utterances of Dr. MacVicar, Dr. Gardner, and other qualified authorities. It is significant that both Dr. MacVicar and Dr. Gardner should have passed by unnoticed the alleged discovery of anthracite by Dr. Gyax, and still more so that Mr. Alexander Dixon, in his list of Ceylon minerals sent to the Melbourne Exhibition, took no notice of anthracite, although he sent a specimen of plumbago associated with crystalline quartz, as also iron pyrites from Nambápána, the very locality in which Gyax professed—so Tennent understood him, as general readers of his report must have also understood him—to have found graphite, anthracite, and basalt in association. Neither—and this is very significant—did Mr. Dixon say a single word about any form of coal in the list of Ceylon minerals (eighty-six varieties) prepared by him for insertion in the Transactions of this Society in 1880, and which he naturally rendered as complete and exhaustive as possible, including, as it did, specimens of plumbago from Kurunégala, Kégalla, and Nambápána.

It may be added that no trace of anthracite has been detected in India, although ordinary coal exists in many places, and graphite, distributed in crystalline rocks, is abundant from

south to north of the continent. Near Darjiling, in the district of British Sikhim, there is a very curious result of the crushing of coal by slipping mountain strata. The friction of the process must have evolved heat to a considerable degree, but instead of anthracite the crushed coal was converted into a substance which the geologists have named "semigraphite,"—a hint here, probably, of the agencies at work in producing true graphite in India, Ceylon, and elsewhere. Indeed real graphite *has* been found as the result of the alteration of a coal seam by intrusive basalt, as at New Cumnock in Ayrshire. So writes Geikie, but like other geologists he notices graphite as being amongst the older formations, where it occurs in distinct lenticular beds and also diffused in minute scales. Geikie's full description of the mineral is given in a note.* In

* *Graphite*.—Rarely crystallized in hexagonal forms, usually granular scaly, or compact. H. 0.5—1.0. Gr. 1.9—2.3. Nearly pure carbon, but generally with at least 1 or 2 per cent. of silica, lime, iron, or other impurity. Under the microscope, opaque; appearing velvet black with reflected light. Found chiefly in ancient crystalline rocks, as gneiss, mica-schist, granite, &c.; some of the Laurentian limestones of Canada being so full of the diffused mineral as to be profitably worked for it; in rare instances coal has been observed changed into it by intrusive basalt (Ayrshire). Probably in most cases the result of the alteration of imbedded organic matter, especially remains of plants; occasionally observed as a pseudomorph after calcite and pyrites, and sometimes enclosing sphene and other minerals.

Graphite is little affected by percolating water, hence it is not a replacement mineral. But Vorn Rath has described an example from Westphalia, where calcite has been partially replaced externally by an encrusting pseudomorph or graphite.

Geikie also states: "The opinion of the organic nature of *Eozoon* has been supposed to receive support from the large quantity of graphite found throughout the Archaean rocks of Canada and the northern parts of the United States. This mineral occurs partly in veins, but chiefly disseminated in scales and laminae in the limestones and as independent layers. Dr. Dawson estimates the aggregate amount of it in one band of limestones in the Ottawa district as not less than from 20 to 30 feet, and he thinks it is hardly an exaggeration to say that there is as much carbon in the Laurentian as in equivalent areas of the carboniferous system. He compares some of the pure bands of graphite to beds of coal, and maintains that no other source for their origin can be imagined than the decomposition of carbon dioxide by living plants. In the largest of three beds of graphite at St. John he has found what he considers may be fibrous structure indicative of the existence of land-plants."

North America the conversion of gaseous coal into anthracite has been distinctly traced to the powerful chemical forces evolved by the tilting up of previously horizontal strata.

Mr. Alexander Dixon described, or intended to describe, for the annals of this Society, a deep-seated deposit of what no doubt was drift timber carried down by floods in the Kelani river, and which was discovered in the course of the borings made in connection with the erection of the new railway bridge near Colombo. Deposits of this kind may in the process of far future ages give Ceylon coal, or at least lignite, but at present I fear our formations include nothing more nearly approaching coal than the apparently poor species of peat found at Mutnaráwela near Colombo, in Nuwara Eliya, and some other swampy places, apparently the result, chiefly, of decomposed aquatic and semi-aquatic plants, such as flags, rushes, and grasses. On the Nilgiris, I believe a somewhat similar but evidently superior formation is used as fuel, after being compressed and dried, but I am not aware that any experiment in this direction has been tried in Nuwara Eliya. The owners of the brewery and of the adjacent tea plantations might probably find it worth while to test the combustible value of the black peaty matter, compressed into bricks and thoroughly deprived of moisture. For use in tea houses, however, there might probably be the objection of the peaty smell, while anthracite, if it really existed, would be, like coke, free from objection on the score of odour, and for tea house purposes its intense smokeless heat would render it specially valuable.

The table of descent amongst mineralogists seems to be from the diamond to graphite, next to amber, and then coal, peat, and petroleum. In connection with coal formations and petroleum springs, shales are always found, but certainly no writer on Ceylon has ever said that any formation, even remotely resembling oil-bearing shale, has been seen in our rocks, any more than that a Ceylon well-digger has ever "struck ile." Seeing that Indian rock strata include the diamond, while the gem-bearing rocks of Ceylon, rich also in graphite, show no trace of the brilliantly crystallized carbon which shines in crown and diadem as the diamond, the case might, some would say, be reversed as regards anthracite, which although absent from the Indian continent might exist

in the Indian island; but all the evidence as yet seems to show that as regards the existence of anthracite in Ceylon, a huge and very annoying mistake has been made, and that all the probabilities, unfortunately, are adverse to the discovery of any form of coal in our rocks.

I feel sure I need not apologize for the space devoted to a matter so closely connected with the subject of the paper I have been asked to prepare, and of such incalculable importance to Ceylon, should Dr. Gygax, after all, be shown by the indisputable "testimony of the rocks" to have been in the right. No one would more sincerely rejoice than the writer of this paper, were such to be the answer to the question he has felt it his duty to raise. There seems to be no trace left, in the Museum, at any rate, of Dr. Gygax's specimens of so-called anthracite. Anxious not to do injustice in the matter, however satisfied my own judgment was of the completeness of the negative evidence, I referred the question before giving an adverse verdict to a most competent authority, and his deliverance is :—

"I think you may safely assert that there never was any anthracite in Ceylon. The only thing resembling it that Gygax was said to have seen was a piece that was brought from about Haldummulla. But it would not have been the only piece in the Island had it been anthracite; and, handling plumbago as I have done for the last 20 years, I would scarcely have failed to see some of it, if it existed."

This seems conclusive; and if Gygax received a specimen of anthracite from Haldummulla, it was probably a piece sent from England as a guide to research. There was, nearly forty years ago, some excitement created by an alleged discovery of true coal in Héváheta, the discovery having no better basis than some bits of English coal washed down an estate stream from the late General Braybrooke's bungalow.

The calculation is that the amount of mineral fuel consumed in India in 1882 was equal to 1,500,000 tons, of which only one-third was imported. At the pit's mouth in Raniganj, local coal can be delivered for 2½ rupees per ton, while the average price of imported coal, although taken from Britain almost as ballast, at exceptionally low rates of freight, has been over Rs. 18. In consequence of the

presence of abundance of coal near the line, the East Indian railway obtains its fuel at a rate cheaper than any other railway in the world. If coal of passable quality and in large quantity were produced in Ceylon, we might even supply the demands of some parts of India which are far from territorial sources of supply, besides meeting an ever-increasing local demand for steamer, factory, railway, gas-works, and general purposes, which was represented by an import rising from 81,000 tons, in 1880, the year in which the Colombo harbor first gave shelter to steam shipping, until now the annual introduction of foreign fuel into the island is close on 200,000 tons, of a local value of over £400,000. The figures for 1883 were 195,883 tons, and for 1884 nearly an equal quantity. The total for the five years ending 1884 was 742,000 tons, and the average 148,000 tons; but the resort of steamers to Colombo is increasing at such a rate that it may be safe to predict an aggregate of $1\frac{1}{2}$ million for the five years ending 1890, making an annual average import of 250,000 tons; that is, unless some great discovery in the economy of fuel in steam navigation is made in the interval. If, therefore, the supposed presence of coal in Ceylon was considered so important in 1848, how much more so would its real discovery now be deemed!

But if the diamond, amber, coal, and petroleum are absent from our rock formations, happily there can be no question as to either the quality or the quantity of our mineral carbon in the shape of PLUMBAGO, of which indeed, in the form most valuable for the manufacture of metal-melting crucibles, Ceylon seems to have as much a natural monopoly as she has of first class cinnamon in the vegetable world. There are, no doubt, vast deposits of graphite in North America, especially in Canada, but the mineral seems to be generally diffused in rock from which it is difficult and expensive (labour being scarce and dear) to separate the small particles. Graphite, although rare in a form economically valuable, seems very widely distributed over the face of the earth. In India plumbago has been found in a large number of places, and has been the subject of many experiments and much discussion, but the results have been hitherto disappointing. It generally appears sparingly in very quartz rock, and in heavy ferruginous gneiss. The mineral is

deficient in lustre, contains much iron, and one specimen gave 35 per cent. of lime. Lime is, perhaps, even more fatal to the value of plumbago than iron, and although graphite may occur in the magnesian limestones of Ceylon (I never heard of but one instance,) it is quite manifest that digging in the dolomite need never be resorted to, the mineral being so plentiful in our quartzite gneiss, where the only enemy encountered, and that, happily, not very frequently, is iron. Like some other adversaries, this one sometimes appears in guises the most radiantly beautiful, in the present case as pyrites varying from splendidly crystallized masses, with facets polished like finest silver, and again simulating auriferous treasures by putting on the most glorious colorings of gold, shading away to a lovely and delicate green, indicative of this tint, it is supposed, of the presence of sulphate of copper.

This auriferous coloured pyrites is appropriately named in Sinhalese *Diya rat-ran*, or 'water gem-gold,' the recognition of water as the agent to which the formation and its brilliant colours are largely due being, curiously enough, in perfect accord with the conclusions of the most advanced geological scientists.

To Mr. Williams, Acting Government Agent of the North-Western Province, I am indebted for a collection of interesting specimens from Polgola on the road to Dambulla, showing how plumbago is associated with and forms round a nucleus of crystalline or semi-opaque and sometimes garnetiferous quartz (the position of the minerals being, I am told, occasionally reversed), and quite a number of pieces of rock which the non-scientific might well be excused for regarding as coated and permeated with brilliant golden ore. These may be regarded as the flowers of the subterranean regions where plumbago is mined. I am bound to state, however, that the brilliancy of iron pyrites has no effect in modifying the inimical feelings with which those connected with the plumbago enterprise regard the mineral, while they talk with disapproval and disgust of the *Yabora* = (a) *ya* iron, *bora* dross, iron dross, the hard, iron-like form of plumbago; and any one desirous of procuring specimens, will be made heartily welcome to what in the eyes of the plumbago dealer is associated with a rocky, inferior, and unsaleable product. But truly the pure

soft mineral itself, in its various forms of crystallization, the most prevalent being a radiating star-like arrangement, and its variation of sparkling colours from steel grey to plates of jet black, may be regarded as a veritable "thing of beauty." A collection of first class lumps, each highly polished and lustrous, intended for shipment to Germany, which could be seen at Mr. W. A. Fernando's store recently, was certainly a striking sight. In connection with this collection of silvery masses, Mr. Fernando showed us specimens of a dark-coloured variety, of needle-like formation, which he said he had been requested by his customers to make up separately, as the ordinary mills could not easily grind that particular quality. Graphite generally, like iodine, shows a bright metallic sheen, but it is at once distinguished from the true metals by its soft and nunctuous mechanical condition. I am speaking of first class mineral, for, showing us a specimen of plumbago formed, apparently, over an ironstone nucleus, Mr. Fernando declared such ore to be unsaleable. In truth, the reasons why our Ceylon graphite is so much sought after, are the entire absence of lime from the mineral, and in most cases its equal freedom from ferruginous particles, the small proportion of foreign substances, if any, being volatile matter and minute fragments of silica and alumina. Besides grinding to extreme fineness, an acid bath is used thoroughly to purify graphite, used for certain delicate purposes, such as electrotyping, when the finest and purest dust is required to coat surfaces of wood, plaster of Paris, and gutta percha, &c., to render them conductive. An authority of all in the world, perhaps best qualified to speak, describes Ceylon plumbago as combining the two qualities of being almost as refractory as asbestos and at the same time the most perfect conductor of heat.

The North of England mines, which at one time supplied the world with pencils, although ordinary lead pencils have been in use in the present century, seem exhausted, while the supply of the somewhat allied mineral—jet—is still available for the manufacture of ornaments at Whitby. There is graphite in Scotland, (plentiful in Aberdeenshire according to Mr. Ferguson of Kinmundy) though not, I believe, of useful quality. The black lead mines spread

over Germany—in Prussia, Austria, Bavaria, and Bohemia—are only second in fame to the peerless English pits; while finds of the mineral are reported from places so widely separated as North America, Finland, Greenland, Siberia, Spain, Australia, Japan, and Madagascar. It is a curiously suggestive fact, too, that traces of this form of carbon have been found in meteorites which have reached our globe from the regions of planetary space.

In addition to a large lump of Pasdun Kóralé plumbago on the lower floor of the Colombo Museum, the gift of Sir Charles Peter Layard, beside which stand specimens of plumbago crucibles from the Battersea Factory, there are, in one of the mineral cases upstairs, associated with pieces of the Ceylon ore, pure or with a rocky matrix, a collection of graphites presented by Mr. W. W. Mitchell, illustrative of the mineral as found in Siberia, Canada, Finland, Japan and Travancore. Allowing for the fact that the foreign plumbagos are dulled by time and climate, their appearance certainly does not convey any idea of superiority over our local product.

If Bennett (author of "Ceylon and its Capabilities") is correct, Ptolemy mentioned this substance amongst the productions of Ceylon, when writing in the second century of our era. It is curious that Bennett, of all the writers on the Island, should alone have made this statement. Tennent, who carefully epitomized the geographical information contained in Ptolemy's writings, does not quote him as mentioning the mineral. Pridham, of whose classical research Tennent entertained a high opinion, is equally silent. Mr. Green, Director of Public Instruction, kindly endeavoured at my request to test Bennett's statement by reference to Ptolemy, but no copy of the original work was accessible, and a summary of Ptolemy's statements in the *Indian Antiquary* does not confirm what Bennett wrote. Should further research show that Ptolemy really mentioned plumbago, it would be interesting to ascertain if the native name (Sinhalese or Tamil) was merely transferred, or if a word was used indicative of a knowledge by the Greeks and Romans of graphite and any of its uses.

If the ancient native historical records, in their almost exclusive devotion to the glorification of monarchs who

built irrigation works and promoted the interests of Buddhism, failed to notice cinnamon, it is no wonder they make no mention of *kalu-miniran*, which though lustrous as silver was neither a precious metal nor a precious stone fitted for the adornment of kingly crown or royal palace,—palace far inferior to thousands of European kitchens, with their iron stoves and grates shining with the brilliancy of highly polished “black lead.” To Mr. W. P. Ranasinghe I am indebted for the information, conveyed in a letter which is printed as an appendix to this paper, that *kalu-miniran* (*black miniran*, the word *miniran* applied to mica signifying *mini* = *mani*, gem, and *ran* = *ratna*, also gem, or the ‘golden gem,’ just as two superlatives, *gloriosa superba*, are applied to the splendid inverted lily of our jungles) is mentioned in a native work, the date of which it is difficult to fix, but which seems to have been written in the fourteenth century of our era. In this medical work “*Yôga Ratnakarê*” (‘the ocean of the gem-like prescriptions’) directions are given for reducing *miniran*, that is mica, to ashes that it may be taken as a medicine, while to fit *kalu-miniran* (graphite) for similar use it has to be purified by means of the milky juice of a *euphorbia*, and boiling for three days over a low fire such as is used for boiling rice. The small pieces subjected to the processes mentioned are finally taken out and washed, and they are then purified and fit for use. The affections for which this purified carbon is prescribed are not mentioned, beyond the statement that it is used as a tonic, but we all know how largely the antiseptic properties of charcoal are valued and applied, a digestive charcoal biscuit being at this moment prominently advertised and pretty extensively used. I have also in my reading come across a notice of the use of coal as a medicine, the purer forms being probably chosen, while a paragraph has recently appeared stating that “a chemist in Munich has succeeded in obtaining from distilled coal a white crystalline powder which, as far as regards its action on the human system, cannot be distinguished from quinine, except that it assimilates even more readily with the stomach. Its efficacy in reducing fever heat is represented as quite remarkable, and it even renders the use of ice unnecessary.”

But in the process of my researches I find that it is not only the ancient Sînhalese wedarâlas who prescribed graphite. The English black lead, it seems, was formerly held in high repute as a medicine, and a writer on the Cumberland plumbago in 1709 asserted it was much sought after by physicians and apothecaries as being a present remedy for colic, gravel, and other diseases. The use of *euphorbia* juice in the purifying process applied in Ceylon to plumbago is very curious and interesting, the powerfully active properties of *euphorbia* "milk" being well-known. The Tamil coolies are said to give doses of *euphorbia* juice to new-born infants for the alleged purpose of clearing away impurities, but the result is probably to account in a large measure for the high rate of infant mortality amongst the class referred to. Any one who knows, as the writer does, the agony arising from a single drop of *euphorbia* "milk" getting into the eye, will appreciate the effect of this caustic poison on the delicate internal organs of infants. On the external skin it acts as a blister. Its action on graphite is probably to dissolve away the impurities mixed with the mineral in the shape of particles of gneiss, quartz, iron, &c. Having seen it stated that in connection with specimens of plumbago at the Exhibition of 1862, the eminent surgeon, Sir Benjamin Brodie, had fully discussed the properties of the mineral, I requested Dr. Vanderstraaten to ascertain if Brodie's views were embodied in any book in the Medical Library; he has replied in the negative, but tells me that the Chinese use both black lead and white as medicines.

The species of carbon of which we are treating never forms a compound with any other substances, and large masses of it are often found so pure that the return of carbon to the analyst is sometimes considerably above 99—very nearly 100 per cent. indeed, while the specific gravity of the soft and unctuous mineral compares with that of the diamond thus: diamond 3.6; graphite 2.2. The fact may not be wanting in significance, that quartz occasionally encloses drops of liquid carbon, destined perhaps to emerge, after a very long period of intense heat and pressure, as solid gems. (?)

In cases of impaired digestion, purified carbon, in the shape of graphite, may well be conceived to have valuable corrective effects, but native treatment is generally so empirical that

we may err in giving the ancient wedarālas credit for knowledge of the principles on which certain substances ought to be exhibited. If there is really no mention of plumbago in Sinhalese records earlier than the fourteenth century A.D., it is a curious fact that a document should exist in Europe, supposed to be ruled by means of the mineral, of date 1387—that is in the very same century. But, although some form of pencil must have been known and used from time immemorial, notably the lead pencil with its paler mark than that of plumbago, the first mention of a rough “black lead” pencil, was by Gesner in 1565, about the time when the famous Cumberland mines were discovered.

I have not been able to ascertain if plumbago, the Tamil name of which is *kār-iyam*, is mentioned in any ancient Tamil records, and I cannot trace any notice of the mineral by Muhammadan or Chinese voyagers, while Portuguese writers on Ceylon seem, so far as they have been consulted, to give no sign of a knowledge of black lead or its properties. The effect of the publication of this paper may be, however, to reveal matter not within my reach, although I did not fail to refer, directly and through competent scholars, to a very large number of the best authorities. The officer of the late Ceylon Rifle Regiment who wrote a book on Ceylon stated that Thunberg, the Scandinavian naturalist, who wrote in 1777, was the first to notice plumbago as a product of Ceylon. This was an error. Robert Knox, who wrote in 1681, mentions the existence of the mineral; and Valentyn gives a letter of a somewhat earlier period by the Dutch Governor Rykloff van Goens, dated 24th September, 1675, addressed to his successor the Governor-General Jan Maatsuyker, in which he mentions veins of plumbago (*potloot*) in the hills, and mines in the low-country. He described it as a product of quicksilver, an error which, repeated, may explain the alleged discovery of a mine of quicksilver near Kótté, soon after the British took possession of Colombo. So important was the latter discovery deemed at the time that a military guard was placed over the mine; but subsequently the existence of quicksilver in Ceylon became as mythical as that of anthracite seems now to be, or the alleged discovery of coal by the Dutch who are said to have disregarded it in view of

the abundance of wood fuel. The old Dutch Governor's notice of plumbago is so curious that it may be well to reproduce its terms. The translation from Valentyn is as follows :—

“Of the other minerals found in the hill-country there is little to be said, for want of information; but we ourselves have found both black lead [*potloot*] and common lead; from which metallurgists, infer that there must also be quicksilver there, of which black lead is the product. It is also believed that in the low-country, where the black lead is found, large mines will be discovered so that it seems necessary to inquire into this further, with a view to quicksilver, as this is as it were the blood of minerals and a sign of richer mineral.”—Vol. V., p. 205.

Changes the most extraordinary are now known to be produced by metamorphic agencies, but I suspect that even the most potent forces at work in nature would be powerless to change mercury into black lead. Modern mineralogical science, too, scarcely recognizes the principle that quicksilver is the blood of minerals, and its occurrence an indication of the existence of still more precious minerals. The possible solution of the anthracite mystery may be that although graphite is no more a carburet of iron, as it was once deemed, than it is a darker form of the common metal lead, yet iron in very anomalous forms is sometimes associated with plumbago. I was once in possession of a bit of iron formation found in a plumbago mine, which so closely resembled the rootlet of a plant, that the probability seems to be that particles of iron ore in the soil had aggregated round a tree root, assuming its shape and taking its place, after a fashion which gold and other metals have frequently adopted. When rock thus takes the place of wood, we call the result a petrification. In the case of metallic particles, the process may be regarded as a form of natural electroplating, a process in the arts for the success of which the use of good conducting graphite (for some is said to be non-conducting) is essential. There is, it may be well to say, a metallic graphite produced in iron furnaces, known to the workmen as “kish,” but it differs somewhat from natural plumbago, which is all and always immediately of vegetable origin, whether the vegetation has passed directly into graphite or through the intermediate stages of coal or shale.

But to return to the place in history of our subject. A

Mr. Ive, who wrote apparently in 1755, professed to have discovered "black lead" and copper ores in Ceylon. Mr. W. P. Ranasinghe has unearthed for me the tradition that the last King of Kandy, infamous for his cruelties as he is famous for his esthetic taste, added to his many-sided character a development of the commercial instinct, supplying, it is said, plumbago to merchant ships, more than seventy years before such enterprising traders as the Fernandos and De Mels appeared on the scene. The tradition seems also to indicate that some of the plumbago in which the monarch traded was dug from a mine on the lands of Molligoda Disawa. Cordiner who wrote at the commencement of this century, stated :—"Plumbago is found with mica at the foot of mountains, in clay and red earth, most frequently at a considerable depth : but is sometimes met with by itself in dry soil."

In more modern times, 1812-20, Dr. Davy, the brother of Sir Humphrey, mentioned plumbago as a mineral found in Ceylon, "which might become an article of export." Dr. Davy was apparently correct in his scepticism as to the existence in Ceylon of ores of quicksilver, copper or tin, but wrong in doubting the existence of gold. Coal however is not, like gold in its very wide diffusion. Still, the mistake of Davy in regard to gold forbids dogmatism. Bertolacci, who wrote his work on the commerce of Ceylon in 1816, although he dealt with every article of any importance in detail up to the end of 1813, makes not the slightest mention of plumbago. The export of the article must have commenced between 1820 and 1830, however, for Mr. Joseph Dixon, the founder of the great American Crucible Company, obtained a shipment of Ceylon plumbago in 1829. In that very year Col. Colebrooke, one of the Commissioners on Ceylon affairs, stated in his report that provision had been made for the delivery of cinnamon and black lead in the Kandyan Provinces (then including the Seven Koralés) at fixed rates. Reference to the Government Calendars shows that there is no mention of plumbago until 1831, when it was included in the list of articles liable to export duty, the rate being 10*d.* per cwt. The amount of revenue at this rate in 1832 was £22 18*s.* 6*d.* The mineral did not, however, assume real importance in the commerce of Ceylon until 1834, and for the half century which has elapsed between

that year and the end of 1884 I possess, thanks to the courtesy of the Assistant Auditor-General, Mr. C. Dickman, full details of the rise, progress, and fluctuations of the trade, until from small beginnings it has in the past five years attained truly important dimensions, whether regard be had to the quantity and value of the mineral exported, or the revenue derived by Government from a royalty finally fixed in 1877 at the very moderate rate of Rs. 5 per ton.

For the first three years of the period beginning with 1834 no export duty was levied on this article. From 1837 to 1846, and again from 1858 to 1869, a duty of $2\frac{1}{2}$ per cent. was levied, which yielded in the earlier period sums so low as Rs. 12.25 in 1839, rising to Rs. 759 in 1846. In the second series of years, when export duties were levied expressly for railway purposes, the duty rose from Rs. 1,190 in 1858, to the appreciable sum of Rs. 22,240 in 1869. The latter sum was levied on cwt. 226,132 valued at Rs. 889,620. The rated duty seems, therefore, to have been as nearly as possible one-tenth of a rupee per cwt. The only Customs impost to which plumbago is now liable is, apart from the royalty, 7 cents per barrel, recently exacted for harbor purposes. As each barrel contains $5\frac{1}{4}$ cwt. net of mineral, the burden is only a fraction over one cent per cwt., in addition to the royalty which since 1877 has been levied at the rate of Rs. 5 per ton, or 25 cents per cwt., equivalent to $2\frac{1}{2}$ per cent. on the Customs valuation of Rs. 10 per cwt., but rising to 5 per cent. if the real value is only about Rs. 100 per ton. Previously to 1851 no royalty was levied, and the varying rates since then have been—

In 1851 per ton ...	4s.	In 1864 per ton ...	16s.
„ 1852 „ ...	5s.	„ 1869 „ ...	30s.
„ 1859 „ ...	7s. 6d.	„ 1873 „ ...	Rs. 10
„ 1862 „ ...	14s.	„ 1877 „ ...	„ 5

There can be no possible question, it would seem, of the propriety of exacting a royalty, moderate in proportion to its market value, on this mineral, which is entirely an article of export, and which is as much the property of Government, or the people of Ceylon, as are the pearly treasures of the “oyster” banks off Aripn,—providing, too, as the revenue from plumbago does for the construction, amongst other

public works, of means of communication which facilitate and cheapen the operations of the diggers. We could only wish that copper, tin, nickel, and other ores which have been so positively written about as occurring in Ceylon, with gold, which beyond question does exist, were found in quantities sufficient to add appreciably to the revenue in the shape of royalties. The one necessary qualification is, of course, that the amount of the tax should be such as not to bear heavily on an enterprise which is always toilsome and often precarious. Taking the average value of plumbago at Rs. 10 per cwt., the Customs figure, the present impost of 25 cents is, as noticed above, only equivalent to a rate of $2\frac{1}{2}$ per cent., which certainly cannot be complained of as unduly onerous, however justifiable complaints and remonstrances were when 14s., 16s., and even 30s. per ton were exacted, or Rs. 10 between 1874 and 1877. The present rate has the merit of being light, easily collected, and productive, for in the five years ended 1884 an average export of nearly 12,000 tons per annum, of an annual value of Rs. 2,400,000, yielded royalty equal to a yearly average in round numbers of Rs. 60,000. When the proceeds of digging licenses and leases of Crown lands, and stamps on those leases are added, the average may be raised to Rs. 65,000. The maxima of quantities exported, total value, and total revenue were reached in 1883 when the figures were :—

Plumbago exported cwt.	262,774
Value @ Rs. 10 per cwt.	Rs. 2,627,737
Total revenue	{ Royalty ... Rs. 65,694 }	... „	70,421
	{ Leases & licenses 4,727 }		

Wonderful contrasts these, even if we reduce the Customs valuation by one-half, to an export of only 423 cwt. in 1839, valued at only Rs. 490, or a little over Rs. 1 per cwt., and yielding to the revenue of the Colony only Rs. 12-25, a sum scarcely worthy of collection! The totals for the whole period of half a century of the export trade in Ceylon plumbago are striking, viz. :—

Quantity exported	...	cwt.	3,526,000
Value of this quantity	...	Rs.	25,742,000
Contributions to revenue	...	„	841,000

Crediting plumbago revenue with items brought to account under stamps and other headings, the amount

might be raised to Rs. 900,000, and had Government always got its own in the shape of royalty, the round million of rupees would be considerably exceeded.

Taking averages of qualities and periods, it is probable that Rs. 200 per ton is too high a valuation for this mineral, and that twenty millions of rupees would more nearly than twenty-five millions represent the total value of the plumbago exported in fifty-one years, for which figures are given. At any average price of less than Rs. 100 per ton it would probably not pay to dig plumbago, and as a matter of fact what was evidently over-production between 1880 and 1883, led to a reaction in 1884, when not only did exports fall off, but operations in the preparing yards in Colombo were stayed for a time by general consent, some not opening again even when the probability of a war with Russia gave a fresh fillip to the trade.

It is a melancholy fact that plumbago is one of the class of articles like "villainous saltpetre" and some others, the trade in which prospers when war has broken out or when warfare is threatened. The reason in the case of our staple mineral is, that the chief use by far to which Ceylon plumbago is put is the manufacture of crucibles, nozzles, &c., employed in the preparation of Bessemer and other steel, now in such large requisition for shipbuilding, plates for ironclads, torpedoes, shot, shell, &c.; this, in addition to the melting of the precious metals for which crucibles of refractory plumbago are eminently suited from their superior strength and perfect smoothness. There are many minor uses to which plumbago is put, as will hereafter be shown, but I believe I am right in stating that its extended consumption (if that word can be correctly applied to an article which is almost uncousumable) in recent years, is due to the great and rapid advance of the steel industry on both sides of the Atlantic, not merely to provide materials for ships, durable and light, but for the dread weapons and appliances of modern warfare, such as Krupp and Armstrong guns, steel shot, &c. But the abundance of the ore in Ceylon, and the enterprise and activity with which the mining, preparing, and shipping of the mineral have been pursued, have in this case, as in so many others, recently led to production considerably in excess of demand, so that

the profits of the pursuit, never very great and always precarious, have recently been low or *nil*.

When at its highest market value I do not suppose that Ceylon plumbago ever sold for more than £50 per ton: indeed the highest price of which I have evidence is £48 realized by Mr. W. A. Fernando, of Brownrigg-street, Colombo. What is this to the celebrated Borrowdale pencil "black lead" mines, which, after having been worked since the reign of Queen Elizabeth, recently gave out, so that now pencils picked up at Keswick as curiosities cost sixpence each, being formed, if local ore is really used, of fragments found scattered amongst rocks or in the beds of streams! In the report of the Mátara District for 1870 the Assistant Government Agent stated:—

"To meet Ceylon plumbago in Cumberland was certainly a surprise; but when recently at the English Lakes I learned that plumbago from this Island was mixed with the local graphite to make good pencils."

In the palmy days of the plumbago mines of the North of England the black lead obtained from them was valued at 30s. per pound, or over £3,000 per ton, or within about two-thirds of the price of ordinary gold. We cannot be surprised therefore to learn that a couple of centuries before the world heard of the gold escorts of California and Australia, the black lead of the English Lake region was guarded in its transit, in carts, from mine to manufactory by parties of military, the robbery of black lead mines being, by an Act of George II., constituted a felony. The Act, curiously enough, recited that black lead was employed for divers useful purposes, and more especially for the casting of bomb-shells, round shot, and cannon balls. The connection, therefore, with the art of war of the mineral so long associated with the most intellectual and humanizing of the arts of peace—writing and drawing, to wit—does not date from yesterday, neither was appreciation of the value of the Borrowdale mineral of late date, for a grant of the manor of Borrowdale as far back as the reign of James I. refers to "the wad holes and wad, commonly called *canke*." The affinity of graphite to coke, whether artificially obtained from coal or naturally occurring as anthracite, was thus early recognized.

The quality of the Borrowdale ore, dark-coloured, pure and soft, rendered it eminently suitable for pencils of the finest descriptions, and for about two and a-half centuries the world was practically supplied with pencils from this one source. From one pound of the ore, worth 30s., or at the rate of £168 per cwt., the number of pencils obtained averaged from 18 to 20 dozens. The mineral was stated to be found in pipes, strings, and irregular masses called "sops," a description which, substituting modern terms for olden, applies equally to the Ceylon graphite formations. Since the exhaustion of the Cumberland mines, the best ore for pencils is *said* in some books to be obtained from Siberia, while no doubt the massive and soft stove polish black lead, occurring in various parts of Germany—Bavaria, Bohemia, &c.—is applied to the manufacture of pencils. It cannot be questioned also that some of the finest quality Ceylon plumbago is thus used in Britain, and also in the United States, notwithstanding directly contradictory statements on the subject, one writer declaring that the presence of grit or iron rendered the much-lauded Siberian mineral unsuitable for pencil manufacture; while another, with equal positiveness, writes that, notwithstanding the acknowledged purity of Ceylon plumbago, it is not applicable to pencil-making.

The old method of making pencils was to saw blocks of so-called black lead into strips to be inserted in cedar wood cases, but now the general mode of manufacture—and this applies to crucibles as well as pencils—is to grind and comminute the ore as finely as possible, and then after washing and intermixing with definite proportions of certain qualities of clay, also ground fine, to subject the mixture to tremendous pressure and to a baking process. For blocks composed solely of black lead dust, prepared for pencil-making, the air-pump has also been utilized to render the blocks perfectly solid. Germany, besides supplying the form of so-called "black lead" suitable for stove polish and pencils, yields also a peculiar kind of clay, which in the United States at any rate is used to give adhesiveness to the ground particles of plumbago when subjected to the extreme pressure which has been mentioned. Secrecy is, I believe, observed at the Battersea Crucible

Works as to the exact substances and processes used to give adhesion, but there can be little doubt that there, as in all other manufactories of plumbago into crucibles, nozzles, pencils, &c., fine clay of some sort is used in varying quantities. Into coloured pencils, clays no doubt enter still more largely.

The earliest pencils used were, probably, pieces of chalk and clay, true lead pencils succeeding, until perfection for drawing, writing, and ruling purposes was attained by the use of "black lead," properly graphite—a name which indicates, as already noticed, the large use of the material by artists and in literature. Into pencils, the marks of which cannot be erased, aniline dyes are said to be introduced, but the test of a good black lead pencil is now what it always has been, the ease with which a black mark by its means can be made on paper and again erased. Molybdenite, on the other hand, which abounds in Ceylon and closely resembles plumbago in appearance, leaves a green streak. For inferior pencils Mexican and Spanish lead dust mixed with antimony has been used, but the marks made by such pencils cannot, like those of black lead, be easily removed by India-rubber.

Of course the importance of black lead pencils for ruling purposes has been greatly lessened by the invention and application of machines which rule with pens and coloured inks, but for drawing, taking memoranda, &c., pencils are still used to an enormous extent, of which some idea may be formed from the fact that one manufactory in the United States turned out sixteen millions in the one year 1882. This, however, is as nothing to the estimated annual output of Nuremberg, where twenty-six factories employing 5,500 persons, produce two hundred and fifty millions, valued at £400,000. Counting those made in America and Europe together, the total for the world cannot, probably, be less than one thousand millions of pencils per annum, worth at least $1\frac{1}{2}$ million sterling.

It is curious that the quaint old city of Nuremberg, besides being the principal toy depôt of the world, should also be the principal source of supply of pencils. It seems that when the English mines showed signs of giving out, the firm of the old Faber family in the

German city began the manufacture of pencils with pulverized graphite cemented into solid blocks by means of gums and similar substances; but useful pencils in quantity were manufactured only after Conté of Paris in 1795 devised the process by which now all black lead pencils, and indeed pencils of all sorts, are manufactured. As will be seen subsequently, this is the process adopted in The Joseph Dixon Works in America, and the writer in the *Encyclopædia Britannica*, from whose article I am quoting, asserts that the Conté method has, now that even dust cannot be obtained from Borrowdale, quite superseded the processes patented by Mr. Brockendon in 1843, of subjecting pure graphite to enormous pressure and air exhaustion.

In the Conté process graphite and clay are first and separately brought to a condition of the finest subdivision, the graphite being calcined to a bright red heat. The particles of each mineral are then floated from one vat of water to another, the finest particles last to sink being of course used to make the finest pencils. The minerals are then thoroughly incorporated, ground together (that is the various qualities), placed in bags, and squeezed in a hydraulic press to the consistency of dough. The mass is then forced through apertures, taking the shape of pencil rods, and being finally subjected to more or less furnace heat as hard or soft qualities are desiderated. The prepared "rods" are then put into cedar cases, on which quality is indicated by letters, such as "B" for black; "H" for hard; "S. T." for soft streak, &c. Black lead pencils of an inferior quality are made from graphite dust mixed with melted sulphur and run into moulds, those used by carpenters being mixed with tallow to give them softness. Coloured pencils are made from appropriate mineral matters mixed with clay.

The graphite in Borrowdale was found in the primitive rocks in pockets or nests, and so in Ceylon very large masses of pure plumbago, over a quarter of a ton in weight, have been dug out of our crystalline rocks perfectly free from all impurities, with no particles of iron pyrites, gneiss, or of the beautifully white and transparent quartz with which the black mineral is so generally associated. But here, as in India, the United States, Canada, and other countries, graphite is also

found in particles of greater or lesser size diffused through the including rock, whence it has to be separated by careful and costly processes of breaking, picking, washing, drying, sifting, and sorting. The wet process applied to plumbago means that rock impregnated with the ore is pounded and put into water, when the low specific gravity of the graphite (only twice the weight of water) causes it to float. Graphite, as already noticed, has been found in a large number of places in India, but always in too close intermixture with the siliceous, ferruginous, or other constituents of the rocks to be economically valuable.

The Canadian and United States plumbago is of as pure a quality as that of Ceylon, but good as the American ore is, when freed from the rock in which it is generally scattered after the fashion of mica, I suspect the high cost of the labour necessary for first mining and then separating the mineral by the wet process—for the dry has proved a failure—will prevent continued and successful competition with Ceylon. We shall soon see, however, for The Joseph Dixon Crucible Company had produced in 1882 a quarter of a million pounds of native plumbago, against 16,000,000 pounds imported from Ceylon, and a determination to “go ahead” was expressed. Some as yet unthought of machinery, cheap chemicals, and appliances must, however, be brought into play before the pure, massive Ceylon product and our far cheaper labour are distanced in the race. And if, as Professor Dawson states, some of the Canadian ore is fibrous enough to indicate by its texture its vegetable origin, there is room to suspect that, however pure the mineral may be as carbon, its mechanical condition cannot be so good as that of the more highly crystallized Ceylon plumbago. One important element in the question is, that according to our American friends themselves, enterprise and competition have had such influence, that Ceylon plumbago can now be obtained by them at 25 per cent. of what it cost some years ago.

The effect of competing demand for the substance, however, between 1850 and 1870, chiefly on the part of the Battersea Crucible Company in England and The Joseph Dixon Company in the United States, was to enhance the value of the

ore to such an extent in Ceylon as to produce temptations to cheating, which the native headmen, whose business it was to weigh the output and collect the royalty at the pit's mouth, were unable to resist. These estimable servants of Government cheated the diggers out of bribes by threatening to report them as having surreptitiously removed plumbago on which royalty had not been paid, and they impartially cheated Government by accepting bribes to largely under-report the quantities really dug and removed. The Customs figures enabled the Government authorities to appreciate the vast extent to which the demoralizing system had gone, and so in 1873 legislation was initiated, the main object of which was the collection of the royalty at the custom-house—a mode in itself far preferable to the direct system of collection previously in force, and securing every sixpence of royalty due because, practically, every hundredweight dug is exported, the quantity as yet used in local foundries or for any local purpose being quite insignificant. I believe a few crucibles for gold and silversmiths' use are locally made, and the result of inquiries made by Mr. W. P. Ranesinghe, at my request, is that Ceylon potters occasionally employ the mineral for giving a glaze to pottery, as is the practice in India.

The mercantile community strove hard in 1873 to make out a case for the entire abandonment of the royalty, but the Press supported Sir William Gregory's Government in resisting the pressure brought to bear in this direction, only that the *Observer* strongly urged a rate so low as Rs. 5 per ton, which after four years' experience of Rs. 10 per ton, under which exports declined, was conceded in 1877. Under this rate, which is still in force, the exports more than trebled in the six years between 1878 and 1883.

As Government in making grants of land has always reserved royalties on minerals and metals, of course the plumbago dug from private lands paid royalty when exported equally with that taken from rented Crown lands. There was a singular exception in the case of some plumbago lands sold in the district of Kurunégala without any reserve, which lands subsequently gave unprecedented yields of very fine plumbago. When it was determined to levy royalty on all plumbago exported, the Kurunégala purchasers

claimed compensation, which was awarded them. The result in the case of Mr. Jacob De Mel, who had paid £450 for four acres of land, was that he received all his money back except £5.

Mr. De Mel has been amongst the most prosperous of all who have engaged in the plumbago digging enterprise in Ceylon, his prosperity being mainly due to the rich yield of his Knrunégala district mine, which is by far the most important in Ceylon, having been sunk to a depth of 450 feet near the base of a hill, Polgolla, which seems to be largely composed of fine quality plumbago. From this mine Mr. De Mel obtained an average of 800 tons annually for eleven years, his profits, he authorizes me to say, being at the rate of £2,000 per annum. No wonder if, notwithstanding lessened production and profits in the past two years, connected with this mine there is a steam crane for raising water and a considerable length of Decauville railway for the carriage of the ore from pit mouth to cart, or that the enterprising owner has commenced a base level tunnel at an estimated total cost of £2,000 to free and keep the mine free of water, whether the result of springs in the rocks or of monsoon rains. The effect of the latter during the recent exceptionally heavy burst of the South-West monsoon in May was to fill up the pits and put a stop to digging everywhere. This, irrespective of a fall of £2 per ton from the price to which the mineral had been sent up by the war scare.

The tunnel in Mr. De Mel's mine, when completed, will not only carry away water, but facilitate the output of mineral from the lower, which are generally the richer strata, besides ventilating the mine so as to prevent injury from mephitic gases or inconvenience from the smoke of the explosives employed in blasting. The draft will also alleviate the heat in the interior of the mine, which the workmen now complain of as sometimes intolerable. For blasts under water large quantities of dynamite cartridges are employed, in addition to gunpowder used in portions of the galleries comparatively free from moisture. The wages paid to diggers in this mine, chiefly low-country Sinhalese, vary from 9d. per diem for coolies to Rs. 1 for those who perform the boring and blasting operations. In the Pasdun Kóralé there is a system of payment for labour by shares in

the profits, after all preliminary expenses defrayed by the capitalist have been reimbursed.

The hill in which Mr. De Mel's mine has been opened—Mr. W. A. Fernando having another at a higher elevation than De Mel's, with a depth of 330 feet—seems to be permeated in its whole extent by generally horizontal veins of the richest plumbago, associated with beautifully snow-white crystalline to semi-opaque quartz, the latter occasionally showing specks of garnet and bands of soapstone, and Mr. De Mel brings to the surface practically pure plumbago. As regards the generality of pits, he agrees with the estimate of Mr. W. W. Mitchell (who has probably purchased, prepared and shipped to America as well as Europe, more plumbago than any European merchant who ever resided in Ceylon) that the extraneous matter in the shape of earth and rock brought to the pit's mouth is equal to one-half of the whole, about 10 to 15 per cent. being the proportion carried to Colombo and separated from the ore in the preparing yards. Mr. Fernando's estimate, however, of foreign matter brought to Colombo, is 5 per cent. for pieces of quartz round which plumbago adheres, and $2\frac{1}{2}$ per cent. for minute fragments of silica, iron, &c., mixed with the smaller pieces and dust. Any person who has witnessed and appreciated the difficulty and the expensiveness of the processes whereby small fragments of rock are separated from the lower classes of plumbago in Ceylon, can well imagine the obstacles to profitable separation of the mineral from rock in America where there are no masses, but only scales of the mineral distributed throughout the rock.

When the Prince of Wales was in Colombo in 1870, Mr. De Mel exhibited what I suppose was the largest mass of pure plumbago ever shown in this or any other country, its weight being only 14 lb. short of 6. cwt. For this unique specimen a sum of £50 was offered. It was subsequently sent to the United States, and is understood to have been placed in the Philadelphia Exhibition, and finally in an American Museum. Finds of plumbago in large masses do not, however, always prove profitable, such masses being sometimes, although pure carbon, of such a rocky-hard consistency, that they resist the best tempered saws and yield with

difficulty to hammers and axes. Such masses are of course proportionally difficult to grind for use in the manufacture of crucibles and other articles, and do not realize the prices paid for lumps which are soft as well as large. Dulness of colour as well as hardness of texture, decrease the value of plumbago, even where iron may not be present, brilliancy of crystallization being generally an index of a correspondingly good quality.

In legislating for and discussing the subject in 1873, it was announced by Governor Sir W. H. Gregory, that no lands known or supposed to contain plumbago in quantity should in future be sold, for the reason that a few rich men might thus monopolize a pursuit, the benefits of which Government properly wished to see diffused amongst the population. Only leases, therefore, are generally granted, on terms easy for the lessees and fair to the community, of whom Government were the trustees. The Government Agent of the Western Province is now, however, in favour of selling plumbago lands in small lots. Instead of a system exclusively of fees, which would have to be paid whether the land taken up was productive or barren, the rules for leases in force in the Western Province, but, strangely enough, not in the Southern (the mines in the North-Western Province being all on private lands), are embodied in the following memorandum, which I owe to the courtesy of the Hon. Mr. Saunders :—

“When a person wishes to dig for plumbago in a Crown land, he is required to make application in writing to the Government Agent or Assistant Government Agent, who forwards the application to the Mudaliyár of the district for report as to whether the land is such as might be properly leased, and the applicant a proper and fit person to be granted a lease. If the report be satisfactory, the applicant is required to mark the boundaries of the land he wishes for, by trenches and stones, in such a way as to leave no doubt of the exact land selected. A lease bond is then entered into on a stamp of Rs. 10. An extent of one acre only is leased at one time, and only for one year ; but the lease is extended from year to year if applied for by the lessee.

“Instead of charging a fixed sum for [the rent equivalent of] an annual lease, it has been found better to take one-tenth of the plumbago dug.

“No plumbago can be removed without a pass from the headman. When the lessee has a sufficient quantity dug and ready for removal, he applies for a permit. The headman reports the amount and the value of the plumbago so dug. The lessee is generally allowed to purchase the Crown share at its assessed value, and one-tenth of the value of the Crown share [or one-hundredth of the whole] is deducted and given to the headman who weighed and valued the plumbago, and the balance is brought to account as rent for the land.”

Under this system a sum of Rs. 954.24 was collected in the Western Province in 1884 (a great falling off from nearly Rs. 4,000 in the previous year), the proportions for the various districts being :—Colombo, Rs. 13.72; Ratnapura, Rs. 158.28; Kégalla, Rs. 79; Negombo, Rs. 87.99; Kalutara, Rs. 615.25.

An obvious objection to the Western Province system, and one which has been preferred, is that it seems to revive the temptations to which the headmen of 1873 succumbed; but in reply to remarks to this effect, the Government Agent, Western Province, pointed out that only a tithe of the quantity dug on Crown lands is now in question, and that of this Government tenth the headmen receive one-tenth, or one-hundredth of the whole. One-tenth of a ton, if the plumbago were taken at the Custom-house valuation of Rs. 200 per ton, would be Rs. 20 for 2 cwt., or twice the total royalty fixed in 1873. But the Customs valuation is excessive, and as the plumbago is mixed with extraneous matter, and has to bear the cost of carriage and preparation, of course a “spot value” at a much lower rate is calculated for the rent-royalty. Having referred this question to the Government Agent of the Western Province, he states :—

“Your note has reached me on circuit, and I cannot lay my hand on the exact figures; but I am inclined to think that the value of Crown plumbago, dust and lump together, which varies between Rs. 15 and Rs. 120 per ton at the pit’s mouth, is on an average about Rs. 70 a ton, and that the Crown royalty is about Rs. 4 or Rs. 5 a ton. So that, whilst private plumbago pays a royalty in shape of Customs duty of Rs. 5 a ton, plumbago dug on Crown land pays in rent and royalty Rs. 9 or Rs. 10. Considering that plumbago dug from Crown land is generally easily got at, and that it is optional with a man at any time to cease paying rent and to acquire the land, I don’t think the rent high. We would always rather sell the lands outright than rent them.”

In the latter part of this note, Mr. Saunders seems to have lost sight of the policy announced by Sir W. H. Gregory's Government in 1873, viz., that lands containing plumbago were to be leased, not sold, so as to prevent anything like a monopoly. It is lands which have been proved not to contain the mineral in any quantity, or which have been exhausted, we understood, that are sold. It may be, however, that only large lots of plumbago land were intended not to be sold, the prohibition not extending to one-acre lots. [See appendix No. 14.]

The merit of the system, provided the rent-royalty is moderate, is that the lessee of the land pays only and just in proportion to the productiveness of the land he has leased, payment being accepted in money or in kind. At the end of each year the lease can be either renewed or abandoned, and plumbago lands which have been for a certain time abandoned, and which evidently do not contain appreciable quantities of the metal, are sold on the terms applied to ordinary Crown lands. Copies of an application to dig, and of a lease granted by the Government Agent of the Western Province, are appended to this paper. From the terms of the lease it will be seen that timber for props, &c., can be obtained by the lessee from Crown land at a fair cost, and that roads, paths, &c., can be used for purposes of the mine. The effect of the different systems in operation in the Western and Southern Provinces becomes apparent from a glance at the table of plumbago revenue contributed by each, which is given as an appendix to this paper. Previously to 1881 the contributions of the two Provinces, apart from Customs collections, was pretty equal, but while in 1883 the plumbago revenue (mainly rent-royalty) of the Western Province was no less than Rs. 3,987, that of the Southern Province, derived solely from 74 licenses to dig issued at Rs. 10 each (no rent being charged), was only Rs. 740.

Exaggerated figures have sometimes appeared in the Blue Books, as representing the total number of plumbago mines in Ceylon, from the inclusion of large numbers of abandoned pits. Many such pits are doubtless subsequently worked, so that it is difficult to get even an approximate estimate of the mines existing in Ceylon; and such information, if

attainable, would not help us much, because mere numbers would not distinguish between holes of a few feet deep and Mr. Jacob De Mel's great mine in the Kurunégala district, already described. Some years ago there was an account of a mine on a large scale opened for a Mr. Mathew by a European miner in the district of Kégalla, and many years ago a couple of North of England men, brothers named Sims, tried their luck in mining plumbago, but without success. What are called mines are generally, however, vertical holes, and the great trouble of the miners, as it is also of the gem-diggers, is to keep out water or get rid of it. Steam machinery has been on a few rare occasions resorted to, and in one instance it has been stated that owing to a deficiency of hose sent out, the primitive means in use amongst the natives of baling by buckets had to be reverted to in supersession of the steam engine. From the Government Agent of the Southern Province I have received a translation of a Sinhalese description of a plumbago mine, illustrated by a diagram, which is printed as an appendix, and will be found curious and interesting.

As a general rule, graphite seems to exist not far from the surface, on which its presence may be revealed through fissures, while in regard to this mineral as well as gold and other ores, indications in streams guide explorers up to the including rocks, generally quartzite gneiss, in which the mineral is embedded or diffused. Mr. De Mel tells me that very good plumbago is often found near the surface, but that, as a general rule, the lower the digging operations go, the better the quality and the larger the quantity of the mineral. I remember once at Baddégama, near Galle, seeing in a rice field what looked like a large gneiss boulder, the top of which had been blasted away, the process revealing a "pocket" of plumbago. As a general rule, the mineral runs in long thin horizontal veins through the quartzite strata of the gneiss, but downward veins are not uncommon. Of course the purer the finds are, and the larger the masses the better, but a visit to any of the preparing yards in Colombo will show that besides the cost of prospecting and mining and the uncertainty of ultimate success, a good deal of expense is involved in conveying a

considerable proportion (already noticed) of extraneous matter to Colombo, there to be hammered, cut with small axes, picked, sifted, and washed out.

Still, with all its drawbacks, the plumbago enterprise is valuable to the country not only for the revenue it yields, but for the generally remunerative employment it has given to many thousands of the population (from 10,000 to 20,000 men, women, and children, probably, including cartmen and carpenters), especially since the period when the collapse of the once great coffee interest led to so much distress in the country. The Kurnégala Administration Report of 1873 stated that in that district alone the plumbago industry had given employment to some 5,000 persons. The Galle report for 1872 estimated that each mine required from two to eight or ten miners, and even up to fifty or sixty, at high wages. The Kurnégala report for 1875 mentioned that all the plumbago which had been dug, the figure being given at 2,567 tons, had been removed by rail, coming on the railway at Polgahawela of course. As the principal mines are 18 miles from Kurnégala with 12 miles additional to the railway, the expense of cartage for so heavy an article must be very considerable. We cannot be surprised, therefore, to hear that at a period when the plumbago industry was at the height of its prosperity, Mr. De Mel and other mine owners had almost concluded an arrangement with Messrs. John Walker & Co. for a light railway line from the mine region to the Government railway. Depression in prices caused this design to fall through, but the day cannot be far distant when Kurnégala at least will be connected with the Government railway system at Polgahawela, forty-five miles from Colombo. The Western Province plumbago found in the Pasdun Kóralé (a kóralé which is famous for the quality as well as the quantity of ore it produces) does not come on the railway at Kalutara. Once it is loaded in boats it comes by water all the way to Colombo.

A return furnished by Mr. Pearce shows that nearly one-half of all the plumbago exported from Ceylon comes on the railway at various points, mainly at Polgahawela, the quantity so carried in 1882 being no less than 5,642 tons. Small quantities come from points so distant as

Nāwalapitiya, 87 miles, and Mátalé 91 miles from Colombo. Most of the plumbago dug in the Southern Province, and perhaps some from places ranked in the Western Province, are shipped at Galle. Of the total exports from the Island, an average of 12,000 tons annually for the past five years, less than one-tenth goes from Galle; the rest enters into the export trade of Colombo.

To show the vicissitudes of the plumbago enterprise, I may quote from the Sabaragamuwa report of 1873 to the effect that plumbago, which formerly sold at Rs. 200 per ton, then realized only Rs. 90, while the working expenses had considerably increased in consequence of the enhanced prices of labour. It will be remembered that 1873 was the year in which the change was made to the collection of royalty at the Custom-house, in anticipation of which the great manufactories in Britain and America had provided themselves with stocks of the mineral. Hence a fall in exports and prices. Eleven years subsequently, in 1883, Ceylon sent away her largest export of plumbago, but the depression had even then set in, which led to greatly reduced shipments in 1884. In the one matter of cask-making, however, the increase in the export of plumbago during the past five years must have largely filled up the void created by the decrease in coffee. Here, one of our most inferior timbers, can be utilized for plumbago casks, and as the casks are uniformly made to hold a quantity somewhat over a quarter of a ton ($5\frac{1}{2}$ cwt. nett), an average of 45,000 casks per annum for the past five years, or a total in the quinquennium of 225,000, must have given, in their manufacture, remunerative employment to a considerable number of carpenters who had previously been largely dependent on cask-making for coffee.

But to revert to the subject of plumbago mines. They seem to have been until a comparatively recent period, practically confined to the Western and Southern Provinces, the quantity of plumbago dug in the Central Province being insignificant, and the industry now so wonderfully successful in the North-Western Province being apparently of quite recent origin. In a memorandum furnished to me by Mr. C. Dickman, Assistant Auditor-General, I find the remark that no collections on account of plumbago were made

in this Province until 1872, when Rs. 60 were received; in 1873, Rs. 1,966; in 1874, Rs. 210. There the record ends, and it rather looks as if the money had been received for lands sold, for I have it on good authority that all the mines now worked in the Kurunégala district are on private property; my informant, Gate Mudaliyár Jayatilleke, adds in reply to my queries as to whether there was anything hereditary, or a system of payment by shares amongst the mining class :—

“All the plumbago quarries that are now worked in the district are purchased from the Crown. No licenses have ever been applied for or granted to dig plumbago. The diggers are paid wages, and they are coolies from the Siyané and Hápitigam Kóralés, in the Western Province. Very few Kandyans are employed, as they are not handy in blasting and excavating any depth of more than 15 or 20 feet.”

I may add that but few Tamils are employed in the Ceylon plumbago mines, which are, I believe, exclusively owned by Siphalese, although no doubt the ubiquitous Chetty of Southern India is interested in the recovery of advances made or supplies furnished in some cases.

To Mr. G. S. Williams, the Acting Government Agent of the North-Western Province, I had previously been indebted for responses to my questions, thus :—

“The pits are about sixteen miles north-east of Kurunégala on the Dambulla road. There is a good resthouse at about the 12th mile, and the journey in decent weather is easy enough.

“The trade altogether failed last year—I mean no digging was done—on account of the fall in price, but this year operations have been resumed, and I am told that about 2,000 men are employed. The plumbago is found in rocky ground in which are very large crystals transparent like Derbyshire spar.* De Mel is the owner of the principal pit. The resthouse is at Gókerella. It is not mentioned in Fyers’ Itinerary, but is between Polgolla (about a mile beyond it) and Ambanpola. On page 20 of the new edition (1881) Part I., you will find Wētakeyyápota, which is 15·55 miles from Kurunégala and 0·55 mile beyond that, or 16·10 from Kurunégala, ‘minor road to plumbago pit on right.’ There are other plumbago pits, some actually by the roadside.”

* Crystalline quartz, of course, as lime taking the form of spar seems to be non-existent in Ceylon?

It thus appears that the best deposits of plumbago at present worked in Ceylon are situated at the foot of the north-western portion of the mountain zone. The mineral exists at high elevations, up to Nnwara Eliya indeed, but apparently not in paying form or quantity. It would appear that while the veins of plumbago run generally from south to north in the Western Province, their direction in the Knrunégala District are from east to west.

In the Central Province as now constituted, few plumbago mines seem to have been opened. The mineral must be rare in the North-Central Province, and still rarer, if really existent, in the Northern Province. Plumbago mining, in any case, seems to be, at present, practically confined to the North-Western, Western, and Southern Provinces, and a Sessional Paper, issued with reference to the legislation of 1873, stated that the number of pits then was altogether no less than 1,779, of which 1,181 were on Crown land, 539 on private land, and 59 on land specially exempted. Of the pits enumerated, 1,086 were in the Western Province, 644 in the Southern, and 82 in the North-Western. In the Western and Southern Provinces by far the larger proportion of the mines were on Government land, there being none on Government land in the North-Western Province. Of the 1,779 mines enumerated, more than half were represented as having been abandoned. In dealing with the question of mines in the "Ceylon Directory" of 1880, the compiler stated that it was impossible to obtain the exact number of plumbago mines in Ceylon, but that it was usually reckoned at about 400, besides 230 gem pits and 30 iron quarries.

It seems possible that if digging for gems and plumbago continues on a large scale, and becomes widespread, legislation may be needed such as exists regarding the protection of wells, and that measures to prevent accidents from subterraneous blasting and the collapse of tunnels, as also to secure free ventilation, may be necessary. Though not so much so as gem-digging, plumbago mining is, no doubt, largely a speculative pursuit, involving the loss and demoralization which ever accompany gambling pursuits. The ultimate result is, however, beneficial to the people and the country.

From some of the Administration Reports consulted, it would seem that the plumbago industry is a recent one in

the district of Sabaragamuwa, although the existence of the mineral must, surely, have been revealed to the gem-diggers who have for ages been engaged in searching for the sapphires and rubies for which the region around "the city of gems" (Ratnapura) is so famous. After adverting to gold, the report of 1868 stated: "A more remunerative speculation than gold-digging has sprung up during the year, viz., the digging of plumbago or graphite, which has been found in a very pure form and in some abundance in nearly every division of the district." In the report for 1869 disappointment was expressed that the demand was not brisker, but strong adverse reasons were suggested in the case of so bulky an article "in the distance from and costliness of the carriage to the stores in Colombo." As regards Kurunégala, too, the report for 1875 speaks of plumbago being found at Mipitiya, about 18 miles north-west of the capital of the Province, as if the discovery had only recently been made.

Under the rules now in force royalty is levied on plumbago, the produce of all lands, private or public, all special exemptions being abolished, but of course the owners of private lands are not bound to apply or pay for licenses to dig, nor is any plumbago or its money value in the shape of rent exacted from them, only the royalty collected at the Customs. A vivid idea will be formed of the extent to which Government—that is, the public—were formerly cheated under the system of collecting the royalty at the pit's mouth, when it is mentioned that while cwt. 226,000 were exported in 1869, the royalty recovered was only Rs. 16,000, against Rs. 65,000 on cwt. 263,000 in 1883, the rate in the latter year being only one-third of that in the former.* The extreme rate of 30s. per ton in 1869 evidently proved an irresistible temptation to diggers and headmen, and the royalty recovered was only one-tenth of the sum which

* How striking is the illustration here afforded of the value of indirect (and especially Customs) taxation, rather than a direct levy in the case of Orientals. No greater fiscal boon could probably be conferred on the people of India and Ceylon than—if it were possible—the collection of all Government dues through the Customs Department, so saving an amount of oppression on the one hand, and of bribery and corruption on the other, of which European administrators never get more than a faint idea.

ought to have been collected. No wonder if from 1869, until the new system came into play, Government had to confiscate considerable portions of the mineral, or that Sir W. H. Gregory in closing the session for 1873 should have remarked: "The Plumbago Ordinance will, I firmly believe, give a great impetus to mining enterprise throughout the country, and put an end to the widespread fraud and demoralization which the present system entails." Fraud and demoralization were at once checked, but the anticipated impetus to mining enterprise was only fully given when the royalty was reduced from Rs. 10 per ton to Rs. 5, in 1877. The criterion, I need scarcely say, is not to be found in Blue Book returns of the number of mines open or dormant, but in the figures of the Custom-house.

In the Blue Book for 1884 the figures given for plumbago mines are 81 in 1884 against 246 in 1883, in both cases exclusive of mines in the Southern Province, whence returns of mines seem not to have been sent, the details for 1884 giving 57 mines in the Western Province and 24 in the North-Western. I find, however, that in the Southern Province the licenses to dig plumbago issued in 1883 were 74, falling to 10 in 1884. From the North-Western Province estimates are given in the Blue Book, which are manifestly imperfect, the figures for 1884 being 1,500 tons of mineral valued at only Rs. 150,000. The addition of the mines open in the Southern Province would doubtless bring the number of plumbago mines at work in the year of reaction and depression (1884) up to considerably over 100, a number which will, probably, be doubled or trebled, should rumours of and preparations for war give a fresh impetus to the pursuit. Although no estimate of the number of mines in the Southern Province is attempted, the Blue Book return mentions: "Plumbago and iron mines; gems and minerals in small quantities are taken from rivulets and the surface of the earth in numerous places;" and the curious statement follows: "Plumbago about 65 tons, valued at from Rs. 20 to Rs. 100 per ton." We may safely assume that the figures for quantity and value are equally inadequate. Indeed, the Customs returns of revenue show that 753 tons were exported from Galle in 1884. It was natural that the mineral should be valued at a low figure in

1884 in view of the depression which prevailed, and which is vividly represented by the comparative figures for the totals for the Island of ten-rupee license fees to dig on Government ground for 1883 and 1884, which, with (in the Western Province) rent of 10 per cent. of the yield, gave Rs. 4,736 for the former year and only Rs. 1,054 for the latter, a falling-off equal to Rs. 3,682, representing probably a deficiency of a couple of hundreds in the licenses applied for and granted last year as compared with 1883.

As has been proposed in the case of chips in the cinnamon trade, it would almost seem desirable that low quality dust should be excluded from the exports. Buyers are strongly inclined to confine their attention to lump of best quality, and I have heard that some of the local dealers have injured their own reputation, and that of the article in which they deal, by mixing lower qualities with the higher. As matters stand, the proportions in which the mineral seems to be exported are:—lumps, 1st and 2nd quality, 50 per cent.; chips and dust, each 25 per cent.; so that dust is only one-fourth of the whole. In the home market during the past five years of unprecedented outturn, I am informed that prices have ranged from £20 per ton, the highest for lump, down to £10. In Colombo, apart from the exceptional case in the experience of Mr. W. A. Fernando, already mentioned, the highest prices ever known are stated to be Rs. 320 per ton for fine, Rs. 270 for ordinary, Rs. 95 for dust. In the old sailing ship days plumbago was taken at an exceptionally low rate of freight as “dead weight.” Since 1880 the average rates for a ton of 20 cwt. have been:—steamer 40s.; sailer 35s.

The United States are our best customers in the case of plumbago, the Ceylon form of which the late Mr. Joseph Dixon saw and appreciated in 1827, and of which he secured a first shipment in 1829. In 1882 the quantity received in the United States from Ceylon was stated at 16,000,000 lb., and of the comparatively small quantity of 22½ millions of pounds sent from Ceylon in 1884, more than half went to the United States. But a memorandum showing the various countries for which the plumbago exported in the past five years was destined, will clearly indicate how important a customer for our mineral we have in the United States with its large steel manufacturing

industry. Besides the quantities which may subsequently have been transhipped thereto from Britain, the direct shipments for the United States from Ceylon were 133,000 cwt. out of a total of 205,000 in 1880; 160,000 from 260,000 in 1881; 113,000 from 260,000 in 1882; 141,000 out of 262,000 in 1883, and 94,000 out of the total of 182,000 in 1884. The general result is that of the whole export of 1,170,000 cwt. in the five years, 641,000 (or very considerably more than one-half of the whole) went to the United States, the United Kingdom taking the bulk of the remaining 529,000 cwt. How far the continent of Europe may draw on Britain for supplies of graphite, I am not aware, but the shipments of plumbago from Ceylon diverted in the past five years to other ports than those of the United States and the United Kingdom have not been important. To Trieste went 4,217 cwt. in 1881; to Hamburg 4,031 in 1881; to British India 1,095 in 1880; to France 884 in 1884; to Holland 945 in 1884; to Australia 885 in 1881; and to Hongkong 739 in 1883. But for all practical purposes we may regard Great Britain and the United States as taking at first hand the whole of the plumbago Ceylon produces. Out of an export of 263,000 cwt. in 1883, Britain took 119,000 and the United States 142,000, leaving only 3,000 cwt. for all other places. The memorandum referred to is appended as a note.* It seems probable that three-fourths of all the

* PLUMBAGO exported in each of the last five years, showing the countries to which the mineral was shipped:—

	1880.	1881.	1882.	1883.	1884.
	cwt.	cwt.	cwt.	cwt.	cwt.
United Kingdom	70,276	89,709	143,450	119,312	84,981
Holland ...	—	—	—	438	945
Trieste ...	107	4,217	1,828	—	210
France ...	507	699	300	294	884
Hamburg ...	—	4,031	—	—	816
U. S. of America	133,556	160,259	113,451	141,664	94,083
British India ...	1,095	109	999	326	506
Australia ...	197	885	118	—	—
China ...	—	—	12	—	—
Hongkong ...	—	—	8	739	—
Total ...	205,738	259,909	260,166	262,773	182,425

plumbago which Ceylon exports is used in the great crucible factories of Britain and the United States, that established by the Messrs. Morgan Bros. at Battersea and the crucible factories of Jersey City, New Jersey.

Both establishments are on a very large scale, and afford remunerative employment to a considerable number of operatives. Mr. O. V. Morgan, the principal partner in the English Company, will be a candidate for Battersea at the forthcoming Parliamentary election, and will pretty certainly be chosen. He is a gentleman of high character, intelligence, and enterprise, and has travelled much, including a visit to Ceylon. His firm, that of Morgan Brothers, besides their manufacturing and banking pursuits, turned their attention to periodical literature, having founded the *European Mail* and the *British Trade Journal*. Mr. Morgan has taken an active part in general social improvements, and has done a great deal to secure the well-being of the operatives at the extensive crucible works, which he and the brother next to him in age founded in 1855. The American establishment had been at work long before this period, but no doubt its productions did not go beyond local demand, for in a notice of the Battersea works we find it stated that previously to 1855 crucibles were almost exclusively imported from Germany. Now that country, together with other centres of industry on the continent, is principally supplied from Battersea, where crucibles are turned out at from 8*d.* per dozen, up to a gigantic melting pot costing £6 5*s.*, and capable of taking in 1,000 lb. of steel. Such a crucible can bear from 8 to 10 meltings, while in the case of gold a crucible taking in 1,200 ounces can sometimes stand seventy meltings. So in the case of brass, while crucibles for assaying the precious metals are very carefully manufactured, being rendered porous by the use of charcoal. The proportions of graphite and fire-clay used in crucibles for various purposes differ widely no doubt, but good serviceable melting pots contain from 25 to 50 per cent. of graphite, the proportion of graphite being, we may take it for granted, larger in crucibles used in mints. The absence of coal fuel from Ceylon is probably a fatal objection to local iron or steel manufacture on any extended scale, but for small quantities of superior steel for special local use, I would, with some diffidence,

suggest that crucibles composed of our indigenous plumbago and kaolin clay, both abundant and cheap, might be profitably used. The existence of "millions of tons" of iron ore in Ceylon is not so apocryphal as that of anthracite, and those who owe their origin to Britain are not likely to forget that her wealth in iron quite casts into the shade all the treasures of the diamond mines of Golconda and the gold diggings of California and Australia.

But to return to the Battersea works. Messrs. Morgan Bros. get credit for a liberal and sensible scheme of pensions for their workmen, while to some extent the men have a share in the profits of the firm. Although the plumbago sent from Ceylon is carefully prepared and assorted before being packed for shipment, it yet appears, from a description of the Battersea Patent Crucible Company's works contributed to the *Chemist and Druggist* by Mr. J. C. Brough, that, preparatory to grinding and manufacture, there is a careful process of selection. Mr. Brough stated :—

"The graphite imported by the Company is not used solely in the manufacture of melting-pots and metallurgical apparatus. A good proportion of this valuable raw material is prepared for domestic purposes, and sent from the Battersea works in the form of ordinary 'black lead.' As this article is used wherever there is a grate or stove to be kept bright, its annual consumption must be very large. There is no substitute for it—nothing that can be employed in the same way to polish and protect the ironwork of common fireplaces. Without the factitious lustre produced by the action of 'elbow grease' on black lead, the most elaborate kitchen range would soon become unsightly, the trim parlour grate blush with rust, and the cottager's 'wee bit ingle' would leave off 'blinkin' bonnily.'

"The various qualities of black lead which the Company sends into the market under different fanciful names are all prepared from graphite or plumbago, and nothing else. The highest qualities are distinguished from lower by their superior fineness, softness, and lustre; but chemically they are identical. The article sold under the sentimental name of 'Servants' Friend' at 28s. per cwt. is quite as pure as the 'Prize Medal Lustre,' which fetches double the price, or 'Halse's Roman Lustre,' the best quality of black lead manufactured by the Company. Again, the analytical chemist would fail to detect any essential difference between either of the abovenamed products and the article labelled

'carburet of iron,' in remembrance of an exploded opinion respecting the nature of graphite. How comes it, then, that one quality is so much superior to another? The explanation is simple enough. The difference in the manufactured article may be traced to certain variations in the physical properties of the raw material. Thus, one sample of graphite may be soft and lustrous, while another, equally pure, may be hard and dull. These variations are subordinate to the distinction between amorphous and crystallized graphite, which we referred to when describing the stores of raw material. For making domestic black lead, the amorphous or soft graphite is almost exclusively used.

"The separation of the different qualities of graphite is a labour which demands great experience and judgment, and can only be successfully performed by the old hands. The best pieces are soft and nunctuous, perfectly free from grit, and capable of receiving a very high polish. The worst pieces, technically called 'gruffs,' are, on the contrary, harsh, gritty, and deficient in lustre. The latter are only employed for making 'leads' of the lowest brands. The numerous intermediate qualities are distinguished one from another by characters which are only apparent to the experienced eye.

"The manufacture of black leads includes three distinct operations—grinding, sifting, and packing. At the Battersea works, the first operation is performed by means of a large mill driven by steam power. The ground 'lead' is conveyed to an upper floor by an endless-band elevator, and is then sifted through the finest silk by a contrivance resembling an ordinary dressing machine for flour. The packing is chiefly done by boys, who work with marvellous rapidity. The powdered black leads are done up in neat packets in quantities from two ounces upwards; they are also packed in 1-lb. tin canisters and in wood boxes. Papers of various colours are used to form the small packets, so that the different qualities may be readily distinguished. A paper covered on one side with burnished black lead is employed for wrapping up some of the higher qualities.

"Two descriptions of 'blocked black lead' are manufactured by the Company. The blocks are formed by pressing the powdered and sifted graphite into suitable moulds by the aid of machinery very similar in construction to that employed for making bricks, though, of course, on a much smaller scale. There are two blocking-machines constantly at work, and the number of little bricks they turn out annually would amply suffice for the building of a Lilliputian city. * * * *

“Crucibles have been in use for melting and refining metals from that distant point of time when man exchanged his stone hatchet and bone chisel for implements of bronze. The earliest melting-pots were doubtless made of the plastic and infusible substance, clay, and there is no reason to suppose that they differed essentially from the earthen crucibles now commonly used in our foundries.

“The works of the Patent Plumbago Crucible Company cover a large space of ground at Battersea, and have good river frontage. As we proceed along the lane which leads from near Battersea-bridge, we find that the ground gets blacker and blacker, and before we reach the threshold of the office we notice the familiar black-lead polish beneath our feet. Passing a regiment of clerks, we enter the private office of the manager of the works, where we put on a very large coat and a very old hat, which are kept for the use of clean visitors. There are many things in this little office which attract our attention. The walls are covered with testimonials from British and foreign mints respecting the excellence of the Company's manufactures, with here and there a prize medal. The International Exhibition of 1862 is recalled, not merely by the prize medals awarded to the Company for crucibles and black leads, but also by the splendid collection of samples of plumbago, which formed such a striking feature in Class I. In this collection every quality of plumbago is represented by specimens from all the most celebrated mines, particularly those of Ceylon, Germany, Spain, Siberia, Canada, Finland, and Borrowdale. We learn from the manager that some of the samples would not be adapted for the manufactures of the Company. The Siberian plumbago, for instance, contains too much iron; and, although this could be entirely removed by the Company's patented process for purifying plumbago, it is found cheaper to work with the Ceylon plumbago, which contains but little iron.

“Before we leave this snug office for the busy factory, we will jot down a few notes on plumbago, or, to use its more correct name, graphite. The old mineralogists, misled by its remarkable metallic lustre, placed graphite among the metals, and at the present time there are doubtless many persons who accept ‘black lead’ as an appropriate name for this substance. In most dictionaries graphite is defined as ‘carburet of iron,’ in accordance with the opinion formerly held by most chemists that it was a compound of carbon and iron. This definition is now known to be incorrect; for although iron is generally present in graphite, it

must not be regarded as an essential constituent any more than the silica or alumina which usually accompanies it. The iron, silica, and alumina, when present, are simply in a state of mixture, and not chemically combined. Graphite is one of the forms of carbon, that Protean element which also occurs native as the sparkling diamond and the black and lustrous anthracite, and which also appears in the familiar shapes of charcoal, coke, and lamp-black. According to Dr. Wood's analysis of a sample of the graphite used at these works, it contained upwards of 98 per cent. of pure carbon, the remainder being silica with mere traces of iron and alumina. Few samples have been found to contain less than 95 per cent. The variform character of carbon is exhibited by graphite itself, for it is sometimes crystalline and sometimes amorphous. The crystallised, or foliated graphite, is found occasionally in six-sided tabular crystals, but commonly in foliated or granular masses. It is chiefly obtained from Ceylon, where it is found imbedded in quartz. It is also found near Moreton Bay, in Australia; in the States of New York and Massachusetts; and in Siberia. The amorphous graphite is that variety to which the terms 'plumbago' and 'black lead' are ordinarily applied. It is much softer than the crystalline graphite, and makes a blacker streak on paper. Formerly it was obtained almost exclusively from Borrowdale in Cumberland, but the mine there is nearly exhausted, and we believe is no longer worked. The bulk of that used at present comes from Germany, principally from Griesbach near Passau. Both varieties are used in the manufactures of the Company—the crystalline for crucibles and the amorphous for polishing powders.

"The consumption of Ceylon graphite at the Battersea works has had an extraordinary effect upon the price of the article. When the Company commenced business it cost about 10*l.* per ton, but now (1864) it cannot be bought at double that price.

* * * * *

"The total quantity of graphite exported from Ceylon in 1862 was 40,895 cwt., of which no less than 34,730 cwt. was shipped to Great Britain. The Customs returns for last year have not reached us. We do not wish to be understood that the Patent Plumbago Crucible Company use up all the Ceylon graphite brought to the United Kingdom, but it is well known that they are the principal consumers. We must now take leave of chemistry and statistics, and see what there is to be seen at the Black Potteries.

"We commence our tour of inspection at the Receiving Stores, where we are shown the stock of raw material, which comprises

at present about 2,000 casks of graphite, each one holding from four to five cwt. The heads of a couple of casks are broken open in order that we may compare the hard iron-grey fragments of the Ceylon graphite with the black, dull, friable lumps of the German variety. A piece of the latter pressed between the finger and thumb feels pleasantly soft, and flattens readily into a lustrous cake. From the stores we pass to the engine-house to take a peep at the prime mover of the machinery employed on the factory. One horizontal engine of 25-horse-power serves to do all the work that does not require skilled hands.

"The organisation of labour is thoroughly understood at the Battersea works. There is a place for every man, and every man is in his own place. A strict code of rules is enforced by fines; but these fines are paid over to the Fund of the Workmen's Provident Club. We have been over many great industrial establishments, but have not seen any better managed than this crucible factory."

Let us now turn to the older American Company, which, if we count from Mr. Joseph Dixon's beginnings in 1827, has not been merely thirty years handling plumbago, but for a period of over half a century. Mr. Orestes Cleveland, writing in the *Journal of Applied Science*, some years ago, stated:—

"We (Joseph Dixon Crucible Co., Jersey City) have been forty-five years engaged in the manipulation of plumbago, being the oldest house in the trade in this country, handle more of it now than any other single establishment in the world, and have been successful in its application to different branches of industry; we may, therefore, offer information without being accused of not understanding the subject treated. The black lead of commerce, and what is so called by the trade, in first hands, is found only in Europe, principally in Germany. The plumbago of commerce comes mainly from the island of Ceylon, but is also found in many parts of the United States, being mined successfully, however, only at Ticonderoga, in the State of New York. It is also mined to a small extent in the Ottawa region of Canada, though thus far without profit. It is therefore known in trade as Ceylon plumbago. It is very refractory. I have experimented by subjecting for two hours a piece with sharp projecting angles to a heat that would melt steel, and on cooling found the sharpest points perfect; but it will exhaust if left on top of such a fire. It is found in veins in a pure state, is removed in lumps, and a selection of these

forms the 'prime lump' of commerce. The formation most common in a pure state is that of laminated crystals, elongated at right angles with the side of the vein, if not more than from four to six inches wide; but when the vein widens the crystallization often radiates from numerous centres, and the whole formation is very beautiful; the foliated variety is equally valuable and more brilliant, but rare in any quantity; the acicular form of crystal is not apt to be as pure in the lump, but it is useful for most purposes; the granulated variety, the purest of all, is of little use for crucibles, but, with suitable manipulation, produces the finest grades for electrotyping and fine lead pencils, and is unequalled for lubricating. Pure plumbago is free from grit when pulverized and rubbed between the fingers, and the polish produced in the same way is instantaneous and very bright, being like a darker shade of polished silver. It is found mixed with iron, rhomb spar and other forms of lime, the rock and earth in which the vein is carried, and many other foreign substances injurious for all the purposes for which pure plumbago is needed; so that much care is necessary in purchasing the raw material for a given purpose. Lime, for instance, is fatal to plumbago for crucible-making. The plumbago is mined in the interior of the island of Ceylon, and is brought down to Colombo in bullock carts. It is there selected into grades; so much as may be finely broken up is sifted, and the coarser part of this is called 'chips,' while the finer part is called 'dust.' The 'dust' from the prime lump is, of course, very different in character from the dust left from the poorer grades of lump, and all of it, whether lump or dust, after being handled and packed in barrels in Colombo becomes so black and bright by the poor particles rubbing against the good, that the touch of an expert is required to distinguish between the grades. The German black lead is not refractory, and is therefore useless for any purpose that brings it in contact with the fire. It has no value for the crucible-maker, or for stove polish, and is of but little use as a lubricator. It has a very low conducting power, even in its pure state, and the best quality that comes to market is far from pure. None of it comes in its original state as mined, but all of it is washed and floated, and so the grades are produced. In fact, it resembles a weak black clay more nearly than it does true plumbago in nature as well as appearance. It is used often on account of its cheapness, when it would be cheaper to use the real plumbago even at five times the price."

Mr. Cleveland then proceeds to state that the first [first in order of time] and still the most extended use of plumbago

is for making pencils. Originally, lumps of the mineral were cut into the required shape. Then, until the Borrowdale mines gave out, the masses were sawn into thin pieces to be enclosed in wood. And now Mr. Cleveland proceeds to describe, in detail, the process of which, according to the latest edition of the *Encyclopædia Britannica*, M. Conté, of Paris, was the discoverer :—

“The present method consists in selecting the best granulated plumbago (found till recently only in Germany), pulverizing it very finely, and floating it in water through a series of vats ; the coarser particles settle to the bottom of the first vat, the finer in the next, and so on, till, after passing through several, that which settles in the last vat is considered fine enough for the purpose. A suitable clay is found as yet only in Germany, and this is treated by the floating process, the finest only being fit for use. The plumbago and clay are then mixed together with water to the consistency of cream, ground together like grinding paint. When the operation is completed, the mass is plastic, water enough having evaporated to leave it in that state. It is then placed in a press and forced through an opening of the size desired for the pencil leads, and the leads are cut to a suitable length, straightened, and dried. When dry enough to handle, they are placed in a crucible, the air excluded, and subjected to a high heat, which bakes them and brings them out ready to be placed in the cedar for pencils. The different grades are produced by the different mixtures of clay and plumbago ; the more clay, the harder the grade produced. Skill in the manipulation, the exercise of great care as it progresses, and an expert to select the materials, are absolute prerequisites for a perfect product.”

It will thus be seen that the finishing process in the manufacture of black lead pencils is baking in a crucible composed, probably, of the same mineral.

In most of the works consulted in the preparation of this paper—and they have been many and various—the credit of having first made and used plumbago crucibles has been given to the Germans. Mr. Cleveland awards the credit to the Dutch, and it is certainly significant that the Dutch name for the mineral should be *potlood*, or pot lead, the lead of which crucibles are made (?)—Mr. Cleveland states (writing some six years ago):—

“*Crucibles or Melting Pots, Retorts, &c.*—Forty years ago the only plumbago crucible was made by the Dutch, the melting

pots used in most countries being made of clay and sand; but the late Mr. Joseph Dixon, the founder of our house, in 1827 made crucibles by using the plumbago found in the State of New Hampshire, of a quality so far superior to the Dutch black lead pots that he took the market from the first. He afterwards saw specimens that had been brought from Ceylon as curiosities by Captains in the India trade; and finding them so much better than the New Hampshire plumbago, he procured a shipment, being the first importation of Ceylon plumbago to the United States. For crucibles the pure lumps known as 'prime lumps' only should be used, ground to a fineness that leaves the particles bright and glistening when held to the light, but not so fine as to destroy this appearance. It is then mixed with clay, and the best known for that purpose is found at Mayence, comes down the Rhine, and is shipped to this country from Rotterdam. A small amount of finely-pulverized charcoal should be added to render the crucible porous. As little clay should be used as will suffice to hold the plumbago together, the object in using the clay being only to cement the particles of plumbago. After a thorough mixture, the crucibles are turned into the desired shape, much the same as potteryware; they are then dried in a kiln like pottery. In use the crucibles should be placed in the fire, and not on it. The fire should surround the crucible to the very top. If used with a blast, the blast should not strike the crucible direct, but there should be coal for the blast to strike against. The crucible should be kept in a dry place, the least dampness being fatal. If they are well made, no annealing is needed, the object of annealing being only to complete the shrinkage that should be fully accomplished in the 'burning' by the crucible-maker. To provide against slight dampness, however, it is well, when possible, to use the crucible for the first time in a new fire, placing the crucible in the furnace at the time of lighting the fire, so that it heats up gradually with its surroundings. After the first time even this precaution is unnecessary. For melting brass, copper, gold, silver, or alloys of metals, a Dixon Plumbago Crucible should run from twenty to forty meltings according to the fuel, draught, care, or other circumstances. I have known them used seventy and even eighty times, with a natural draught and great care. For melting steel, they will run from four to six times. They can be made to run longer by care and a system of cleaning the slag from the surface after each melting, and coating the crucible with a mixture consisting of fire clay, plumbago, charcoal, and silica; pure fine quartz sand being, in my judgment,

the most useful form of silica to employ ; other substances have been used, but these are all that are of any real value. The carbon from the interior of gas retorts would be better than charcoal, but it cannot be had in quantity, and is too hard to pulverize cheaply ; in consequence of that hardness, it is used successfully in electric batteries where a carbon is wanted."

Mr. Cleveland then proceeds to describe the processes by which stove polish is produced, the great point being that the more finely the plumbago is pulverized the better and brighter will be the result, large particles flying off and getting wasted in the process of rubbing. He adds :—

"The polish from pure Ceylon plumbago will last on the iron for a long time, while the polish from the German black lead will burn a reddish brown when the stove is raised to a red heat. But as the German is less than half the price of the Ceylon, it is used with it as an adulteration, and for the cheaper kinds the German is used alone. The Ceylon is adulterated also with coal dust, pulverized slate, and many other substances. Dishonest makers of stove polish have this temptation, that only experts can detect the adulteration ; and they succeed in palming off their mixtures, because the particles of adulteration do not prevent the particles of plumbago from polishing the iron to a small extent. For instance, a thousand particles of adulteration and a thousand particles of plumbago, mixed together, can be sold at a low price, and the particles of plumbago will do the polishing, while most of the particles of adulteration will fly off in the process."

And so our plumbago, like our coffee, suffers from the "ways" that are literally "dark" of the adulterators. Mr. Cleveland, in a kind of despair, exclaims :—"Perhaps no article except mustard can be so successfully adulterated as "plumbago." He means, of course, for stove polish, because adulteration in the case of plumbago used for crucibles would soon be betrayed in the trial by fire, one great value of the pure plumbago in crucibles being that it conserves carbon in steel when being melted. Mr. Cleveland strongly deprecates liquid stove polish and varnish. Premising that the plumbago should be very finely pulverized, we may, for the benefit perhaps of the owners of stoves or other articles of cast iron in Ceylon, quote the description of the proper mode of application of a substance which is not merely a

bright paint, but the best possible protection of the iron from rusting. Mr. Cleveland states :—

“The proper way to polish a new stove is to mix the plumbago with water to about the consistency of cream, have it in an open dish, apply it to the iron like paint, and with a dry stiff brush polish quickly till dry ; and this polish will be brighter, and last longer, than any varnish polish ; and if the plumbago is right, this method is much more economical in material and labour.”

As a lubricant for metal surfaces, journal boxes, carriage axles, and all metal bearings, we can easily understand why only the very finest plumbago should be used, the choicest lumps being pulverized till the particles will not glisten but the mass becomes a dead black. It cannot, Mr. Cleveland states, be made fine enough by bolting (he means sifting through silk), but must be floated either in water or air. He adds :—

“The simplest method is the water separation, and during the process it should be treated to a bath of dilute sulphuric acid, which will take up the particles of spar and iron, leaving the sulphates of lime, magnesia, and iron easily washed out.

“The Dixon lubricating plumbago is pulverized by rolling thirty-two-pound iron balls, and is brought into infinitely fine grains, giving it more body and usefulness than the scale form. There is no purpose for which plumbago should be as pure and as fine as for lubricating, except for electrotyping ; but a large part of that which is offered for sale as a lubricator is adulterated, some of it being composed mainly of the German black lead, and is of no more use than common clay for the purpose. For blowing cylinders the best quality of Ceylon plumbago, pulverized to the finest grade, pure, and left with a good body, is the most economical. For engines, rolling mills, and machine bearings the very finest should always be used. For wood bearings, after oiling with the plumbago a few times, the oil can be dispensed with, and the pure plumbago only applied in the dry powder. For metal bearings it should be freely mixed with oil. On hot axles or journals, apply it freely, dry, and then oil up as usual. If the railroads would all use the best grade of Ceylon plumbago, pulverized and prepared as described, hot journals would be very rare, and much delay and loss in freighting saved, as well as annoyance to passengers avoided. No substance is known that is so useful for lubricating as plumbago, and yet, although used for that purpose more than two hundred years ago, the true

method of preparing it was not known till within a few years, and it comes upon the market now little understood, and almost like a new material. It is destined to work great changes. Mixtures and quack nostrums are sold with sounding names, but as the plumbago in them is all they contain of the least value, it is better to use it pure."

I notice, however, from advertisements in the American papers, that "mica grease" as a lubricator is competing with plumbago, but how far successfully I cannot say. What I know is that the writer of a recent article on American minerals strongly supports Mr. Cleveland's view as to the great superiority of plumbago as a lubricator. I am not aware that it is so used to any extent in Ceylon, either in foundries or on the railways, although if all stated regarding its value be correct, Ceylon plumbago ought to be much more largely used in Ceylon than it is at present, as a lubricant and for other purposes. For all uses it would seem that grinding to extreme fineness is essential. Mr. Cleveland proceeds :—

"*Electrotyping.*—To the electrotyper absolute purity in his plumbago is a necessity, and hence any adulteration will discover itself at once on trial. The purest selected Ceylon lumps should be treated as described for lubricating, but the separating process should be carried to a finer point, and the acid bath given with care. This acid should be applied till with a thorough stirring no effervescence takes place, or bubbles rise to the surface. In electrotyping the great conducting power of the plumbago asserts itself."

Mr. Cleveland, it will be observed, speaks of plumbago as if it were invariably a good conductor, but another writer on the subject (Smee), who seems to write from experience, says that some lumps are non-conducting, just as some pieces though perfectly pure carbon are so hard as to resist the saw. And now we come to a use for plumbago, scarcely if at all inferior to that of crucible manufacture, viz. :—

Facing for Moulds or Foundry Facings.—For this purpose plumbago is but little understood, although it is used to a limited extent. That it is valuable, most skilful moulders are aware ; consequently, much of the trash that is sold for 'facings' is called plumbago, to make it sell, without containing a particle of

anything even resembling the real mineral. Most of that which is sold to the stove-plate and other smooth-casting foundries for 'black lead,' is innocent ground slate, but some of it is a mixture of ground coal and German black lead, while charcoal would be better than either if ground fine enough. Ceylon plumbago combines the two qualities of a substance almost as refractory as asbestos, and the most perfect conductor of heat. These are the essentials of a perfect 'facing.' It cannot be pretended that any other substance will answer as well, unless it will combine and form a flux upon the surface of the metal. As for the mechanical operation of filling up the pores, or smoothing the mould, plumbago has no equal. For iron castings it need not be a perfectly pure article, but that it be pulverized very fine is absolutely necessary for economical work and the best results."

We now come to some miscellaneous and curious uses to which plumbago is put, the mineral being applied to articles so different as musical instruments, hats and boots, bottles, paint, boats and yachts. Listen:—

"For pianos, plumbago is employed to coat the bridge over which the wires are drawn, because of its perfect lubrication; it prevents the wire from adhering to the wood, and should be as free from impurity as that used by the electrotyper, but need not be pulverized as finely. For organs, it is used to lubricate the sides, and should be the same as that used by piano-makers. The German black lead imparts a peculiar tone to the colours and a softness and smoothness to the touch of felt hats. The very best lump only should be accepted. As it has once been washed and dried in lumps, they will readily separate again in water, and no pulverizing is needed. For colouring dark glass for carboys, bottles, &c., the best German black lead is used in lumps, but no inferior grade will answer. For paint, plumbago has long been known as possessing great value. The elements do not exhaust it, water sheds from it as from oil itself, and fire does not affect it. The grade need not be the highest. For the bottoms of boats and yachts it has long been used, especially for racing boats; but only the best Ceylon plumbago, very finely pulverized, is valuable."

A substance which used, as a paint, resists the action of the atmosphere and is both waterproof and fireproof, is surely of great economic value, and ought to be specially useful as paint for the numerous tea factories erected or in course of erection in Ceylon.

Finally, Mr. Cleveland gives the following information :—

“For Blast Furnaces.—Plumbago thrown into the blowing cylinders, if adulterated with coal dust, will be worse than nothing. It should be pure and very fine, so that each particle that strikes the side of the cylinder assists in polishing the surface. The German black lead is of no value, because as many particles of the clay character will stick to the iron as there will be particles of the black lead character to lubricate the iron and render it smooth.

“Refractory Mixtures.—For tweers, pointing-up furnaces, &c., take ‘prime lump’ Ceylon plumbago, pulverized to scales as directed for crucibles. Then mix equal parts of Dutch pipe-clay, fireclay, half the quantity (by measure, not weight) of charcoal, and the same half quantity of silica (pure quartz sand ground fine being the best); to this mixture add as much of the plumbago as possible and leave the mass thin enough to work. It should be made just thin enough with water, so that it will run rather sluggishly. Plumbago for polishing powder should be of the very best quality, finely pulverized. The German black lead is sometimes used, but is not economical for the powder maker, and for high-priced powder is useless. Shot is polished with plumbago, and it should be absolutely pure, pulverized to the finest grade from Ceylon ‘prime lump.’”

Mr. Cleveland's very interesting and valuable notices of the American Crucible Company, and their varied manufactures of plumbago, is supplemented and brought down to solate a date as 1883 by the writer (Mr. John A. Walker) of an article on Plumbago in a volume on the “Mineral Resonrces of the United States,” prepared by the National Geological Snrvey Department, and supplied to our Library by the Smithsonian Institute, to which my attention was attracted by our Honorary Secretary, when he asked me to write this paper. In the summary prefixed to this volume it is stated that the amount of graphite mined in the States in 1882 was 425,000 lb., worth crnde at the point of production 34,000 dollars, equivalent to about Rs. 70,000. Dnring the first six months of 1883 the production was estimated at 262,500 lb., worth 21,000 dollars. From Mr. Walker's detailed account we learn that graphite is, as a mineral, widely distributed in the United States ; as an ore it is found in but few places in sufficient

quantities and purity to be profitably worked. The terms of Mr. Walker's report apply to India and many other places where plumbago exists over wide areas. In North America it is found in the older rocks of the Appalachian chain, from Alabama to Canada. Its occurrence is said to have been reported in great purity, and in veins from 18 inches to 5 feet thick, in five different localities. If such graphite were abundant, with fairly cheap labour and good means of communication, Ceylon might tremble for her supremacy in this branch of commerce; but we find it added, that of the Eastern deposits those of Pennsylvania, New Jersey, New York, and Canada are of the crystalline or foliated variety, are the best known, and are the only ones which are at present being worked. The amorphous plumbagos found in the Southern States are said to be of such a nature that purification is economically impossible. They can be used only in the crude state, and but for few purposes. The attention being paid to the mineral in America may be judged from the fact that samples had been received and reported on by The Joseph Dixon Crucible Company from no fewer than 33 localities between October, 1877, and January, 1882. Mr. Walker's notice of the "Origin and Characteristics" of the United States graphites, I append as a note.*

Under the heading "Productive Localities" Mr. Walker states :—

"The only place in the United States where graphite is now mined successfully is at Ticonderoga, New York. This property, owned originally by the American Graphite Company, now belongs to The Joseph Dixon Crucible Company, of Jersey City,

* "*Origin and Characteristics.*—Graphite is now generally conceded to be of organic origin—the result of the metamorphism of some of the products of destructive distillation of vegetable tissue. It occurs in veins, beds, and disseminated through strata (graphitic schists). The veins occur principally in New York, Canada, and the Far West. They are true fissures in gneissoid rock. The vein graphite is usually associated with calcite and quartz. Pyroxene, mica, and apatite are sometimes found with it. Crystals of calcite are found, which on being split show scales of foliated graphite along the planes of cleavage. Graphitic schists are found in the same regions as the

New Jersey. The American Graphite Company worked the vein deposits to a depth of 600 feet. The Dixon Company now mine a graphitic schist 15 feet thick, carrying from 8 to 15 per cent. of graphite, practically an inexhaustible supply."

And as to "Ore-dressing":—

"The process used by The Dixon Company at Ticonderoga owes its success to careful supervision. It is a wet process in which the ordinary practice is reversed, the "tails" being the useful product, while the "heads" are thrown away. All attempts at dry concentration have failed."

The production in 1882 was, as already stated, 425,000 lb., of which the output of the Ticonderoga mine was 400,000 lb., all others giving only 25,000 lb., better than which they were not expected to do in 1883, while The Joseph Dixon Company had laid themselves out to produce 500,000 lb.; altogether 525,000 lb., valued at 8 cents per lb. Let us say 18 cents of our rupee currency, and we get the high value (founded on cost as well as quality?) of Rs. 20 per cwt., or Rs. 400 per ton. The local production, however, was certainly not much to place against 16,000,000 of pounds imported from Ceylon in 1882, with considerable quantities in the two following years.

The following as to kinds of graphite and their characters is interesting:—

"*Kinds.*—On account of the peculiar advertising it has had, graphite is commercially known as German black lead, Ceylon plumbago, and American graphite. German black lead is a product of Bavaria. It is of the amorphous variety, and is dressed chiefly by washing. Its price depends on its percentage of graphite and the nature of its impurities, varying from \$1 to

veins, and also in New Jersey and Pennsylvania. These are metamorphosed sand-stones with foliated graphite very evenly disseminated throughout in small flakes. The graphite found in beds is amorphous, and occurs principally in the south. It is in a sedimentary formation, is quite impure, and on account of its fineness cannot be successfully purified. Geologically, graphite occurs from the coal measures back to the oldest rocks. (See article by Professor Frazer, Transactions American Institute of Mining Engineers, Vol. IX., page 732; also Prof. J. S. Newberry's pamphlet on "The Origin and Relations of the Carbon Mineral," Annual Report, New York Academy of Sciences, Vol. II., No. 9, 1882.)

\$10 per hundredweight in cargo lots. It is used in the manufacture of pencils, stove polish, and foundry facings. Ceylon plumbago is mined at Travancore, Ceylon, and is shipped from Colombo to all parts of the world. It occurs in immense veins of great purity: cobbing and sizing are the only preliminary operations it undergoes. It appears in the market graded according to size, as large lump, small lump, chip, and dust. Its price varies from \$2 for dust to \$10 per hundredweight for prime lump in cargo lots. It is used for all the purposes of the trade, except the manufacture of pencil leads. American graphite, from the nature of its occurrence, appears in the market only in the dressed condition. Its price ranges from \$2 to \$10 per hundredweight wholesale, according to purity and fineness. Fineness exercises considerable influence on the price of graphite on account of the difficulty of pulverizing it. American graphite is used for all purposes of the trade, and excels all kinds as a lubricant. It is the same geologically, &c., as the Canadian. Before the development of the American and Canadian mines the Ceylon mineral was the standard."

I cannot help the contradictory accounts as to the relative fitness of German and Ceylon plumbago for pencils, but must simply adhere to my belief that the finer Ceylon ore is largely used for pencils. Mr. Walker evidently writes under the impression that Travancore is that portion of Ceylon in which the plumbago is found which is exported from Colombo, the fact being, I believe, that not a pound of Travancore graphite is exported. The latest Travancore Administration Report, indeed, does not even mention plumbago as a product of the country. "Cobbing" seems to mean beating with a flat board, but has probably the extended meaning of breaking with hammers, &c. The preliminary operations are, except in the case of pure lumps, much more complicated than is indicated in the extract, involving hammering, cutting, picking, sifting, washing, &c., one of the tools employed in the Colombo yards being a combined hammer and axe. It will be seen that while Ceylon and American graphite are valued equally at \$2 to \$10 per cwt. (Rs. 4.33 to nearly Rs. 22) the German mineral has a minimum so low as \$1, a price which could scarcely pay freight and charges. Comparative analyses of the Ceylon and Canadian varieties of graphite are given, which,

as of permanent value, will be found as a note to this paper.*

The figures are said, truly, to prove the often-repeated claim of the dealers in Canadian and American graphite that it is equal to the best Ceylon. The claim, pre-supposing that the samples were fairly chosen, must be fully conceded, for while the highest percentage of carbon in the Ceylon specimens analyzed is 99.792 per cent., the best Canadian is actually up to 99.815. The Ceylon mineral seems to have had a few fractions more of volatile matter. Both are almost absolutely pure, and did the Canadian and United States mineral occur in such a form in the enclosing rocks that it could be cheaply mined and prepared, there would of course be an end of the export of Ceylon plumbago to America. But if, in America, plumbago, however pure, is only distributed in the proportion of 8 to 15 per cent. mineral to 92 to 85 rock, those connected with the Ceylon enterprise need not, it would seem, concern themselves greatly with the competition in America of indigenous ore with that from our island. In view of analyses which give results so near 100 per cent. of carbon, we may well be amazed at the fact that the specific article on "Plumbago" in the new edition of the *Encyclopædia Britannica* should characterize graphite

* ANALYSES of Canadian and Ceylon Graphites.

LOCALITY.	Specific Gravity.	Volatile Matter.	Carbon.	Ash.
Canada, Buckingham; vein graphite; variety, foliated	2.2689	per cent. 0.178	per cent. 99.675	per cent. 0.147
Canada, Buckingham; vein graphite; variety, columnar	2.2679	0.594	97.626	1.780
Canada, Grenville; vein graphite; variety, foliated	2.2714	0.109	99.815	0.070
Canada, Grenville; vein graphite; variety, columnar	2.2659	0.108	99.757	0.135
Ceylon; vein graphite; variety, columnar	2.2671	0.158	99.792	0.050
Ceylon; vein graphite; variety, foliated	2.2664	0.108	99.679	0.213
Ceylon; vein graphite; variety, columnar	2.2546	0.900	98.817	0.283
Ceylon; vein graphite; variety, foliated	2.2484	0.301	99.284	0.415

as an "impure carbon." It is, on the contrary, the purest form of carbon in nature, with the one exception of the diamond, as indeed is explicitly asserted in other portions of the *Encyclopædia*.

Under the heading "Manufactures" there is interesting summarized information, which I quote :—

Proportionate Amounts of Graphite used for different purposes.

Manufactures.	Kinds of Graphite used.	Per cent.
Crucible and refractory articles, as stoppers and nozzles, crucibles, etc.	Ceylon, American...	35
Stove polish	Ceylon, American, German ...	32
Lubricating graphite	American, Ceylon...	10
Foundry facings, etc.	Ceylon, American, German ...	8
Graphite greases	American ...	6
Pencil leads	American and German ...	3
Graphite packing	Ceylon, American...	3
Polishing shot and powder	Ceylon, American...	2
Paint	American ...	$\frac{1}{2}$
Electrotyping... ..	American, Ceylon...	$\frac{1}{4}$
Miscellaneous :—piano action, photographers', gilders' and hatters' use, electrical supplies, etc.	—	$\frac{1}{4}$
		100

A table like this will give many of the readers of this paper a new view of the multifarious uses of the mineral carbon called plumbago. It will be observed that, next to the manufacture of crucible articles, the great use of the mineral is for polishing and preserving from rust the ranges of stoves and other cooking appliances, which contribute so much to the neatness, cleanliness, health, and comfort of modern abodes. The proportion used for this purpose in Europe—in Britain at least—cannot certainly be below that given for the United States. There are graphite greases as contradistinguished from lubricants, and the mineral seems to be used for the packing of engines. From the largest forges where tons of steel are manufactured in Pittsburg, down to the studio of the photographer and the shops of the gilder and hatter, plumbago is of valuable use. And not only is it

called into requisition to produce the highest order of steel guns and steel armour for war-ships, but it is good for polishing the sportsman's powder and shot. Gunpowder used for blasting operations is also greatly improved by receiving a glaze or varnish of graphite, the philosophy of the operation being that thus the grains are prevented from absorbing the moisture which exists in mines and quarries.

Graphite enables the electrotyper to prepare and present to the world, cheaply and at will, casts of coins, woodcuts, copperplate maps, &c., equal in the most minute and intricate detail to the most highly prized and costly originals. But next to the boon which the real discovery of anthracite or natural coke in Ceylon would be, is the certainty, of which we are assured, that in our teeming supplies of plumbago the tea planters of Ceylon can get a paint for their stores, equal in its fire-resisting properties to asbestos paint. If this should prove to be correct, and we see no reason to doubt the statement, the prospect is that Ceylon will be speedily exporting, instead of importing, fireproof paint. Mr. Walker may well say in conclusion :—

“The growth of the graphite industry has kept pace with the age, each new development in metallurgy and engineering offering some new field of usefulness for graphite. For instance, it furnishes the pots for the manufacture of cast steel, and the nozzles and stoppers used in the Bessemer process. It is used in the manufacture of electrical supplies, &c. Fifty years ago graphite was little known and mis-named. Now it is of constantly increasing importance. From an insignificant beginning in the present century the industry has grown to its present proportions.”

A list is then given of twenty-five American firms engaged in the plumbago industry, of which The Joseph Dixon Company of Jersey City, New Jersey, takes the lead, employing 500 hands in the manufacture of everything for which graphite is used. The same number of hands finds employment from the Eagle Pencil Company; while A. W. Faber, probably an immigrant or descendant of an immigrant from Nuremburg, employs 150 persons in his pencil factory. Others employ lesser numbers, six firms giving crucibles as their exclusive manufacture; three, lead pencils; four, foundry facings and lubricants; seven, stove polish and lubricants. It will thus be seen that except in the

branch of pencil-making, and perhaps electrotyping, the New World has gone, or is rapidly going, in advance of the old in the plumbago industry, which means corresponding advance in the steel industry. It is surely a striking incident in the romance of commerce that this ancient eastern isle of "Serendib," the scene of the mythical adventures of Sinbad the Sailor, should be the main source of supply of an article so useful in the industries and elegancies of life, the appliances of peace and war, and the pursuits of the artist and literary man, not only to countries in the Eastern hemisphere, but to the regions of the Far Western world.

Having noticed the leading establishments in Europe and America, where our Asiatic ore is so largely utilized, let us now turn to one of the compounds, or yards, with its brick and tar "barbecue" or platform, and surrounding sheds, in which Singhalese men, women, and boys prepare, assort, and pack the mineral when received in Colombo from pits, none of which are nearer than thirty miles, and some of which are so distant as the District of Hambantota at the eastern extremity of the Southern Province. The chief exhibitor of plumbago at the Melbourne Exhibition of 1880-81 was Mr. W. A. Fernando, of No. 1, Brownrigg-street, Cinnamon Gardens, Colombo, and a description of his establishment, which the editors of the *Ceylon Observer* gave in their paper of August 12th, 1880, is, in all substantial details, correct in August, 1885. Mr. Fernando's exhibits at Melbourne were illustrated by a set of photographs; which, having been presented by the writer to Mr. Charles Moore, of the Sydney Botanic Gardens, unfortunately perished in the fire which destroyed the Exhibition building at Sydney. The photographs were thus described:—

"Photographs Nos. 1 and 3 (counting from the left-hand corner) show an enormous block of plumbago weighing originally 4 cwt. (one-fifth of a ton), and the dimensions of which, when photographed, were as follows:—2 feet in height, $2\frac{1}{2}$ feet in breadth, 6 feet in circumference horizontally, 4 feet 10 inches vertically.

"The block, with other large and small specimens of the mineral, is placed on the platform (barbecue, or asphalted floor) on which pieces of plumbago (after being washed in water, so as

to remove earth and other foreign substances) are spread out to dry. In the background is seen the cadjan (cocoanut leaf) covered shed, in which Sinhalese (and a few Tamil) male and female labourers are employed, breaking up pieces of plumbago, removing hard pieces and bits of rock, and assorting. In this process small axes are used, which will be seen in the hands of coolies represented in the group No. 2.

"No. 4 shows one of the native bullock carts in which plumbago is conveyed to and from the stores, and No. 5 represents the casks into which—according to the classes into which it is carefully separated—the mineral is packed for export.

"No. 6 represents the owner of the establishment and his trusted overseers.

"Mr. Fernando's Plumbago Exhibits include :—

One case large lump plumbago.

One barrel ordinary lump do.

Do. chips do.

Do. dust do.

"Mr. Fernando also exhibits a Ceylon elephant, cut out of plumbago, and polished."

I have no doubt that photographic or other illustrations of the now important plumbago industry of Ceylon will accompany specimens of the mineral or objects, such as figures of elephants and other animals carved out of its substance, to the forthcoming Great Exhibition of the products and manufactures of the Colonies of Britain and her Indian Empire. Elephants and other figures are usually sculptured from blocks of the softest, and therefore the most valuable form of plumbago, and in proportion to the softness of the material, the sculptured objects are specially liable to breakage. I would suggest that blocks be chosen for sculpture purposes, of the variety of plumbago which in commerce is ranked second class, not because it is not pure in quality, but because in mechanical condition it vies in hardness with the rocky quartz for which the mineral has such a striking affinity. The account of Mr. Fernando's establishment to which I have alluded is as follows :—

"A visit we paid the other morning to the plumbago store of Mr. W. A. Fernando at No. 1, Brownrigg-street, Cinnamon Gardens, has given us a new and enlarged view of the ramifications of the Plumbago Industry of Ceylon. We were, of course, familiar with the rise and progress of our export trade in this the

only mineral of any importance of which Ceylon can boast. * * * But although it was quite evident that the digging and mining which brought so large a quantity of plumbago to light, as well as the carting, preparation, and picking, must give employment to a great number of people, we had no idea before the inspection of Mr. Fernando's store of the very considerable influence which the industry now has on the welfare of many thousands of the population in the Western, the North-Western, and Southern Provinces. The favourite mining districts are at present in the neighbourhood of Kurunégala, Avisawélla, Ratnapura, and Kalutara, and in the Pasdun Kóralé. Mr. Fernando, a most intelligent enterprising Christian Singhalese of Moratuwa, whose father and family have for many years been connected with 'plumbago,' was unable to tell us that the seekers after plumbago were guided by any better indication than the appearance of the surface soil, or of pieces of the mineral cropping up through fissures in the rock. Here is just the case where a Government Geologist might afford valuable aid in developing an important industry. Mr. A. C. Dixon, if employed by Government during the Academy vacations, might be able to point with much confidence to undeveloped Crown lands likely to prove of great value for their beds of plumbago, and his advice to private proprietors might also save much time and money in trial pits, surface digging, and general exploration. Plumbago mines have been sunk in Ceylon several hundred feet in depth, and some are worked with all the appliances of an English mine, but, as a rule, the plumbago is found near the surface. It is difficult to say how many men are engaged in digging plumbago, but taking half-a-ton for each man per month in a favourable field as a high average, and making allowance for the wet seasons, holidays, &c., we may feel sure that no less than from 4,000 to 5,000 men were required to provide the quantity shipped last year. The carting to Colombo must have given employment to a good many others, perhaps more or less to 500 carters, carts, and pairs of bullocks. But it is the elaborate preparation now observed in the Colombo stores which has taken us by surprise. Plumbago is now picked and sized, we may say, as carefully as coffee. The various processes are seen to perfection at Mr. W. A. Fernando's store. He gives employment to from 120 to 150 men and women,* paying

* Singhalese women have only lately been induced to work as plumbago pickers; their manual dexterity gives them an advantage over men, but Mr. Fernando had trouble in overcoming a strange prejudice they had to plumbago, as poison or worse for them to touch with their fingers! Now they like the work and come to it readily.

from 50 to 75 cents per diem to the former, and 25 to 30 cents to the women. His stores and picking houses are all cadjan-roofed (that is, roofed with cocoanut leaves), for the very good, but to us novel and strange, reason that the tiles would inevitably fall off any roof under which plumbago was stored or prepared. The dust blown about makes everything so polished and slippery, even the roof rafters and reepers, that tiles constantly slip off and therefore the only safety lies in cadjans ! The first process, is to wash the plumbago in large baskets, the smaller pieces and dust being afterwards spread on an asphalte barbecue to dry. By this means the quality is easily discovered by the practised eyes of the pickers, who separate (in much the same way as coffee) pieces affected by iron ore, pyrites, quartz, or other foreign material, a small piece of which passing into a consignment to the Battersea Crucible Works might ruin the whole lot. Some of the pickers are furnished with iron hammers to break up suspicious-looking pieces of the plumbago, and others again are employed in brushing the dust off good lumps, and polishing the same with cocoanut husks. There are punched sheet-iron sizers with holes of different dimensions (Nos. 1 to 4), and accordingly large lump, small pieces, chips, and dust plumbago are now-a-days carefully separated. It takes about 100 expert men and women to prepare two or three tons in a day ; consequently this branch of trade must give employment to several thousands of people for the greater part of the year. The cask-making and packing afford further occupation, each barrel holding about 5 cwt., so that some 35,000 casks all made of *hora* staves (generally deemed a useless timber) were required for last year's shipments. The plumbago is also carried from the mines to Colombo in barrels, which, however, are sent back in shooks and so used repeatedly. Three men are supposed to make 8 or 10 barrels a day. Altogether, therefore, it will be seen that the Ceylon plumbago industry is a very important one to our Singhalese neighbours.

“Mr. W. A. Fernando, whose model store is well worthy of inspection, sells to the European mercantile houses as much as from 1,200 to 1,800 tons per annum. In olden days he used to ship on his own account, and he has received prices as high as £32 and £48 per ton for lump plumbago, which is now only worth £15. His Brownrigg-street store should be visited during the present busy season by all who wish to get some idea of the importance of the PLUMBAGO INDUSTRY OF CEYLON.”

We now feel confident that the number to which the

pursuit gives employment was much under-estimated in 1880, and that, considering that 5,000 persons were said to be engaged in mining in one year in a single district of the North-Western Province, our higher estimate of an average of 20,000 men, women, and children at present engaged in the various operations of mining, carrying, preparing, packing, and shipping Ceylon plumbago, is not beyond the truth.

It is curious that the Sinhalese women should entertain a prejudice against plumbago as poison, seeing that it is included in the native pharmacopœia. We should have expected members of what Artemus Ward called "the female sect" to have been more troubled about the soiling of their persons and clothes by contact with the mineral, but in truth a coating of the shining ore, while easily got rid of by the use of water, produces no such hideous effect as that so familiar to us now in Colombo of the truly uncanny-looking coaling coolies, when proceeding to their houses after loading or unloading the bunkers of one of the multitude of magnificent steamers which now resort to our harbour. A polish of person, if not of deportment and manners, is the result of working amongst even the dust of plumbago, and it is curious to see the dark-skinned coolies of the plumbago stores walking about with their bodies shining as if they were electrotype statues vivified.

In its further metamorphic progress from vegetable to mineral, the form of carbon we call plumbago has certainly taken a great step in advance of the carbon we call coal, in getting rid of smoke entirely, and also of dirt. Coal, however, cannot be accused, as plumbago justly is, with causing a whole roof-covering of tiles suddenly to fall off, from the slipperiness created by wind-blown particles of the greasy mineral. We were greatly amused by Mr. Fernando's statement at the time, but others, Europeans included, who have to do with the preparation of plumbago, have fully confirmed his representation as to the incompatibility of plumbago dust and tiled roofs. In this connection we would advise visitors to plumbago compounds to be careful how they bear themselves in such slippery places. A sudden step on to the polished platform may end in an undignified tumble. And this reminds me of the sensation produced many years ago in Mincing Lane by the peculiar appearance of some

Ceylon coffee which had been dried on a barbecue where plumbago had been previously spread. An attempt to impart a factitious colouring to the beans was suspected until the requisite explanation was afforded.

As this paper may be read beyond the limits of Ceylon, it may be as well to explain that *cadjan* is a word, curiously enough of Malay origin, applied in Ceylon to plaited branches of cocoanut palms, used for roofing houses, sheds, carts, &c. *Compound* is a yard or enclosure, and *barbecue* is a platform.

I have already shown, what I may be allowed to repeat, that for the average shipments of 12,000 tons per annum of plumbago from Ceylon for the past five seasons, the yearly supply of casks must have been 45,000, and that the manufacture of these alone must have given welcome and remunerative employment to carpenters out of work by reason of the partial collapse of the staple colonial industry: this apart from the large numbers of persons (estimated above at 20,000) engaged in mining, carting, preparing, packing, and shipping the mineral.

Let us, therefore, hope that the plumbago industry of Ceylon may continue to prosper and extend, not as the result of wars or rumours of wars, but because of the steady and beneficial progress of the peaceful industries and arts which contribute to the elevation of humanity in all that constitutes comfort, happiness, and means to cultivate the loftier instincts and destinies of our race.

Appendix No. 1.

Letter from Mr. W. P. Ranasinghe.

In the Sinhalese work called “Yōga Ratnākara” (‘the ocean of the gem-like prescriptions’) I find the mode of purifying plumbago for medicinal purposes given at chapter XLIV. In the same chapter is found a mode of reducing mica or talc to ashes for the like purpose. The process of purifying is thus stated:—“Break the plumbago into small pieces, put it into a pot, pour over it the milk-like exudation of the *daluk* tree (*Euphorbia*

[For continuation see page 242.]

Appendix No. 2.—Statement showing the Quantity and Value of Plumbago exported from Ceylon for the Fifty-one Years from 1834 to 1884, with the Revenue derived from the Mineral in the shape of Royalty, Customs Duty, License Fees, &c.

[NOTE.—Pounds in the years anterior to the introduction of the Rupee currency have been converted into Rupees at the rate of Rs. 10 to £1.]

Year.	Quantity exported.			Value.		Customs Duty.		Royalty.		License Fees, &c.		Total Revenue.		Remarks.
	Cwt.	qr.	lb.	Rs.	cts.	Rs.	cts.	Rs.	cts.	Rs.	cts.	Rs.	cts.	
1834 ...	2,582	2	14	12,054	0	Free		—		—		—		Customs Duty at 2½ per cent. ad valorem.
1835 ...	4,952	3	0	11,082	50	"		—		—		—		
1836 ...	12,644	0	5	14,663	50	"		—		—		—		
1837 ...	3,700	0	0	4,293	0	107	33	—		—		107	33	
1838 ...	1,164	1	12	1,379	0	34	44	—		—		34	44	
1839 ...	423	1	18	490	0	12	25	—		—		12	25	
1840 ...	981	0	0	1,225	0	30	66	—		—		30	66	
1841 ...	2,002	2	7	2,684	50	67	62	—		—		67	62	
1842 ...	7,285	0	3	12,317	0	308	0	—		—		308	0	
1843 ...	8,677	3	20	5,238	50	131	0	—		—		131	0	
1844 ...	9,914	3	21	12,946	0	323	66	—		—		323	66	Free by Ordinance No. 9 of 1847.
1845 ...	19,245	0	15	24,519	50	613	0	—		—		613	0	
1846 ...	25,036	3	7	30,361	0	759	0	—		—		759	0	
1847 ...	9,248	3	11	10,583	50	Free		—		—		—		
1848 ...	6,787	0	0	7,062	0	"		—		—		—		
1849 ...	3,329	2	20	3,302	0	"		—		—		—		
1850 ...	23,021	1	6	38,380	0	"		53	0	—		53	0	
1851 ...	23,865	1	2	52,554	0	"		229	0	—		229	0	
1852 ...	13,110	1	21	26,281	0	"		406	0	—		406	0	
1853 ...	19,577	2	25	40,572	0	"		533	0	—		533	0	
1854 ...	17,451	2	19	39,162	0	"		103	0	—		103	0	
1855 ...	6,129	3	16	11,448	50	"		11	0	—		11	0	
1856 ...	13,380	2	27	33,380	0	"		438	0	—		438	0	
1857 ...	33,497	0	4	33,650	0	"		894	0	—		894	0	

	19,432	3	12	33,841	50	571	0	219	0	1,190	0	Customs Duty at 2½ per cent. ad valorem.
1858	19,432	3	12	33,841	50	571	0	219	0	1,190	0	
1859	17,610	3	11	41,138	0	1,029	0	374	0	1,403	0	
1860	75,660	0	23	239,335	50	5,990	60	3,190	0	9,180	50	
1861	38,345	1	23	110,643	50	2,767	0	3,836	0	6,603	0	
1862	40,895	3	13	130,789	50	3,271	0	5,843	0	9,114	0	
1863	65,128	0	3	281,246	0	7,032	0	15,549	0	22,581	0	
1864	84,028	2	4	404,314	50	10,109	50	11,999	0	22,108	50	
1865	40,143	3	6	151,206	0	3,775	83	2,289	0	6,064	83	
1866	56,278	3	14	218,005	50	5,473	87	4,200	0	9,673	87	
1867	45,836	0	14	193,001	0	4,842	0	3,187	0	8,029	0	
1868	141,085	0	14	720,410	50	18,013	0	13,026	0	31,039	0	
1869	226,131	3	8	889,620	0	22,240	50	16,118	0	38,358	50	
1870	85,248	3	18	345,622	0	Free		6,796	0	6,796	0	
1871	125,257	1	5	620,953	50	"		9,948	0	15,659	0	
1872	136,051	2	23	488,866	64	"		15,659	0	15,659	0	
1873	173,996	0	17	1,479,395	44	"		* 45,660	0	45,660	0	
1874	149,938	1	3	1,440,166	87	† 47,209	94	—	0	54,722	94	Licenses to dig for plumbago, Rs. 10 each, with 10 per cent. of value of plumbago dug in the case of the Western Pro- vince.
1875	110,023	1	0	1,100,232	63	55,011	79	—	0	62,180	79	
1876	117,361	1	2	1,173,612	64	58,680	55	—	0	59,375	55	
1877	96,792	1	21	967,924	37	† 48,396	32	—	0	48,636	32	
1878	84,634	3	15	846,348	84	21,546	81	—	0	21,757	81	
1879	162,495	2	24	1,624,957	15	40,624	15	—	0	42,410	15	
1880	205,798	2	9	2,057,385	81	51,434	94	—	0	52,664	94	
1881	259,909	0	16	2,599,091	42	65,028	4	—	0	66,670	4	
1882	260,166	1	6	2,601,663	3	65,042	3	—	0	67,627	3	
1883	262,773	3	1	2,627,737	58	65,693	94	—	0	70,420	94	
1884	182,425	3	10	1,824,258	40	45,606	82	—	0	46,660	82	
	3,626,211	0	27	25,742,446	22					841,389	49	

The value of some confiscated mineral included.

confiscated mineral included.
 † Royalty of Rs. 5 per ton, or 25 cents per cwt., from 21st December.
 ‡ Royalty of Rs. 10 per ton, from 1st April.

† Royalty of Rs. 5 per ton, or 25 cents per cwt., from 21st December.

antiquorum) and boil it three days in a low fire such as is used for boiling rice; take it out and wash it. "It is now purified." It is, I understand, used by the Siphalese medical men as a tonic. Siphalese medical science is derived from the ancient Aryan works of Northern India, and latterly to some extent from Southern India. I have not with me any very old medical work of the Siphalese.

I am very much puzzled about the date of the book I refer to.

At the commencement of the work the author says it was begun in the month of Wesak (May to June) in the sixteenth year of King Bnwanéka Báhu. Now there were, it appears, seven kings who bore that name.

The last king of that name flourished in A.D. 1557, and reigned according to Turnour only eight years. I do not find his name mentioned in the Siphalese translation of the Mahawamsa. The sixth of that name ascended the throne in A.D. 1464, and reigned only eight years. These two kings not having reigned sixteen or more years each, the work could not be attributed to their times. The fifth of that name, beginning from A.D. 1378, appears to have reigned twenty years. The fourth reigned only fourteen years. The time the second and third reigned is not stated. The first reigned only eleven years.

So that the book must have been composed either in the reigns of the second, third, or the fifth kings of that name. Taking the latest as the safest, it must have been composed in the reign of Buwanéka Báhu V., who reigned from 1378 to 1398 A.D. The tradition, according to the editor's preface, is that the king in whose time the work was composed reigned at Jayawardana Pura, or Kótté. Mr. Turnour says that Bnwanéka Báhu the 5th reigned at (Gangásiripura) Gampola. This is a mistake; for the Mahawansa (chap. 91) distinctly says that Bnwanéka Báhu V. built Jayawardana Pura, south of Kelani Pura.

If the tradition is correct, there could be no doubt that the work was commenced in the reign of this king, because I find that the second and third kings of that name reigned at Kurunégala, and not at Kótté.

The sixteenth year of the reign of Buwanéka Báhu V. would be A.D. 1394, and the work I referred to must have been commenced 491 years ago.

The word මිනිරන් [*miniran*] is also used for talc or mica, but the book in one place qualifies it by saying කළුමිනිරන් [*kalu miniran*], 'the black *miniran*,' which is no doubt the plumbago of commerce.

Appendix No. 3.

Revenue derived from Royalty on Plumbago dug on Crown Lands, including Payments for Licenses to dig for Plumbago, from 1850 (when Royalty was first levied) to 1884.

	Western Province.		Southern Province.		Total.
		Ra.		Ra.	Ra.
1850	...	53	...	—	53
1851	...	229	...	—	229
1852	...	406	...	—	406
1853	...	533	...	—	533
1854	...	103	...	—	103
1855	...	11	...	—	11
1856	...	399	...	39	438
1857	...	859	...	35	894
1858	...	219	...	—	219
1859	...	341	...	33	374
1860	...	3,045	...	145	3,190
1861	...	3,464	...	372	3,836
1862	...	4,722	...	1,121	5,843
1863	...	12,725	...	2,824	15,549
1864	...	10,768	...	1,231	11,999
1865	...	2,025	...	264	2,289
1866	...	3,682	...	518	4,200
1867	...	2,839	...	348	3,187
1868	...	10,398	...	2,628	13,026
1869	...	14,493	...	1,625	16,118
1870	...	6,001	...	795	6,796
1871	...	9,086	...	862	9,948
1872	...	14,537	...	1,122	15,659
1873	...	40,371	...	5,289	45,660
1874*	...	5,588	...	1,925	7,513
1875	...	6,939	...	230	7,169
1876	...	475	...	220	695
1877	...	—	...	140	140

* From April of this year the royalty was collected at the Customs at the rate of Rs. 10 per ton—a rate which was reduced to Rs. 5 in December, 1877. Of the royalty collected at the Customs from April, 1874, this table takes no account, but only of sums collected at the Kachcheries. For the revenue under every form see the comprehensive and detailed return constituting Appendix No. 2. The great disparity between the figures for the Western and Southern Provinces, from 1881 onwards, seems to be due to the fact that, while in the Western Province 10 per cent, of the plumbago mined is taken as "rent" in

	Western Province.		Southern Province.		Total.
	Rs.		Rs.		Rs.
1878	...	81	...	130	211
1879	...	956	...	800	1,786
1880	...	—	...	1,130	1,130
1881	...	1,172	...	470	1,642
1882	...	1,995	...	590	2,585
1883	...	3,987	...	740	4,727
1884	...	954	...	100	1,054

It would appear that the royalty collected at the Galle Custom-house in the past five years has been :—1880, Rs. 5,962 ; 1881, Rs. 3,972 ; 1882, Rs. 3,228 ; 1883, Rs. 4,798 ; and 1884, Rs. 3,764. The licenses issued in the Southern Province seem to have been :—1880, 113 ; 1881, 47 ; 1882, 59 ; 1883, 74 ; and 1884 only 10,—the latter a significant sign of the depression of the industry.

A return of licenses issued in the Western Province for the four years ending 1884 enables us to appreciate the preponderance of the Kalntara district as a plumbago-yielding territory over the other districts of the Province. The licenses taken out in this district for each of the past four years were, respectively, 35, 94, 102, and 25. Colombo shows 10, 13, 5, and 1 ; Negombo 2, 23, 10, and 2 ; Ratnapura 7, 7, 5, and 1 ; Kégalla shows very poorly, proving that the vast bulk of the mineral which came on the railway at Polgahawela was from the Kurunégala District. In 1891 none were reported as issued in the Kégalla District ; 1882 and 1883 gave only 2 each, and 1884 only one. For the whole Province the figures were :—

	Licenses.
1881	... 54
1882	... 139
1883	... 124
1884	... 30

All the figures within our reach seem to show that in the past

addition to proceeds of licenses to dig at Rs. 10 each, no rent is collected in the Southern Province, but simply the Rs. 10 license fees.

N.B.—That some small sum ought to be added to plumbago revenue, which is at present credited to stamps ; for Mr. Saunders, Government Agent, Western Province, states that “the license fee of Rs. 10 is collected and brought to account in different ways at the different Kachcheries. In some cases cash is taken and credited to Land Revenue under the head ‘Licenses to dig Plumbago ;’ in other cases a stamp of Rs. 10 is fixed to the bond, and then of course the revenue gains that amount under the head ‘Stamps.’”

five years of large export, the Kurunégala district of the North-Western Province and the Kalutara district of the Western have supplied probably three-fourths of the whole plumbago recorded in the Customs returns.

Appendix No. 4.

SESSIONAL PAPER XIX. OF 1873.

Return of the Number of Plumbago Pits.

	Crown Land, on license.	Private Land.	Land specially exempted.
Western Province	... 762	... 280a	... 38
North-Western Province	... —	{ 18b 54c }	... 10
Southern Province	... 419d	... 187e	... 11f
	<u>1,181</u>	<u>539</u>	<u>59</u>

- (a) The claims to exemption of royalty of many of these lands are under consideration.
- (b) Land purchased from Government and subject to the payment of royalty.
- (c) Private lands so far as is known.
- (d) 108 mines now in operation.
311 mines abandoned for the reason of their contents having been exhausted, or not worth the expense of incurring.
- (e) 51 mines now in operation.
136 mines abandoned for the reason of their contents having been exhausted, or not worth the expense of incurring.
- (f) 8 mines in operation.
3 mines abandoned for the reason of their contents having been exhausted, or not worth the expense of incurring.

Statement showing the Quantity of Plumbago exported during the last twenty years, during periods of five years ; and the Amount of Royalty received during each of such periods.

Years.	Quantity exported. Cwt.	Amount of Royalty received. Rs.
1853 to 1857	... 87,011	... 2,080
1858 to 1862	... 191,845	... 13,464
1863 to 1867	... 291,415	... 37,227
1868 to 1872	... 713,785	... 61,611
	<u>Cwt. 1,284,056</u>	<u>Rs. 114,382</u>

Statement showing the Quantity of Plumbago exported and the Amount of Royalty received from 1868 to 1872.

Years.		Quantity exported. Cwt.		Amount of Royalty received. Rs.
1868	...	141,095	...	13,026
1869	...	226,132	...	16,119
1870	...	85,249	...	6,796
1871	...	125,257	...	9,949
1872	...	136,052	...	15,721
		<hr/> Cwt. 713,785		<hr/> Rs. 61,611

Appendix No. 5.

An Ordinance to provide for the collection of the sums due to the Crown on Plumbago.

No. 21 of 1873.

Preamble.

WHEREAS a certain sum in lieu of rent is now levied on all plumbago dug on Crown lands, and a royalty is due to the Crown on all plumbago dug on private lands, and the payment on these dues is largely evaded, and it is expedient to secure the same by collecting them as a royalty at the different ports of shipment: It is enacted by the Governor of Ceylon, with the advice and consent of the Legislative Council thereof, as follows:—

Dues on
plumbago.

1. There shall be raised, levied, and paid, as a royalty upon all plumbago of the produce of this Island exported beyond seas a duty of 50 cents per cwt.*

* The royalty of Rs. 10 per ton, or 50 cents per cwt., was levied from 1st April, 1874, but by the Ordinance No. 22 of 1877 the royalty on all plumbago exported was fixed at 25 cents per cwt., instead of 50 cents, from 21st December 1877.

Appendix No. 6.

Report on the following Petition for permission to dig for Plumbago on Crown Lands, referred by the Government Agent of the Western Province to the Mudaliyár of Héwágam Kóralé.

To whom addressed :—The Hon. the Government Agent, Western Province.

Name of Petitioner :—Merenge Don Sadris Senerat Appuhami, of Liyanwala.

Purport of Petition :—Praying for permission to dig for plumbago in an acre of Crown land called Wellendalanda, situated at Liyanwala in the Mēda Pattu of Héwágam Kóralé.

Date of Petition :—2nd June, 1885.

Report No. 464.

Name of Land :—Wellindalanda.

Bonndaries :—North by land purchased by Abraham Appuhami and Don Carolis Appuhami; south by a goraka tree and a kahāṭa tree; east by goraka tree and ant-hill; west by a date tree and kahāṭa tree.

Description of timber trees on the land :—No valuable trees.

How far from nearest forest? No forest.

Whether petitioner is a lessee of any other land or not? No.

His character and means? Bears a good character; he has no landed property in this district, but he says that he has in the Rayigam Kóralé.

Whether there is an abandoned pit on the land, and, if so, abandoned by whom? No.

Reference to any former reports made touching this land :—None.

(A printed application is enclosed for the survey of the land.)

J. M. E. PIERIS.

Ranalé, 8th June, 1885.

Appendix No. 7.*Form of Lease of Plumbago Land.*

THIS Indenture, made at Colombo on the 6th day of July in the year of Our Lord One thousand Eight hundred and Eighty-five, between the Hon. F. R. Saunders, Government Agent for the Western Province, acting for and on behalf of HER MAJESTY QUEEN VICTORIA, of the one part, and M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, and assigns, of the other part.

WHEREAS the said M. Don Sadris Senerat Appuhami, of Liyanwala, has contracted and agreed with the said Hon. F. R. Saunders, as such Government Agent as aforesaid, and acting as aforesaid for and on behalf of Her Majesty, for a Lease of the MINES hereafter described, and intended to be hereby demised for the term of one year from the date of these presents, at the yearly rent hereinafter specified, and payable as hereinafter is mentioned, and under and subject to the covenants and agreements hereinafter expressed and declared :

Now this Indenture witnesseth, that in consideration of the yearly rent hereinafter reserved, and the covenants and agreements hereinafter contained, on the part of the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, and assigns, to be respectively paid, observed, and performed, he, the said Hon. F. R. Saunders, as such Government Agent as aforesaid, and acting for and on behalf of her Majesty as aforesaid, hath granted, demised, and leased, and by these presents doth grant, demise, and lease, unto the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, and assigns, all and all manner of Mines, Beds, and Veins of Plumbago, and the Ore thereof, which have been or shall hereafter be discovered or opened under, within, or about all such lands and premises as belong to Her said Majesty, within the boundaries following, to wit :—

One acre of Crown Land called Wellindalanda, situated at Liyanwala in Meda Pattu of Héwágam Kóralé: on the north by land purchased by Abraham Appuhami and Don Cornalis Appuhami; on the south by a goraka tree and kahata tree; on the east by a goraka tree and ant-hill; on the west by a date tree and kahata; —with full and free liberty, power, and authority, to and for the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, and assigns, and their agents, servants, and workmen, with or without horses, waggons, carts, or other carriages, from time to time, and at all times hereafter, to enter into and upon the said lands and premises, or any of them or any part thereof, or to dig and sink such and so many pits and shafts as shall be proper for getting all such Plumbago or the Ore thereof, and to stack or deposit the said Plumbago or the Ore thereof, when raised, on the lands contiguous to such pits or shafts, until the same can be conveniently removed; and to erect any engine or engines for working or getting such Plumbago or the Ore thereof; and to make all necessary ditches and drains; and to use for foot-people, horses, waggons, and other carriages,

all necessary and convenient roads for carrying of the said Plumbago or the Ore thereof; and all other privileges which shall be necessary, requisite, and appertaining for or to the finding, discovering, raising or working, procuring or carrying away, the said Plumbago or the Ore thereof; and all the right, title, interest, property, claim, and demand whatsoever of Her said Majesty in, to, out of, or upon the said Mines, Beds, and Veins, hereby demised as aforesaid; and for the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, and assigns, to cut, take, and appropriate all such indigenous timber growing on the said lands, as may be necessary for any purpose connected with the opening and working of the said Mines, or preserving or removing the Ore or Plumbago which may be obtained therefrom, upon payment to the said Hon. F. R. Saunders, Government Agent, or his said successors, of so much money as he or they shall or may demand for the said timber.

To have and to hold the said Mines, Beds, Veins, and all and singular other the premises hereby demised or intended so to be, and every part thereof, with their and every of their appurtenances unto the said M. Don Sadris Senerat Appuhami, of Liyanwala, and his heirs, executors, administrators, and assigns, for and during the term of one year, to be computed from the day of the date of these presents, and from thenceforth ensuing, and fully to be complete and ended, yielding and paying in advance for the said term the sum of Ten Rupees and further one-tenth part of all Plumbago dug, or its value, unto the said Hon. F. R. Saunders, or his said successors in the said office of Government Agent for the Western Province.

And the said M. Don Sadris Senerat Appuhami, of Liyanwala, doth hereby covenant that he and his heirs, executors, administrators, and assigns, shall and will, within three months from the date hereof, open and work one or more Mines within the lands aforesaid; and in default of doing so the lease shall be forfeited.

And the said M. Don Sadris Senerat Appuhami, of Liyanwala, further agrees that he will not remove any of the Plumbago so dug from the dépôt where it is stored until it has been inspected and measured by the proper officer appointed by the Government Agent, and the correct value of the share due to Government has been correctly ascertained, and that he will at all times, upon being required, allow the said Hon. F. R. Saunders or his said successors, or his agent or servants, at all times to enter upon the

lands hereinbefore mentioned, and to reside thereon, and to inspect the Mines, Beds, or Veins that shall have been opened thereon, and to take an account of the produce thereof; and, if need be, to secure and remove all other metals or minerals, not being Plumbago, which shall be found in the said lands.

AND it is further agreed by and between the said parties hereto, that in case the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, or assigns, shall assign over or otherwise part with this Indenture, or the Mines, Beds, or Veins, or the rights or privileges hereby demised, or any part thereof, to any person whatsoever, without the consent of the said Hon. F. R. Saunders, Government Agent, or his successors, being first had and obtained in writing for such purpose, or if the said M. Don Sadris Senerat Appuhami, of Liyanwala, his heirs, executors, administrators, or assigns, or if they, their servants, or agents, shall in any manner act contrary to these presents or to the provisions of the Ordinance to provide for the collection of the sums due to the Crown on Plumbago, No. 21 of 1873; then, and in either of the said cases, it shall and may be lawful to and for the said Hon. F. R. Saunders, or his successors, for and on behalf of Her said Majesty or Her successors, into the Mines, Beds, Veins, hereby demised, and the said lands, or any part thereof in the name of the whole, wholly to re-enter, and the same to have again, retain, re-possess, and enjoy, and to confiscate all Plumbago excavated from the said lands by the said M. Don Sadris Senerat Appuhami, of Liyanwala, anything herein contained to the contrary notwithstanding.

IN WITNESS WHEREOF the said parties hereto have set their hands and seals, the day and year first above written.

Witnesses :

CHARLES FLANDERKA.

J. H. WITTEBRON.

The stamp is
here affixed.

F. R. SAUNDERS,
Government Agent.

The license holder will be allowed the option of redeeming the Crown share at the assessed value. If he declines, the Government share will be sold by public auction.


Witness :

CHARLES FLANDERKA.

H. L. CRAWFORD,
for Government Agent.

PLUMBAGO MINING.

Plan of an Underground Cutting.



[To face page 251.

Appendix No. 8.*Description of a Plumbago Mine, and the System of Excavation pursued in the Southern Province.*

[Translation from the Sinhalese, supplied by W. E. T. Sharpe, Esq., Govt. Agent.]

PLUMBAGO is excavated in two ways :—

- (i)—Sinking large pits [*minirāṇ patala keṭṭima*]; and
- (ii)—Cutting underground [*dónā keṭṭima*].

From large pits the ore is taken without much difficulty. An underground cutting is shown in the accompanying plan. The pit between the two straight lines shown by the figure marked is first dug. The breadth of it is from 4 to 8 cubits. The pits are not square, but oblong. If the underground cutting is to be dug straight, it cannot be dug deeper than 70 or 80 yards [210 to 240 feet, but Mr. Jacob De Mel's is 450 feet] owing to the difficulty of breathing for want of sufficient air deeper on. A lamp is kept in it.

Figure 2 shows the extension of an underground cutting ; this is generally $2\frac{1}{2}$ by 5 cubits. In some places they are large enough to allow a miner to walk erect, and they are generally 16 yards underground, and are cut to a length of 24 yards; at a depth of 60 yards, they are cut to a length of 8 yards. No. 4 is a deeper cutting, but as it cannot be extended at such a depth, a new shaft (No. 5) has to be sunk, and access to it availed of by No. 6. This pit is called the air pit, because it is purposely opened to admit of air. If any more diggings towards other directions in the pits marked 1 and 5 are required, it can be done in the same manner. The water, earth, and plumbago in these pits [*dónā*] are taken up through the first opened pit. If necessary, they could be taken on land [to the surface] from the air pit also. For the purpose of taking out earth, &c., there is a winch fastened on the surface. By tying a rope to the body of the winch, by hanging one or two tubs to the rope, and by winding the winch, the water, earth, and plumbago in the pit are taken out. A shed is put covering the pit for protection against sun and rain. After lining the inside with planks on the underground cutting to prevent land slips, very strong beams are fastened close to each other. As the digging progresses the planks are placed and beams fastened. Three or four workmen are necessary to descend to these underground cuttings. It is with small crowbars that the pits are dug. In the course of the digging, if rocks are found, they are blasted. The miners descend at 6 o'clock in the morning and

come up at the same hour next morning. They take their meals inside the pit. In some places, when they descend the pit at 6 in the morning, they ascend at 6 in the evening. When one batch comes out another goes in. The underground cuttings must be lighted both day and night. There must be on the top (on land) about five men to work the winch and to receive the earth, &c. By means of an air pump the pit can be penetrated further than the distance mentioned above.

Appendix No. 9.

The Precariousness and Difficulties of the Plumbago Mining Enterprize.

[The Galle "Gravets Mudaliyâr" having reported that although plumbago is found in various villages of the Akmimana Division, mining for the mineral is not remunerative, the following remarks were made, apparently by the Atapattu Mudaliyâr.]

"I BEG leave to state that there are signs of plumbago being in the land within the four gravets, besides in the villages enumerated by the Mudaliyâr, but the difficulty is to get to the regular vein. While there appears to be plumbago on the surface of the land, when a little deeper is dug there is nothing to be found; when sinking the pit somewhat deeper still, there appears again, and it is very deceptive."

"It is unsafe for a person to try on his own account the mining of plumbago, unless by chance the proper vein can be found. While in search of the vein the pit is sunk; within a few yards of the pit there may be the proper vein unknown to the persons employed. It is an expensive and unsafe speculation, as the baling out of water, which requires to be done both day and night, is very costly. Some pits have to be sunk between 30 and 50 feet deep. At Nidowa in Ratgama there is to be found good plumbago, but after much expense, if by some cause or other while there is much plumbago to be had, a day or two should fail to bale out the water, the whole pit is apt to be covered with the surrounding earth, and no one would attempt to renew the search in that pit. Thus the loss to the speculator is great, even if he should afterwards succeed in getting some."

Appendix No. 10.

Graphite, Mica, and Asbestos, and the absence of Fossils from the Metamorphic Rocks of Ceylon

are thus discussed by Dr. William King, of the Geological Survey of India, in reply to queries preferred by me when asked to write a Paper on Graphite :—

“Our knowledge of the organic origin of graphite is as yet little better than speculation..... I fancy graphite expresses a greater amount of metamorphism than anthracite..... We have one of the finest specimens, almost, in the world of museums in our museum at Calcutta, which my brother Ælian sent up. It is difficult to tell you why there are no fossils in your metamorphic rocks : there may have been very little life at the time of their formation and that of the lowest forms, and these may have been obliterated by metamorphism, or so altered that nothing but the result of their chemical decomposition now remains—e. g., this graphite. I do not think age would have anything to do with the obliteration of vegetable structure, if it ever existed ; metamorphism (which includes a tremendous lot of forces, chemical and otherwise) is quite sufficient..... I do not think there is any relation between graphite, mica, and asbestos—except in this way, that mica, being the common mineral in mica schist, and mica schist being an altered form of veinic shales, it is reasonable to suppose that seams of vegetable matter might have been associated with those shales. For instance, it is conceivable that shales with vegetable matter in layers will, by pressure and in time, become carbonaceous shales and coal : while intense metamorphism might bring about a further change into mica schist and graphite—graphite which exists in granite veins ; and mica in that case is the constituent of the granite, the graphite being an accidental mineral. Asbestos is a form of the magnesian rocks, so common in some gneiss regions ; it has nothing to do with the graphite.

“Very possibly the forms of vegetable life were more minute than those of coal : but they may have existed in immense numbers.”

Dr. King's opinion is of course decisive as to the absence of mineral affinity between the two substances which of all others best resist fire, and which common quality led me to put the question. But associated with our gneiss rocks are beds of that very magnesian limestone of which asbestos is stated by Dr. King to be a form. As regards mica, the Sinhalese describe graphite as its black form, “*Kalu-miniran*,” and one can scarcely wonder, for

not only is graphite lustrous like mica, but specimens occasionally occur which can be separated into plates, like lamellar mica, while very dark brown mica, when found associated with plumbago, simulates to some extent the lamellar forms of the latter mineral.

Appendix No. 11.

Minerals associated with Plumbago.

KNOWING that Mr. A. Murray, of the Public Works Department, had received a geological training, I referred some specimens of plumbago, quartz, and iron pyrites for his opinion, with the results shown in the following correspondence :—

Mr. Ferguson to Mr. Murray.

“I hope you won't think me troublesome, but in my paper on plumbago I wish to make no mistakes. Mr. Williams has kindly sent me some specimens from a mine on the road from the North-Western Province to Dambulla, mainly to show how plumbago is associated with quartz. The very best mineral and in largest quantities thus occur. Kindly look at No. 2 in the box sent herewith, and say if I am correct in describing it as crystalline quartz. Mr. Williams wrote of pieces of the quartz looking like Derbyshire spar, and I am sorry he did not send me a specimen separate from the plumbago, but this specimen will enable you to judge if the quartz is normal or any variety worth indicating.

“No. 1 includes a number of beautiful auriferous-looking bits of iron pyrites, which came in the box from Mr. Williams. You will notice that the golden iridescence shades off occasionally to faint green. Mr. Dixon attributed the green tint to the presence of copper, when reporting on a specimen sent by Mudaliyār Jayetilleke in 1880, when the gold fever was on. Do you agree with Dixon? Or have we nothing beyond very beautiful iron pyrites? I enclose a bit of white quartz ending in gold and green pyrites in this letter, which I think of getting set as a brooch. Of course the plumbago people do not delight in iron in any shape, and I am sorry I have not, to send you, a piece of compact heavy ironstone, the nucleus of plumbago which Mr. W. A. Fernando told me was unsaleable. I suppose that, apart from particles of iron being in the mineral, the quality of the plumbago was adversely affected by contact with the iron? In any case, those interested in plumbago love the appearance of veins of white quartz, while, with good reason, they hate iron.

“And talking of iron, look at that magnificent specimen of iron pyrites(?), No. 3, so like a mass of polished silver, which was found in Mr. Jacob De Mel's mine just as you see it. De Mel tells me it has not been touched up in any way. In returning it kindly say what you think of it—whether you think that by any possibility the beautiful polish of its plates is due to the contiguity of graphite? I fancy you will say “no.” Is the mass a conglomeration of iron pyrites, or what? De Mel said the weight was 14 lb.

“The amount of negative evidence I have obtained as to the existence of anthracite in association with plumbago, or in any form or place in Ceylon, seems to me overwhelming. But I should like to have your opinion before closing up. Do you think it possible that Gygax could have mistaken any black ore of manganese or iron, or any other substance, for anthracite? Certainly, no human being has seen any of the mineral since he announced its existence.”

Mr. Murray's reply.

“I have looked over the fine geological specimens you have sent for inspection.

“No 2 I should describe as semi-opaque *quartz rock*.

“*Quartz*, properly speaking, is pure silica, of which rock crystal is the purest and most transparent.

“The specimens in No. 1 packet are very pretty samples of iron pyrites. The green tints are due to the presence of sulphate of copper, but in very small quantity.

“I should much like to see a specimen of the compact heavy ironstone (metamorphosed, I conclude) you refer to as being associated with plumbago. Ceylon miners have probably the same reason for objecting to its presence as colliers at home have to the presence of trap rock in the coal measures, since in the vicinity of such rock coal has lost its bright lustre and regular face, as well as much of its bituminous or inflammable character, more nearly resembling anthracite than coal, and yet different from both in that it has concretions of iron pyrites or other minerals.

“No. 3 specimen—iron pyrites—is simply splendid.

“It is one solid crystal of that metal, and by no means a conglomeration of pyrites: the polished surface is quite natural, and not due to the contiguity of plumbago.

“Plumbago is held to be a metamorphosed form of anthracite, and probably Gygax classed the impure forms of this mineral

under that head. I have never seen anything approaching to real anthracite in the Island.

"I return the samples. The specimen of pyrites (iron), quartz rock, and plumbago is exceedingly interesting."

Mr. Murray wrote again with reference to some other specimens I sent for his inspection :—

"The minerals you got at De Mel's are all iron pyrites closely associated with plumbago. The ferruginous appearances of some of the specimens I am inclined to attribute to oxidation through the agency of water or damp finding its way along natural fissures.

"The specimen of plumbago is perfect, and exhibits an exceedingly fine form of crystallization.

"Still more interesting is the specimen of garnetiferous quartz associated with plumbago. The dark dullish mineral in the quartz matrix is, I believe, an amorphous form of plumbago in a state of transition, for, on breaking a piece off your specimen for the purpose of testing it, I found secretions in a semi-carbonised state which were easily pulverised.

"The crystal (octahedron) of iron pyrites is certainly exquisite, and one of the forms by which it is recognized.

"Among other forms of crystallization the *cube* is common. I enclose some crystals of it, which please return after inspection. They were taken out of the gneiss quarry at Fishers' Hill, Mutwal."

Rocks associated with Plumbago.

Having received from Mr. Williams, Acting Government Agent of Kurunégala, a very fine mass of quartz crystal found in a plumbago mine, and which bore traces of having been embedded in kaolin, I obtained Mr. Murray's opinion of the specimen, thus :—

"The specimen of translucent rock crystal is exceedingly fine. The crystal is the typical form—rhombohedral—a six-sided prism terminating in a six-sided pyramid; the white earthy substance is kaolin.

"Crystals in process of formation assume plane, smooth surfaces: the polished facets are not due to the influence or action of other closely-associated minerals, but are merely the definite shapes or forms assumed in obedience to the laws of crystallization. Geologically, quartz belongs to the metamorphic or hypogenic system, and contains one equivalent of silica to two of oxygen."

On other specimens of pyrites, mica, quartz, &c., found associated with plumbago, Mr. Murray reported thus :—

"*Specimen No. 1.*—A garnetiferous nodule of quartz, apparently found imbedded in plumbago. I have broken the specimen in two to show this clearly.

"*Specimen No. 2.*—Brown mica, which is mainly composed of silica, potash, and magnesia.

"*Specimen No. 3.*—One of the best and purest forms of plumbago I have seen.

"*Specimen No. 4.*—Mica schist (quartz and mica), closely associated with plumbago, iron pyrites, &c. The piece I have broken off exhibits two shades of yellow, due doubtless to presence of sulphur in varying proportions.

"*Specimen No. 5.*—A fine specimen of a highly garnetiferous vein of quartz passing through plumbago.

"*Specimen No. 6.*—Iron pyrites, plumbago, and quartz, with a thin shell of ironstone—the first of the kind I have seen.

"*Specimen No. 7.*—A band of steatite or soapstone traversing plumbago. The crystallized rock in the smaller specimen is quartz.

"*Specimen No. 8.*—Of the three varieties, the light dull-looking stone seems to me an impure amorphous form of plumbago, impregnated with iron and mixed with felspar and silica.

"The last two specimens are brown mica schist associated with plumbago and iron pyrites."

Appendix No. 12.

Local Use of Plumbago.

As this paper was undergoing final revision, the following interesting communication reached me from Mr. W. P. Ranasinghe, who, in consequence of inquiries made at my request, has ascertained that native potters do use plumbago as a glaze. He gives also information as to the local manufacture of crucibles, and a curious tradition as to the last King of Kandy being a dealer in plumbago:—

"I just got from a man the mode of glazing pots in this country.

"The pots are made and kept in the shade to dry, and when half dry they are trimmed and smoothed with a stick, and are again smoothed with a chank. Then plumbago is pulverized and rubbed over the pots, and again smoothed with the chank and dried in the shade. If the plumbago does not stick to the pot, a little lime-juice is sprinkled over the pot, and the plumbago is

rubbed over it and dried. When quite dry, the pots are exposed to the sun and then fired.

"Crucibles are now made with a mixture of pulverized plumbago. To three parts of potter's clay one part of plumbago and one part of burnt chaff are added, and the whole ground well. The crucible made of this material will last four months, whilst the ordinary crucible will last only a month.

"I understand that the last King of Kandy sold plumbago to merchant vessels. There is, I am told, a field at Kégalla where it is said that Molligoda Adigar dug plumbago. This will be interesting if true."

Appendix No. 13.

Plumbago and Pencil-making in Germany.

The following is the reply of Mr. Walter Freudenberg to questions of ours respecting the use of plumbago in Germany:—

"In reply to your letter of 13th I beg to say that Ceylon plumbago is not used for pencil manufacture in Nuremberg—Siberian graphite is taken instead.

"The 'needle' plumbago you refer to is not to be had in very large quantities, and I cannot give you accurate information about its final destination—i. e., whether it is used for crucibles or lubricating purposes.

"In Germany, a great many Steel Works do not use any plumbago at all, but Krupp takes large quantities every year. As far as I can judge at present—I have no accurate knowledge of the statistics—the consumption of Ceylon plumbago in Germany is not on the increase.

"I send you a catalogue of Johann Faber, Nuremberg, which kindly return after perusal. It will give you an idea of the importance of the pencil industry in Nuremberg, and one or two items in the preface may be of interest to you."

The large "Illustrated Catalogue of Johann Faber, of Nuremberg and London," alluded to above, is a very fine specimen of lithography, and gives certainly a vivid idea of the extent and importance of the pencil-making industry, the coloured illustrations showing many hundreds of varieties of pencils of every possible shade, from deep black to red and azure blue, with combinations of pencils, pens, erasers, and all the appliances required by the artist, literary man, accountant, artizan, ball-goer, &c. The preface states:—

"The first black lead pencils were manufactured in England,

from the celebrated Cumberland graphite, more than three centuries ago.

“At the end of the last century Conté of Paris invented an entirely new system in the manufacture of lead pencils, and artificially produced them in various degrees from inland graphite mixed with clay, ascribing to them the term “Polygrades” derived from the Greek words “γραφειν” (to write) and “πολως” (many), signifying a writing material possessing many degrees.

“Conté being the original inventor of the above system, all other statements are incorrect.

“In the year 1761 the ancestor of Johann Faber established a factory under the title of A. W. Faber, and in 1840 Johann Faber and his brother Lothar (the present proprietor of the firm of A. W. Faber) succeeded their father at Stein in the management of the business. From that period dates the success and popularity which the firm of A. W. Faber has enjoyed. Whilst Johann Faber devoted himself exclusively to the manufacturing department, Lothar Faber occupied himself with opening business connections throughout the civilized world. It may therefore be stated, without any pretence to ostentation, that the reputation which the A. W. Faber pencils have acquired is due to the indefatigable energy and labour of Johann Faber, and to his experience as a pencil manufacturer during a period of upwards of 37 years.

“In 1876 Johann Faber withdrew from the business of his father, and in 1880 established under his own name, “Johann Faber,” a new establishment for the manufacture of black and coloured lead pencils, &c.

“It need scarcely be mentioned that the goods now produced by Johann Faber are of the same excellent quality as those which he previously manufactured for the old firm, and his newly-invented system of grinding the graphite and clay, called “System Graphite Broyé,” has enabled him to produce the most perfect and uniform quality of lead which the modern pencil industry can furnish to-day.

“The present production and sales of Johann Faber’s pencils are now (after only four years’ existence) about 3,000 gross per week, and he employs 200 hands. These figures will speak for themselves.”

This firm is, of course, but one of many engaged in turning out 250 millions of pencils per annum in Albert Durer’s ancient city.

The following details as to quality of black lead pencils are given :—

“*Designation of the Degrees.*—The below-mentioned marks

are those generally adopted by artists and others to all lead pencils in order to distinguish their grades or depth of shade :—

BBBBBB	extra soft and extremely black	}	for a full rich deep shade.				
BBBB	very soft and extra black						
BBB	very soft and very black	...	for very deep shading.				
BB	very soft and black	...	for deep black shading.				
B	black	...	for ordinary shading.				
HB	medium and black	...	for sketching.				
F	firm	...	for ordinary drawing and office use.				
H	Medium hard	...	for sketching and drawing.				
HH	Hard	...	for firm lining and drawing and short-hand writing.				
HHH	Very hard	...	for firm sharp lines and sharp drawing.				
HHHH	} Extra hard	...	for very sharp and very defined lines.				
HHHHHH							
No. 1	2	3	4	5	”		
Very soft and black.			Soft and black.	Hard.	Harder.	Very hard	

The tendency of the following paragraph is to show that Johann Faber, at least, does not use Siberian plumbago, and the fair inference from what is stated would seem to be that “Graphite Broyé” pencils are made wholly of finely-ground black lead, although I suspect no pencils are now manufactured without some mixture of clay :—

“*Johann Faber’s Finest and best Lead Pencils, Graphite Broyé.*”—These lead pencils are made from the very finest graphite procurable. The graphite, after undergoing a series of washing and grinding by the most delicate and improved system in existence, thus rendering it perfectly pure, is very highly compressed.

My Graphite Broyé pencils stand unexcelled as the finest drawing material in existence, combining all the qualities which art can demand :

- 1st. Their points are firm and keep well.
- 2nd. The lead consists of one piece throughout.
- 3rd. They are absolutely pure and free from any particle of grit or foreign substance.
- 4th. The degree is maintained throughout, whether hard or soft.
- 5th. The most renowned artists throughout Europe all testify to the superiority of these “Graphite Broyé” pencils over the so-called “Siberian” or “Spanish Graphites.”

6th. The harder degrees are extremely even in temper, and are better adapted for photographer's use than anything that has yet been introduced."

Appendix No. 14.

The Local Average Prices of Plumbago, and the History of The Joseph Dixon Company

are thus noticed in a communication from a merchant who had read proofs of this paper :—

"You refer to the average valuation and Customs valuation as Rs. 200 a ton for qualities and periods. The average by the figures you have given would be Rs. 146, but even that I should say was high. If dust and chips are included, I question if you should put it higher than Rs. 100. Good lump is now worth say Rs. 120; chips, Rs. 75; and dust, Rs. 45 or thereabouts.

"You refer frequently to The Joseph Dixon Crucible Company. This Company has had a good many vicissitudes. Dixon, I think, was originally a partner with Dr. Gautier in the firm of J. H. Gautier & Company, of Jersey City, who sent Mr. Whiteford here about 1873; and I understood from Whiteford that Dixon and Gautier disagreed and split. Then I think Dixon died, and the Company was formed, and, if I am not mistaken, dissolved and re-formed."

Appendix No. 15.

The Renting and Selling outright of Plumbago Lands

are thus discussed in a note from the Government Agent of the Western Province, the Hon. F. R. Saunders :—

"I still adhere to my view that it is better for Government to sell than to rent plumbago land. What we do is to cut the land up into small lots of a little above one acre, and this induces competition and prevents any monopoly being created.

"I send you a list showing the prices realized for a block of plumbago land in the Rayigam Kóralé, sold in 1880. It would be many a year before we should get Rs. 8,150 as *rent* from a land of 1 acre, 1 rood and 13 perches. (See lot 556).

"These lands are situated at Pelpitigoda in the Rayigam Kóralé, and were the subject of a law-suit, which we won in appeal to the Privy Council, after losing our case in the Supreme Court here.

"The value of Rs. 200 a ton put on plumbago by the Customs is very misleading. I presume it is done to show the great value of exports from this Island.

"If a man pays Government the sum of Rs. 5,000 an acre for plumbago land, and yet has to pay Customs duty of Rs. 5 a ton, I don't think the man who is renting an acre of land need complain of paying an extra Rs. 5 a ton, instead of Rs. 5,000 down."

MEMO.—*Pelapitiyagoda Plumbago Lands in Rayigam Koralé, Kalutara District, sold at Colombo Kachchéri in June, 1880.*

		Lot.		Extent.			Sold for Rs.
				A.	R.	P.	
1	...	552	...	1	1	11	240
2	...	553	...	1	2	30	480
3	...	554	...	1	1	30	185
4	...	555	...	1	2	36	300
5	...	559	...	1	1	27	130
6	...	561	...	1	1	20	185
7	...	562	...	1	3	24	70
8	...	563	...	0	3	8	31
9	...	564	...	1	3	24	200
10	...	567	...	1	0	17	1,000
11	...	570	...	0	3	38	150
12	...	571	...	1	0	6	540
13	...	572	...	1	2	23	6,200
14	...	573	...	1	3	16	2,900
15	...	574	...	1	3	38	1,000
16	...	575	...	1	2	18	2,050
17	...	576	...	1	0	24	4,000
18	...	577	...	1	0	14	550
19	...	579	...	1	2	28	255
20	...	580	...	1	2	28	1,000
21	...	582	...	1	1	14	250
22	...	583	...	1	0	34	1,900
23	...	584	...	1	1	2	255
24	...	586	...	1	1	13	8,150
25	...	557	...	1	2	9	1,600
26	...	558	...	1	3	34	135
27	...	566	...	1	2	5	2,750
28	...	569	...	1	1	18	1,600
29	...	565	...	1	3	14	180
30	...	560	...	1	0	28	110
31	...	585	...	1	0	34	830
				45	0	25	39,226

Average price per lot, Rs. 1,265.

Do. per acre, Rs. 871.68.

There can be no doubt that the Customs valuation of Rs. 200 per ton for plumbago is, as Mr. Saunders states, too high, but as the royalty is at a fixed rate, the over-valuation does not affect exporters. As to the policy of leasing instead of selling lands, so as to prevent monopoly, here is what Governor Sir W. H. Gregory said in 1873 :—

“ With regard to the other proposal to sell the land, the reason why we could not agree to that has been pointed out by an hon. gentleman (the Government Agent, Central Province), who speaks with some authority on this subject. I think that would be the wrong course to pursue. We have tried it in one or two instances; we have had paddy rents sold to the cultivator. The sums thus realized benefited the Colony for a time, but it was a short-sighted and unjust policy against posterity to alienate a source of income for all time in order to obtain food for the present. It is precisely so in this case. We can't tell to what proportion this trade may grow: capital will no doubt be attracted to it, machinery be employed once the trammels and restrictions are removed; and therefore to sell the plumbago land at once would be unwise as regards the future of the Colony. Then, as regards the natives themselves. What has fallen from my hon. and learned friend (Mr. Ferdinands) is intimately borne out by all parties in the country. He says that the natives who understand the case are entirely in favour of this measure, and extremely anxious that this Bill should pass. There are those who would like the land put up for sale; but they are the capitalists—the small digger infinitely prefers taking out a license and working a pit himself; in the one case he realizes for himself the profit of the venture, whereas if all the promising lots fall into the hands of rich people, he merely becomes a workman at wages for them. Undoubtedly the sale of plumbago lands, irrespective of the objections I urged before, would be eminently distasteful to the bulk of the people, though popular enough with the rich few.”

Appendix No. 16.

The Dutch Name or Plumbago

being “*pot-loot*” (‘pot-lead’), it would seem as if the Hollanders must have recognized what is now the principal use of the mineral, from their earliest acquaintance with it. I referred the philological question to Mr. Donald Ferguson, who replied as follows :—

“ Yes; *pot* in Dutch is the same as English. I find in the Dutch-French dictionary I have (published 1768), that *pot-loot*

is explained as "blue mountain-chalk with which one can write and draw," the French being given as "crayon bleu, crayon de *Hollande*," which looks as if the Dutch were the first to use it for pencils, &c. The word *pot-loot* was also used for pencil simply, as "Leen my uw *pot-loot*" ["Lend me your pencil"].

Appendix No. 17.

Plumbago in the Kolonná Kóralé.

MR. Charles Shand states :—

"The plumbago found at the Vegiriya village, Kolonná Kóralé, below the Kolonná estates, is considered to be the finest flaky (micaceous) plumbago found in the Island, being peculiarly soft and dark in colour, and realizes the highest price in the London market. This deposit has only been largely worked within the last three or four years, and there are several promising spots in the neighbourhood, but the present low price and heavy transport interfere with development."

Specimens sent by Mr. Shand bear out his description of the fine quality of the mineral. It is, however, not micaceous, only mica-like in its laminated structure.

Appendix No. 18.

Return of Plumbago conveyed by Rail to Colombo.

Station from		1882.	1883.	1884.
		Tons.	Tons.	Tons.
Kalutara South	...	—	7	16
Veyangoda	...	346	223	—
Mirigama	...	322	258	18
Ambépusa	...	7	26	—
Polgahawela	...	4801	4664	3349
Rambukkana	...	32	78	74
Kandy	...	112	18	35
Katugastota	...	14	43	61
Wattégama	...	8	72	—
Mátalé	...	—	—	—
Náwalapitiya	...	—	15	10
Total ...		5642	5404	3563

The above table I owe to the courtesy of Mr. Pearce, who explained that no separate accounts of plumbago as an item of traffic were kept before 1882. The figures given show that the

contribution made by the mineral to railway traffic has been important, the quantity carried verging closely on half the total exports, and there can be little doubt that a very large proportion of the plumbago which came on the line at Polgahawela was from the rich mines of the North-Western Province, very little being from the Kégalla District. It seems probable that all the plumbago mined in the Central Province came on the railway at the stations between Máatalé and Náwalapitiya, the quantity being insignificant.

Appendix No. 19.

Export of Plumbago in 1885.

Just before printing, we have received the following figures :—

Export of Plumbago.

January-June, 1885	...	cwt.	92,386
In July	...	„	25,846
Total—cwt.			<u>118,232</u>

Carried down by Railway.

1st January to 9th August, 1885	cwt.	<u>47,026</u>
---------------------------------	------	---------------

Appendix No. 20.

A Faithful and Intelligent Sinhalese Kangani.

[From the "Ceylon Observer," 31st August, 1885.]

"OUR researches into the history and character of the plumbago enterprise brought us into pleasant intercourse with the two plumbago princes—fine specimens of shrewd, well-educated Christian Sinhalese gentlemen—Messrs. Jacob De Mel and W.A. Fernando. We ought to reverse the order of the names on the principle of *senior prior*, for Mr. Fernando claims to be "the father of all the plumbago merchants." We were amused at this assumption of paternity by so juvenile-looking an individual. Mr. Fernando is one of those men who seem as if they never would grow old, or at least never look old. His brilliant black eyes have all the lustre of youth, and he moves about with all the elasticity of a young man. We were, therefore, greatly surprised to hear him claim ten years more of age than has passed over his grave and rather aged-looking brother-in-law, Mr. De Mel. Mr. Fernando is enthusiastic in regard to all connected with the plumbago

enterprise; but to see how his eyes glisten when he speaks of his kangani,* the head man of the preparing works! He told us that all who came to his place acknowledged the superiority of his kangani, and certainly we were no exception. It was to Cornelius De Silva, known familiarly and in every day life as Harmanis Appu, we were ever referred, and always with the result that we obtained just the full and correct and substantially scientific details we desiderated, regarding the characteristics of the purest and best forms of plumbago, as contra-distinguished from the hard form known as *yabora*, or iron dross; and also regarding the rocks associated with plumbago, such as *tiruwnagala* (white stone, or quartz), *miniran* (mica), and *diya-rat-ran* (water-gem-gold, or iron pyrites.) Although kangani, and quite an intelligent-looking gentleman in his out-of-door dress, Harmanis Appu, in the preparing compound, dresses as scantily, works as hard, and is as effectually electrotyped and polished by the black shining mineral as any of the coolies he superintends. It was he who, with great pains and ingenuity, overcame the difficulties connected with one of the most slippery substances in nature, by sawing first-class lumps of plumbago, and securing them one above another with iron pins run through them, so as to form the pyramidal trophy, which was placed on a table in the hall of the Asiatic Society, to illustrate the Paper on Plumbago, and which still stands there with chips, dust, and the associated rocks. In order to reach the Museum in safety, the plumbago had to be wrapped round and secured with gunny cloth. Besides the large mass of plumbago to which Mr. Davidson alluded as in prospect for the Exhibition, we submit that a trophy of first-class lumps of our staple mineral in the form of a good-sized dagoba would be a very effective and very characteristic object in the Ceylon Court, as much so, perhaps, as a trophy of pearl shell. The lumps could be sawn smooth, so as to be easily superimposed, and the slipperiness could doubtless be overcome by the use of a dark-coloured cement."

[It may be added, that from long observation and experience the kangani is able, by a kind of instinct, to recognize lumps which come to the store, as fine soft plumbago; as plumbago, pure but hard, or as mineral formed over a matrix of quartz, or mica, or iron pyrites, without testing the specimens by their very different specific gravities: the purest plumbago, being lightest in weight, as well as brightest in lustre.]

ROYAL ASIATIC SOCIETY, CEYLON BRANCH.

PROFESSOR VIRCHOW'S ETHNOLOGICAL STUDIES ON THE SINGHALESE RACE.

Read before the Anthropological Society of Berlin, January 17, 1885.

TRANSLATED BY W. R. KYNSEY (FELLOW KING
AND QUEEN'S COLL. OF PHYSICIANS) AND J. D. MACDONALD, M.D.

(Read February 13, 1886.)

AT the time when I wrote my treatise concerning the Veddás of Ceylon, and their relations to the neighbouring races, it was not possible for me to obtain a single satisfactory scientific description of the principal race of the Island, viz., the Singhalese. What I was able to ascertain concerning them is stated on page 60 and the following pages.*

My disappointment was great at not seeing the large caravan which Herr Hagenbeck brought to Europe in 1883.

At the sitting of the Paris Anthropological Society, of October 18, 1883 (Bulletins, page 713), M. Manouvrier made an official report concerning that company, the meagreness of which is even acknowledged by the author himself, who explains it as due to want of courtesy on the part of the leader.

Last year another caravan visited the country, and I consider myself fortunate in finding it still here on my return

* Of his former treatise on the Veddás.

to Berlin. Herr Hagenbeck himself had the kindness to give the necessary instructions, so as to facilitate my examination. After his departure Herr Von Schirp had the kindness to bring the people before me one by one. Notwithstanding this, I was only able to examine a small number of the forty persons of which the company consisted. There was all the preparation of their approaching departure going on, and I must say, like the Paris Commission, that the time spent in obtaining my results was too short. Besides, the determination of personal relations was surrounded with much difficulty. At first I was informed that with the exception of some dancers from Hindústán, the whole company was of Ceylon origin, and that of the latter, two, viz., Pichchai and Murugappa, were Tamils. Both, I was informed, belonged to a suburb of Colombo. Later, however, I ascertained through the interpreter (who said he himself was born of European parents in Ceylon) that the Tamils in question belonged to the neighbourhood of Bombay.

Herr H. Becker ("Cinghala and the Siphalese, the Land and the People of Ancient Paradise": Frankfurt-on-Maine, page 18), who wrote a not sufficiently trustworthy description of the same people, says that Murugappa came from Madras, and Pichchai from Negapatam, south of Madras. Whatever the truth may be, the hope to see Ceylonese Tamils face to face proved a delusion, and the zeal with which I engaged in the examination of this rarity influenced not a little my further proceedings.

Of the Siphalese proper, I chose two groups. As representing the first group, I chose the following:—

1. A little three-year old boy called Jimmy (Sinni), who with justice had become the favourite of the public; stark-naked, with the exception of a silver fig-leaf, he tumbled unweariedly, and in constant good humour, about the arena.

2. His mother Lúsa (Louise?) Nóna, about twenty-five years old; his father Girigóris, or Grigóris Appu, twenty-

nine years old ; his mother's sister, Igga Nóna, sixteen years old ; and his mother's brother, Andre Appu, twenty-one years old.

Herr Becker had made three families of these. A *Nóna* family, an *Appu* family, and an *Appuhámi* family. Nay, he went a step further, in taking Abuhámi for an Arab, or, as they say in Ceylon, for a Moor. I must leave it undetermined whether the man was called Appu or Abu. The name sounded to me almost like Appu, and Herr Kotelmann writes it so ("Magazine of Ethnology," 1884, page 165). There was no difference of opinion, however, concerning the family connections of the group.

For the second group I made choice of two of the tallest and strongest men. Both were Kúruwe (elephant-drivers) from Kandy, viz., Puñchi Baṇḍá, twenty-four years old, and Ukku Baṇḍá, twenty-two years old. Herr Becker has given a photograph of the latter. Becker is inclined to suppose a mixture of Malabar blood in these, on account of their size ; but I would refer to my treatise (pages 60–64), where I have quoted the evidence of the best observers, Davy, Cordiner, and Sirr, according to which the Kandyans differ from the rest of the Singhalese by their greater strength, darker colour of skin, and better growth. Our Kúruwe may, therefore, be considered as the representatives of the highland type, as the members of the Abu Nóna family that of the lowland type.

In how far these represent the pure type must be left undetermined, in view of the differences of my former craniological examinations, and of the strongly prominent individual peculiarities appearing in the persons before me. The Paris Commission, whom the same difficulty faced, had come to the conclusion that the persons brought to Europe were taken from a very mixed portion of the population, and contained a large mixture of Malabar blood. I shall refer to this again, after I have discussed the principal peculiarities ; but will here observe that I have come to no sure conviction

on the point. In my former works I had come to the conclusion from the reports before me, that "the Singhalese belonged to a dark, or more correctly, a brown, smooth-haired race, not prognathous or moderately so" (page 65); and this has been confirmed in the numerous persons by whom we were visited.

As far as the colour of the skin is concerned, the Paris Commission had found that the darker portions corresponded to No. 28 of the colour table; the lighter lay between No. 22 and No. 43.

According to the table of the Stenochromic Society, the colour at the bend of the elbow in one man was determined at the letter *g*, in the second transition stage from cinnabar to greenish orange, and that of the breast of a little girl at *i* orange.

I found in the family of Abu Nóna the following:—

1. The father Girigóris showed a dark brown colour: on the brow 28=Radde 3 *g*; on the cheek 21=Radde 4 *k*; on the breast 29=Radde 3 *g*; on the hand (back) 28-29=Radde 2 *e*; palm 30-31=Radde 4 *o* approximately.

2. The mother's brother Andre: brow Radde 3 *j*; cheeks Radde 4 *h-i*; breast Radde 3 *h*; back of the hand 28-29; the fingers Radde 30 *d*; putting the skin on the stretch Radde 3 *h*, palm 26. The deep colour of the breast was on the whole reddish, but still with a strong shade of yellow.

3. The mother Lúsa Nóna: brow 30-31=Radde 4 *i*; face 32-33; breast 29-30=Radde 3 *i-k*; back of hands 22-37=Radde 4 *h-3 h*; palms 24. In these are shades of unequal lightness.

4. The mother's sister Igga: very light, back of hands 29.

5. The little Jimmy (Sinni): breast 29-30; arm Radde 3 *f*; face lighter, more yellowish brown.

NOTE.—I may observe that according to Radde, 1 cinnabar signifies 2 cinnabar in the first, 3 in the second transition towards orange, 30 carmine in the transition towards cinnabar.

Of the Kúruwe, of Kandy :—

1. The older, Puñchi Baṇḍá : on the brow Radde 30 *i*; on the cheek Radde 30 *k*; on the arm 29=Radde 3 *f* and Radde 10; on the palm 30-31=Radde 3 *e*.

2. The younger, Ukku Baṇḍá : face 4 *k*; breast 28-29; arm (inside) 29-30=Radde 3 *i*, (outside) Radde 2 *e*; dorsum 28-29; palmar 31.

These are chiefly shades of colour which, according to Radde's scale, belong to orange (4), and to cinnabar in the second stage of transition to orange. Next follow some cases in which cinnabar in the first stage of transition to orange (2), or carmine in the second stage of transition to cinnabar (30), was determined.

There is some interest in comparing the two persons from India :—

1. Murugappa, thirty-two years old : brow 29=Radde 3 *g*; breast 27-28; dorsum of hand likewise=Radde 30 *b-c*; palmar surface 31-32=Radde 4 *g-h* and 3 *g-h*. The nails are light and short. The shades of colour belong to the mixture of cinnabar with orange, of carmine and of orange. On putting the skin on the stretch, an underground of a yellowish colour appears, with black specks and stripes. On a simple inspection, the impression of a reddish tone of colour is imparted.

2. P chchai, nineteen years old : face 21=Radde 4 *h*; breast 43=Radde 4 *f*; dorsum of hand 28=Radde 2 *f*; palm 26=Radde 4 *k*.

In these appear no other colour than that occurring in the Ceylonese, and here also orange (4) dominates. Still, there is not wanting the transition stage of cinnabar to orange (2 and 3) and from carmine to cinnabar (30). I cannot therefore say that I found in the colour of the skin any different shades of colour not found in the skin of the Ceylonese. If the former, for example, show a much darker shade of skin than the Kandy men, still it must not be overlooked that even the Ceylonese among themselves show different degrees of darkness and fairness in their skins.

Lúsa Nóna had much lighter shades of colour than her husband and her brother. For example, I noted for Girigóris 3 *g*, for Andre 3 *h*, for Lúsa Nóna 3 *i*, therefore at the time one degree lower (clearer), whereas Pichchai (4 *f*) showed a degree higher (darker) than Girigóris.

In Ceylon the opinion prevails that the Tamils are distinguished by a darker skin than the Sighalese. But when Davy asserts that the colour of the skin of the Sighalese varies from light brown to black, it must be clear that the difference cannot be constant. Percival expressly declares that the colour of Sighalese women approaches the yellow, and even Cordiner asserts that the colour of the higher classes is quite as light, or even lighter, than that of brunettes in England. One may perhaps infer from all this that the variation of colour of skin among the Sighalese is even greater than among the Tamils, and that a larger number of persons with a small amount of pigment in the skin occur among the Sighalese; but a means of distinguishing the dark Sighalese from the Tamils is not to be looked for in the skin colour alone.

I would like finally to remark that the assertion of Cordiner, that the palmar surfaces of the hands and feet of the Sighalese of all classes are uniformly white,—an assertion also found in Selkirk,—has not been quite corroborated in our Sighalese. The palms of the men show 30–31, of the women 26–24 of the Parisian colour table, therefore quite clear shades, yet still plainly pigmented. The man from Madras or Bombay, viz., Pichchai, had likewise No. 26. Yet it must not be forgotten that the Parisian colour table leaves lacunæ, and that the determination of Radde's tables give different values: for example, for No. 30–31, at one time R. 3. E., at another time R. 4. O.

The colour of the hair was fixed by the Paris Commission, No. 48 of the table, *i. e.*, as pure black. In fact, the richly developed heads of hair of the men, woven long and gathered at the back or side of the head into a knot (*konḍé*),

has an ebony tone of colour in all, only in the case of Ukku Bandá it had a brownish appearance, was at the same time slightly curly, whilst it otherwise looked flattish, and at the most somewhat wavy towards the points. With Jimmy (Sinni) it was quite black. The careful attention paid to the hair in the way of washing, combing, and oiling, contributes not a little towards increasing the favourable impression made by it.

Hair was also richly developed on the upper portions of the body. This was especially true of the eyebrows and the eyelids, whilst the beard in the case of the men was not thick, and in several was somewhat curly.

On the other hand, the older men had hair richly developed on the body, a fact which the Paris Commission had also noted. It said: "The rest of the body was remarkably covered with hair, the breast and the hollow of the spine in particular presented, in the case of the oldest men, true tufts of hair somewhat curly and several centimetres long."

I give here shortly my notes of each person examined:—

1. Lúsa Nóna: Hair strong, black, quite smooth, only at the ends somewhat wavy, slung in a knot behind; eyebrows strong; eyelashes long and thick.

2. Inga Nóna: Hair quite black and smooth; only a few wavy "love locks" before the ears. The hair descends far on the brow, so that a large portion of it (brow) appears black through short hairs. There is a soupçon of a moustache on the upper lip.

3. Andre Appu: Hair quite black, 30 cm. long, and throughout slightly waved; eyebrows strong, quite black, and shining; eyelashes long and thick; beard on chin and lips more richly developed; hair somewhat wavy.

4. Girigóris Appu: Hair long and black, stretched back over the head and held by a comb, gathered up in a knot behind; moustache and beard on chin somewhat sparse and wavy.

5. Jimmy: Quite black, short cut, thick rough hair.

6. Ukku Bandá: Hair long, black, with brownish shade, curly, gathered in a knot; eyebrows moderately developed; eyelashes short.

7. Puñchi Bandá: Hair long and wavy, gathered in a knot behind; black beard, thin, but long and somewhat wavy; breast and arms strongly covered with hair.

I add here also the results of the examination of the two Indians:—

1. Murugappa: Hair smooth and black, cut short in front, slung in a knot behind; beard thin, but individual hairs strong; breast and abdomen covered with strong and long hair.

2. Pichchai: Hair quite black, drawn back tightly, scarcely wavy; eyebrows strong; eyelashes long; moustache black and strong; whiskers moderately strong.

On microscopic examination I find that in the hair of the Sinhalese there is, without exception, almost a complete failure of, or an extremely diminished, medulla. On transverse section a very small central pith is occasionally observed, generally not greater in diameter than a blood corpuscle, and quite colourless; only sometimes, as, for example, in the case of the little Jimmy (Sinni), this narrow strip of medulla is pigmented. The peculiar colouring matter of the hair lies in the fibrous portion, and strongest in the superficial parts. Only the outermost layer (cuticula) is quite colourless and homogeneous. The colour, which is due to particles of pigment arranged lengthwise in stripes, varies very considerably. In many of the hairs observed lengthwise the colouring particles appear quite black, and also on cross section the particles appear almost pure black, whilst in other cases the external particles appear of a brown colour, and the cross section of same show light brown, nay sometimes yellowish-brown particles. This is the case with Lúsa Nóna and her brother Andre Appu, although their hair, on microscopic examination, appeared a pure black. Even in Ukku Bandá the microscopic colour is brownish.

I must also add here that Tamil hair, which I obtained through the good offices of Herr Freüdenberg, the German Consul, and from Dr. Kynsey, has the same characteristics. In four of the examples, one shows a light yellowish-brown, one a light greenish-brown, a third a dark brown, and only one a pure black pigment. In the case of one Malabar I found, besides black hair, also brown.

The form of the cross section in the case of the Siṅhalese is either quite round or slightly compressed on one side, so more or less kidney shaped. This is very distinct in Ukku Baṇḍá. The hair of the women is finer, but very dissimilar in thickness. On the whole, the hair of the Tamils appears to me, on comparison, darker, somewhat stronger; yet even in their case the thickness, as well as the shape of the cross section, varies in the same individuals in a similar manner as amongst the Siṅhalese. The Paris Commission determined the colour of the iris partly at No. 2 of the table, and partly between 5 and 3 *d h*, more or less dark brown. I can corroborate this, only that I also noticed nut-brown eyes, as did Davy before me. The iris of Lúsa Nóna corresponded to No. 3 of the table, whilst her brother Andre showed the dark brown colour of No. 2. Really black irises as noted by Sir Davy and Cordiner I have, like Herr Kotelmann, never seen. I consider that they never occur. Cordiner asserts that the white of the eye appears strikingly clear, and I can corroborate this in the case of children and women, yet the men had invariably yellowish-brown pigment in the conjunctiva, especially in the middle layer. In Andre and Puñchi Baṇḍá, I noticed light brown specks. The same occurred also in the Indians, of which Pichchai showed a moderately dark brown; Murugappa, on the contrary, a somewhat variegated iris, which externally showed a dark brown, internally a light brown zone, and between these zones a light yellow ring. Further, the eyes of the Siṅhalese appeared generally large and brilliant, somewhat elongated in the case of the men, more round in the women and children.

The interorbital distance was small, a fact also noted by the French Commission. The distance in the case of the women was 31 mm., in the men from 34 to 35 mm., whilst in the Indians it amounted to between 37 and 39 mm. The length from canthus to canthus measured in the women 30 mm., in the Appu group of men 55 to 57 mm., in the Kandyans 62 to 64 mm.

Of the Indians, Murugappa measured 30 mm., Pichchai only 55 mm. Both showed a somewhat elongated, almost narrow, still straight, palpebral opening. Concerning refraction, sharpness of vision, and colour blindness, Herr Kotelmann has given details.

I now come to the shape of the head. From the tables attached it will be seen that of the seven Singhalese, there were:—

Two brachycephalic, four mesocephalic, one dolichocephalic.

Brachycephalic were Lúsa Nóna (82·7) and her brother Andre Appu (83·5); dolichocephalic, on the contrary, her husband Girigóris (72·3). Next to him stand among the mesocephalic the sister Igga Nóna (75·8); whilst the little son Jimmy (79·6) must be classified among the brachycephalic. The average cephalic index for the whole family may be set down at 78·7, the same mesocephalic number which was obtained from all the seven measurements. The Paris Commission (Dep. 719) measured seven men, five women, and two children. Among these fourteen persons none were dolichocephalic, eight were brachycephalic, six were mesocephalic. As also here among the mesocephalic a high index number appeared, it follows that the average is brachycephalic, viz., 81·9. Both averages, that of Berlin and that of Paris, approximate each other, but it must be distinctly remembered that they were obtained from different persons.

These results stand in strong contrast to those obtained from any examination of Singhalese skulls hitherto made. I have described these in my treatise (page 73 and the follow-

ing) in detail, and with every care. After eliminating all doubtful skulls, I had fourteen left. These had a mean index of 71·8, a distinct dolichocephalic measurement; nay, there was not among them a single brachycephalic, not even a mesocephalic skull. On account of this peculiarity I refer here to my writings, and I have no reason to doubt the correctness of the results then obtained. The results obtained by the measurements of skulls of these living persons cannot be made to agree with those obtained by me from the skulls formerly measured, even making all reasonable allowances and corrections.

There remains a want of agreement not to be for the moment reconciled. Either the type of the Sinhalese skull is not dolichocephalic as I assumed, or the living Sinhalese, even including Girigóris Appu, were not pure Sinhalese.

The latter appears for the moment more probable than the former, because in the first place it is difficult to explain where these Ceylon dolichocephalic skulls could have come from if they were not Sinhalese, as I have already proved (page 91) that the mean cephalic index of Tamil skulls from Ceylon hitherto examined is mesocephalic, viz., 76·3. If one therefore were inclined to conclude with the Paris Commission that these persons were fair Tamils (Malabars), a more satisfactory explanation would be obtained.

Now, however, I would accept such an explanation with the greatest reserve.

The opinion that the Sinhalese is a mixed race is very old, and a descent from the Malays and Mongolians has been surmised. More details on this point will be found in my treatise on the Vēddās, on page 110 and following pages. I will only add that should in reality a large portion of the Sinhalese turn out brachycephalic or high mesocephalic, the question of the relations with Indian races would acquire a greater significance than I have been hitherto inclined to accord it. Discussing the examinations of the

Chittagong races made by Herr Riebeck, some considerations of this kind occurred to me. (His travels will shortly appear.)

A second point of difference appears in the auricular index. From the appended tables, it can be seen that only dolichocephalic Girigóris and the low mesocephalic Igga offer a smaller number for the auricular index, the former 60·6, the latter 64. All the other Siphalese have high numbers, the highest Lúsa Nóna (72·6). One may therefore conclude that the majority of the persons are hypsocephalic. This also corresponds more with earlier numbers (pages 92-140) found by me in Tamils, than with those for Siphalese.

A third point is the breadth of the brow, which, making all allowances for the fleshy portion, is, in all the Ceylonese measured by me, more considerable than any measured in Siphalese, and even in Tamil skulls.

Whilst the highest measurement of the skulls only amounted to 93 mm., the lowest measurement among the living was 98 mm. (Lúsa Nóna), and the highest 109 mm. (Puñchi Baṇḍá). This great breadth of brow contributed not a little in improving the appearance of the persons in question. In the Kandy people the forehead was high, from 70 mm. to 75 mm.

Girigóris was 67 mm., and Andre only 55 mm., less than even the women showed (58 mm. and 59 mm.).

As far as the face is concerned, I have confirmed the opinion that the Siphalese are not prognathous. With the exception of one woman, they were all orthognathous, and had a small mouth, although the lips were full and the front teeth large. In several it seemed to me the lower lip was comparatively strongly prominent, whilst the teeth showed a peculiar mother-of-pearl brilliancy, in which a loss of enamel forming a hollow in the crown occurred. I looked upon this at first as artificial, but according to their own assertion it arises spontaneously. It seemed to me, however, as if the mode of cleansing their teeth caused this loss of enamel. I add here a few special particulars :—

1. Ukku Baṇḍá: Mouth small, 50 mm.; lips full, but only moderately prominent, mostly the underlip, which looks bluish internally, but does not allow any peculiar pigment to be seen; teeth greatly worn.

2. Puñchi Baṇḍá: Mouth large, 55 mm.; lips full, underlip strong, livid bluish colour, but little pigment in the mucous membrane; teeth large, particularly the upper incision, much worn.

3. Girigóris Appu: Mouth 51 mm.; lips full, quite blue; pigment in the gums; teeth (above) large, shining, much worn.

4. Lúsa Nóna: Mouth 44 mm.; lips full, but short, red, no pigment in the mucous membrane; teeth, large, straight, brilliant, like mother-of-pearl, worn, with a hollow in the right middle incisor in the enamel.

5. Jimmy: Mouth 34 mm.; lips thick, but only the underlip prominent.

6. Andre Appu: Mouth small, 44 mm.; lips full, somewhat bluish, but not pigmented; upper lip short, not prognathous; teeth large, brilliant, like mother-of-pearl, with several hollows in the enamel; chin delicate, round, and prominent.

Indians :—

1. Murugappa: Mouth large, 61 mm.; lips full, especially the underlip, which from a full supply of blood and pigment has a dark bluish-brown appearance; on the gums a brownish stripe parallel to the edge, but still separated from it.

2. Pichchai: Mouth shorter, 52 mm.; lips full, upper short, underlip advancing, blue; the gums pigmented; teeth large, much worn.

The face index was in all chamæprosop (broad face), with the exception of Girigóris Appu, who gave a leptoprosop (long and narrow face) measure, 91·3. His long face had, as Herr Becker has remarked, a semitic touch. Andre Appu's face appeared longish: still, this was more due to the fact that it contracted very much below. The faces of the women were short, broad, and more rounded, with somewhat prominent cheek-bones. The noses also differed from descriptions

hitherto given. The oldest descriptions by the Chinese (*cp.* Vedd. Book, page 61), ascribed to the Ceylonese a "bird's beak," yet many forms appeared to us amongst these people, as the index numbers will show. Girigóris' nose was the most prominent. His nose index amounted to 68·6. The two Kandyans followed with 71·1 and 71·6, then Igga Nóna with 76·1; on the contrary, Lúsa Nóna 83·7, her brother Andre 88·8, and the little Jimmy 90·9. This last group also includes the two Indians, with 80·0 and 83·3.

The French Commission obtained similar results: three men and two women had an index over 83. Three men and three women under 74 (among these one 64·4, one 66·6, one 68·5, one 68·7, and one 69·2).

I add here a short description of their noses:—

1. Girigóris Appu: Nose strongly projecting, ridge curved, point prominent (snub?), alae small and narrow; a decided semitic expression.

2. Ukku Baṇḍá: Nose strongly projecting, straightest of all, sunk at the root, ridge slightly curved, point thick, alae not large.

Puñchi Baṇḍá: A nose strongly inclined to but not quite an "eagle nose," somewhat curved, point prominent, looking downwards, alae moderately wide apart.

4. Lúsa Nóna: Nasal ridge curved, short, point thick, overhanging; alae wide apart, somewhat flat; nostrils large.

5. Jimmy: Nose short, bent, point thick, projecting; septum short; alae very broad and full.

6. Andre Appu: Upper portion of nose thin and small, somewhat curved, point projecting, alae wide apart.

Davy has given us a poetical description of a Sinhalese beauty (Vedd. Book, page 63). The nose is described in it as a "hawk's beak." Our ladies had nothing of that, yet it seems as if such faces had not quite died out. The cabinet photograph of a Sinhalese beauty, which Herr Hagenbeck has presented to me, shows such a nose, and we can only regret not having seen the original.

In the Indians I found the following : Nose on the whole straight, but small and narrow, towards lower part wider, even in the bony part ; point little developed ; septum little projecting ; alae very broad, 46 mm.

As a conclusion to this discussion of the shape of the face, I mention that the ear, as a rule, was delicate, and in many cases small. In three persons, viz., Lúsa Nóna, Andre Appu her brother, and the Kandyen Ukku Baṇḍá, I noticed that the lobule was adherent to the side of the head. This was also the case with the Indian Pichchai. The body was strongly built in all cases. The Kandy men alone attained to a good height. Puñchi Baṇḍá 1,745, Ukku Baṇḍá 1,674 ; Girigóris and Andre Appu measured only 1,576 and 1,583 mm., the women 1,425 and 1,451 mm. Travellers have given five feet four, five, six, or seven inches = 1,626 to 1,702 mm., as the average height of the men. The French Commission give only two measurements, 1,596 and 1,576 mm.

The family (Abu Nóna) appears to be, from this, unusually small. Girigóris is at the same time thin, his calves are but little developed, notwithstanding which he is a tree-climber by profession, and climbs with the greatest ease the highest tree. Andre is also thin, but nevertheless of great strength. Lúsa Nóna, although said to be only twenty-five years old, makes a pleasant impression, but is yet aged ; she has a delicate build of body. The little Jimmy, on the contrary, is a fat, chubby-cheeked boy of unwearied activity, but truly a little glutton. His shining blackish-brown body corresponds exactly with the description given by Emerson Tennent of Singhalese children : "They looked in their nakedness like living bronzes." Igga Nóna is sixteen years old, very light, small, and fat ; her form is quite round, her bosom prominent, and her thick cheeks swell still more prominently when she laughs.

Puñchi Baṇḍá has a proud-looking figure, with full form and strong muscles. He looks older than twenty-four years, the age assigned to him. Ukku Baṇḍá is also strong and muscular.

For dynamometric measurements, I refer to the report of the Paris Commission.

The ratio between the measurements round the hip and the height of the body showed such great differences, that I thought at first on revising my notes,—I had made some mistakes. The measurements were in all cases greater than the height of the body: even the women showed differences of 67 and 57 mm. Among the men the difference is more striking: Girigóris Appu had 82, Andre Appu 123, Puñchi Baṇḍá 60, Ukku Baṇḍá 118 mm. of a difference. The differences in the lengths of the arms are not less striking: Girigóris 732, Andre 761, Puñchi 806, Ukku 784 mm.

Shoulder-breadths measurements:—Girigóris 340, Andre 376, Puñchi 395, Ukku 391 mm. These are comparatively not widely diverging numbers. The circumference of the chest was considerable, greatest in the case of Ukku Baṇḍá, viz., 925 mm. The women have, on account of the full development of the breasts, a larger circumference than the men; the lengths of the lower extremities vary also. The height of the trochanter in Puñchi Baṇḍá amounted to 934 mm.—that was the largest number: the smallest was Andre Appu, 840 mm.; but the ratio is everywhere the same in men and women, *i. e.*, the height of the trochanter is to the height of the body as 1 to 1·8.

The shape of the hands and feet was uncommonly elegant, especially that of the feet. The Kandy men wore leather shoes, and although these were comparatively loose, still the small toes were pushed somewhat inwards, and this was even noticeable also in the next toe. Girigóris wore sandals, and had a wide divergence between the great and the second toe. Nevertheless, his feet also appeared comparatively natural. In the rest the shape of the foot was free from artificial deformities. I do not remember ever having seen such naturally shaped feet. As is well known, the feet among nations wearing shoes or boots are exposed from the earliest years to so much pressure, that a naturally-formed foot

is only seen in the case of the newly born, or in children of tender years. Even sandals when constantly worn press the toes together, and cause a permanent deformity very soon.

One seeks in vain among marble statues for a regularly formed foot. Even the gods of the Greeks have their small toes laterally compressed. Here, however, I was overjoyed to find feet with perfectly natural shapes. As their stay in Berlin was to be short, I begged Herr Hagenbeck to have a selection of casts of hands and feet made for me in Hamburg, and I am in the fortunate position to be able to lay before you good models of these. For this I have to thank Herr Hagenbeck.*

In the first place, there is a strong contrast between the feet of the Sîghalese and that of the Indians. This is partly due to the general development of the body. The ratio between the length of the foot and the height of the body is in all three the same, viz.: in the men as 1 : 6·6; women, 1 : 6·5. But the development of the feet is quite different. In Murugappa the whole foot is heavy, bony, and broadly developed, whilst in the Sîghalese the foot is delicate, thin, and narrow. The breadth-index of Murugappa is 40·5, of Girigóris 36·8, of Lúsa Nóna 28·2. The Paris Commission found among the men indices of 39·5 to 44·3; among the women 36·5 to 40·6.

In all, the toes were very movable, and they were capable of diverging widely at will. On this depends the safety in climbing,—which is possessed by Girigóris to a wonderful degree,—and the capability to seize objects with their toes. As seen from the illustration,* the divergent position in the

* Illustrations of a few of these are annexed to the German text. The views of them are taken laterally and from above, and designed with the greatest care by Herr Eyrich, one-sixth their natural size. No. 1 is the foot of Lúsa Nóna, No. 2 that of Girigóris Appu, and No. 3 that of Murugappa, one of the Indians. The cast of the foot of Iuga Nóna is not given, nor the casts of the hands of any of the troupe.

case of Murugappa is well shown ; in the case of the Siphalese to a much smaller degree. In all cases, however, is seen the great interval between the great toe and the others, especially in Murugappa. The three middle toes form a group by themselves.

At the same time, one may notice the length of the toes of this middle group, especially of the second. The Siphalese have these toes almost in the shape of fingers, straight and long. Murugappa, who also has short and thick fingers, shows also short toes, thick and plump ; and the great toe is so widely divergent as to project but little over the second. Among the women, the second toe projects beyond the first, notably in Inga Nóna, whilst in Girigóris the corresponding toe is shorter. This is strongly developed in Andre Appu. The terminal phalanx of the great toe is very broad in all cases ; the smaller toe is very short. The middle of the foot is small, thin, and straight. It widens gradually up to the heads of the metatarsal bones, where it, in comparison with a foot accustomed to shoes, appears strikingly broad. Notwithstanding this the great toe has no proper ball ; externally the little head of the fifth metatarsal bone is somewhat prominent. Further back the external border runs uniformly, whilst in the inner border rises quickly, forming a well-marked arch. The heel is strong and firmly set. The span of the foot is high and delicately arched, especially behind the first metatarsal bone. The tarsal bones are strong, little prominent, and very high. In Murugappa the height above the ground is 59, in Lúsa 46, in Girigóris 48, in Inga 54, and in the two Kandyans 61 and 65 mm., respectively.

With this I finish the analysis to which this interesting company has given rise. Without as yet classifying the subjects of my discourse, I dare to hope that the communication as it stands will be a sufficient excuse that I do not come to any definite conclusion. How many of the differences observed are merely due to the individual, how many are due to race-difference, I cannot satisfactorily say. Take an

example: according to my earlier craniological examinations, the Singhalese are dolichocephalic. Now, among the people actually measured by me here, I find only one dolichocephalic, viz., Girigóris Appu, the same whom Herr Becker took for an Arab. In reality his face, particularly his nose, had a distinct semitic look. But the Moormen are now-a-days Muhammadans, and if in rare cases they mix with the Singhalese (see my *Veddá Book*, page 94), it does not follow that they also change their religion.

Besides, the Jewish face appears among so many of the inhabitants of the islands of the East, that I would not support such a supposition on that ground. Also the deduction drawn by Herr Becker from the name *Abu* is so uncertain, as I have already shown, that it proves nothing. If Girigóris is not an Arab, he must be considered as a typical Singhalese. If this is accepted, then the others measured by me are not typical: even the stately Kúruwe from Kandy, and least of all the woman Nóna. Their short and broad skulls, their chamæprosopia (broad faces), and in particular their broad-pressed-in-curved noses, with the alae wide apart, point with a strong probability to a mixture with the Tamils.

The little Jimmy resembled his father so little, that one felt almost inclined to disbelieve the relationship. He was, however, the very image of his mother. His roundish-square head, his full-moon face, his ape-nose were only exaggerations of the mother-type. But the colour of the skin was quite dark, whilst the mother's was light. Who can doubt but that here individual and sex peculiarities were recognisable? but where is the line of demarcation of ethnical peculiarities? Unfortunately there is still wanting an exact description not only of the Ceylonese Tamils, but also of the Indian Tamils. I have therefore earnestly requested Herr Hagenbeck, in case he should again bring such people to Europe, which is not at all unlikely, to bring well-authenticated Tamils. One thing seems to me certain. If the French ethnologists entertain the opinion that the dark-skinned races of India

originated from Negritos, it is most probably a mistake. The Negritos known to us have that woolly hair which consists of small, close, spiral rolls, quite similar to the Blacks of Africa, and not only to the Niger proper, but, as lately discussed, also to the Caffirs and the other Bantu nations. In the case of the Africans, each spiral roll is so hard that it feels like a solid body. In the case of the Negritos the rolls are somewhat soft, from the fineness of each individual hair. Our Ceylonese show the very opposite of this. They are in the plainest meaning of the term smooth-haired, without the shade of a curl; the beautiful appearance of their long black hair is certainly improved by the care they bestow upon it, but no Negrito is capable, so far as we know, by any amount of care to change his hair in a similar manner.

Even the Dravidian Indians have nothing of the Negrito hair. One must therefore look to other sources than this, and it is possible that they are a very mixed race. As far as language is concerned, the Singhalese must be referred to an Aryan origin. Their history favours this idea; but are, on this account, Mongolian and Malayan connections to be excluded? I cannot believe it; at all events, I can say that many among the people presented to me, especially among the women, seem to point to Eastern relationships, and that if these people are really Singhalese, without any fresh mixture of blood, then must the Singhalese race be looked upon as a mixed race in the highest degree.

Siphaliese and Indian.	Siphaliese.						Indians.			
	Girigóris Appu. ♂ 29 J.	Lósa Nóna. ♀ 25 J.	Jimmy (Sinni). ♂ 3 J.	Andre Appu. ♂ 21 J.	Ippa Nóna. ♀ 16 J.	Puñchi Bandá. ♂ 24 J.	Ukku Bandá. ♂ 22 J.	Murugappa. ♂ 32 J.	Pichchai. ♂ 19 J.	
II.—BODY MEASUREMENTS.										
Body, height	1576	1425	769	1583	1451	1745	1674	1657	1613	
Hip	1658	1492	—	1706	1508	1805(?)	1792	1815	1723	
Breast, circumference...	800	825	—	830	855	900	925	900	790	
Shoulder, breadth	340	322	—	376	330	395	391	388	349	
Shoulder, height	1314	1199	—	1330	1214	1482	1404	1375	1334	
Elbow, height	1008	912	—	1022	948	1142	1083	1042	1024	
Wrist, height	743	670	—	744	730	866	810	753	752	
Middle finger, height...	582	520	—	569	572	676	620	588	594	
Nasal, height	971	—	—	990	—	—	—	970	981	
Trochanter, height	863	758	—	840	789	934	901	887	878	
Knee, height	463	412	—	481	450	540	534	488	500	
Malleolus ext., height...	48	46	—	49	54	65	61	95	61	
Hand, length	170	155	100	190	160	182	188	179	175	
Hand, breadth	75 (100)	70 (86)	50	81 (94)	75 (95)	94 (100)	89 (102)	59	85 (95)	
Foot, length	236	216	136	250	224	260	276	249	240	
Foot, breadth	87	81	60	97	86	102	100	101	91	
III.—BERECHNETE INDICES.										
Langenbreitenindex	72,3	82,7	79,6	83,5	75,8	79,4	78,0	75,0	80,3	
Ohrhothenindex	60,6	72,6	65,9?	67,6	64,0	67,7	67,2	65,3	69,4	
Gesichtsindex	91,3	79,8	73,6	85,0	83,2	81,0	84,0	82,3	79,4	
Nasenindex	68,6	83,7	90,9	88,8	76,1	71,6	71,1	80,0	83,3	

II.—BODY MEASUREMENTS.

OUTLINE OF TWO YEARS' SCIENTIFIC
RESEARCHES IN CEYLON.

BY DRS. C. F. AND P. B. SARASIN.*

(Read February 16, 1886.)

IN the short space of a report it will naturally not be possible to enter into any details: we can simply give a few results which seem to us to be of interest. Further, we must omit to refer to and compare notes with works already published on the different objects we speak of: this we reserve for our future publications in Europe, of which copies will be sent to the Society.

I.—ANTHROPOLOGICAL.

We begin with some anthropological notes, and shall later on refer to our chief branch of study, zoology.

We did not intend, when we came to Ceylon, to make anthropological investigations; but as the races in this Island proved of the highest interest, we could not but spend a part of our time in examining them. During our journeys, in which we traversed the Island in nine directions, we acquired a great deal of information on this subject.

As is very well known, Ceylon contains three principal races, the Singhalese, the Tamils, and the Veddás. There are others, whom we may dismiss with a brief remark; for instance, the Moors, more or less casual inhabitants, Arabian

* In offering this Paper to the Ceylon Branch of the Royal Asiatic Society, we wish to express our best thanks for the kindness shown to us by this Society in presenting us with an almost complete series of the Society's Journals. Besides, we owe a debt of gratitude to many individual Members for the ready assistance they have been good enough to give us in our exertions, and to which we think we cannot reply in a more appropriate way than by laying before you a preliminary report of our researches.

merchants, who settle in every trading place of the East. In a very few parts only the Moors have their own villages, chiefly so in the Batticaloa district, where they form about one third of the inhabitants. The Afghans, Malays, Kaffirs, Parsees, &c., are of no importance for our purposes.

The two races, Singhalese and Tamils, are not living side by side in the same districts, as is often believed ; such is only the case in the large towns and upon the hills, whither the Tamils are imported as coolies by the planters. Generally speaking, the Singhalese inhabit the hilly zone and the fertile and wet Western and Southern Provinces ; they attain their greatest density, according to the census of 1881, in the district of Colombo ; they are very scarce in lower Uva, in the North-Central Province, and in the northern parts of the Kurunégala district.

The Tamils, on the other hand, with the exception of those in the planting districts, live on the eastern coast of the Island. They are numerous in the Batticaloa district, less so in the district of Trincomalee, almost wanting on the coast north of Trincomalee. The real centre of the Tamils, however, is the densely populated Island of Jaffna, where they live to the exclusion of every other race : even the ubiquitous Moor is very seldom met with. Maññár and Puttañam, further on, are Tamil places, and south of Negombo there is an old Tamil colony, which has existed since the time of King Gaja Bahu I. (113 A.D.).

It would be erroneous to suppose that the districts of Singhalese and Tamils are adjoining each other : this is only the case in very few places, as, for instance, north of Chilaw. Otherwise, a broad belt of forest land separates the Singhalese countries from the Tamil ones. This belt, which is almost uninhabited, and in many parts completely so, begins to the east of Saffragam (Sabaragamuwa), maintains a breadth of 20-30 miles adjoining lower Uva, and expands to about forty miles in Tamankaḍuwa. This separating belt increases to a breadth of about sixty miles in the northern parts of the

Island : almost the whole Northern Province is without any cultivation, and therefore the Tamil Island of Jaffna is separated by an enormous rampart of forest from the Siphalese districts, even more so than the Tamil coast of Batticaloa.

We learn in the histories of Ceylon, and observe it at the present time, that Siphalese and Tamils intermarry sometimes. We know, even, that many kings of Ceylon have been of Tamil blood ; but notwithstanding this, a certain mutual aversion of the two races is not to be overlooked, and it is just that aversion which proves that a deep difference of race is existent. We learnt, for instance, in Trincomalee, that no Siphalese will die in that Tamil place, but as soon as one gets ill he returns to his native country ; and other facts still further illustrating this aversion could be mentioned.

The enormous belt of forest just mentioned, and the open park country the solitude of which is only interrupted by relatively few small villages, and very seldom by large patches of cultivated land, such as near the lake of Kantalay and round other smaller tanks, is the abode of the Vēddás. They live in the eastern part of Ceylon, and are the remnants of a tribe which deserves our attention in a very high degree.

We arrived too late for the exploration of this tribe. The original wild Vēddás are extinct,—at least, beyond some quite incredible rumours, we could not find any traces of them during the three months which we spent in searching for them in the remotest parts of the Island. All the Vēddás have been induced to leave the rock-caves, their old natural dwellings, and to settle in small villages under the charge of the headmen of the adjoining districts. The purest Vēddás we found are living in the Nilgala district, and near Bintenna ; others near Mahá-oya, in the Eastern Province, and in the Friars-hood range. But even these are already so accustomed to Europeans by their frequent visits to Kandy and Badulla, and by the hunters who have been to see them, that the Nilgala Vēddás, for instance, as soon as

they saw us coming, began to dance and to sing, and tried to tell us incredible stories. The settlement of the Veddás in villages gives naturally much occasion for mixing with other elements; many Sinhalese villagers marry Veddá wives, and therefore, all the intermediate types between Veddás and Sinhalese are to be met with. In many villages of lower Uva, where Veddás are already completely extinct, the traces of old Veddá blood are easily noticed in the features and in the dark colour of many a Sinhalese villager.

Similar intermarriages, or those which happen in the Sinhalese districts, are taking place on an even larger scale in the Tamil countries. On the east coast, north of Batticaloa, there are many villages, and Veddás have been induced to settle; and in these places the mixture of Tamils with Veddás is conspicuous. In this way the Veddás will disappear completely at a not very distant time; already, according to the census of 1881, there are not more than 2,228 individuals who still call themselves Veddás. The race is not dying out, as is generally believed, but is being absorbed by intermarriage with the surrounding tribes.

Our chief object was to ascertain whether the three races of Ceylon are really so different from each other that they could be distinguished by anatomical characters, or whether the differences between them were so insignificant that no positive result could be obtained by a careful comparison. A great obstacle to our purpose was necessarily the frequent intermarriages of the three tribes, which often left us in doubt whether the men we examined were of pure blood or not. The only way to obtain a satisfactory result was therefore to collect as large a number of skulls as possible, and to take measurements of numerous specimens of each race to compile averages. Thus we collected nineteen skulls of Veddás, fifteen of Sinhalese, and fifteen of Tamils. We dug them all up ourselves,—with the exception of some Sinhalese skulls,—and thus are sure that no confusion has arisen. We found no time during our stay in Ceylon to

examine these skulls,—we shall do so in Europe,—and therefore are now able to speak only of the results which we obtained by measurements of living individuals. Many of these measurements will have to be compared with those of skulls where alone measurements can be taken with mathematical exactness.

To begin with the height, we found the Veddás to be the shortest of the three races. Veddás of Maha-oya had an average height of 1,541 mm., eight from Nilgala 1,575, thirteen coast Veddás north of Batticaloa 1,591 mm. After these, range twenty-two Sinhalese with 1,624 mm., and finally, as the tallest, the Tamils, of whom twenty-five have been measured with 1,652 mm. of height on the average. The size of the head does not at all correspond with the height, as the largest head does not belong to the Tamils, but to the Sinhalese; and this fact is in accordance with the higher intellect of the latter. In size of head the Tamils range after the Sinhalese, then the coast Veddás, and by far the smallest heads are those of the Veddás in the interior. The coast Veddás contain, as already mentioned, many Tamil elements, and therefore in a number of measurements range between the Tamils and the other Veddás.

It may be interesting to point out in which measurements the principal differences are found. Firstly, the height of the face, that is the distance from the notch of the nose to the chin, is with the Veddá the smallest (105 mm.) on the average; it is larger in the Tamil head (111 mm.), and largest in the Sinhalese (115 mm.), and this difference gives to the whole face a different appearance.

Secondly, we have the diameter of the back part of the skull, or the distance between the two mastoid bones, in the Veddá only 124 mm., in the Tamil 130, and in the Sinhalese 132. The head of the Veddá is therefore in its back part narrower than the head of the two other races, and especially of the Sinhalese, and we have strong reasons to suppose that the brain of the Veddá is likewise much

smaller than that of the Tamils, and still more so than that of the Sighalese.

Thirdly, the lower jaws of the Veddás are much narrower than those of their neighbours. A fourth difference is found in the size of the eyes, as the Veddás have the largest and the Sighalese the smallest eyes of the three, the Tamils ranging here also between the two others. The differences in this last measurement are naturally very small, but still noticeable.

One of the most striking features in the face of the Veddá is the shape of the nose; firstly, it is very broad, 40 mm., while with the Sighalese it is only 39 mm., and with the Tamil 38 mm.; secondly, the bridge of the nose between the eyes with the Veddá is in most cases very low, sometimes almost flat. This fact gives to the Veddá nose a strange shape, and strikingly influences the features: the bridge is higher with the two other races. The Sighalese have often very well-formed eagle-shaped noses.

Besides these peculiarities of the Veddás already mentioned, shortness of face, narrowness of the back part of the skull and the lower jaw, largeness of the eyes, and lowness of the bridge of the nose, we could mention more differences in the measurements of the head; but it would lead us too far for the present, and we think it sufficient to show that such peculiarities do exist, and are to be traced by measurement. The results which we shall obtain by comparison of the skulls, we shall be glad to lay before this Society after our return to Europe. Taking exact measurements of the limbs is still much more difficult than measuring the head, and of the results obtained we venture only to specify now the following one as fairly well established. The lower arm of the Veddá and also of the Tamil is relatively a little longer than that of the Sighalese.

The colour of the Veddás is always a dark and dirty chocolate brown, a colour which is likewise frequently found with Tamils, but seldom amongst Sighalese.

Summing up, we learn by the measurements that the Singhalese, Tamils, and Veddás are three well-distinguishable races, and further, the measurements give much reason to suggest that the Tamils are more closely allied to the Veddás than the Singhalese, which latter no doubt represent the highest race, whilst the Tamils in many respects range between the two others.

One result in any case is certain, viz., that the Veddás are by far the lowest in the scale of the three races, not only in their habits, but also in their anatomy, and this fact confirms the opinion of those who claim the Veddás as the remnants of an old tribe of Aborigines. We can pass over the customs and the religion of the Veddás, because former writers have dealt with them, and the principal facts are generally known. We will call attention to one point only, because it illustrates clearly the primitive customs of this race, and that is the wearing of leaves as a cloth. A string is tied round the loins, and small branches are put underneath, till a thick belt of leaves is formed. This custom is now almost extinct by increasing civilisation, but almost every Veddá, if requested to do so, will appear in a few minutes in his dress of leaves.

It is our intention at a later period to deal more exhaustively with the anthropology of Ceylon, and to illustrate our writings by maps and photographs. We therefore confine ourselves in the meantime to these preliminary notes.

II.—ZOOLOGICAL.

As zoologists, our labours in Ceylon were naturally devoted to the study of animals. Before we came to this Island we had set ourselves the special task to discover the development, then entirely unknown, of *Epicrium glutinosum* = *Coecilia glutinosa* (Linn.). This is a kind of ground snake, living in the tropics of the East, and known long since; the shape of the animal is like that of an eel, one to one and a half feet in length, dark brown in colour,

with two yellow side-bands. The skin is lubric, like that of a frog or a salamander. It lives under the surface soil near rivulets or ponds, in cavities which it digs for itself. Its eyes are small; there are no feet. Two tentacles, which are at the top of the snout and are retractile, are very remarkable; further, the skin is particularly interesting, because there are imbedded in it numberless very small round scales like those of fish, but invisible from the outside, and also different from the fish scales in their finer histological composition. The genus *Epicrium* has some few relatives in America, which bear the old name of the whole class, viz., *Coecilia*.

It is but natural that this animal should excite the greatest interest of naturalists, and that many efforts have been made to arrive at a clear knowledge of its position in the natural system. The conclusion arrived at was, that it ought to be ranged under the order of the *Amphibians*, and not, as it was supposed formerly, under that of the *Reptiles*, especially of the snakes. Later on, as there have been found different anatomical peculiarities which pointed out a somewhat isolated position of the animal, it was raised to a special order, that of the *Assoda*, and was put in the lowest rank of the general class of the *Amphibians*.

We know from experience, that if the position of an animal in the natural system is not clearly understood, its development throws light upon the question, the animal in its development showing the traces of those forms which it had to run through, according to the theory of evolution, to arrive at its present form. We know, for instance, that the well-known water-salamander (*Triton*) is an animal which for some time of the year lives on land, and breathes through lungs; it lays its eggs in the water, and out of them come forth larvæ, which have at each side of the head near the ear a bundle of gills. Feeding in the water the animal gradually obtains lungs, the gills atrophying, and finally dropping off; it then seeks land, and

breathes air. Now, the question is this: Does *Epicrium* show the same mode of development as the water-salamander, or not?

It was known that the order *Epicrium* has been found living in the water, and at each side of the head, where gills were expected to be, they had little openings. But this was all that was known about the development of *Epicrium*. Here began our work. It was evident that we had two suppositions: Either, *Epicrium* lays its eggs in the water, and there the young ones take their development (as is the case with the salamander), or *Epicrium* is viviparous. So we carefully examined all ponds and rivers in the vicinity of which we found the full-grown animals, but though we often met with young specimens living in water, with a gill-hole at each side of the head, yet we never found gills, but always well-formed lungs; earlier stages did not come to our notice. So we began to dissect the full-grown animals, and to examine them for embryos; we opened about a thousand females, yet we never obtained the result so much wished for. At last a cooly brought a little lump of eggs, which he had found in the ground near a rivulet, and from this moment the mode of development was discovered, which generally proceeds in the following manner:—The pregnant female forms in the soft damp soil at first a small globular cavity, and deposits there a lump of about thirty pretty large eggs, connected with each other by a sort of string. The mother curls herself round the eggs, and broods probably in order to keep them damp with her body in the case of sudden drought. The eggs are of the size of a very large pea, and yellow, bearing a close resemblance to those of reptiles, the lizard for instance; in size, therefore, they cannot be compared to the eggs of a frog. In such an egg an embryo develops, which is especially interesting owing to the circumstance that behind the eyes, on the same spot where the salamander has them, three long gills are growing, of which one is directed forward, one upward, and one

backward. The gills have the shape of ostrich feathers, and as they are red like blood, the embryo, after being artificially freed from the egg, looks really pretty. Its colour is black, but the yellow yolk adheres to the belly. This shows that the *Epicrium* whilst in the egg passes through the same stages which the salamander passes through in the water. In the salamander, the reason for gills is clear: they serve the young animal to breathe in the water like fish; in *Epicrium*, the gills are as well formed as in the salamander, but as they are not required to act as breathing organs under water, their existence is not so easily understood; yet they are perhaps of some importance as organs of breathing of the embryo in the egg. The embryo remains in the egg for a very long time, until it reaches the size of about six to seven centimetres; it also moves rapidly if at that time it is artificially freed and put into water. The next thing we observed was the young *Epicrium* living in water with two gill-holes, but without gills; the size of the youngest was only a little larger than the full-grown embryos. It is therefore certain that the embryos break the shell of the egg, strip off their gills when wandering through the soil to the water, and live for some time in water with simple gill-holes and lungs, which had developed already in the embryonic stage. A young *Epicrium*, or so-called larva, when living in water comes from time to time to the surface to inhale air. By and by the gill-holes close, the young animal appears on land, and no more leaves it; when put back into the water it is soon drowned.

It now would no longer be correct to assign to the *Epicrium* the lowest position in the natural system amongst *Amphibians*. The *Epicrium* has generally the same development as the salamander, and has therefore its position quite near the latter. The salamander belongs to the *Amphibians* with a tail, in contrast with the frog, which is a tailless *Amphibian*. The *Epicrium* was considered to be without a tail; in the full-grown specimen, however, a trace

of a tail is discernible, and the embryos show clearly a short tail with a well marked fin. These are the main features of the development of *Epicrium*. There are many other points of interest, but they come more into the scope of a specialist, and could not be explained in a short paper and without the aid of drawings, and they will have to be dealt with accordingly at a later period.

The chief results are briefly—

- (1) *Epicrium* (like *Coecilia*), on the basis of its anatomy, cannot be placed in any known group of Amphibians.
- (2) Its embryonic evolution passes through the same stages as the salamander as a larva.
- (3) In consequence, *Epicrium*, notwithstanding its very different appearance, has to be classed as the nearest neighbour of the salamander.

The researches just referred to occupied us about eight months at Péradeniya. We then proceeded to Nuwara Eliya to begin studying the *rain-worms of Ceylon*, both from a histological and a systematic point of view. The hills of Ceylon are of special interest in possessing quite a gigantic species of rain-worm, which attains a length of about four feet, and a thickness of a big thumb. We hoped to find other similar species, but we met only with smaller kinds that were new, amongst which were a beautiful blue-ringed one of rather large size, and many smaller ones of less striking appearance. Ceylon being an island long since separated from the continent, those animals living in the soil, as they are, must be of a peculiar interest, and an exact systematic examination of the rain-worms of Ceylon might induce an investigation of those of India. The comparison of the forms in both countries promises valuable results as to the range of geographical distribution; it might also furnish a further basis for speculation about the changes of the continents and islands in the course of time. Now, it is true that the rain-worm is very easily transferred in many ways;

we know already, that upon the different elevations of the hilly zone of Ceylon, different forms are found which are not to be met with in the low country, and which represent probably similar endemic forms, as for instance amongst the lizards in *Ceratophora* or *Cophotis*. It is not the place here to enter into our anatomical and histological examinations of these animals, as they are of too special a scientific interest; but we may mention that a considerable portion of our labour was directed towards the examination of the vascular system of the rain-worm, which we tried to investigate physiologically.

A result of more general importance, which we obtained by histologically examining the skin of *Epicrium* in Périadeniya, and that of the rain-worm in Nuwara Eliya, is the following :—

The body of every animal, with the exception of the lowest order, as the animalculæ, &c., is surrounded by a more or less thin layer, the so-called epidermis: it is not homogeneous, as glass for instance, but composed of innumerable very small corpuscles, the so-called cells, which are arranged like paving stones. Just under this epidermis the finest branches of the blood vessels are spread like a net. The same is the case in the lungs, and as here the blood comes to a very near contact with the air, it absorbs oxygen and returns carbonic acid; that is the process we call breathing. As the blood is separated from the outer air by the above-mentioned fine skin, the epidermis, the receiving of oxygen and returning of carbonic acid was explained as possible by the physical law of diosmose. But further it was observed that the different cells of the epidermis do not adjoin each other, but that between them a number of cavities exist, and the cells themselves are connected with each other by exceedingly fine communicating filaments. The outer layer of the body was found therefore to be not solid. In the *Epicrium* we observed that from the finest vessels just underneath the epidermis, little tubes ascended outwards, which

after having reached the epidermis, divided into tiny arms like those of a chandelier, and these arms again were connected with the range of cavities between the cells of the epidermis. These cavities communicate with the surrounding medium ; so we learned that the fluid of the vascular system communicates by means of the very fine tubes, and the cavities of the epidermis just described with the outside. The tubes are so small that even a blood-corpuscle is much too large to pass through ; and further the blood-fluid, the so-called serum itself, cannot flow out of the skin, according to the law of capillarity. We pursued the subject further, and found a similar state in the gills of fishes, the skin of snails, leeches, and rain-worms. This discovery of a direct communication of the vascular fluid with the outer medium, obviates the use of the law of diosmose, and the process of breathing becomes more intelligible. It is to be hoped that injection into the vascular system may lead to a conclusive proof of our theory.

The next five months were devoted to travelling in the south-east of the Island, partly in search of information about Veddás, partly with the object to obtain an embryo of an elephant. His Excellency the Governor had the kindness to give us free permission to shoot elephants, with the special right also to kill females for the aforesaid purpose. But unfortunately our exertions in this latter direction were not successful. Three female elephants were killed, but none had an embryo. Part of the intestines of the animals has been preserved for future histological examination.

During our stay in Ceylon, we used to collect whatever seemed to be important, and thus a fair amount of scientific material has been accumulated, which will be dealt with in Europe after our return. Many new specimens which we were able to secure in the course of our stay we pass over here, because they have not yet been exhaustively examined. However, we shall briefly touch upon the chief results of our four months' stay at Trincomalee.

We discovered there two snails living as parasites on a sea-star. Until now only very few parasitic snails have been found. The most famous kind is *Entocontra mirabilis*, which lives in a holothuria, and is an animal that in appearance is only with difficulty to be distinguished from an intestinal worm; but its eggs develop fully-formed young snails with shell, feet, and eyes. This is a new example to show how impossible it is in many cases to understand the systematic position of an animal without the knowledge of its development. The snails examined by us are not so extraordinarily deformed as the *Entocontra*, yet they have many characteristics. Our two snails are quite different from each other: they are also living on different parts of the sea-star. The one which inhabits the interior of it is about a quarter of an inch long, and has a well-formed somewhat hard shell. Where it dwells, the body of the sea-star is inflated to a spherical cavity, and when the apex of the shell touches the skin of the sea-star, a little hole is formed, which through the interior of the cavity is in communication with the outside. The snail can hardly move, and thus lives like a captive in his cell. The most remarkable feature is, that the mouth of this snail, which is small in other species, is extended into an enormous proboscis, almost twice the length of its body. This proboscis is immovably connected with the inner side of the body-cavity of the sea-star, and through it the snail sucks the fluid of the sea-star as its nourishment. Underneath the shell the snail has a gill, and for breathing it requires sea-water; this streams through the above-mentioned hole into the cell of the snail. The water for breathing has constantly to be renewed, and to render this possible, the following apparatus serves: At the root of the long proboscis rises a bell-shaped muscular fold, which rests with its inner side against the shell of the snail, with the outer side against the wall of the cavity, and which is so large that it covers the shell completely. We have not

watched the function of this muscular bell, but we believe that it very likely works as a pump for constantly renewing the water in the cavity. This snail is most probably to be ranked in the system near the genus *Hylina*.

The other snail lives not inside the sea-star, but upon its skin; its shell has the shape of a Phrygian. It is like the other, immovably connected with the sea-star, the base of its proboscis being enlarged to a disc, and this being connected with the skin of the sea-star by numberless little folds. It lives like the other on the body-fluid of the sea-star.

The sea-urchins are characterised by a globular hard shell, which is covered all over with spines. The regular sea-urchin has the mouth at the lower pole of the spherical shell, at the upper one the arms. Wyville Thomson was the first to discover a sea-urchin the shell of which was not hard but flexible like leather; the spines were quite short, only about a quarter to half an inch in length, and surrounded by a thick skin: thus they looked like little clubs. In later years a good number of other specimens have been brought up from the deep sea during the expedition of the "Challenger." In Trincomalée we were lucky enough to discover in a depth of four to six fathoms in the harbour, a beautiful new species of this group. The greatest diameter of the animal was about six inches; its height not quite two inches. The colour was a dark brownish black, and this ground was covered with small spines resembling clubs, in consequence of the skin around them. Besides, small azure corpuscles on stalks ran in radial lines from the upper to the lower pole, and adorned the sea-urchin like jewels. These corpuscles, as well as the other larger spines, have a most striking peculiarity. If the animal is taken into the hand you feel a pain as of about a dozen bee-stings, which lasts for some three or four minutes, then it ceases completely. The small spines as well as the blue corpuscles turn against everything that approaches, and from a more precise examination, the result we came to

was, that, as is known to be the case with insects, every spine is provided with a peculiar bag of poison, the spine itself being hollow, and the poison flowing out of the bag through it into the wound; the blue corpuscles especially have round the bag of poison a fairly thick ball of muscular substance, and this contracts if the fine spine inside of the corpuscle penetrates into the skin. We have no doubt that a similar apparatus also exists in the other leather-urchins, but it has not yet been determined. It is evident that this soft sea-urchin would soon be destroyed by fishes of prey if it had not the formidable arms just described. This circumstance a small fish availed itself of; this little animal, which is in length about one inch, lived just between the spines of the sea-urchin, so that a pursuing fish could not come near it at all without being wounded by the spines of the sea-urchin; moreover, the little fish had the same dark brown colour as the sea-urchin, and was thus doubly protected.

Until now in no sea-urchin had a real eye been found. It was noticed that many had a very feeble perception of light; but it was impossible to state that they could really see. This is quite correct of the great majority of the sea-urchins; but in the genus *Diadema*, which is very common throughout the tropics, we found most curiously composed eyes, somewhat similar to those of insects. As light blue spots they run round the surface of the black sea-urchin, like the above described blue corpuscles of the leather-urchin. Each of these blue spots consists of many hundred small crystal cones, which rest upon a layer of nervous substance. Microscopical examination had already shown that the blue spots were eyes, and the simplest physiological experiment confirmed it. If the hand is brought near the aquarium which contains the sea-urchin, without touching the water of course, the urchin at once directs all its long spines against it to protect itself; it sees therefore very well. Between the spines of *Diadema* a little fish lives, which

is protected in this case by the length of the spines, while the above-mentioned one found protection in the poison-apparatus of its host.

During the last days of our residence in Trincomalee, a sea-urchin was brought to us, which both by its size and by the splendour of its colours quite surprised us. It was a foot in diameter exclusive of the spines, which were two to three inches long. Its height was about six inches; on the ventral surface were shorter and stronger spines than above. Its colour was brownish black, and over it ran from the apex downwards broad Saturn-red bands, which in the whole of their length were dotted with very large splendid azure spots; these spots we discovered to be eyes, as in the case of *Diadema*. This gigantic sea-urchin has up to the present no rival, as far as we can learn from the literature on the subject. Probably it was brought up from a great depth to the shore by the strong current of the north-east monsoon. Should it prove, after a more exact systematical examination, to be a new species of the genus *Diadema*, we would propose to give it the name of *Diadema imperator*.

A BRIEF SKETCH OF THE MEDICAL HISTORY OF CEYLON.

BY J. L. VANDERSTRAATEN, M.D.

Principal, Ceylon Medical College.

(Read Nov. 18, 1886.)

INTRODUCTION.

AS I am to deal with a subject which is somewhat special, it is my natural desire, in expectation of meeting a mixed assembly, that my treatment of the contents of this Paper should be such as to prove interesting and instructive to non-professional as well as professional persons. To the professional part of my audience, the medical annals of this Island cannot but be replete with interest; and I trust that my other hearers will derive some useful information from an attempt to give an account of diseases which have prevailed in this country from the earliest period of which we have any record, the progress made by European medicine, and of the improvement in the sanitary condition of this Island effected during the present century.

Although the inhabitants of this beautiful Island have had a fair share of the "ills that flesh is heir to," it is satisfactory to know that the efforts which have been made by the officers of the Medical Service of this Colony, under the direction of an enlightened and beneficent Government, and by local self-governing bodies, for the improvement of the health of the people, have, through the blessing of a merciful Providence, been crowned with a great measure of success.

It is not my purpose to give you statistical details: these might add greatly to the value of the information contained in this Paper, but would detract from its interest. I shall merely give a statement of facts: and in taking a rapid glance at our past medical history, I will, in the first place,

touch on the salient points connected with the native or Buddhist system of medicine ; next, on the medical history of the Portuguese and Dutch periods, so far as learned from records at my command ; and lastly, on the great sanitary reforms effected since the British occupation of the Island.

There is a mine of rich material worthy of exploration in the archives of the Civil Medical Department, dating from its separation from the Military Service in 1858 ; but I have been able only to make use of published records and of the Administration Reports and Sessional Papers of the Legislative Council from 1864, the period at which their publication commenced.

SINHALESE SYSTEM OF MEDICINE.

In the early part of the third century B.C., Aśóka was the great Buddhist sovereign of India. He propagated the new doctrines of Buddha by erecting columns or pillars, on which were engraved those memorials or edicts he was desirous of making generally known. These inscriptions are remarkable monuments of the sagacity and benevolence of that great sovereign, who erected viháras, monasteries, and hospitals, thus giving effect to whatever there is of beneficence in Buddhism.

From an early period, the priests charged themselves with the duty of educating children and relieving the sick. It was in Ceylon that the Buddhist doctrines were first reduced to writing. These doctrines addressed to mankind in general, besides inculcating the duty of reverence to parents, love to neighbours, charity and other moral precepts, recommended the prosperous and wealthy to found Refuges for the blind, the destitute, the crippled, the sick and wounded both of man and beast. This was taught to be the surest method of attaining to the highest degree of perfection and holiness on earth, by means of which the future reward of the Buddhist faith might be obtained, viz., *Nirváṇa*, or an easy departure and utter annihilation. These motives actuate some of

the Buddhists to this day, and I have learned from reliable authority that the Buddhist contractor of the Planters' and Anthonisz Wards (Mahámarakkala Kurukulasúriyapāṭa-bēṇḍigé Solomon Perera) has actually built these hospitals simply at the cost price of the materials, in the hope of obtaining merit here and *Nirvāṇa* hereafter. King Aśóka also recognised the sanctity which attaches to human life, and directed that the life of no living being was to be taken; and that wells were to be dug, trees planted, and *caravan-saries* erected in public highways for travellers.

The medical houses, or hospitals, of that period, were to be provided with all sorts of instruments and medicines, consisting of mineral and vegetable drugs, and food; and skilful physicians were appointed to administer them at the expense of the State. Those physicians, or *Vedarālas*, who had gained a knowledge of Sanskrit, committed to memory stanzas, and recited them by the bedside of the patient. These stanzas were from the *A'yur-Veda*, a religious treatise on the science of life and medicine.

The *A'yur-Veda* (from *áyur*, period of living, and *ved*, to know, treating of the science of life and medicine) is said to have been first preserved by oral tradition in the form of hymns, prayers, and precepts. It is regarded as the most ancient and authentic book on Oriental medicine, next to our own Bible, and consists of one hundred lectures, of a thousand stanzas each, called *ślokas*.

Fragments only of the manuscripts are now extant. It was supposed to have been composed by Brahma, 900 B.C., and handed down to the Buddhists by the Brahmins. It was intended to teach the proper manner of preserving life, and the means of preventing and curing diseases. Dr. Wise, the author of the "History of Medicine among the Asiatics," says that it contained a description of the structure of the human body prepared from actual dissection, an account of the causes and diseases to which it is subject, the enumeration of many useful remedies, and precepts for preserving

health and curing diseases. The works studied by our *Vedarálas* in Ceylon now, are the *Śastris*, *Charaké*, and *Suśruta*, which are commentaries on the *A'yur-Veda*. The first is arranged in the form of a dialogue or conversations between *Atrya*, the master, and his pupils in their conferences. Sir Whitelaw Ainslie gives a list of twenty-one Sanskrit medical works, known in the early part of this century among the Singhalese and Tamil. There are no doubt several very intelligent and trustworthy *Vedarálas*, who are Sanskrit scholars, and study manuscripts on “olas,” or leaves ; but there are also a larger number of ignorant impostors in the villages, to whom the words of Job are applicable : “But ye are forgers of lies ; ye are all physicians of no value !”

The Tamil books of medicine derived from the same source are published in the Tamil and other Dravidian languages. The Tamil practitioners are styled *Vayittiyan* and *Parikári*. The *Vayittiyan* of the Tamil people is largely engaged in treating infantile ailments, and many of them even confine their practice to children only of all classes, Muhammadans as well as Hindús. Those who take an interest in the Oriental system of medicine, and wish to pursue the study of the ancient Hindú, Buddhist, Arabian, and Chinese systems of medicine, will find a full account in Wise's “History of Medicine,” published in 1867. The Moors or Muhammadans of Ceylon have their own native practitioners, who blend the Arabic with the Hindú systems of medicine. The recognised physician is called *Hakim*.

There were many kings of Ceylon who built hospitals and practised medicine themselves, and by their noble example made it an honourable profession. According to the *Mahá-waṇsa*, Buddha Dása, who reigned for twenty-nine years, from 339 A.D., was the author of a medical work called the *Sárārtha Saṅgrahaya*. Many wonderful cures are attributed to him. He built hospitals for every ten villages, and placed medical men in charge of them. They were to receive one-fortieth of the revenue derived from fields for their

maintenance. He also appointed medical men to attend on his infantry, and veterinary surgeons to attend on cattle and elephants. Along the roads he built halls for the lame and blind. It is said that "When he went out of the palace, his surgical instruments were always in his waist, and he operated upon all sick persons whom he met." King Agbo, who reigned six years, from 782 A.D., caused medicines to be distributed among the sick; and Dappula II., who commenced his reign in 795 A.D., is most highly spoken of in this respect, in the following words: "That most gracious Prince built a hospital at Polonnaruwa. He also in like manner built a hospital at Pandaviya, and endowed it with villages which yielded the necessaries of life. He also built in several places halls for the cripples and the blind. In short, he did not leave anything undone which was called meritorious; he even gave growing paddy crops to cattle, and rice, mixed with honey and sugar, to children."

Parákrama Báhu, who reigned from 1163 to 1196 A.D., built a large hospital capable of accommodating hundreds of patients, and appointed a manservant and maidservant to attend on each patient for the purpose of supplying him or her with necessaries of life and medicine. He ordered medicines and the necessaries of life to be made and stored in the hospital, and appointed skilful and salaried medical men to attend on the patients. Divested of his royal robes, he visited the hospital four times a month, and inquired into the nature of the disease of each patient, and the mode of treatment adopted; and whenever the treatment was in his opinion erroneous, he taught the physicians the proper method, and attended himself to some cases.

When the patients recovered, he distributed clothes amongst them. This prince is said to have cured a crow of a tumor, and the bird, it is stated, would not leave the hospital until attended to! Nor was sanitation ignored. King Pandukábhayo, who reigned 437 B.C., employed one hundred and fifty men to carry dead bodies to the cemetery, and one hun-

dred and fifty men as cemetery-keepers and sextons, besides two hundred night-soil men, a small number of day and night guards, and a small army of sweepers.

PORTUGUESE PERIOD.

In the history written by a Portuguese author, Juan Ribeyro, in 1685, there is only a very brief description given of the diseases which prevailed in Ceylon at that period, and I can find no allusion to the methods of treatment adopted by medical men of his own nation. The Portuguese priests and captains of companies appear to have been in medical charge of the garrisons of Colombo, Kalutara, Negombo, Batticaloa, Trincomalee, Jaffna, and Mannár.* Ribeyro states that most of the Portuguese on their first arrival were subject to bowel complaints, fevers, and other diseases, to which the natives are not liable. He thought that the Siphalese retained their health by frequent baths, and states that when he first came out to Ceylon he had two illnesses in the first two years. He then adopted the native habit of bathing twice daily, and during the sixteen subsequent years he lived here he never became ill. Frequent bathing is acknowledged to be one of the best means of preserving health, and is practised by the natives to this day ; but it is in strange contradiction to the experience of an old colonist of 70 years, an Italian, now dead, who attributed his immunity from disease to his *never* bathing !

Ribeyro describes “beri-beri” (*bére-bére*) as a disease to which Europeans were very liable. He recommended as the best remedy pork and biscuit, with palm wine (toddy) and smoking, to be persevered in for three months. As a

* A correspondent points out that Le Grand has not followed Ribeyro accurately here. “It is not strictly correct to say that the Portuguese priests and captains of companies appear to have been in medical charge of the garrisons of Colombo, &c. Ribeyro (Bk. I., chap. xiii) distinctly says that when the soldiers were seriously ill they were sent to the hospital at Colombo, and that the surgeon had to certify the necessity of this : Le Grand omits this statement.”—*Hon. Sec.*

prophylactic against this disease, the Captain General Antonio de Mascarenho issued an order for every one in the camp to smoke.

Ribeyro only briefly alludes to "Parangi" disease (*Parangi leda*), that unsightly and disfiguring skin disease which prevails to this day in the districts of Mullaitivu, Vavuniya-Vilankulam, Anurádhapura, and Kurunégala. He called it the "Neapolitan disease," named by the natives "*Paranguelere*," or "Portuguese sickness," since the Portuguese first introduced it into this country; and he says it "is not easily cured."* Fever is only mentioned, to be dismissed with its remedy, viz.:—a decoction called *coantru*.† Those who know Portuguese are aware that the remedy is a common and useful one, employed to this day. Coriander seeds boiled down with ginger into a decoction is commonly used in the cold stage of ague, and in catarrhs and colds in the head. Ribeyro states, as we can bear testimony even now, that no people understand the use of simples better than the Sinhalese, so that with a few herbs or roots they cure wounds, ulcers, and swellings; but it is extravagantly stated that they set broken arms and fractured legs, and put those matters to right in a very few days. He also noted the good effects of herbs as antidotes against the bites of snakes and venomous insects. We must admit that many *Vedarálas* are good bone-setters, although they have no proper appliances for preventing shortening of broken limbs. Their method of stuffing a wound and keeping it dilated, when it is connected with a compound fracture (although aromatic, antiseptic, and astringent herbs are used to check bleeding and prevent putrefaction) cannot be approved except as a temporary measure, until proper surgical aid is obtainable. The historian

* The writer quotes Lee's translation of Ribeyro, which is merely Le Grand's version Englished. Ribeyro's actual words are :—"As mal gallico chamao Parangue vere," &c.—*Hon. Sec.*

† Ribeyro, "*coentro*."

must have been deluded, when he was induced to believe that cancers, which are considered incurable in Europe, were cured in a week in Ceylon. Ribeyro also alludes to the prevalence of small-pox, which the natives called "*ankaria*, or an affair with God," because it appears as if only a miracle can cure it.*

The following sketch of the mission of Padre Vaz, a Portuguese Priest in Ceylon, who died in 1711, is taken from a Portuguese work written by Padre Dorego :—"The small-pox now visited Ceylon, and made fearful ravages. The people believing that all persons labouring under the disorder were possessed by the devil avoided them, as they would him ; the father ran away from his children, the wife from her husband, leaving them to perish without food : the sick perished, therefore, as much from hunger and panic as from the virulence of the disorder. The dead became so numerous that they were left unburied, or carried to distant places, while the poor wretches affected were driven by the Government into the jungle. When the contagion had reached Kandy, the king left it, as the stench of the dead bodies in the streets was unbearable. *Vaz* resolved to visit both Christians and Pagans, and being with provisions from his followers in Colombo, relieved their distress. He also followed the sick into the jungles, and building huts as well as time and place would permit, there sheltered them from the elements and the attacks of wild beasts : in a word, he contrived to supply every want, temporal and spiritual, performed the most menial services, opened hospitals in the deserted houses, and dared everything for their relief. The result was that members who were saved joined the Church,

* The same correspondent writes :—"This is Le Grand's statement. Lee in his translation of Le Grand did not attempt any explanation of this wonderful word *Ankaria* : what Ribeyro really wrote was *Deanéchariya*, i. e., *Deviyankâriya*. Le Grand apparently mistook the first syllable for the proposition *de* ! (I may mention that I possess the MS. of Ribeyro's narrative used by Le Grand, and that it reads *deancharia* ; in this MS. the words are run together very much, so that there was some excuse for this blunder.)"—*Hon. Sec.*

and had their children baptized. Ribeyro's editor, Le Grand, speaks of the habit of betel chewing among the natives, Portuguese and Dutch; he thinks it a wholesome practice, which purifies the breath, strengthens the gums, and cleanses the bowels. The Sinhalese at that time attributed their long and healthy lives to its use, and Ribeyro confirms it by saying that men and women were seen in Ceylon who had not lost a single tooth. We unfortunately know that the practice of betel chewing presents another side; it produces "betel-chewers' cancer."

DUTCH PERIOD.

The Leper Asylum at Hēndala is perhaps the only monument of the medical history of Ceylon during the Dutch period which is left to us. There is no authentic record of its foundation beyond an inscription on a stone, "Anno 1708," and a monogram scarcely decipherable, indicative perhaps of date of building and of the original owner of the property on which the institution stands. It is generally believed, on traditional authority, that it owes its origin to a philanthropic Dutch lady, daughter of a Dutch Governor, who was herself a leper, and at her death left the property to Government, in trust for the pauper lepers of the Colony.

In a memorandum made by Governor Van Imhoff in 1740, he commends this institution to the care of his successor. Although frequent search has been made among the archives of the Government Record Office for documents or information relating to the transfer, nothing has come to light to show how the Government became possessed of a property sixteen acres in extent, occupying one of the most beautiful sites in the neighbourhood of Colombo, at the mouth of the Kēlani river, admirably adapted from its situation, isolation, and distance from town for the segregation and treatment of lepers. This hospital was certainly the first in the Colony founded by private benevolence, and supplemented only of recent years by the foundation of other charitable institu-

tions, especially at the hands of the De Soysa family. In this Asylum, which has separate wards for lepers, and paupers suffering from incurable diseases, one hundred and forty-four remained at the end of 1885 and sixty-five were admitted during the year 1886, making the total number treated two hundred and nine : one hundred and ninety-seven lepers and twelve paupers. The patients treated in this institution, one hundred and seventy-six at present, are well cared for, and all that science and humanity can suggest is adopted for their comfort and happiness. The new wards are the finest of any in the Island, well built and well ventilated.

There is no certain information available with regard to the state of medical practice in this Island during the Dutch period, extending from 1656 to 1795. It is reasonable to suppose that there were army surgeons among the Dutch, as under the British, and that some of these were probably regularly qualified men from the colleges of Amsterdam, Utrecht, and Leyden,—with the latter of which the name of the great Boerhaave will ever be connected. There may have also been one or two civil practitioners, and these may have been assisted by young men of the country, who helped them behind the counter, and picked up a knowledge of medicines and their application. Among the hospital dressers and dispensers of that day, there were many who attained a certain eminence, whose names are yet recalled by old residents, who can remember them “with a touch of affectionate pride.” In those days the apprentice system was in vogue, and if there was no opportunity of walking the hospitals, there was, at least, for mixing and tritulating drugs. Medical skill was empiricism, and although Stahl, Boerhaave, and Hoffman, with the ancient medical classics, might have been studied by a few old Dutch doctors who came to Ceylon, the probability is, that like the early British army surgeons, the Dutch doctors who came here were not university men. However, from the large number of those who took service under the British at the cession of the Island in 1795, it is evident that medical

science had made some considerable progress in the Island, and that many native and Dutch descendants had applied themselves to its study.

Dutch physicians have been noted for their knowledge of botany, and the extensive field afforded in Ceylon for its study was an especial attraction. The flora of the Island was arranged and described by Linnaeus, with the aid of the celebrated herbaria collected by Herman and Hartog, both of whom were sent out to Ceylon by the Dutch East India Company, in 1671. It is also interesting to note that the first European writer on tropical diseases was a Dutchman named Bontius.*

There are no records extant to show that any effort was made by the Dutch to teach the science of medicine systematically to the natives, but it appears that the kings of Kandy often requested through the Government the medical aid of Dutch doctors, which the Dutch Governor of Colombo complied with.

The mission of Doctor Danielsz and his apprentice to the court of Kandy in 1739, to cure the King Śrī Vijaya Rājasinha of a bad leg, as recounted in his journal, is replete with interest. The late Doctor Koch, in his introductory lecture delivered at the opening of the session of the Medical School in 1872, thus recounts the particulars of that memorable visit : "Doctor Danielsz went accompanied by his apprentice ; but all he could see of his royal patient was the ailing limb. Under such circumstances it was impossible he could adopt any other course of treatment but what consisted of outward dressings. These he tried without any satisfactory results, and alarmed

* The same correspondent notes here :—"So far as I know, Dr. Vanderstraeten is correct in stating that Bontius was the first European writer on tropical diseases ; but there was another medical writer on the subject, who followed not so long after, and whose work passed through several editions. I refer to Dr. Egidius Daalmans, a native of Antwerp, who went to the East in the service of the Dutch in 1687, visiting Ceylon, Java, and India, and returning to his native land in 1689. Dr. Daalmans' book is very rare, the British Museum not possessing a copy."—*Hon. Sec.*

at the consequences of failure, he insisted on His Majesty taking a course of tonics. The decoction was prepared, but the king found it so bitter that he emptied the cup into the royal spittoon, suggesting that the doctor should employ the more agreeable article of arrack for the conveying of the nauseous potion. Doctor Danielsz hereupon brewed two bottles of bitters, but he prescribed so small a dose of it at a time (he calls it a small beer-glass full) that His Majesty demanded either a double dose or to be allowed extra liquor over the bitters ; after a good deal of resistance the doctor was at last compelled to yield, and as he said he was himself in the habit of taking a *schnap* before meals, his patient also might, but positively not beyond the third day. In the meantime the leg was not improving, and the *régimen* was becoming intolerable, and so Doctor Danielsz was bid prepare to leave Kandy ; and, if he could not congratulate himself on his professional success, we may yet suppose he was glad enough to escape the attentions of his patient, which now began to assume a form slightly more imperative than was altogether pleasant. So Doctor Danielsz and his apprentice returned to Colombo, and continued no doubt to adorn the profession till the natural close of his not uneventful life."

BRITISH PERIOD.

Mr. Henry Marshall, Surgeon to the Forces, who served here from 1808 to 1821, has left us a valuable work on the " Medical Topography of Ceylon, and on the Health of the Troops employed in the Kandyan Provinces from 1815 to 1820, with brief remarks on the prevailing Diseases." From this work I have gathered some interesting passages. The troops employed during the early British occupation consisted of Europeans, Caffirs, Malays, and natives of India. Marshall says that the individuals of each class preserve a strong physical and moral resemblance, using the same food, having similar wants, undergoing the same labour, and suffering the same privations. Each class had particular

prevailing diseases, according to the effect of the climate, exposure to malarious influences, and variations in their food-supply. The Europeans suffered from the endemic intermittent and remittent fevers, abscess of the liver, and dysentery, but they were greatly exempted from many diseases to which they are liable in their own country. A large number of British soldiers suffered from the effects of intemperance added to the effects of the climate, and no wonder when arrack was then retailed at sixpence a quart ! It was Marshall's opinion that the regular issue of spirit rations engendered the desire for the immoderate use of spirits, and that frequent indulgence created a craving which had to be supplied. The same sad tale of spirit drinking, as one of the principal causes of sickness and mortality among the troops in Ceylon, is repeated in the Military Sanitary Report for 1864. Five per cent. of the troops were then reported to be confirmed drunkards.

Africans, called at that time "Kaffries," and who composed five companies of the 2nd Ceylon regiment, the remains of two other regiments 3rd and 4th, were chiefly recruits procured on the east coast of Africa, in the neighbourhood of Mozambique. A few of them were evidently children of Africans brought here by the Dutch. They made good soldiers, and were remarkable for longevity. They were habitually temperate ; but the Malay recruits from Java and Sumatra, for the Ceylon regiments, were addicted to the use of bhang and opium. Although the immoderate use of these narcotics was nearly as hurtful as the free indulgence in spirits, the excessive opium eaters among the Malays were less numerous than the immoderate drinkers among the European troops. They were liable to intermittent fevers or ague when exposed to malaria in the jungle ; inflammation of the lungs, consumption, asthma, and pocky-itch, so called by Mr. Marshall from the eruption leaving deep marks on the skin. The Indian troops, who formed the corps of Gun Lascars, the Pioneer Corps, and five companies of the 2nd Ceylon

regiment, came from the Madras Presidency. They were a useful addition to the garrison, and were capable of much exertion when kindly treated. They were sober, temperate, and submissive, but extremely filthy, and owing to their neglecting to provide against sudden changes of temperature, were more liable to intermittent fever, inflammation of the lungs, dysentery, and diarrhœa; Malabar itch was, as may be expected, very common among them.

Distress was caused in 1812, 1813, and 1814 by repeated droughts resulting in failing of the crops of rice. It was deplorable, says Bertolacci, to see the numerous children of the Ceylonese families reduced and emaciated for want of food, and depending upon parents who were in no way able to provide for their large families. No substitute could be found for the staple article of diet for the native troops, and consequently privation and exposure led to much suffering. At Minery, between Kandy and Trincomalee, fifty-three men of the 19th regiment were attacked with fever, thirty-three died, and twenty recovered; but several of them had their constitutions much impaired. Of thirty-three artillery men, eleven died.

In December, 1820, there were thirty-two military stations in the interior, the chief posts being Kandy, Badulla, Aliput (fifteen miles east of Badulla), Ratnapura, Fort King and Kurunégala, all of which were hospital stations. The Rev. Mr. Cordiner records that a small outpost in 1803, Koṭṭadeṇiya (thirteen miles from Kurunégala), was so unhealthy that of seventy men of the 65th regiment who marched to it, every one was seized with fever, and within a month Lieutenant Hutchings and two privates were the only persons of the party who remained alive.

It will be interesting, before proceeding further, to glance at the nature and extent to which the principal diseases which existed in Ceylon prevailed in the earlier years of the present century, soon after the British settlement in this Colony. Davy considered the effects of the climate of Ceylon

under three heads : "First, those which occur immediately ; second, those which are produced slowly and gradually ; third, those which arise occasionally and unexpectedly from the agency of peculiar causes. As to the immediate effects which result from the transition of the body from a temperate climate into a tropical one, we have ample evidence derived from the accounts of voyagers ; such as disagreeable sensation of heat, acceleration of the heart's action, increased perspiration, languor, restlessness, and thirst, diminished appetite and general indisposition"; but these do not constitute actual disease, nor do they necessitate active medical treatment. "Europeans landing in Ceylon are liable to few ailments due to immediate causes." Prickly heat (*lichen tropicus*) is perhaps the most common. "During the wet seasons," says Percival, "the Ceylonese are subject to a variety of diseases. Every man is here his own physician, and the mode of cure adopted is of course very simple. A plaister of herbs is applied to the part affected, and I have seen the same remedy applied to a man in a high fever, when his whole body was daubed over with this ointment. A skill in medical herbs is almost universal among this race, and they have a variety of prescriptions for curing diseases by their application. This knowledge is owing to their peculiar fondness for gardening, rearing all sorts of plants, an employment in which they are engaged from their infancy, and it is from among them that the European gentlemen are anxious to procure their gardeners."

Small-pox seems to have been, as it still is now, the most dreaded disease. It has doubtless been the one great cause of the depopulation of the Island, and Forbes thinks it was this visitation which was described as the "red-eyed demon of pestilence" that swept the country of half its people in the third century, under the reign of Śrī Sangabo. It is called *mahā ledḍa*, or "the great sickness," and is believed to be "a direct infliction of the gods." Percival states that persons dying of this disease were considered

accursed, and that, viewed as a means of God's vengeance, no attempt is made by incantations and exorcisms, as is done in other diseases, to propitiate the gods. Even the rites of burial are denied, the body of the dead being removed to a distant jungle, and then left covered with bushes and branches of trees to decompose. The goddess *Pattini* is believed to have the peculiar power of averting or preventing small-pox, and to her is dedicated a temple situated in the forests on the side of Ambokkekanda, where also stands the remains of Raṅgula Nuwara.* Pridham relates that during the prevalence of small-pox at Mátalé, the *Kapurála*, or lay priest, of Ambokké, was in constant request, and reaped an abundant harvest from the terror and superstitions of his neighbours. Every village in the vicinity of an infected place, by means of presents nominally offered to the goddess, but the most valuable of which were appropriated by the *Kapurála*, procured his presence; and the relics from the temple, consisting of a shield and bangle (amulet), were borne through the village followed by all the inhabitants, and duly honoured by the noise of every tom-tom, pipe, shank, shell, or trumpet which they could procure. The *Kapurála* had been at a former period afflicted with the natural small-pox, and was shrewd enough to have his whole family vaccinated, though his supposed temerity in visiting infected villages, and his good fortune in escaping contagion, were accounted for by himself, and believed by the people, to arise from the protection of the goddess. His influence was hence considerable, and his selfishness led him to use every secret means of checking the progress of vaccination among the dupes, by whom he was enriching himself.

Active measures in the prosecution of vaccination, the introduction of legislative measures to help on this good work, and to enable those in authority in the exercise of a wise discretion to isolate and effectually segregate the

* See R. A. S. Journal, No. 29, 1884, pp. 368-394.

infected, have diminished the horrors of epidemics of this disease, and in the present day a scene like the following, as described by Forbes, cannot be expected to occur: "I found," he says, "lying in a field, with her head close to a well, the body of a woman who had but lately expired. Tormented by thirst and deserted by her friends, she had crept to the water, whilst in the last agonies of this loathsome disease. By permission of her relatives I offered her property, including a portion of land, to whoever would bury the body, but all my arguments and entreaties would not induce anyone, even the most wretched pauper, to acquire a competency by burying it."

Cholera, as an epidemic disease, has at different times made fearful havoc in the Island. Marshal states that epidemic cholera having prevailed in 1817 in India, broke out at Jaffna and Mannár in 1818. It subsequently appeared in Kandy, Colombo, and other garrison towns, a few only of the smaller outposts in Sabaragamuwa, &c., escaping the infection. One of the earlier outbreaks occurred in 1832, at Trincomalee, when it decimated the detachment of the 78th Highlanders at that time stationed there. A very eminent medical man, who had examined the military building at Trincomalee at this time, gave the late gallant Admiral Sir John Gore, his opinion in the following emphatic words:—"The position and construction of the barracks are admirably adapted for originating, and the hospital for maintaining, disease." Subsequent and later epidemics will receive notice under their respective years of occurrence.

Berry-berry, beri-beri, or bere-bere, prevailed in Ceylon during the earlier part of the present century. It receives notice from Percival (in 1803), who states that it was occasioned by "the low diet and bad water which the natives are accustomed to use, and in part, perhaps, by the dampness of the climate in the wet season. It swells the body and legs of the patient, and generally carries him off in twenty hours." In his time the plan of treatment was to rub the

patient over with cow-dung, oil, chunam, lime juice, and other preparations from herbs, and then bury him up to the chin in hot sand.

I shall now attempt a cursory notice of the principal events in the medical history of Ceylon, gathered from official documents.

Vaccination was introduced into Ceylon as early as 1802. According to Bertolacci, who wrote in 1817, the population of Ceylon eight or ten years prior to that date was calculated at 700,000. The number vaccinated between 1802 and 1812 was 221,082, and it is stated that the efforts of the British Government to eradicate small-pox by means of vaccination were so successful that for eleven years the disease did not occur in Ceylon. The low-country Sinhalese, when they found by experience the protective benefits of vaccination, crowded into the British settlements for the purpose. The Kandyan, or natives of the hill country, who had been at enmity with the Portuguese, Dutch, and British, still kept aloof from communication with the Maritime districts; but, though they did not acquire the direct benefits of vaccination, they were free from the disease when it had been eradicated by the prophylactic in the low country. They used to drive their small-pox patients into the jungles of the low country.

In 1803, Mr. Percival, an officer of the 19th regiment, suggested that vaccination should be made compulsory (sixty years afterwards, in 1863, it was made compulsory by Sir Charles McCarthy); in 1837, Dr. Kinnis, of the Army Medical Department, wrote a long letter to the inhabitants of Ceylon on the advantages of vaccination. It was translated into Sinhalese, and must have done much good in making the benefits of vaccination generally known.

The first mention of the Lunatic Asylum occurs in the speech of Sir James Stewart Mackenzie, delivered before the Legislative Council in 1839. Up to that time insane persons had no special hospital provided for them, the common jails, and for a period, the Leper Asylum at Hendala, being

used for their safe custody. In "earnestly pressing for adoption," the draft of "An Ordinance to establish Lunatic Asylums," His Excellency said that "the cases of distress and misery from time to time brought to the notice of Government, prove beyond a doubt that the time has arrived when it has become imperative for the protection of those unfortunate persons, and, in some cases also, for their maintenance and support." Not long afterwards, under the *régime* of the same Governor, arrangements were completed "for the purpose of receiving those unhappy lunatics, who," to use Sir Stewart Mackenzie's own words, "are rather numerous, and from various parts of the Island are now boarded, lodged, fed, and taken charge of at a much larger expense than if they were under one superintendent for the males, and another for the females, in buildings contiguous to each other. All this is now done in a most unsatisfactory manner in respect to health, cleanliness, and every requisite for such an establishment."

The cost of converting the small-pox hospital at Borella into a lunatic asylum was estimated at £2,000, and this alteration was ultimately carried out satisfactorily. Since then this building, which was added to and enlarged from time to time, served the purpose until growing needs and advance in sanitary science, led to the adoption of a fresh site and improved architectural plans for the present new asylum situated at Jávatta. There are now 353 patients in the old and new asylums. On the opening of the Borella Asylum, in 1847, the Government placed the institution under the medical care of a specialist, Dr. Davy, who was sent out from England. The appointment, however, on being subsequently vacated by him, passed into the Medical Department, Mr. Ebert being appointed to the post in 1849. Under the care and supervision of successive officers of the Civil Medical Department, everything possible was done that could conduce to the comfort and well-being of the unfortunate inmates.

The administration of Sir Stewart Mackenzie, and the year

1839, was further marked in medical annals by the first mention in His Excellency's speech to Council of a Medical School for Ceylon, and of certain measures to be adopted by Government, which afterwards contributed in a very great measure to the efficiency of the Civil Medical Department.

His Excellency then said :—"The evident inadequacy of the former rates of salaries, to ensure the services of persons duly qualified in point of professional attainments and general respectability, left no doubt in my mind of the necessity of increasing the remuneration of the native medical establishment ; and while a higher scale of salaries was introduced, steps were taken to ensure to the junior members a regular course of instruction, both by the Military Medical Officers serving in the Colony and at the Colombo Academy. I also took advantage of the means of education Calcutta afforded to medical students, by sending certain more advanced youths to be educated there at the expense of this Government, with a view to employment in the Colony on their return. The Home Government has directed me to submit to you these arrangements, involving as they do an annual expenditure of about £3,500. It is for you, gentlemen, to declare whether this Colony does not stand in need of an efficient class of medical practitioners." His Excellency, in alluding to the necessity of a School of Medicine, added that he hoped the time was not far distant, when he should be able to propose to his Council, in furtherance of his views for the improvement of the class of medical men in the Department, the establishment of an Anatomical School ; and it was even suggested that certain alterations might be effected in the late Pettah Hospital (at present the headquarters of the Ceylon Light-Infantry Volunteers) for this purpose ; or failing this, that Her Majesty's Government would sanction "there being attached to the Colombo Academy such a system of medical education as will provide the means of adequate instruction in the medical profession in future for the Colonists, without their leaving their native

Island." Sir Stewart Mackenzie predicted what has been fulfilled. "I need scarcely add," he said, "that if these measures are successful, they will become the means of opening to the inhabitants of the Colony a new and most useful branch of professional employment."

Very few are now alive, who, under the designation of "Medical Sub-Assistants," served under Military Medical Officers, heads of the old Department. One of the earliest lists of the officers of the Civil Medical Department which I have been able to find is that for 1817. Between this date and 1858, when the Civil Medical Department became a distinct establishment, a large number of individuals, natives of the country, were educated and trained under Military Medical Officers. Many of these Military heads of the department appear to have been as kind-hearted as they were eminent for their scientific attainments, and the members of the subordinate department who still survive speak with a respect and affection of Forbes, Stewart, Barclay, Kinnis, Rowe, Ferguson, Templeton, Cameron, Fleming, and others, who, while ruling the department wisely and well, took a personal interest in the welfare of their subordinates.

Dr. Kevett, in 1835, was the first who attempted to organise a medical class. His pupils were the late Mr. Ferdinands of Kandy, E. F. Kelaart, P. H. Van Cuylenburg, M. B. Misso, Trask, Cleveland, and Ebert of our service. Of this number, Kelaart having obtained the opportunity of a free passage to England, as surgeon's assistant, accompanied the 78th Highlanders, and returned with a Commission as Staff Assistant Surgeon in 1840. Dr. Kelaart may, therefore, be considered as the first Ceylonese who acquired a British Medical degree; and his career as a physician and a naturalist was distinguished. His work "*Prodromus Faunæ Zeylanicæ*" is a monument of his talent and industry.

The slight attempt at imparting medical knowledge which I alluded to, was shortly after followed by a regular class for

the systematic teaching of the science of medicine under Staff Assistant Surgeons Templeton and Cameron, under the supervision of Dr. Arthur Stewart. The lectures delivered were mere explanations of the contents of text-books. This plan of educating medical officers was but partially successful.

The clinical teaching at the Military Hospital, Colombo, not being found to answer as fully as desired, the Government determined to send students to Calcutta for their medical education. It was not until the beginning of 1843 that graduates of the Bengal College joined this service, and among them may be specially mentioned the names of Drs. Anthonisz, Loos, Dickman, Kriekenbeek, Ondatjee, Andree, Wambeck, Markus, Margenout, and Breechman, who have all, either by death or retirement, now severed their connection with a department they served honourably and usefully, the first two having had the distinguished privilege, upon more than one occasion, of administering the Medical Department, during the temporary absence of its head from the Island. Speaking of his predecessors, Dr. Koch, himself a graduate of Calcutta, says in his lecture: "Nothing conduced more to familiarise English practice amongst the natives of the Island than the services of these young men on their return. They undertook and performed with success the most formidable surgical operations, and the name of Dr. Anthonisz will always be connected with the first successful cases of œsophagotomy and ovariectomy in Ceylon. Indeed, if I am not mistaken, the first-mentioned operation was the first successful one of its kind ever recorded in the whole annals of British surgery."

Dr. Ondaatje was Acting Superintendent of the Royal Botanical Gardens at Pérádeniya in 1843-44, before the appointment of Dr. Gardener, and he has since given proof of his intimate knowledge of the productions of the country, and their economic uses, in his contributions to the Journal of the Asiatic and other societies.

Much attention was devoted in 1852, during the administration of Sir George Anderson, to the operation of the quarantine laws, and the improvement of the drainage system of the capital. That pestilential ditch in the Pettah, misnamed "St. John's River," was entirely covered in, several new streets were opened, drainage on an extensive scale was planned, both by the opening out of new drains and the widening of old ones; indeed, at no great cost, much was done to increase the salubrity of the town and the comfort of its inhabitants.

Various sums were from time to time voted by the Government of Sir Henry Ward for the improvements of Civil Hospitals. The state of the Pettah Hospital, then the General Hospital of Colombo, was not creditable to the Colony, and a sum of £3,000 was voted for the purchase of a better site in the suburbs. It was after this that the present General Hospital was built, and opened in 1864.

In 1857 a Select Committee was appointed by the Legislative Council to report upon the Fixed Establishments of the Colony, and one of the recommendations made was that the Civil Medical Department should be separated from the Military Medical Department, and placed under the control of a Civil Medical Officer, as the existing Civil Department was insufficient for the requirements of the Island, and the military heads of the department were shifted too often for opportunities to acquire local experience. A Civil Medical Establishment was proposed, consisting of a Principal Civil Medical Officer, two Colonial Surgeons, eight Assistant Colonial Surgeons, and twenty-eight Medical Assistants, all with salaries adapted to secure efficiency and ability. Dr. Elliott, eminent in Ceylon as a public man, and well-known for his ability and philanthropy, was in England when the report was published, and he lost no time in applying to the Secretary of State for the Colonies for the new office of Principal Civil Medical Officer. He was appointed, but his tenure of office was unfortunately too short to enable

him to carry out several beneficent plans. He died, deeply regretted, on May 22, 1859.

In 1865 cholera broke out in a severe epidemic form at the pearl fishery, and rapidly spread to Trincomalee, Negombo, and Colombo. In the following year it occurred in all the principal jails, but with care and attention it did not spread, and there were but seventy-seven cases among prisoners, with thirty-one deaths. The visitation was of a sporadic character, until the close of that year, and then broke out severely in an epidemic form in the Northern Province. The whole of that Province was rapidly affected, but the disease established itself more particularly in the Peninsula of Jaffna; 9,092 cases occurred in the Northern Province, 8,696 of which were in the Peninsula of Jaffna, and 473 proved fatal. The disease was so much on the increase at the close of the year that His Excellency Sir Hercules Robinson appointed a Commission to visit Jaffna and report upon the causes which led to the outbreak of cholera in that peninsula. The Commissioners worked with much zeal and assiduity, conducted their inquiries on the spot, and after personal inspection of the localities which suffered most severely, and examination of the leading and well-informed persons of all classes of the community of Jaffna, drew up a voluminous and valuable report, which was laid before the Legislative Council. The report consists of the history of the epidemic, the modes of treatment adopted, the customs and habit of life of the people as bearing on the epidemic, recommendations for the sanitary improvements of the town and villages of Jaffna, and measures of precaution to be adopted against future outbreaks. In the Northern Province 10,064 cases occurred during 1867, of which 6,862 died. The remaining provinces suffered comparatively little, the total in these being only sixty-three cases, with forty-two deaths.

In 1867 Sir Hercules Robinson ordered an inquiry into the causes of the depopulation of the Vanni, and this investiga-

tion, on the recommendation of Dr. Charsley, was entrusted to Dr. Loos, then Colonial Surgeon of Jaffna. The conclusion he arrived at, after a careful inquiry, was that the depopulation was due to malarious fever and to the prevalence of an inveterate skin affection, possibly associated with an hereditary specific taint, aggravated by insanitary conditions, and known in that district as the "Parangi-disease." His report on this subject is well worthy of perusal. The duty entrusted to him was performed in such an efficient manner that he received the special thanks of the Government; and his report was submitted to the Legislative Council, printed and circulated among the members of the department and others. In accordance with his suggestions, new hospitals at Mullaitivu, Anurádhapura, and Vavuniya-Vilápkulam were established for the treatment of cases of this disease. It was, however, at the special desire of Sir William Gregory that more extended efforts were made during the year 1872 to afford medical aid to those suffering from Parangi; and Dr. Danforth, a very efficient medical officer, educated under the American missionaries, was placed at Vavuniya-Vilápkulam to study the disease, and afford aid to sufferers. Dr. Kynsey wrote a very elaborate report embodying the observations and experience of all the medical officers who had opportunities of studying this disease. He had a series of drawings made illustrative of the disease in its various stages, and presented it, through Government, to the Royal College of Physicians, London. Dr. Kynsey's report is among the Sessional Papers of the Legislative Council, and is a complete history of this curious and loathsome disease.

In 1870 a milder epidemic of cholera prevailed in the Southern Province. It broke out at Kattragama during the Hindú festival there, and followed the track of the returning pilgrims.

Whenever cholera is prevalent on the south coast of India, it generally finds its way into the Island through the medium of the immigrant coolies, who land at Maññár and

travel along the great Central-road to the Eastern Province. There are five immigrant hospitals along this road, where sanitary precautions are taken, and great attention paid to the comfort and health of the immigrant coolies on their long march from the coast to the coffee estates.

It was in 1869 that the new hospitals at Kandy, Gampola, Badulla, and Ratnapura were completed and occupied ; since then new hospitals have been erected in the towns of Galle, Má tara, Negombo, Má talé, Kurunégala, Batticaloa, Puttalam, and Kalutara. These new hospitals have been constructed on the pavilion principle, each ward being a separate detached building, and the ventilation and drainage are satisfactory. The pretty little hospitals at Pánaduré and Má rawila are gifts of the late Susew De Soysa, Mudaliyár, and the Lying-in-Home was built by Mr. C. H. De Soysa.

The year 1870 marked a new epoch in the medical history of Ceylon. To Sir Hercules Robinson belongs the credit of sanctioning the inauguration of the Medical School, which was raised to the dignity of a College in 1880, when the late Sir John Douglas, K.C.M.G., was Lieutenant-Governor.

Thanks to the liberality of one of our well-known public-spirited fellow townsmen, who granted a free site opposite to the Civil Hospital, this school now has a local habitation. Government voted a sum of R12,000 for the erection of a building on this site, which now contains lecture-rooms, library, anatomical, physiological, and chemical laboratories. Mr. Sampson Rajapakse's name has further been associated with this institution for the last thirteen years, as he is also an annual donor of a prize of R100 for the best student in Obstetric Medicine. The late Susew De Soysa, Mudaliyár, built the De Soysa Museum and Library, at a cost of R12,000

This College has been in existence for sixteen years and has prospered. Dr. Loos had the honour of being its first principal, and he vacated the office on his appointment as Colonial Surgeon of the Central Province in 1876, when

the late Dr. Koch succeeded him. The untimely death of this talented officer in December, 1877, from the effects of a dissecting wound, is still remembered, and the handsome memorial tower erected by public subscription, to hold a valuable and massive clock, granted by the Government of Sir James Longden, will remain a monument to his excellence and usefulness.

We have now fifty-nine licentiates on our register, twelve of whom have succeeded in obtaining British qualifications. A number of hospital assistants from the secondary class are also employed all over the country.

The reorganisation of the Civil Medical Department in 1873 testified to the desire of Government to place it on a more efficient footing, and make it more useful to the Colony. The Administration Report for the year 1873 was the last furnished to Government by the late Dr. Charsley, who retired in 1874, but did not live long to enjoy his well-earned pension; he died at the Cape in 1880. It is impossible to avoid adding a tribute to the able and conscientious manner in which he discharged the duties of the high office which he held in this Island for a period of fifteen years. Dr. Kynsey succeeded him, and took up his appointment as head of the Civil Medical Department at the end of March, 1875.

Mr. Joseph Fernando, of Moratuwa, erected a building at Béruwala, and the late Mr. Harmanis Dias one at Baṇḍāragama, in Rayigam Korálé, for outdoor dispensaries. The friends of Dr. Anthonisz have given us two comfortable wards at the General Hospital. Of 156,693 patients treated last year in the forty-five outdoor dispensaries scattered over the Island, 13,010 were attended to at the Béruwala dispensary, which was the largest number treated at any place during 1885.

This concludes a hasty sketch of the principal medical events of the Island. We have reason to be grateful to a paternal Government for the deep interest it has always

taken in the health and well-being of the people, and for its efforts to remove and mitigate evils or causes of disease and mortality.

To the Legislative Council we are indebted for the liberal votes made from year to year for adding to the requirements and comforts of our hospitals, and providing for the sanitary condition of our prisons. That Government has as little to do with charity as with religion, is little remembered by the public of Ceylon. In England, hospitals and dispensaries are supported by voluntary contributions, and large bequests are made by the wealthy for their maintenance and efficiency; whereas in this country, the duty as well as privilege of the rich to provide for the poor is not recognised sufficiently. Beneficence is not without reflex influence on the benefactor. The good Samaritan, who gave pence to support his neighbour, and poured oil into his wounds, “showed mercy on him,” and Shakespeare says of mercy:—

* * “It is twice blessed.
“It blesseth him that gives and him that takes.”

It would be well if more of our well-to-do citizens followed the noble example of Rajapaksa, the De Soysas, Joseph Fernando, and Harmanis Dias. These are the true benefactors of the people.

The wise and judicious Ordinances which have been enacted may also be viewed in a sanitary light. I need only allude to the Ordinances on compulsory vaccination; for establishment of Municipalities and Local Boards of Health; restricting the use of opium and bhang; regulating the sale of poisons; Medical Aid Ordinance for the planting districts; for administration of village communities; regulating the sale of intoxicating liquors; registration of births, marriages, and deaths; quarantine; irrigation; contagious diseases; and for regulating pilgrimages; nor must I omit to mention the advantages we have derived from the appointment of commissions of inquiry on cholera, prison discipline, and on irrigation.

On the whole, I may say we have no reason to be ashamed of the medical institutions of this Colony. We have one Leper and two Lunatic Asylums, twenty-seven Civil Hospitals, six District Hospitals, and forty-five Outdoor Dispensaries. Our prisons are now model institutions, and while stringent measures are adopted by strict penal discipline to make punishment what it should be, a deterrent from crime, every endeavour is made to ensure the health and maintain the physique of the convict, and thereby render him fit for the hard labour he has to undergo. Juvenile prisoners have been long carefully separated from old offenders, and confined in a separate department of the prison; and an Ordinance has lately been passed for securing their reformation in a Reformatory, and in Industrial Schools. Almshouses for the aged and infirm are urgently required, and have yet to be provided. Friend-in-Need Societies have done much good in the time past; but these institutions cannot now cope with the increasing destitution from the rapid increase of population, and from want of employment. The private charity of the more wealthy members of the community is needed, and must be systematically afforded in lieu of the indiscriminate almsgiving, long the practice of the country. The prevailing distress from poverty and want of employment, however, is such that measures on a larger scale must be devised by the Municipalities, or by Government, not only for the relief of indigence, but for the removal of the causes of pauperism, which invariably produces crime.

Civilisation and its advantages enjoyed by those in large towns have yet to be extended to rural districts, the kóralés and pattus of the various provinces, where, at times, under the influence of drought and unfavourable seasons, sickness occasionally breaks out, and decimates the population. This was remarkably the case in 1864, 1866, and 1875, when fever and dysentery were so remarkably rife. The people were not on these occasions uncared for and left to perish of sickness and starvation. Food was provided by Government;

but medical aid could be given only partially, as the prejudices of the people were then found to be strong against the use of European drugs. With time and better agents for dispensing remedies, these prejudices are being gradually overcome. There are fortunately at the same time influences at work to enlighten and elevate the population. The country is being gradually opened up by roads and railways, and little towns are springing up where formerly there was jungle. Irrigation works are being gradually restored, and will in time reclaim wild and uncultivated wastes, formerly inhabited, but which may now be said to be "pathless forests." We may yet hope that ere long the measures adopted to advance the material interests of the country will help "to scatter plenty over a smiling land." Our missionary societies are extending their operations into the far interior, so that moral improvement, as well as material advancement, may be anticipated. But the means of abating deadly disease are still the feeble simples of the Vedarála, and the charms and incantations of the devil-priest. Shall we not aid the Christian missionary in his work, if, like the "Great Exemplar," we be not at the same time missionary and physician? The good work has been commenced in the Medical College. Let us hope that in time the licentiates of this institution will multiply and be found in all parts of the Island, possessed by knowledge which will enable them to combat disease in its varied forms; safe advisers, who will teach the people to avoid the causes of disease, and thus afford to them the blessing of preventive as well as curative medicine.

THE VEDDA'S OF CEYLON.

By C. J. R. LE MESURIER, ESQ., C.C.S., F.G.S., &c.

SOME years ago, while arranging the records of the old Kandy Kachchéri, I came across an account of the Veddás, written, so far as I can remember, in the form of an official report to the resident at Kandy in the year 1820. By the permission of the then Government Agent, I took a copy of this document, and since that time have had several opportunities of verifying the information it contained.

I do not think the account has ever been published, at least I can find no record to that effect, and I venture therefore to offer it in the form of a Paper to the Asiatic Society.

I have myself, on several occasions, come across the hill or rock Veddás, while shooting on the borders of the Central and Eastern Provinces. My first introduction to them was on this wise.

I was tracking up an elephant at some distance from the Pattipola ár, where my camp had been pitched. We were in the midst of a dense forest, when I suddenly heard the sound of an axe. The elephant had heard it too, apparently, for just about this time we saw from his tracks that he had bolted, and we therefore gave him up.

Turning to my tracker, I asked him who was cutting trees in this out of the way forest, and he replied that it was, he thought, a Veddá. I at once dashed off towards the sound, to see what was to me then a curio; but the tracker promptly stopped me, and said, "That is not the way to catch a Veddá: he will bolt the instant he hears you, and you will never see him. You must come like this," whereupon he went down on his hands and knees, and crawled

towards the sound. I followed suit, and when we were close up we "rushed" our man. He was in a terrible fright at first, but we soon quieted him, and the tracker, who knew his patois, acted as interpreter between us. After a few words I asked him if he was alone. "No, he had his wife and children, and his brother and his brother's wife with him." I asked him to go and bring them, and he left us for about half a minute, and apparently without a word being spoken, returned with another man, two women, and two children, one being at the breast. A present of tobacco all round, and a few more words and promises of food, &c., from me made them quite friendly. The men visited me in camp next day, and were very useful in the field, from their knowledge of the country and where to find game. Since then, I have come across Veddás on several occasions, and the result of my personal experience is, in the main, to confirm the accuracy of the following account:—

The Veddás of Ceylon are thought by many to be the aborigines of the country, and their appearance, customs, and language certainly warrant this belief.

They are of two distinct classes, (1) the village, and (2) the rock or hill Veddás.*

(1) There is very little social intercourse amongst the pure village Veddás. They are said never to meet for any purpose of festivity. They subsist on the game they kill, on the fish they catch, on the roots and seeds of certain aquatic plants, and on yams and other jungle plants and creepers. The country in which they live abounds with elk, deer, wild hogs, hares, monkeys, porcupines, iguanas, peacocks, and jungle fowl, all of which they kill with bows and arrows, except the iguana, which they run down, or "tree," with

* The village Veddá differs but very slightly now from the ordinary Sinhalese villager of the interior. Most of the old village Veddá families have either become incorporated in the surrounding villages or have retreated further into the forest, and become hill Veddás.

their dogs. They cut the flesh off the larger animals into steaks, and dry it in the sun. In this state it is eaten raw, seasoned with honey or salt, when they can procure it. They eat the flesh of the iguana fresh, but broiled. They also pound to powder the rotten wood of a tree called *bala*, which is said to be like the *kəkuna*, or country walnut. This they knead into a paste with honey, and then bake into cakes. They are, however, said not to eat this unless they are in want of something more nutritious and palatable, and they explain the addition of the rotten wood to the honey by saying that it is required to fill the stomach. They do not eat the flesh of the ox, the buffalo, the panther, or the bear. Some of the more civilised of these Vēddās cultivate small patches of kurakkan (a small kind of grain) and Indian corn, and a little tobacco and cotton. They flay the deer, but not the elk. The skin of the latter they dress and eat after singeing the hair. When they have the flesh of these animals in plenty they dress it by boiling, but more frequently by roasting, and the flesh of recently killed animals thus dressed appears to be considered a luxury. When all other means of sustenance fail them, they boil the leaves of the *kora* and *tora* trees, which grow in abundance everywhere in the jungle.

They never kill or catch the elephant. They do not use firearms, and their bows and arrows are not intended for so formidable an animal.* They always avoid him in consequence. The bear and the panther are their most dangerous enemies, the former especially.† Many of the Vēddās bear the marks of conflicts with it ; but with his axe, which with its short handle is an efficient weapon of defence against an animal that closes with his enemy, the Vēddā generally

* They are very bad shots with the bow, and they never "fire" until they are within three or four yards of their game.

† They have a number of charms against these animals, the principal ingredient in them being noise.

comes off victorious, though often severely lacerated, and that usually about the face.

They barter their deer skins, dried flesh, cotton, and honey for rice, kurakkan, tobacco, salt, cloth, arrowheads, and axes. They carry on this trade with the Siphalese and Moormen in their neighbourhood. They exercise no art or handicraft but that of making their bows and arrows. The heads of the latter are made by the Siphalese blacksmiths. They all have an axe, and some few of them possess a small hoe; but they make little use of the latter in the cultivation of their lands, all they do previous to sowing the crop being to cut the jungle and burn it. They are fond of salt, but as frequently it is not to be had in their neighbourhood, the only seasoning they have for their food is honey.

They are passionately fond of tobacco, and would use betel could they procure it. They, however, find a substitute for it in the bark of certain trees,* which they chew with their tobacco. They do not practise smoking, they have no knowledge of intoxicating liquors, and drink nothing but water. They never cultivate paddy, the reason they give for this being that they are much fonder of hunting. They never do and will not apply themselves to any sort of labour, except now and then to a little high-land cultivation, and that never exceeds a rood or two for each family. They keep no domestic animals excepting dogs, and sometimes, but very rarely, a few fowls. Their huts are constructed in a very rude manner, some of them being a mere roof composed of three or four sloping poles, one end of which is placed in the ground, and the other end is supported by a cross stick placed on two perpendicular ones. Others have a perfect roof coming down to the ground on both sides, like the old military tents. Their huts are generally covered with the bark of trees, but sometimes with dried grass or straw. They never

* It was while stripping one of these trees of its bark that I first came across them.

remain more than a few months in one place, and often shift their residence more frequently.

The men wear a string round their middle, with a piece of cloth of the width of four or five inches passed between the legs, a flap of which about eight or nine inches long hangs over in front. The women wear a piece of cloth about the size of a small handkerchief, and in the fashion of an apron. The hair of both sexes is never combed, and is disgustingly matted and filthy. They wear no ornament in the hair, but sometimes tie a string round the head to keep the hair out of their eyes. They wear small earrings of iron or brass. Their bodies are never washed unless it be by the rain.

They speak Singhalese, but it is so corrupted that it is very difficult to understand. They make use of some words that are not Singhalese. Their voice is loud, harsh, ill-toned, and disagreeable.*

Polygamy is not practised either on the part of the men or the women. When the females arrive at a proper age, they are asked by the young men from their parents, who never refuse their daughter to the first suitor. No marriage presents are given on either side, nor is there ceremony or marriage feast. The bridegroom merely calls, as they express it, the bride from the hut of her parents to his own.† Their wives are generally prolific, but the great majority of their children die of fever when young. They speak most favourably of the fidelity of their wives, and assert that their caste is distinguished for chastity. They never repudiate their wives, whose duties are purely domestic, except that they assist in reaping the kurakkan. They are kindly treated by their husbands. As to the relative rank

* Many of the hill Veddás that I have come across appeared to have lost the power of modulating their voice, probably from disuse.

† The bride ties a string round the bridegroom's waist, and they are man and wife.

of the females, it is asserted that the men have more regard for their wives than for their brothers and sisters.

Strangers who reside in their country for any number of days seldom escape jungle fever, and they are not a little exposed to the baneful effects of the climate themselves. Besides fever they are subject to cutaneous complaints; but it does not appear that either venereal disease or small-pox is known among them. They attribute all sickness to the agency of malignant spirits, with whom they believe their country to abound. The use of medicine of any kind is not practised among them. They trust entirely to incantations to propitiate the demon who has afflicted them. In all cases of severe sickness they devote a silver ring and a piece of cloth, which are deposited in a particular place. After this, the Yakdesa, or demon priest, who is always one of the eldest of their own tribe, is sent for, and he dances and chants certain incantations before the sick persons. He is then fed with what they have to give him, which generally consists of the cakes made of honey and rotten wood, and the ceremony is concluded by his carrying off the ring and cloth offered in sacrifice from the spot where it was laid. They pay no respect to the dead. The body is thrown into the jungle without ceremony, to be devoured by wild beasts.

Of an all-powerful beneficent being they have no idea, but they believe in the existence of a plurality of malignant spirits. Of a future state they have no notion, and are equally ignorant of the religion of Buddha and the gods of Hindu mythology.*

Their knowledge and moral notions appear to be as limited as their mode of life. They cannot count beyond five, and the stupidity and apathy of some of them is very striking. There is, however, something in their manner, when in their native forests, like the independence or indifference that may

* They also believe in the fostering care of the spirits of the dead, whom, with the sun and moon, they constantly invoke in time of need.

be expected in a savage. One of them, on being asked to show how they steal upon their game, gave a most striking specimen of good acting. The keenness and intensity of his eye, the lightness of his step, and the eagerness of desire displayed in every limb and muscle of his body, could only be compared to those of a cat or a tiger stealing upon its prey.

Their whole appearance bespeaks the hardness of their condition. They are lower in stature than the ordinary Singhalese, but are meagre in their bodies and squalid in their looks. Their figures denote that they might be active in their movements, but they give no indication of being possessed of much strength either of body or constitution. Their limbs, however, though thin and slight, are well turned. They are generally of a darker complexion than the common Singhalese, though some are of a much lighter shade than the others. When not in the jungle they carry a white staff about seven or eight feet long, and when they stand, they plant this before them, grasping it with both hands a little above the height of their forehead, and bend forward in a most unmeaning and ungraceful position.

(2) The hill Veddás are of the same caste and description as the others, their habits and customs are much the same, but they are described as being of a savage and ferocious disposition.* Persons who approach them are considered to be in danger, and they are said to be at enmity with all their neighbours.† There were certain seasons when the Veddás had to render a tribute of honey and flesh to Government, but, as the wild Veddás never entered a town or a village, the Veddás of Horabora used to repair to a certain place near their haunts, where they found the honey and dried deer's flesh deposited. They, however, seldom saw the people

* The hill Veddás are fast becoming extinct, first, from constant inter-marriage between members of the same family, second, from the decrease in the game of the country, and the consequent privation and lack of food.

† N.B.—This was written in 1820.

themselves, and when they did they avoided them as dangerous.

Both the wild and village Vēddás rank with the Vellálas (the highest Siṅhalese caste). When the more civilised Vēddás go to the house of a district chief of the Vellála caste, they receive water out of an earthen pot with a spout to it, a privilege that belongs only to the Vellálas.

The men among the wild Vēddás are still more scantily clad than their neighbours, for they wear no cloth, but only a small apron of plaited leaves. The women are scarcely ever to be seen. They remain in the deepest recesses of the wood, or among the rocks in the hill country, and are as naked as the men.

The hill Vēddás speak a language that is not understood either by Siṅhalese or Tamil, but some few words of the Siṅhalese language are to be recognised in it.* They hold no intercourse with their more civilised neighbours, and it is, as above stated, considered dangerous to go near the places of their resort. They are quite migratory in their habits and mode of life, remaining but a day or two at a time in one place. They have no huts, but take shelter under large trees or rocks. They have a fire constantly burning, which they produce by the friction of one piece of wood upon another. They live solely on what nature affords them, on roots, fish, and the game they kill with their bows and arrows.† They

* Notwithstanding all that has been said to the contrary, I believe the Vēddá language to be merely a patois of the ordinary Siṅhalese. Many of their words can even now be traced to a Siṅhalese origin, such as. for instance :—

To drink—*diya-kanawa*—in Siṅhalese, to eat water.

To sleep—*nidenawa*—in Siṅhalese, *nidagannawa*.

Snake—*polongo*—in Siṅhalese, *polonga*.

Lightning—*gini wetuna*—Siṅhalese, fallen fire, &c.

Considering that they have no knowledge of letters, no literature of any sort, nothing to arrest the constant change in their spoken language, it is remarkable that any indication of the affinity of this patois to Siṅhalese should have remained.

† The constant change in their residence is due to their search after game.

cultivate no kind of grain, and make nothing but their bows and arrows. The iron heads of the latter and their axes they obtain in the following manner :—They carry a quantity of dried flesh and honey to a place near the residence of a Singhalese blacksmith, and hang it up on a tree out of the reach of dogs and jackals, together with a leaf cut in the shape of the iron article they want. The smith fails not to accept the offer thus made to him, and in due time hangs up in the same place the article required in return. It is understood were he to fail in doing so, that he would be exposed to the most dreadful vengeance of the Vēddā and his friends.*

It is the general belief that the hill Vēddās are extremely tenacious of the chastity of their wives. They are consequently apt to be jealous, and instances are not wanting of their sacrificing to their revenge both the wife and the supposed paramour; but all speak in high terms of their kind treatment of their wives, and of the fidelity of the latter to their husbands.

The hill Vēddās living along the frontiers of the Kandyan and Maritime Provinces never acknowledged by tribute either the Dutch, British, or Kandyan Governments; but those towards Horabora in Bintenna paid a tribute of flesh and honey at three different seasons of the year to the royal stores at Kandy. This they of their own accord, at the proper time, hung upon a tree, and it was brought from thence by the Vēddās of Horabora, as has already been noticed. The officer whose duty it was to collect the tribute never had any personal communication with the hill Vēddās, and having no control over them he could not have enforced the payment had it been withheld. There was, however, no known instance of their ever having failed to pay in due time.

They never commit depredations upon the crops or property of any kind belonging to their civilised neighbours,

* This custom has fallen into disuse.

nor do they molest traders or travellers on the commonly frequented paths that lead through the country they inhabit. It is dangerous to offend them, and instances are known in the Batticaloa district where they have revenged an injury by deliberate assassination.

In Major Johnstone's expedition from Batticaloa to Kandy, in 1804, the first person that fell was brought down by the arrow of a Vĕddá. On the march of the detachment through the Vĕddá woods between the Nadakádu province of the Batticaloa district and the frontier of Wellassa, a small clear spot was chosen to encamp on for the night. It was on the side of a wood which a party of the pioneers entered for the purpose of procuring firewood. It happened that a few Vĕddás had here taken up their temporary abode. They fled on being discovered by the pioneers, who at once proceeded to plunder the little property they had left in their huts, the most valuable part of which consisted of two or three fowls, who, like their owners, sought safety in the jungle. While one of the pioneers was pursuing a fowl, a Vĕddá concealed in a bush shot him through the loins. This happened but a few yards from the camp. The wounded man was brought in alive, and the arrow was extracted by the medical officer, but he died in a few hours. The Vĕddás effected their escape. An instance of their mode of taking revenge took place in the Batticaloa district about 1822. One of the more civilised Vĕddás, a lad who had established a friendly intercourse with a hill family, conceiving an attachment to a young female of the family, made proposal to the parents for her. The match for some cause or other did not come off, and shortly after the girl sickened and died. The family attributed her death to necromancy practised by the young man, and under this impression, four or five years after, a brother of the young woman left the woods in search of the object of his revenge, and having found him watching a paddy field in the Batticaloa district, walked up to him in the open day, and deliberately shot him through the body.

This was done in sight of another man, a Malabar, who was in the same field at some distance, and from whom the Vēddā had ascertained the identity of the man he was in search of. The assassin, after withdrawing the fatal shaft from the body of his victim, made his escape into the woods.

They are not only ready thus to redress their own grievances, but also those of their friends; and this disposition was sometimes taken advantage of by the Moormen and Malabars, who were in the habit of intervening between those who are in a sort of semi-civilised state, and the absolutely unsocial and uncivilised Vēddās. An instance of this also took place in the Batticaloa district, about the same time. A headman of the Province of Pattipal having rendered himself obnoxious to the chena cultivators near the Vēddā country, a party of Vēddās came down quietly in the night to the village where the headman was residing at the time, surrounded his house, plundered it, and put him to death. In short, the disposition of the hill Vēddās was so well known that the Sinhalese, Malabar, and Moor families, from whom the petty chiefs placed over the partly civilised tribe were generally taken, both in the interior and the Batticaloa district, were objects of dread amongst their neighbours from the influence they possessed over such ready instruments of revenge.

In regard to their origin, it is remarkable that the traditional accounts of them given by the best informed Kandyan chiefs, and the most intelligent Tamil inhabitants of the Batticaloa district, perfectly accord with each other.*

* The historical origin of the Vēddās is as follows :—When Wijayo landed in Ceylon, he married Kuwena, the daughter of a Yakko chief. She betrayed her people into his hands, but when she had served his purpose he deserted her. She returned to her people, but they were so incensed with her that they put her to death; and her two children by Wijayo only escaped the same fate by the intervention of their uncle, who fled with them into the forest near Adam's Peak. Some time after the brother and sister married, and founded a wild race, who kept aloof from all their neighbours, retreated into the forests of Wellassa and Batticaloa on the approach of the Indian invaders, and became "the wild men" of Knox—the Vēddās (or hunters) of Ceylon.

The Kandyans say that the Vēddás are real Siphalese Vellálas, who at a period of very remote antiquity occupied the tract of country which now constitutes the district of Batticaloa. That they were expelled from thence by an invasion of Tamils from a foreign country, and took refuge in the forests in which they are now met with. They would not mix with the other inhabitants of the country, but to criminals and other unprotected fugitives who took refuge amongst them, and to slaves who fled from their masters, they generally afforded hospitality and protection, though they were apt to deliver them up for presents in cloth, &c.

They are totally unacquainted with letters, but the different tribes hold a rude correspondence with each other by small pieces of wood cut into different shapes. Fugitives used to be furnished with passports of this kind, when they removed from one tribe to another, and the treatment they received depended on the recommendation which the talisman conveyed.

Man in a state of nature, or in any degree approaching it, is ever an object of curiosity to the civilised world. The knowledge of the existence of the Vēddás of Ceylon must therefore excite a wish to be acquainted with their origin and history. From themselves, however, no information whatever can be obtained. They trouble themselves little about futurity, and the past is a blank to them. They are said to have been in the habit of addressing the King of Kandy by a word which signified "brother"; but this was merely due to the poverty of their vocabulary, as the word *aluwa** is used by them when speaking of or to all persons with whom they are in friendship, and in consideration of this they were allowed to use this familiar term in the presence of the late king, a liberty that would have cost any other of his subjects their lives.

* Bailey, who, by the way, says that the word is "hoon" (cousin), attributes this familiarity to the fact that the Vēddás claimed and were acknowledged to have a royal origin.

PRINTED AT
THE GOVERNMENT PRINTING WORKS,
COLOMBO, CEYLON.

ROYAL ASIATIC SOCIETY, CEYLON BRANCH.

THE VEDDÁS OF CEYLON, AND THEIR RELATION TO THE NEIGHBOURING TRIBES.

BY PROFESSOR R. VIRCHOW.

*Translated for the Ceylon Asiatic Society from the Memoirs of the
Royal Academy of Science of Berlin, 1881.*

IN the various mixture of races inhabiting the Island of Ceylon, the Veddás (Vaeddás, Weddás, Veddahs, Vaddahs, Vaidahs, Beddás, Bedas) have since a long time been an object of special prominence for the study of ethnography, because, owing to an inferior order of intellectual development, and through defects in physical organisation, it offers the most room for conjecture that here is presented a remnant of the aboriginal inhabitants. And now, when according to all accounts their number is so rapidly diminishing that at no very distant date its last members will have disappeared from among the living, it adds peculiar interest to the study that it is desirable to transmit to posterity at least a trustworthy picture of its singular characteristics. For this the material we now have is nowise sufficient: hence the task for the following disquisition is not merely to collect what has been already arrived at, but to point out the gaps which can be supplied only by farther local researches. It is to be hoped that this may stimulate to the immediate application of all possible means to obtain the wanting material.

The Veddás have dwelt—at least for some centuries—in one district in the eastern, or more correctly, south-eastern part of the Island. Robert Knox, who gave the first exact information regarding them in the year 1681, transferred them to the woods of “Bintan” (Bintenna).* John Davy† in the early part of this century speaks of them as inhabiting the vast forests on the south-east side of the Island, between the mountains and the sea, especially the wild, unhealthy tracts of land called *Vedirata* of Bintenna and *Mahavedirata* of Uva. These they consider as their own territories. On the whole their boundaries remain the same to-day. Sir E. Tennent‡ and Mr. Bertram F. Hartshorne§ assert that the Veddá-land is about ninety English miles in length and forty in breadth, from the hills of Uva and Medamahanuwara toward the east and extending to the sea coast, while Mr. Pridham|| who estimates the area at very nearly 1,500 square miles (English), bounds it more precisely in the following way: Batticaloa on the east, the districts of Mágampattu and Uva on the south, the mountains of Kandy on the west and south-west, and the river Mahaveli-ganga on the north. Mr. John Bailey¶ states that the majority of the real Veddás dwelt in the districts of Batticaloa and Badulla (chiefly in the former); but here it should be said that according to a later division of the country a part of Bintenna has been added to the district of Badulla, and the larger portion of it

* Robert Knox. *An Historical Relation of the Island of Ceylon in the East Indies*. London, 1681, p. 61. New edition, printed in *Philalethes. The History of Ceylon from the earliest period to the year MDCCCXV*. London, 1817.

† John Davy. *An Account of the Interior of Ceylon and of its Inhabitants, with Travels in that Island*. London, 1821, pp. 115, 116.

‡ Sir James Emerson Tennent. *Ceylon: an Account of the Island, Physical, Historical, and Topographical*. London, 1859, vol. II., p. 437.

§ Hartshorne, in the *Fortnightly Review*. London, 1876. New series, vol. XIX.

|| Charles Pridham. *An Historical, Political, and Statistical Account of Ceylon and its Dependencies*. London, 1849, vol. I., p. 452.

¶ John Bailey, in *Transactions of the Ethnological Society*. London, 1863. New series, vol. II., p. 278.

to the district of Batticaloa.* The more savage remnant of the tribe live in the beautiful province of Nilgala and in the forests of Bintenna.

There is much evidence, however, that in times not very distant the Veddás were scattered over a much larger extent of territory. The name "Veddá-land" (*Veddirata*) in the time of Mr. Bailey (1863) belonged to extensive districts in the north-east of the Kandy mountains, which were no longer inhabited by the Veddás, but by the Sinhalese (Wanniyas). The designation *Mahaveddirata* ("Great Veddá-land") seems of pretty wide application. Davy, who in one place transfers it to U'va, in another† gives it to the far-reaching flat lands in which the so-called "lake" of Bintenna lies. Mr. Pridham, who indeed was never himself in Ceylon, places *Mahaveddirata* in Wellassé and a part of U'va. These are subordinate matters, however. More important far are several earlier statements. Cordiner‡ tells us, after mentioning the real Veddás, that "another race of a similar description formerly existed in the district of the Wanny, bordering on the province of Jaffnapatam. They are now, in some degree, civilised." They spoke Malabar, and adhered to the Brahmin religion. In another place he says§ that at the advent of the Portuguese the "Bedahs" dwelt in the north and the Sinhalese in the south. This seems to prove that the Veddás formerly reached much farther northward. But their earlier presence in the south and even south-west is also proved. Knox|| tells us that at "Hourly," a remote possession of the king of Kandy, numerous Veddás were living, who were, however, pretty tame; and Valentijn¶ mentions, besides "Vintana" and "Hoerli," still another

* Bailey, *l. c.*, p. 281. note.

† Davy, *l. c.*, p. 377.

‡ James Cordiner. *A Description of Ceylon*. London, 1807. vol. I., p. 91.

§ *Id.*, p. 137.

|| Knox, p. 124.

¶ François Valentijn. *Oud en Nieuw Oost Indie*. Dordr. en Amsterdam, 1726. Deel V. Ceylon. p. 49.

"Beda" district, farther north than Trincomalee. Bergk, the translator of Percival's work,* says that Van Goen states the "Bedahs" had entire possession of the land between the mountains of "Canducarre" in the west and Passara in the north; while Percival counts† as belonging to them not only the Indians in the adjoining province of Jaffnapatam, but the tribes inhabiting the western and south-western part of the Island between Adam's Peak and the Rayigam and Pasdum kóralés.

In regard to these statements, I remark that Bergk's view of the situation of the district mentioned is erroneous, as a glance at the map by A. Arrowsmith,‡ contained in the book he translated, would have taught him. The district of "Canducarre" (according likewise to the map of Ceylon published by J. Mawman, 1816, which is appended to the new edition of Knox) lies at the east of the Island, S.S.W. from Batticaloa, as well as the immediately adjoining district of Passara, which is a province of U'va directly north of it, and close to Badulla.§ From this the country between "Canducarre" and Passara would be the real Vēddá territory, whereas the Rayigam and Pasdum kóralés lie on the west coast south of Colombo, in the neighbourhood of Saffragam and south-west of Adam's Peak.

Mr. Bailey,|| in whose time indeed there were no longer any Vēddás living there, conjectures that Saffragam (from its old name *Habaragamuwa*) was the original land of the Vēddás (*habara*, "barbarian"), and as proof of this gives a variety of local names still extant. He also finds in a Sinhalese poem, written about four hundred years ago, *Parawi*

* Robert Percival. Description of the Island of Ceylon, translated by J. A. Bergk. Leipsic, 1803, p. 337, remarks.

† Robert Percival: An Account of the Island of Ceylon, containing its History, Geography, Natural History, with the Manners and Customs of its various Inhabitants. Second edition, London, 1805, pp. 282-284.

‡ The map in Tennent's work is by John Arrowsmith.

§ Davy, *l. c.*, p. 413. Pridham, *l. c.*, L, p. 361.

|| Bailey, *l. c.*, p. 313, note.

Sandése, the district right below Adam's Peak distinctly inhabited by Veddás. Possibly only some scattered remnants of the tribe dwelt among these mountains.

That four hundred years ago the Veddá territory extended continuously in this way as far as the west side of the mountains, and even to the western sea coast, is highly improbable, as a Chinese geographer, Hiouen Tshang, in the seventh century of our era, travelling in India states that the Yakkhos had* withdrawn into the south-east corner of Ceylon. It may, however, be correct that as Sir E. Tennent asserts, under the Dutch Government Veddás were found in large numbers, but half civilised, at no great distance north of the peninsula of Jaffna, in the so-called Wanni. The question whether in the earliest ages Veddás inhabited the whole Island I will take up later.

The present Veddá-land is very lovely, embracing a comparatively flat, wooded country, nowhere raised more than two hundred feet above the level of the sea, but frequently having the appearance of a park. It would seem that the character of the soil varies, since dams and unwholesome marshes alternate with rock-ribbed hills. The Rev. Mr. Gillingst† speaks of the province of Bintenna as very dry and rocky. But Mr. Frederick Müller‡ is mistaken in transferring the home of the Veddás to the mountains of Ceylon. All the more recent accounts limit their abodes to the anterior land which separates the central mountains from the sea coast, excluding them wholly from the mountains themselves. Sir Emerson Tennent§ to be sure makes a distinction between the somewhat more civilised village and coast tribes, and the wild "Rock Veddahs, *galle-vedda*."

* Tennent, *l. c.*, I., p. 372, note.

† The Journal of the Ceylon Branch of the Royal Asiatic Society. Colombo, 1853, p. 89.

‡ Reise der östere. Fregatte Norasa. Anthropologischer Theil. Abth. III. Ethnographie. Wien, 1868. s. 139.

§ Tennent, *l. c.*, II., pp. 439-44.

If we reject his attempt to identify these with an ancient tribe of "Gallas," who may have dwelt in the same portions of the south as the present Galle, and admit that the rocky character of the region in which the wildest part of the tribe live accounts for the name, evidently given them by strangers, it does not by any means follow that the rock Veddás are mountaineers. For centuries the real inhabitants of the mountains have been Singhalese, the people of *Máyārata*. Sir E. Tennent established the rock Veddás, who, according to him, had split into five clans or hunting-parties in the woods of Bintenna, and whilst the village Veddás, amounting at the highest estimate to not more than one hundred and forty families, lived in nine small communities around the Laguna district of Batticaloa, the coast Veddás, four or five hundred in number, roamed about in the jungles between Batticaloa and Trincomalee, chiefly in the vicinity of Erávúr and along the coast as far as Vendeloos Bay. Mr. Hartshorne, however, rejects this division wholly; he distinguishes only *Kelē-Veddó* (jungle Veddás) and *Gaṇ-Veddó* (half-civilised village Veddás), the former only as deserving the special attention of ethnologists.

If we study the map of Ceylon, it becomes at once clear that Bintenna, the ancient capital, which Sir E. Tennent speaks of as identical with the *Maagrammum* of Ptolemy,* lies directly upon the eastern boundary of the mountains towards the foreland. The Maháveli-ganga, the largest river of the Island, here bursts out from the hill-country, behind which the mountains of Kandy and U'va rise westward; to the east are fertile plains, swamp lands, and

* Tennent, *l. c.*, I. p. 536, note 2. This he rests on the old name of Bintenna having been Mahiyangana, and asserts that this could not possibly mean Mahagan, as was assumed by Christ. Lassen. (*De Taprobane insula veteribus cognita. Diss. pro aditu, muneris prof. ordin. Bonnae, 1842, p. 23.*)

extensive forests, interspersed with low hills. Sir E. Tennent* paints in rich colours this beautiful country, which he passed through on his way from Bintenna to Batticaloa on the east coast. This is the real home of the Vēddás. Knox† also describes very distinctly this country,—this land of Bintenna,—which he surveyed from afar on the tops of the mountains. He says: “It seems to be smooth land, and not much hilly; the great river runneth through the midst of it. It is all over covered with mighty woods and abundance of deer; but much subject to dry weather and sickness. In these woods is a sort of wild people inhabiting.” The wild Vēddás live here in perfect isolation, as well from their allophylen neighbours as their more civilised tribal brethren, without fixed abodes, but yet upon their own recognised lands, mostly in small groups, or simply in families. Rarely do they venture beyond their own boundaries, and then only for the purpose of exchanging honey, wax, skins, or venison for tools of iron (axes, arrow-points, &c.). For the most part, they shrink timidly back from all human contact, and even their small commerce was not at first openly pursued,‡ but in

* Tennent, *l. c.*, II., p. 451.

† Knox, *l. c.*, p. 9.

‡ Mr. Hartshorne asserts that this mysterious way which Sir Emerson Tennent made so much of is no longer carried on. The first mention of it is by Knox. Earlier authors, in speaking of the secret trade, refer, as far as I can see, not merely to the Vēddás, but to the Ceylonese in general. It does not appear to me at all certain that the passage in Pliny (*Natur. Hist. Lib.*, VI., 24), in spite of Sir E. Tennent's plea (*l. c.*, I., p. 571, note 1), refers to the Ceylonese, as it does not describe the trade in the interior of the country, but outside, near the boundary of the Seræ,—far away upon the continent,—exhibiting it more as a peculiarity of the Seræ than of the Ceylonese. The interpretation put upon the passage is of little importance, however, as Chinese authors—for instance, Fa Hiaen—mention this kind of secret trade in the third century as carried on upon the Island itself. That Pliny at the same time refers to the worship of demons certainly would seem to point to the Vēddás, but on the other hand a report by the Arabic geographer Albyruni (1030 A. D.) shows that in his time the secret trade was pursued along the coast. We should therefore have to assume that the Vēddás carried on a coast trade in the eleventh century, which is not probable.

this wise : they deposited their wares and rough models of the things they wanted in a certain place, and returned later to take away secretly the needed articles. This explains why the estimates of their present number vary so much.

Cordiner says, most indefinitely, "not many thousands in number"; whilst Sir Emerson Tennent,* in the year 1859, considered the estimate at that time of 8,000 an exaggerated one. Mr. Bailey, in 1863, declared the number of the Veddás in the district of Batticaloa to be only about 250, in Nilgala 72 (in 1858), and in Bintenna 364 (in 1856),—altogether only about 686. Mr. Hartshorne speaks of these figures as probably too small ; and a communication from the Rev. Mr. Gillings† seems to corroborate this, according to which, by the census of 1849, in the district of Bintenna alone there was a population in all of 1,538 persons,—half-Sinhalese, half-Veddás. At any rate, from the declarations of Mr. Bailey there is no question that the recruits are very small indeed, and the annihilation of the entire tribe imminent. For he found‡ in Nilgala among 72 persons, 50 adults and 22 children (in one family of 9, and another of 8 adults, only 1 child in each); and among the 50 adults but 14 over fifty years of age ; a single member only seemed to be over seventy years of age. Of 308 persons in Bintenna, 175 were adults and 133 children ; in an isolated horde 22 adults and 4 children. And as if to make this more conclusive, we are assured that there are no indications anywhere of the practice of child-murder among them.

Of late the process of annihilation seems to have hastened on. From a note of the Rev. Somanader, a missionary in Batticaloa, which I received through the kindness of the Director of the Museum in Colombo, Mr. A. Haly, we are led to think there are scarcely any pure blooded Veddás living ; he calls them "a race almost entirely extinct."

* Tennent, *l. c.*, II., p. 444.

† Gillings, *l. c.*, p. 83.

‡ Bailey, *l. c.*, p. 296.

Whether this assertion applies to a particular district or is universal, and whether the extinction has been hurried on by a general dying out or through intermarriages with other tribes, I have not been able to discover from the information given me. We can do little more at this distance than to hold together what has been furnished us by observers, who had opportunities of intercourse with living Veddás in their own home. Among these we must name above all, Dr. Davy, Sir Emerson Tennent, the Rev. Mr. Gillings, Mr. Bailey, and Mr. Hartshorne. But we encounter at the outset a peculiar obstacle, viz.: that each fresh writer designates the statements of his predecessor as "incorrect." Mr. Bailey* criticises Sir Emerson Tennent in the severest manner, and Mr. Hartshorne,† who on this point agrees with him also, calls in question the accuracy of Mr. Bailey's statements.

Yet Mr. Bailey was many long years in Ceylon. First, as a member of the Government in the district of Badulla, and later as Principal Assistant Colonial Secretary of Ceylon, affording him sufficient opportunity to study the Veddás. He puts great emphasis on the fact, and reiterates it frequently, that his statements are sustained by well-tested and often repeated personal observations. It appears to me that the contradiction between Messrs. Bailey and Hartshorne is not in reality so great as the latter pictures it. I find

* Bailey, *l. c.*, p. 279, note. "His [Tennent's] account of them is in some important instances defective, and even inaccurate. He glances casually at those tribes which are in the wildest state, touching with precision none of their peculiarities, and dwells in detail upon those only who from long association with the Singalese and Tamil races have lost much of their originality. Of the ancient aborigines he has compiled much that is curious. Of the existing Veddahs he has given us little besides an epitome of former notices."

† Hartshorne, *l. c.* "They have been described by Sir Emerson Tennent and by Mr Bailey; but interesting as their accounts are, the latter has suffered grievously from misprints, and the value of the former is impaired by the circumstance that its materials were not the fruit of original research."

that in the space of more than twenty years which intervenes between the two accounts, the effects of educating influences pressing in from all sides upon a before almost isolated people is very noticeable, and explains in the most natural way how certain habits and customs disappear, and others come in. I am therefore inclined to value more highly the testimony of the older observer for his time, than the younger observer is inclined to warrant. But I believe I must defend their distinguished predecessor, Sir Emerson Tennent, against them both. His representations bear throughout the character of great soberness and objectivity; and his facts differ in the main points very little indeed from those of his successors, especially the more immediate one. We cannot in justice deny that he was the first to throw light on this subject.

For all this it is very dangerous under such circumstances to decide, at our distance, where the mistakes are, and what is to be accepted as true; and nought remains but to confine ourselves to such changes as can be clearly traced and followed in their development, or to matters about which the various observers agree. Fortunately there is enough to disclose to us the main characteristics of the people. The greatest difficulty here arises from the fact that not a few of the travellers who have treated the subject of the Veddás—notwithstanding a long residence in the Island—have never personally seen any of them, and speak only from hearsay; and others certainly have not encountered the really wild families. Even Knox,* who never saw a single Veddá, and yet furnishes a likeness of one, distinguishes a “tamer sort,” who lived under a kind of subjection to the king of Kandy, and a “wilder,” who were called “*Ramba-Vaddahs*.”† Davy,‡ who divides them into village and forest Veddás, seems only to have seen the former, yet feels justified in assuming from the information he received that both

* Knox, *l. c.*, p. 123. † *Id.*, p. 126. ‡ Davy, *l. c.*, pp. 116, 118.

belong to the same race. In this all later observers entirely agree. Hence, for the study of their physical condition we may without hesitation unite the two groups, so far as they are not already united ; but for the observation of their social and psychical conditions we must hold the two groups strictly apart : of course in the latter respect only are the forest or jungle Veddás of any interest to us. I shall therefore speak mainly of them ; nevertheless we may not venture quite to set aside the village Veddás, since their actual settlement and civilisation has succeeded only very imperfectly as yet.

As a matter of fact, all attempts to bring the Veddás into fixed abodes and to raise them to a higher culture have suffered shipwreck in far greater measure than the efforts to civilise the Australians. Government officials and missionaries have been active among them many years, but their success has been wholly external. Rev. Mr. Gillings states that up to 1844, in Bintenna, 163 men, 48 women, and 85 children had been baptised—since then very few ; and adds, “but almost all of these have gone back again to their former habits and follies : what they formerly heard they have forgotten.” The Veddás have remained on the whole nomadic heathens, and heathens without any developed form of religion. “They are a horde of ‘Free-thinkers,’” said Wolf,* “following the impulses of their bad and savage natures.” Whether they actually have any conceptions of God or God-like beings is, to say the least, very doubtful. The only thing that is proved is a lower kind of demon worship among them, which here and there assumes the form of a worship of their ancestors. If Mr. Taylor† designates this as *animismus*, and therefore “their religion,” as corresponding to that of the barbarous tribes of India, we

* Joh. Chr. Wolf. Reise nach Zeilon. Berlin u Stettin, 1782. Th. I. S. Die omfänge der cultur übers.

† Edward B. Taylor. The Beginning of Culture. Translated by Spang u Poske. Leipsic, 1873. Bd. I. S., 51.

at least must not overlook the fact that it is also close upon the borders of Nihilism. Gillings says they believe the souls of their departed relations to be devils, who have power to hurt them, and therefore they perform ceremonies to them at regular seasons, and especially when they are sick. Bailey and Hartshorne described these matters in detail.

The former* distinguishes the conditions as they were in Bintenna from those of the more barbarous inhabitants of Nilgala. There, he says, they had mourned and buried their dead for a long time; here they had only just begun to do so. Formerly they threw their dead into the jungle,† or left them just where they died. After covering the body with leaves they laid a heavy stone upon the breast, and sought for themselves another cavern, giving up the one where death had entered to the spirit of the departed. This spirit (*yakun*) watches over the welfare of those left behind. The spirits therefore of their ancestors, like those of children, are good spirits (*nēhya yakun*); they come to their relatives when they are ill, visit them in dreams, and grant them flesh of the chase. In every trouble the Vēddās invoke these spirits, especially the spirits of children (*bilindu yakun* or *vitera yakun*). Among their ancestors the great grandmother (*mahakiriammā*) seems to have occupied the first place, although Mr. Bailey is not quite sure whether this distinction is to be understood in the good sense. The spirits are invoked with dance and song, around an arrow, which is planted upright (*Maha kiri amma*).

The description given of all this by Sir E. Tennent‡

* Bailey, *l. c.*, pp. 296-301.

† Davy, *l. c.*, p. 117.

‡ "When sick, they send for the devil dancers to drive away the evil spirit who is believed to inflict the disease. The dance is executed in front of an offering of something eatable, placed on a tripod of sticks, the dancer having his head and girdle decorated with green leaves. At first he shuffles with his feet to a plaintive air, but by degrees he works himself into a state of great excitement and action, accompanied by moans and screams, and during this paroxysm he professes to be inspired with instructions for the cure of the patient." (Tennent, II., p. 442.)

almost reminds one of the customs of the Schamanen. Sometimes, while preparing for the chase, the spirit is promised a piece of flesh of the slain animal. At other times they cook something and put it in the dry bed of a river or other obscure place, invoke the souls of the departed, dance round the food, and perform their incantations.

Sir E. Tennent also reports that the dead were not buried, but simply covered over with shrubs and leaves in the jungle. On the other hand the Secretary of the Ceylon Branch of the Royal Asiatic Society* (1853) tells of their wrapping the dead in mats and burying them; and Mr. Hartshorne† knows of no other practice than burying. When a person is dead they envelop him in the skin of an animal, and dig a grave for him with their axes or pointed sticks. Women are not allowed to be present. No weapons or utensils of any kind are buried with him, and once closed over they never visit the grave again. To the spirit of the departed one, who has now become a *yakká*, an offering is brought in the following way: While invoking the spirit they roast the flesh of the *wandurá* (monkey) or the *talagoyá* (iguana) with honey and edible roots, and distribute it among those present, who eat it on the spot. The word *yakko*, or *yakkho*, designates, according to Turnour,‡ a kind of demon, though the demon worshippers are also called Yakkhos and Yakkhinis. He derives it from the root *yaja*, “to bring offerings.” This word has for a long time justly excited the attention of scientists, since in the great historical work of Ceylon, the *Maháwagso*, the earliest inhabitants of the Island are called by this name.

When Wijayo, the founder of the first known Ceylon dynasty, in the year of Gotama Buddha's death, 543 B.C., landed, as is generally assumed, upon the

* Journal of the Royal Asiatic Society, Ceylon Branch, 1853, p. 89.

† Hartshorne, *l. c.*

‡ The *Maháwagso*, edited by George Turnour. Ceylon, 1837, vol. I., Index and Glossary. p. 30.

north-west coast, not far from Puttalam,* he found an already organised Yakkho state :† indeed, it is related of Gotama Buddha himself that he came to Lañká,‡ a settlement of the Yakkhos. It would hardly be allowable to conclude from this, with Sir Emerson Tennent§ and others, that the people of the north-west coast, to whom the name of Yakkhos was given, were identical with the present Veddás, and that up to the time of Wijayo an aboriginal homogeneous race inhabited the Island ; but it may not be a mistake to assume that in the earliest period almost the entire population were devoted to this *yakkho* worship, as it now exists among the Veddás, and is to be found only among them ; for the Sinhalese are Buddhists, the Moors and the greater number of the Tamils being Muhammadans.

One fact also speaks against the whole Island having been inhabited by Veddás : that the legends tell of kings, princesses, and cities (for instance, Lañká-pura) of the Yakkhos, whilst no trace of all these is to be found among the Veddás of modern times. As they have no God, no priests, no temple, so they make shift to get on without a king, without chiefs, and without cities, even without houses. At least this is true of the wilder portion of them. We should have to assume such deep degeneration of the present Veddás, from the old Yakkho times, as would be without a parallel in history as well as in ethnology. Even for those who, like myself, acknowledge the possibility of a deep mental and physical degradation of whole tribes, it would yet be going very far to admit that a tribe which

* Mr. Brodie (Journal Royal Asiatic Society, Ceylon Branch, 1853, p. 48) states that the place where the first settlement was made (Tambapanni), now called Tammēna Aḍaviya, lies about six or eight English miles east of Puttalam. The word Tambapanni is derived from the Greek name for the Island, Taprobane. Tennent, *l. c.*, vol. I., p. 525, note I.

† Mahāwamsa, pp. 48, 49.

‡ *Id.*, p. 2. Lañká filled by Yakkhos, and therefore the settlement of the Yakkhos. Lañká is an old name of Ceylon.

§ Tennent, *l. c.*, II., p. 438.

had never changed its ground, and was living in the immediate vicinity of comparatively highly civilised tribes, could in a little more than two thousand years have sunk so low. Farther accounts will certainly prove that the question of the deterioration of the Vēddás is not to be evaded; but I must here declare that I cannot bring myself to admit their possible decline from an organised Yakkho state.

Not a single fact sustains the conjecture that Wijayo, with his followers from the Valley of the Ganges, was the first stranger who came to Ceylon. On the contrary, the legend of the advent of Gotama Buddha clearly points to earlier arrivals. This is done no less by the old traditions of the Rámáyana. Lassen* declared outright that in the legend of Ráma we must see the reminiscence of a former attempt to colonise this Island by immigrants from India. The north-west coast of Ceylon lies so near the coast of Coromandel, and the vicinity of Adam's Bridge having always been (then as well as later) the landing place for intruders from Hindústán, it would be astonishing if the first immigration at such a remote period should immediately have become a fixed fact in history. If Wijayo found some kind of political organisation on the Island, we may assume that before him there had been an invasion of other tribes, and the time in which the whole north of the great Island was Vēddá land must then be placed a good deal further back. In historic times one irruption after another from the north and west occurred, and the aborigines were driven toward the south and east. But of these aborigines we must say that only a part of them have preserved in its purity the original type.

The first visit of Gotama Buddha to the Island was, according to the Maháwapso,† at Mahiyangana. This place, to be sure, is found right in the present Vēddáland near Bintenna,

* Christian Lassen. Indische Alterthumskunde. Bonn, 1847. Bd. I. S., 198.

† Maháwapso, p. 3, cap. I.; Introduction, p. xxiv; Glossary. p. 16.

where afterward the kings Devānampiyatissa (307 B.C.) and Duṭṭuḡemuṇu (164 B.C.) had erected a dāgaba.* According to the Yakkhos, in whose midst the Buddha here appeared, he visited on a second occasion "Nāgadīpo," the abode of the Nāgas, or snake-worshippers,† which is generally assumed to be the name for the north and west of the Island; at any rate, mention is made of Nāgas living by the ocean, as well as mountain Nāgas: there is a Nāga king of Kēlaniya spoken of in the neighbourhood of Colombo. Sir E. Tennent‡ compares this idol worship to that of the Rākshas among the Dravidian tribes of Hindústán, and probably with much correctness, but he overlooks the fact that if any importance is to be attached to these mythological traditions, a multitude of tribes, or at least a division of the original population, must be inferred. And it is not without value that the description of the Nāga states in these most ancient myths discloses to us the picture of a much more perfect organisation than we find any account of in the tales of the Yakkhos. Nevertheless, we must renounce the idea of using these myths as the basis for ethnological contemplation and for building up a highly developed Vēddā state in pre-historic times. If the Vēddās of Bintēna were Buddhists before the time of Wijayo, the later absence of all religion among them, their preference for animal food, and many other things, are scarcely explicable.

Up to a very recent date the Vēddās have been a nomadic, half cave-inhabiting race of hunters. As already said a small number of them lived upon a proportionally vast tract of woodland, which without exact boundaries, but under the recognition of a kind of traditional family claim, was distributed among little groups of relations, who clung together. Each family had its special hunting-ground, to which its prerogative was acknowledged. Within this they

* Tennent, *l. c.*, II., p. 420.

† Mahāwanso, p. 4.; Glossary, p. 18.

‡ Tennent, *l. c.*, I., p. 328.

sought honey and bees'-wax, dug edible roots, chased the game, and laid their snares for birds or fishes. Of any kind of culture, be it of garden or farm, there was no trace. They had no tame domestic animals, except the dog; and it may be questioned whether even this was not a later adoption, for according to Bailey* the species differs in no wise from the race common in Ceylon. Moreover, the dogs seem to have been trained to be watchdogs, and not for the chase.†

Sir John Lubbock‡ lays much weight upon their possessing hunting buffaloes, which were so well trained that the hunter guided them by a rope slung round one horn, whilst he himself, concealed behind them, crept up to the game. But Mr. Bailey§ says expressly that this practice, which he certainly had observed in Bintenna, extended all over the Island: we therefore can hardly concede to the Vēddás a claim to this invention.

Their hunting utensils are the simplest possible. They consist of a strong bow, six feet long, and from two to three arrows, three feet and a half long, whose points are of wrought iron. All the writers describe the bending of this bow as very difficult. Sir E. Tennent|| describes the Vēddás in a half-lying position, using the left foot to draw the bow, and gives a picture of one, according to a model carved in ebony, by one of the native wood-carvers. More recent reporters find no trace of the continuance of such a practice; they describe the bow as being drawn with the left arm, and attribute the extraordinary power and development of this arm to this practice.

Besides iron arrow-heads the Vēddás had one iron axe—sometimes, though rarely, two, a larger and a smaller one

* Bailey. *l. c.*, p. 286.

† Davy (*l. c.*, p. 117) says plainly. they do not use dogs for the chase, unless perhaps at *talagoyá* (iguana).

‡ John Lubbock. *Pre-historic Times*. London, 1878, 4th edition, p. 448.

§ Bailey. *l. c.*, p. 288.

|| Tennent, *l. c.*, vol. I., p. 499: Note 7. vol. II., p. 439.

—principally for the purpose of cutting wax and honey out of hollow trees. These tools they obtained by barter with their neighbours. Their only achievement is shaping the arrow-heads for special uses by pounding them. But even these poor specimens of work are rare, and preserved in the family as precious heirlooms; sometimes, indeed, they make arrow-points simply of sharpened wood, ornamented with feathers of birds. Mr. Hartshorne* makes the interesting statement in connection with these facts, that the word *galrekki*, by which they denote the axe, is connected with the Sinhalese *gala*, “stone” or “rock,” and rightly finds in this a reminiscence of an earlier period, when stone weapons were in use among the Vēddās. I am not, indeed, aware that utensils of stone have been found in Ceylon, but on the other hand I do not know that they have ever been sought for there. It would perhaps be a not unprofitable task to explore those caverns thoroughly in the hope of finding other contents, where, according to Mr. Bailey, bones of the dead are still to be found.

They subsist almost wholly on animal food. Like the Buddhists, excluding the flesh of cattle, and also (according to Sir Emerson Tennent and Mr. Bailey) that of the elephant, bear, leopard, jackal, and fowls. They eat, however, the flesh of all other birds, of the Ceylon elk (*samba*, *Rusa Aris-totelis*), deer (*Axis maculata*), monkeys, pigs, iguana, and pengolin (*Manis pentadactylos*)—the last being considered the best: among fishes they prefer the eel.† All their food is cooked; as, however, they have no clay or earthen vessels, the preparation of the meat is very rough. Wolf‡ even asserted they ate the meat uncooked. At present this does not seem to be the rule; they now boil and roast their

* Hartshorne, *l. c.*, p. 408.

† In the choice of their food both classes (rock Vēddās and village Vēddās) are almost omnivorous, no carrion or vermin being too repulsive for their appetite. Tennent, II., p. 439. “Their food being only flesh.” Knox, p. 61.

‡ Wolf. p. 117.

meat. They strike fire in the usual way in the East, by placing one pointed stick against the concave of another piece of wood, which they hold between the feet and whirl round rapidly.* For this purpose they use the wood of the same tree from which their bows are made—the *velanga* tree (*Pterospermum suberifolium*).

It would seem, however, that of late this custom of fire-rubbing had gone out of use; at least Mr. Hartshorne asserts that they now use flint and the steel of their axes or arrow-points for the purpose.

The use of any special stimulant is unknown among them; they have neither betel nor tobacco.† They drink only water, and chew a kind of bark. Even salt was unknown to them, as Mr. Hartshorne‡ informs us; but when it was given them they were much delighted with it.

Only in single places, where European influence is perceptible, do we find a rude kind of agriculture, such as is seen at the present day in Spain and in the Troas. Little strips of the jungle are burnt down and tilled ("chena"), and then again let alone for five, ten, fifteen years§; with this exception, which really cannot be taken into account, their whole existence depends upon the products of the chase. The universal recognition of this appears in their name, which, according to the almost unanimous application of the word, signifies "hunter," "archer," "one who shoots." I shall return to this later. For the present I would only lay stress on the fact that in the customs of the Vēddás there is nothing to speak of which indicates that anywhere, or at any time, they have risen above the condition of a savage tribe of hunters.

Indeed, they have never arrived at even the very crudest

* A detailed description by Sir E. Tennent, *l. c.*, II., p. 451.

† In the illustration by Knox the Vēddá is represented with a lighted pipe, but this was an unwarranted addition by the artist.

‡ Hartshorne, *l. c.*, p. 413.

§ Bailey, *l. c.*, p. 282.

form of permanent dwelling places,* although they sheltered themselves from the inclemency of the weather in the natural caverns of the country, or in simple huts† made of branches of trees and bark put together: they seem never to have made these their settled abodes.

On the contrary, perpetual change of place within their hunting grounds was ever the rule. Hence their social intercourse, indeed their circle of interests, is essentially limited to their nearest of kin, whose number is often very small, consisting, perhaps, of only four or five persons. All stimulant to higher requisitions and enjoyments is therefore wanting. Ambition, jealousy, love of finery, cannot thrive among them; nor, on the other hand, does the need of any sustained mental effort appear. Thus, as it seems to me, may the natural explanation be found of a list of peculiarities; indeed, also, in part of contradictory oddities.

From such a wild and inferior race of people one might perhaps expect that they would assault strangers, menace their neighbours, and live in a state of war with the more remote portions of the tribe. But, setting aside some very old tales and records of individual cases, which may be wholly disregarded, the habits of the Veddás are thoroughly peaceable. They have never even made the step from hunter to warrior. They are peaceable among themselves and towards others, so long as they are unmolested. They

* Knox (*l. c.*, pp. 61, 62) says of them:—"They have no towns nor houses, only live by the waters under a tree, with some boughs cut and laid round about them, to give notice when any wild beasts come near, which they may hear by their rustling and trampling upon them." He saw such places on his flight from an almost twenty years' imprisonment.

† Sir E. Tennent, *l. c.*, II., p. 439, speaks also of this, and that they sometimes slept upon stagings which they prepared in the trees. This would demonstrate habits like those to which Mr. F. Jagor calls attention in his account of the Kanikars in Hindústán. (*Zeitf. Ethnologie*, 1879. *Verhandh. der Berlin Anthropol. Gesellsch.*, s. 79, *Taf.* 9.) On the other hand, Mr. Hartshorne asserts they are bad climbers, and possess no special capacity for catching hold with the feet. Percival (*l. c.*, pp. 284, 285) asserts on the other hand that they climb trees with the greatest expertness and celerity, and sleep on them or at their feet.

respect the rights of property, and are true, and, further, loving. In proportion as their life is limited to the circle of the family, family feeling is more strongly developed. Adultery and polygamy are mentioned* only where attempts have been made to civilise them, whilst among their neighbours, the Sinhalese Kandyans, adultery and polyandry† were so common that the English Government was obliged to issue a special law for prevention. Conjugal fidelity and monogamy, as well as love for their children, were matters of course among the Vēddás. Mr. Bailey‡ quotes the very characteristic remark of a Kandyan about them, that “they are just like wanduroos” (monkeys); and yet the women are far from being attractive, are not conspicuous by their ornaments, nor even cleanly. “They are the most ordinary specimens of the sex I ever saw,” says Bailey.§ Both sexes go almost naked. In former times they wore pieces of the bark of the *riñi* tree (*Antiaris innoxia*, or *A. saccadora*); these were later replaced by little bits of cloth, which were held fast around the body by a string. The women were distinguished by wearing round ivory pegs stuck through their ears. Mr. Hartshorne,|| however, saw ornaments worn in the ears by both sexes—generally pearls, or what seemed peculiarly admired, empty cartridge-boxes. Evidently these are quite modern innovations; and we may without hesitation assume that, up to a comparatively recent date, perfect, unadorned nakedness was the rule, modified at the most only by a slight covering of the pudenda.

If nevertheless neither polygamy nor polyandry has been observed among them, this may be explained by the isolation of families, and the great distances which separated them; perhaps, we can in the same way also account for the other very peculiar custom among them, which has been testified

* Gillings, *l. c.*, p. 86.

† Tennent, *l. c.*, II, p. 128.

‡ Bailey, *l. c.*, p. 293.

§ Bailey, p. 284.

|| Hartshorne, p. 109.

to by various travellers, viz., that of marriage with a sister. It was only with a younger sister, marriage with the elder being considered unchaste. According to Mr. Hartshorne,* even marriage with a daughter was allowed, although probably this, if it occurred, as a matter of fact was not legitimated. Knox † also tells of a king of Kandy who had a child by his daughter, but none of his subjects seem to have considered this a proper relation. Bailey ‡ is inclined to see in this marriage with the sister a last remnant of times outlived. This reminds us that Wijayo, the founder of the Singhalese dynasty, sprung from marriage in India with a sister, and that his son again, Jivahattha, whom he had begotten with a Yakkho princess in Ceylon, had married his sister, and was the progenitor of a special tribe, the Pulinda. Later, this practice was also in use among the royal families of the Singhalese.§ We must allow that these statements are certainly worthy of attention, but these old myths are hardly to be looked upon as positive historical facts. They seem to me only to prove that a practice which existed also in Persia and Egypt, was early permitted in Ceylon ; the reason for it was probably the same everywhere, in the royal families as with the naked Vēddās, the lack of suitable women, or of women altogether. At any rate, it is not unchastity or licence which leads the Vēddās to form such marriage ties. A marriage among them is usually decided by the will of the parents of the bride, who herself is allowed no choice ; the only ceremony consists in the bringing of food for the parents on the part of the suitor. If under these circumstances the matrimonial tie is held faithfully and truly, it surely speaks for the purity of heart in such a wild race.

On the other hand we perceive from the accounts of different observers, that there is no particular depth of feeling among the Vēddās ; all the descriptions indicate rather a

* Hartshorne, *l. c.*, p. 416. † Knox, *l. c.*, p. 38. ‡ Bailey, *l. c.*, p. 310.

§ Sir E. Tennent (II, p. 459) quotes as authority for this, Valentyn, *l. c.* cap. IV., p. 63.

certain morose indolence, which is only occasionally broken through by their love of habit. Most noticeable in this connection is an observation of Mr. Hartshorne's,* which he corroborates by a series of instances. I refer to the incapacity of the Veddás to laugh. Whilst they can help they not only do not laugh themselves, but despise those who do. As far as my knowledge goes, nothing like this has been told of any other race of people; only among certain idiots has this peculiarity appeared.

In point of intellect Veddás seem indeed to stand very low.

According to Mr. Hartshorne† they are wholly unable to count, have no numerical words, and do not even use their fingers for the purpose. Mr. Bailey‡ does not go quite so far; he says they count with difficulty on their fingers, but he gives no numerals in their vocabulary, and relates how hard it is to make a Veddá understand anything which extends beyond the very next day. The Rev. Mr. Gillings§ says they could count only to a very limited extent. Davy||

* Hartshorne, *l. c.*, p. 410.

† Hartshorne, p. 413. "They are wholly unable to count or to comprehend the ideas of one, or two, or three, nor do they even use their fingers for this purpose; and the chief difficulty in obtaining any information from them arose from their inability to form any but the most simple mental synthesis, and from their very defective power of memory." On another occasion Mr. Hartshorne even asserts the Veddás had no idea of the distinction between one and two. (*Journal of the Anthropological Institute of Great Britain and Ireland*, 1878. vol. VII. p. 468)

‡ Bailey, *l. c.*, p. 298.

§ Gillings, *l. c.*, p. 88.

|| Davy, *l. c.*, p. 118. In this place the "Village Veddás" are spoken of. Pritchard (*Researches into the Physical History of Mankind*, London, 1844, 3rd edition, vol. IV., p. 193), who says the same, reports that the description of Dr. Davy refers to a large "party" of Veddás whom he saw during his visit to Kandy. According to their own account these people had come from the neighbourhood of the Lake of Bintenna, where "a little grain" was cultivated. I do not doubt the correctness of this communication, which is of great importance for a true estimate of the statement regarding the intellectual capacities of the people. But it is taken from a work of Dr. Davy's not accessible to me. Pritchard cites it under the title: "History of the Island of Ceylon." In the "Account of the Interior of Ceylon" no reference is made to it, although the visit to Kandy is very circumstantially described (p. 364 sq.).

asserts they have hardly any knowledge of numbers, and cannot count beyond five. Sir E. Tennent* goes a little step further in saying they are incapable of counting over five on their fingers. Even this is after all very little, especially when we realise that these milder statements refer to the "tamer sort." Mr. Hartshorne† also contends that their language includes no word designating colour; that they have neither a fancy for bright colours nor any sense of the distinction in colours.

Finally, he complains of their defective power of memory, and their inability to form any general ideas. Sir E. Tennent says they have no notion of time or space, no words for hours, days, or years—no games—no amusements—no music. These statements, however, in their full breadth apply only to the "wild sort" of the village Veddás. Davy‡ says that they have a rough kind of song, performed as an accompaniment to a very clumsily executed dance. When we add to all this the fruitlessness of any and every attempt to educate them, we are compelled to acknowledge the inferiority of the race. Even granting some of the observations furnished are too exclusive, it would not alter the general opinion.

It looks like a contradiction that, as Mr. Hartshorne§ informs us, they consider themselves as superior to their neighbours. This sort of contradiction is not limited to the Veddás—narrow-minded people not unfrequently over-value their capacities. But it does sound very strange when the different reporters state that the Veddás are looked upon even by their neighbours as members of a high—yes—of a regal caste. They are said to have been allowed in earlier times to speak of the king of Kandy as "*Húrá*," which means "cousin." As among themselves they know of no distinction of caste, this is indeed very striking. It has even been regarded as an evidence of the correctness of the tradition that they are

* Tennent, *l. c.* II., p. 443.

† Davy, *l. c.*, p. 118.

‡ Hartshorne, *l. c.*, p. 409.

§ Hartshorne. p. 412.

of royal blood, or even as Mr. Bailey* assumes, descended straight from King Wijaya himself; but where then is the posterity of those Yakkho people to be found whom Wijaya met upon his arrival on the Island? It is not possible to bring any of the other numerous races represented in Ceylon into a nearer connection with this aboriginal population.

The earliest reporters who have spoken at any length on this subject of caste in the Island, all concur in declaring that the Veddás were counted as members of a higher caste.

Davy,† who enters most minutely into this matter, says that the majority of the Singhalese were assigned to the agricultural caste, to the so-called “Goyivaṇsé,” or, as it is styled in the lowlands, “Vellála,” and that to this caste also the Veddás belonged. Philalethes‡ makes the same statement. He explains the word *Govi* to be Singhalese, and the word *Vellála*, Malabar; to this caste belonged, according to him, the Vanni Veddás, and he speaks of two sorts—one wearing leaves upon their bodies, the other using the bark of a tree made soft by special preparation. That the later observers touch less upon this subject is explained from the circumstance that in recent times the distinction of caste has lost much of its significance among the Singhalese, who even in earlier times left the two highest castes, the Royal and the Brahmin, without representatives. Perhaps this circumstance also explains the peculiar usages by which the Veddás, who really belong only to the third general caste, have been brought into connection with the kings themselves. As late as the year 1853, the secretary of the Ceylon Branch of the Asiatic Society remarks in a note§ that the Veddás of Bintenna and of the sea coast consider themselves members

* Bailey, *l. c.*, p. 312.

† Davy, *l. c.*, pp. 112–15.

‡ Philalethes, *l. c.*, p. 332. The name Philalethes is a pseudonym, as Sir E. Tennent presumes (*l. c.*, Introduction, p. xx., note 5), to conceal that of the Rev. G. Bisset. This gentleman was in Ceylon at the same time with Dr. Davy, who mentions him personally, *l. c.*, p. 372, sq.

§ Journal of the Ceylon Branch of the Royal Asiatic Society, 1853, p. 89.

of a very high caste, and call themselves Vēddā Vellālas. From these communications we see clearly that the designation "Vellāla," which we find also in Hindústān, has only a hierarchical meaning, but is of no help at all toward the discovery of the relationship and derivation of the tribe.

Another name here requires particular mention, as it is liable to introduce confusion. It is the name "Daḍa Vēddās," which is given to a division of the Śudra (Kshudra) caste, that being one of the very lowest classes: hunters dwelling in the wildest parts of the mountain region.*

Knox † says the lowest of the low are beggars, who are the descendants of the "*Dodda Vaddahs*, which signifies hunters;" it had been their task to provide game for the King of Kandy. When, however, instead of venison they brought him human flesh, the king had them thrust out, and given over to beggary. The detailed description which he gives of them shows that he means one of the outcasts. Davy cites two kinds of them: the Gattaru and the Roḍiyas, or Gasmandó, whom he compares with the gypsies. The latter are now usually called Roḍiyas. Of them Sir Emerson Tennent ‡ relates the same story that Knox tells of the Daḍa Vēddās, adding that a legend declares them to be a branch of the Vēddās. A still more minute description of them has been furnished by Mr. Casie Chetty. § He calls them a peculiar and distinctive race, either descendants from a colony of wandering hordes out of India, or the last remnants of an aboriginal population mixed with Siñhalese women of high caste, who had been punished by the king with loss of caste. They live, he goes on to say, in the interior, not great in numbers,—perhaps, in all, not above one thousand,—scattered, or in special detached villages (*kupṇāyam*). In the Seven Kóralés two divisions are distinguished: the *Tiringa Roḍi* and the *Halpagé Roḍi*.

* Davy, *l. c.*, pp. 112-27. Philaethes, *l. c.*, p. 334.

† Knox, *l. c.*, p. 70.

‡ Tennent, *l. c.*, II., p. 187.

§ Simon Casie Chetty, *Journal of the Ceylon Branch of the Royal Asiatic Society*, 1853, p. 171.

They are more robust and athletic than the Singhalese, and the women frequently pretty. Both sexes allow the hair to grow its full length, and wind it into a coil. They live by the chase, and use bows and arrows like the Vēddás; like them also they wrap their dead in mats and bury them. Although Buddhists they offer sacrifices to the *Gará Yaká* and to the *Vēdi Yakku*. They speak Singhalese, but have some peculiar words, which Mr. Chetty thinks remnants of past ages. The description by Sir E. Tennent agrees with this. He visited a Rōḍiya village, which lies on the pass between Kandy and the Mahawēli-gaṅga, and gives a picture of a group of these people. He proves that the Rōḍiyas were mentioned in the *Rājāwāliya* as early as 204 B.C., and in the *Mahāwāṇso* 589 A.D.

According to his opinion they differ physically very much from the Vēddás, and he is inclined to believe they had their origin on the coast of India, and belong to the Chāṇḍálas. For the rest they are only found in the Districts of Kandy. Although they may be compared to the Cagots and Caqueux of the Pyrenees, there are yet two races of outcasts in Ceylon, who were detested even by the Rōḍiyas, namely, the *Embēṭṭāyó* (barbers) and the *Hanomōreyó* (betelbox-makers) in Uva.

The existence of these outcasts is of no little importance to us in explaining the position of the Vēddás among these complicated tribal relations. Had the Vēddás, as many have surmised, been originally outcasts, they would surely have remained so to this day, just as the Rōḍiyas have been for at least two thousand years. If they had, like the Arabs, the so-called "Moormen," subsequently emigrated, they would not be placed in the relatively high caste of Vellála, for the Moormen are in no caste, although attached to the Karáwé (fishermen), a subdivision of the Śulras. Unquestionably, then, the Singhalese must have retained a feeling of the original connection, which in spite of the religious and physical dissimilarities made them acknowledge the Vēddás

as belonging to the social order of the Buddhists. Thousands of years had not sufficed to reduce the Roḍiyas to that degree of degradation to which the Veḍḍás had fallen when Knox heard of them, and which is most strongly expressed in the words of Davy,* who says of the forest Veḍḍás that they are "rather solitary animals than social, and resembling more beasts of prey in their habits than men." We shall yet see what objections there are to our regarding the Veḍḍás simply as "wild Sinhalese," and how it has happened that a great number of direct observers have thought to find their origin on the coast of Malabar. This point will be more appropriately treated of later, and after we have considered the physical peculiarities of the different tribes under discussion. It here seems in place first to bring forward the historical and linguistic observations which concern the relations of the cultivated tribes of the Island.

The natural territory for immigrants is, as aforesaid, the north-west part of the Island, which lies nearest to the peninsula of Hindústán. Here a Tamil population is established, whose connection with the Dravidian of India seems unquestionable. In the history of Ceylon we find very early mention of inroads by the Dravidian hordes. In the *Maháwaṇso* these people are called "Damilos." Since according to the testimony of the trustworthy Childers,† the word *Damiḷa* is in the Páli identical with *Draviḍa* in the Sanskrit, we may without hesitation apply to the Dravidians whatever is said of the Damilos in the *Maháwaṇso*. The English local writers generally call them Tamils or Malabars. Sir E. Tennent,‡ however, repeatedly warns us against understanding this to mean only the inhabitants of the actual Malabar coast. On the contrary, they belonged to one of the earliest organised states in the south of India, to the kingdom of Páṇḍiya,

* Davy. *l. c.*, p. 116.

† R. C. Childers' Notes on the Sinhalese Language. Journal of the Royal Asiatic Society. London, 1875, vol. VIII., p. 133, note.

‡ Tennent. *l. c.*, I. pp. 353-94.

which embraced the largest part of the Coromandel coast as far as Canara on the west coast, and south down to the sea, and of which at present there remains only the little State of Madura. Later on, hordes bearing also the name of Malabars poured over the Island from all parts of the peninsula, and also from the Coromandel coast as far as to the north of Cuttack and Orissa.

As early as the year 237 B.C. an invasion of the Damilos in the north is mentioned, where they established a sovereignty lasting twenty-two years.* Scarcely were they vanquished when, under the next king of the Síhala dynasty, Aséla (about 215 B.C.), again a Damilo, of the tribe of Uja in the Chóla-land,† usurped the throne‡ and ruled forty-four years. Although regularly defeated the Damilos ever anew repeated their invasions. In the reign of the king Mihinda (1023–1054 A.D.) the foreign population in the Island had increased to such an extent that they overpowered the aborigines, and upon a new invasion of the people from Solí the king was taken prisoner, and the country for a long time held under subjection.§ From Malabar fresh hordes continually streamed in, and only after severe struggles was the foreign yoke thrown off. But in the beginning of the thirteenth century the Chólas invaded the land again.|| This time, however, the conquerors came from much more distant places, namely, from Kálinga, and from the part of the Dekkan now called the Northern Circars.¶ Their leader, Mágha, subjected and cruelly devastated the whole country from north to south, and became king of Ceylon in 1211 A.D. Later, the Sinhalese prince succeeded in winning back again the provinces of

* The Maháwapsa, chap. XXI., edited by Turnour, p. 127. In the same book comp. Appendix : Sovereigns of Ceylon, p. lxi.

† According to Turnour, Maháwapsa, Glossary. p. 5, the Sinhalese *Solí* is called Chóla, and probably embraces Mysore and Tanjore.

‡ Maháwapsa, p. 128.

§ Maháwapsa, chap. LXIV.

|| A. De Silva Ekanáyaka. *Journal of the Royal Asiatic Society*, 1876, vol. VIII., p. 297.

¶ Tennent, *l. c.*, I. p. 412.

Ruhuna in the south and Máya-raṭa in the mountainous centre of the Island; but the north of the country, the province of Pihiṭi or Rāja-raṭa, the old land of the kings, remained, even as far as the Mahaweli-gaṅga, in the hands of the Tamils, and was by degrees wholly and permanently Dravidised. Only a part of this population, the Mukwás,* who dwell on the north-west coast, northward from Chilaw, have accepted the Christian religion.†

In the same way, although in a more peaceable manner, came into the country numerous Muhammadan Arabs, who since the time of the Portuguese have been called "Moors" or "Moormen."‡ Sir A. Johnston places their arrival in the early part of the eighth century, and traces their descent from the house of Hashim, whose members were driven from Arabia by the Calif Abdul Melek ben Merwán, and settled in Southern India, Ceylon, and Malacca. But the careful investigations of Sir E. Tennent§ have furnished evidence that the settlements of the Arabs in the Island were of much earlier date. Even when we set aside a very dark passage in Pliny, still there seems to be no doubt that at least since the first, or surely since the sixth century A.D., very extensive mercantile relations existed between Persia and Arabia and Ceylon, and that since that time many of these "Mauren" (as the Portuguese called them later) remained in the land. Sir E. Tennent considers the present Moors descended from the immigrants who intermarried with the natives. Mr. Pridham|| divides the Moors genealogically into two groups: one he traces back to the old Arabian immigrants, who took to themselves

* A similar word (Mokna) is used in Madagascar to designate immigrant Africans. (Verhandl. der Berlin. Anthropological Societät, 1880, s. 190. Zuitf. Ethnolo. Bd. 12.) Here a Negro tribe is alluded to on the eastern coast of Africa that bears this name. (Monatsbere der Academie, 1880, s. 1017.) Possibly the coincidence in the name is a mere accident.

† A. O. Brodie, *Journal of the Ceylon Branch of the Royal Asiatic Society*, 1853, p. 50.

‡ *Id.*, p. 40.

§ Tennent, *l. c.*, I., pp. 546, 555, 607.

|| Pridham, *l. c.*, I., p. 470.

wives from among the natives, and begot children by them; of the other, whom he calls Indo-Moors, who in greater numbers are said to have later settled in the districts of Chilaw and Puttalam, he gives no generic explanation, only contradicting the opinions of Mr. Cassie Chetty, that they derive their origin from a mixture of an aboriginal Hindústání population, the Sonahars, with Arabs and other Muhammadans. At any rate, however, Mr. Pridham acknowledges that no distinction any longer exists between the two groups. They are now in separate villages, portions of them scattered about over the whole Island, and are the chief medium of all mercantile intercourse, even with the Vēddás.

Malays belonging throughout to the Muhammadan religion are to be found in the Island only in comparatively small numbers, but scattered over many regions. According to the representation of Mr. Pridham,* they are descended chiefly from the little Rájás and their followers, whom the Dutch drove either from Java, Malacca, or Sumatra, and who were later by the English taken into their regiments of natives. More important it would be for us if the opinion were correct that the original population of the Island had been Malays. This is supported by the certainly very noticeable fact that the Singhalese used double canoes, or boats with booms, just such as are used in all the regions inhabited or colonised by Malays, that is to the west of the Indian and Arabian coast of Madagascar.† This, however, is the only foothold for the hypothesis of an ethnic relationship.

Naturally in the last centuries the different nations of Europe, especially Dutch, Portuguese, and English, have been added to the population, but for our researches they are of no importance. The same is to be said of the African Negroes and the Parsees, the former of whom have been only recently introduced, whilst the latter immigrated at different periods, but in small numbers.

*Pridham, *l. c.*, I, p. 482. †Tennent, *l. c.*, I. p. 327; II., p. 103 (engraving).

The southerly half of the Island, the old province of Ruhuna, and the central Máya-land, are still peopled by the Sīghalese,* the former by comparatively pure-blooded Sīghalese, the latter by the somewhat more mixed Kandians, who have been repeatedly mentioned as the immediate neighbours of the Vēddās.

The ethnological position of the Sīghalese has been until now discussed chiefly on linguistic grounds.

Since Rask† their language has been considered as Dravidian; Lassen‡ has sustained this opinion with the whole weight of his authority; he regarded the Sīghalese people, according to their language, as belonging to the great family of the Dekkan tribe. Still more recently Mr. F. Müller has declared the Sīghalese language to be an idiom akin to the Dravidian language, strongly mixed with Indian elements, which, however, differing from them genealogically, has therefore had an independent development. Hence he infers the population to be a mixture of immigrated Indians|| with the aborigines, who seem to be of the same race as the Dravidians. Directly the opposite opinion (and one which of late is more and more generally recognised) has been maintained by d'Alwis¶ and Childers,** both of whom were employed in the civil administration of the Island. Childers, whose thorough knowledge of the Indian languages is universally acknowledged, separates the present Sīghalese language from the ancient Ēlu, from which, as he says, it is certainly derived, but from which it also differs through the immense number of Sanskrit words it includes, partly unchanged, as the English

* In the writing of this name I follow the explanation of it by Childers, *l. c.*, p. 37 (instead of Singhalese or Cinghalese).

† Rask. *Singalesisk Skriftlaere*. Kolombo, 1821, (quoted by Lassen).

‡ Christ. Lassen. *Indische Alterthumskundl. I.*, s. 199-303.

§ Fr. Müller. *Allgemeine Ethnography*. Vien., 1879, s. 466, sq.

|| *Reise der Novara*, O. S., 139.

¶ James d'Alwis. *On the Origin of the Sīghalese Language*. Journal of the Ceylon Branch of the Royal Asiatic Society, 1867-70.

** Journal of the Royal Asiatic Society. New series. London, 1875. vol. VII. p. 35; 1876, vol. VIII. p. 131.

of to-day differs from the old Anglo-Saxon. According to him the name of *Ēlu* is identical with the word *Sīṅhala*, as the Sīṅhalese call themselves, which borrowed from the Sanskrit is by the uneducated generally pronounced *Hīṅhala*; it stands for the old word *Hela* or *Helu*, and this again for a still older *Sela*, which leads us back to the Pāli of *Sīhala*. The old tradition, according to which the founder of the Sīhala dynasty (Wijaya) came from Lāla, a district of Magadha (Behar) in India, agrees very well with the fact that according to another tradition Pāli was originally a Magadha dialect. Pāli and Sīṅhalese are so nearly related that one might almost believe at the first glance the latter to be derived from the former, but on closer inspection we should see that Pāli, in which the teachings of Buddha were written, represents only the dialect of one district of Magadha. Hence Sīṅhalese is one of the native Aryan (Sanskrit) languages of India, and very ancient. For it is absolutely identical with the *Ēlu* of the fifth and sixth centuries A.C., which is found also on the rock inscriptions of Mihintalé of the second or third century. The early establishment of the language is explained by the fact that Mahinda, at the beginning of the third century B.C., translated a Buddhist work from the Pāli into the Sīṅhalese, thereby making the latter the written language.

What place the Vēddá language holds relatively to this is still in the highest degree dubious. In Ceylon itself the opinion has long prevailed* that it is a broken or corrupted Sīṅhalese. Mr. Bailey† also adopted this opinion, although he considers the Vēddás as descendants from an ancient Tamil population. But he found in their language numerous Hindú words—personal names—corresponding often to the names of Hindú gods or goddesses. Hence he was inclined to assume an

* Knox, *l. c.*, p. 104. Mr. Justice Starke. Journal of the Ceylon Branch of the Royal Asiatic Society, 1853. p. 80. Gillings, *id.*, p. 84.

† Bailey, *l. c.*, pp. 297, 305, 309. He mentions especially that the so-called elk of Ceylon (*Rusa Aristotelis*) is in Vēddá language called "gawra," which reminds one of the gaur (*Bos gaurus*) of Hindústán. But to be sure the pengolin (*Manis pentadactylos*) is also called "gal gawra."

early mixture of the Vēddās with the Sanskrit-speaking people of India. Mr. Max Müller* confirms the frequency of Sanskrit words in the Vēddā language ; more than half the Vēddā words, according to him, are, as in the Sinhalese itself, mere corruptions of the Sanskrit. Mr. E. Tylor† also, who considers the Sinhalese an Aryan tongue, holds the Vēddā language for a Sinhalese dialect, although with a mixture of Dravidian (Telugu) words. Therefore he finds a striking contradiction in that probably a non-Aryan, aboriginal tribe speaks an Aryan language. This he calls a perfectly unique instance in ethnology. Later on he repeats his thesis in the following words : “ Their legends as well as their language make a mixture of Aryan blood along with Aryan language probable ; whilst bodily characteristics show that the race of Vēddā belong chiefly to the native pre-Aryan type.

Mr. Hartshorne‡ has again recently asserted, in direct opposition to Mr. Tylor, the entire absence of a distinct Dravidian element in the Vēddā language, and allows in it only approaches to the Sinhalese, to the Pāli, and to the Sanskrit. Mr. Cust§ contends for the reverse, objects to the idea of any admixture of Pāli or Sanskrit, and holds the

* Max Müller. Address to the First Meeting of the Aryan Section of the Oriental Congress of 1874, cited by Childers, *l. c.*, vol. 8., p. 131, note.

† Journal of the Ethnological Society of London, 1870. New series, vol. 2, p. 96.

‡ Hartshorne, *l. c.*, p. 417. “ Besides the words which indicate an affinity with Sinhalese, there are others which are allied with Pāli and with Sanscrit, and an important residue of doubtful origin : but it is worthy of remark that from beginning to end the vocabulary is characterised by an absence of any distinctly Dravidian element, and that it appears to bear no resemblance whatever to the language spoken by the Yakkas of the East Nipal. A similarity may, indeed, be traced here and there between a Wedda word and the equivalent for the same idea in modern Tamil, Malayalam, or Telugu ; but the cases in which comparison is possible are so rare, that these apparent coincidences may be fairly considered to be merely fortuitous.”

§ R. Cust. A Sketch of the Modern Languages of East India. London, 1878, p. 63.

Veddá language to be simply a dialect of the Sinhalese, which he, like the other writers, looks upon as an Aryan language.

With these disagreements in the views of linguists, we gain, unfortunately, very little from them towards a just comprehension of the phylogenetic position of the Veddás. On the contrary, the mystery that envelops this people, so remarkable in themselves, is vastly increased, and the purely anthropological interest comes even more into the foreground.

So far as we at present know, this people, like so many others, bears a name ascribed to them by outsiders. Mr. Hartshorne only, in a communication made by him to Childers,* asserts that they gave themselves this name (pronounced Vaeddá). The reports generally say just the contrary. The designation Veddá or something like it (Vedda, Veda, Vedan, Vaidan, Beda, Bedan, &c.), is widely used in India, as Mr. F. Jagor† has lately shown by a comprehensive grouping of facts. A whole series of little tribes dwelling far apart, and probably not having the least connection with another, bear this very same name, or one quite like it. The translator of Percival's work, Bergk,‡ reminds us that there are Veddás even in Sumatra and Borneo. At any rate, whether that word is derived from the Sanskrit (*Vyádha*, "hunter") or the Tamil (*Védan*, "hunter," "wood-dweller"), so much seems to be certain, that except where it is used in combination, as, for instance, in the earlier mentioned Daḍa-Veddá, it always relates to aborigines or savage races. In so far it stands, as Mr. Bailey§ remarks in a paragraph, with the purely literary words "Habara" (barbarian) and "Vannacharakiya" (hunter), and the like. Dr. Max Müller, who declares the

* Childers, *l. c.*, vol. 8, p. 131.

† Verhandlungen der Berliner anthropologischen Gesellschaft, 17th Mai, 1879, s. 172. Zeitschr. für Ethnologie. Bd. XI.

‡ Percival, a. a. O. S., 335.

§ Bailey, *l. c.*, p. 297.

correct writing of it to be Vaeddá, or originally Veadí (Vaediminita—Vēddá-people), agrees entirely with the derivation from Vyádah, and Childers therefore defines the Vēddás as “wild Sīphalese.”

How long the name has been in use is not yet clearly established. In the works of ancient Occidental writers only one passage has as yet been discovered wherein the Vēddá name is preserved, although in a mutilated poem. In a work* ascribed, falsely perhaps, to the Bishop Palladius of Helenopolis in Bithynia (defunct 410 A.D.), which describes the journey of a man from Thebes in Egypt to Ceylon, we read *εἰσι δὲ καὶ οἱ Βισσάδες ἀνθρωπάρια κολορα, μελανοκέφαλα ἀκαρτα καὶ ἀπλότριχα*.†

Sir E. Tennent,‡ following another edition, reads *Βισάδες*; but *Βισσάδες* is more like the word Vēddá. Since the further description likewise suits the Vēddá right well, we may conclude that here the name was for the first time transmitted to the Occident. Before this we only hear that Megasthenes in the time of Alexander knew§ of “Palæogonen” upon the Island, which signifies, according to Sir E. Tennent,|| “Pali-putrá” (sons of Pali); but according to Lassen,¶ referring to the Rākshasas, or giants. In the first case it should apply rather to the Sīphalese, in the latter to the Vēddás (though certainly not in the sense of giants). The inland writers do not use the name of Vēddás until much later.

Mr. Hartshorne,** on the authority of an ancient ola (a book written with a stilus upon palm leaves) which was

* Παλλαδίου περὶ τῶν τῆς Ἰνδίας καὶ τῶν Βραγμάνων. Palladius *De gentibus Indiæ et Bragmonibus*. London, 1668, p. 5.

† Tennent gives *μεγαλοκέφαλα* instead of *μελανοκέφαλα*, as read in the edition from which I have quoted, although the first perhaps seems more consistent. I must remark that the Latin translation given in the edition of 1668 is *capite nigro*.

‡ Tennent, I., p. 538, note 2; II., p. 438, note 6.

§ Plinius. *Natural History*. lib. 6., cap. 24.

|| Tennent, I., p. 529.

¶ Lassen. *De Taprobane Insula*, p. 9.

** Hartshorne, *l. c.*, p. 414.

in the possession of one of the Kandyan chiefs, states that King Dutugemunu (160 B.C.) appointed the Veddás servants of the god Skanda, in the temple Kataragama Déwále built by him, on account of the purity of their caste. As, however, the age of the ola is not known, we can draw no sure conclusion from this statement. Only the fact that here again the purity of caste is emphasised must make us cautious about looking upon the Veddás as a mixed people. When we consider for how long a time, and with what scrupulous care, the people of India have matured and preserved the distinction of caste, *the fact that they have acknowledged without exception the unity and purity of such a wild tribe* must surely appear of great significance.*

Indeed, all inquirers testify to the unmixed character of the tribe. The different names which have been given to separate divisions do not indicate different tribes, but geographical and topographical distinctions. Thus the Tamils distinguish the “Mañalkádu,” or sandy jungle Veddás, from the “Cholaikkádu” Veddás, that is, those living on the sea coast, who speak Tamil and till chena land, from those yet leading a nomadic life, who, as they say, are quite different from the others, have preserved much of their original barbarism, and inhabit the more remote parts of the Bintenna district. At any rate, this distinction is not to be understood as referring to typical differences in the tribe.

From the preceding we gather that up to the present time two leading views stand opposed to one another, which are mainly supported by linguistic observations, and only in part by genuine anthropological facts. According to one, the Veddás would be next of kin to the Dravidians; according to the other, members of the great Aryan family. In both cases they must have immigrated from the continent, only in the first very much earlier than in the second. I find only one single conjecture mentioned of any such immigration. The

* Hartshorne, *l. c.*, p. 406.

† *Id.*, *l. c.*, p. 411. .

Rev. Mr. Gillings* repeats the story that the Vēddās originally formed a part of a Sīghalese community living on the sea coast of India, and that from there they had been transported for certain offences over to the Island at a very early period, and before the Sīghalese, as a people, had set foot on its shores. But we do not find it said anywhere that such a Sīghalese community had existed on the Indian coast. Moreover, the Vēddā language, if any such separation from a common Aryan family had so early taken place, must have retained certain peculiarities belonging to that earlier period of development ; and of this also nothing is known.

The explanation should be much simpler, if one might assume that the Vēddās were originally of the Dravidian race, or at least nearly related to the Dravidians ; or even if different from them, at any rate, a savage aboriginal tribe ; and that they only received their present language subsequently from their Aryan conquerors. With such an assumption the identity of this language with the Sīghalese, which is defended by authorities, would be supported without an effort. But it cannot be denied that it is difficult to conceive how the process of Sīghalesing the language could have been accomplished, whilst their whole way of living, their customs and habits remained wholly unchanged.

In the name chosen by Childers of "Wild Sīghalese," little is gained. If it means savages with a Sīghalese language, we have a fact given us, but no explanation. If, on the other hand, it means Sīghalese who have become savage, we should then, with our explanations, have to fall back on some period after Wijayo, and contrary to all common experience be forced to add the hypothesis (against which I protested in a former passage) that the Vēddās from a high state of comparative civilisation, such as plainly had once been attained by the Sīghalese, have sunk to the lowest level of human

* Journal of the Ceylon Branch of the Royal Asiatic Society, 1853, p. 84.

existence. Religion, political organisation, civil life, all the arts and customs of firmly located tribes have been lost, indeed, forgotten, and that, too, while in closest proximity—even in direct contact—with a people who had passed through a long and eventful history. Such a degradation is not conceivable, unless we can prove at the same time very deep physical demoralisation.

From whatever side we consider the problem, we must always come to the conclusion that linguistics can only be used as aids in the investigation ; and that if a real solution is to be found, it is only possible by means of physical anthropology. What I have to offer in this direction is nowise adequate to lead on to a full solution, but it will perhaps contribute in reducing the possibilities of explanation to a small number, and thus prepare the way for a final decision. At the same time my hope is that these suggestions will stimulate to new labours, especially in the Island itself, that, if possible, even at the last hour every effort shall be made to obtain a correct description of the last remnants of this fast dying out people.

The hitherto ascertained facts regarding the physical peculiarities of the Veddás are the following :—

Even the description of Βιθσαδες (βισσάδες) furnishes truly characteristic features. The principal passage has been already quoted : smallness and feebleness of stature, heads black and apparently large, with long, smooth unshorn hair.* Added to this is the further statement that the people dwelling in the rocky caverns are the smallest (πάνν μικρότατον καὶ ἀδρανέστατον), and that they are very agile in climbing the precipices.

* The bad Latin translation of this, which is ascribed to the Holy Ambrosius, in the reprint appended to the above-cited edition of Palladius (S. Ambrosius *De moribus Brachmanorum*, p. 59) : Nam et ipsos exiguos homunculos esse et grandia quaedam capita asserit habere cum levibus et detonsis capillis. Here, therefore, once more is the supposed manner of reading μεγαλοκέφαλα.

Knox, as already cited, saw in his flight through the woods of the Veddā country no human beings, only empty dwelling places. Hence the picture contained in his book represents a man differing from the likenesses of the Singhalese in look only, by his shorter and more thick-set figure; he wears the hair and beard noticeably long like the Singhalese, the former being gathered into a knot on the back of the head.

Percival,* 1798, saw some captive Veddās in Colombo. According to his representation, they were of lighter complexion than the rest of the Ceylonese, being rather copper coloured, were remarkably well-made, wore long beards, and their hair tucked up close to the crown of the head.

Valentyn† says the Bedas, or Wedas, are a kind of wild bushmen, and the oldest inhabitants of the Island: "Zvort-van berwe, beandend van Oogen, niet groot van gestalte, maar gezeten rad van Lieden." To these very broad statements, followed at last by John Davy‡ the first definite scientific description resting on autopsy. He says: "Such of the village Weddhas that I have seen were in general small men, between 5 ft. 3 in. and 5 ft. 5 in. high, slender, muscular, and well made; in colour, form, and features resembling the Singhalese. Their appearance was wild in the extreme, and completely savage.....Their hair was quite emblematic of their forests: it seemed never to have been cut, or combed, or cleaned; and was long, bushy, and matted, hanging about their shoulders, and shading their faces in a very luxuriant and disgusting manner; nor were their beards less neglected."

Sir Emerson Tennent§ gives the following general description of the Veddās in the region of Bintenna:—"They all presented the same characteristics of wretchedness and dejection—projecting mouths, prominent teeth, flattened noses, stunted stature, and other evidences of the physical depra-

* Percival, *l. c.*, p. 283. † Valentyn, *l. c.*, bl. 49. ‡ Davy, *l. c.* p. 116.

§ Tennent, *l. c.*, II, p. 450.

vity, which is the usual consequence of hunger and ignorance. The children were unsightly objects, entirely naked, with misshapen joints, huge heads, and protuberant stomachs. The women, who were apparently reluctant to appear, were the most repulsive specimens of humanity I have ever seen in any country." Pridham* gives the report of Mr. Bennett, who, during his residence at Hambantōṭa, had two village Vēddás brought before him. The latter says of them : " They were not more than 5 ft. 2 in. in height, their hands small, but their feet were long and flat ; hair matted and tied in a bunch at the back of the head ; a large bushy beard, almost covering the face ; eyes small, piercing, and constantly in motion to the right and left, and their ears seemed almost as restless as their eyes."

If from these general descriptions we come to details, we observe that all the accounts agree first in this, that the average stature of the Vēddás is small, not to say very small. Dr. Davy (in the citation by Prichard) says of them : " They are well made and muscular, but of a spare habit ; and in person they chiefly differ from the Kandyans in the slightness of their limbs, the wildness of their looks, and their savage appearance." Gillings declares : " The Veddahs are mostly low in stature, but some of them are strong, active men, and most of them appear to be healthy, and little subject to disease." The description of Mr. Bailey† is to this effect : " In appearance the Veddahs differ materially from the Singhalese. They are smaller in every respect, and rather dark, or, more properly, more dusky in complexion. They are short, slightly built, yet very active. Though far from being muscular, their limbs are firmly knit together, and they are athletic and capable of enduring great fatigue. Though spare, they are generally in very fair condition, and look more healthy than many of the Singhalese in the adjoin-

* Pridham, *l. c.*, I., p. 460.† Bailey, *l. c.*, p. 232.

ing districts." He measured several of them. The tallest man, and one towering considerably above his fellows, was only 5 ft. 3 in. in height; he was a more civilised Vēddā from Bigtēna. The shortest whom he saw measured was 4 ft. 1 in. He considers the average height of the men from 4 ft. 6 in. to 5 ft. 1 in., and the women from 4 ft. 4 in. to 4 ft. 8 in. In a list of measurements taken at his suggestion, two men are reported as 5 ft. 3 in. and one as 5 ft. 3½ in. If these measurements are correct, they exceed, in his opinion, the average measure. Among fourteen Vēddās of Bintēna, the tallest was 5 ft. 3¾ in., the shortest 4 ft. 6¼ in.; the medium was about 5 ft. ½ in. Of twelve women, the tallest was 5 ft. 2½ in., the shortest 4 ft. 4½ in., the medium about 4 ft. 9 in.

Mr. Hartshorne* gives only two measurements of persons, whom he believes to be fairly average specimens of the race. One of them, Latty, eighteen years of age, was 5 ft. 4¼ in. in height; the other, Bandiey, about twenty-five years old, measured 4 ft. 11¾ in.

If we reckon this in metres, we have the following:—

The tallest man	...	1,638 mm.
The shortest man	...	1,245 mm.

The medium, according to measurements taken in Bintēna:—

For the men	...	1,537 mm.
For the women	...	1,448 mm.

The conclusion to which we arrive is that the Vēddās are a very small, not to say dwarfish, race.

In reference to details of the size, the majority of observers in reality present no facts which indicate disproportionate or imperfect development of the separate members of the body. Only Mr. Hartshorne, who characterised the general appearance of the Vēddās as "distinctly non-Aryan," asserts that they have short thumbs and sharp-pointed elbows. It would be very satisfactory if these accounts could be corroborated by fresh observations.

* Hartshorne, *l. c.*, p. 408, note.

The complexion of the Vēddás is dark,—according to most reports, darker than that of their neighbours, the Siphalese, of whom Davy says, that their colour varies from light brown even to black. Bailey speaks of the colour as dark, or rather dusky, by which, at any rate, a very deep shade is meant.

The hair of the head and beard Davy describes as long and matted; it is never cut or combed. Sir E. Tennent* says: "Their long, black hair and beards fell down to their middle in uncombed lumps." Sirr† reports that "their hair, beards, and whiskers are never shorn or cleansed, and these redundant tresses hang over their shoulders and bosom in matted masses." Bailey calls the beard "short and scant; the hair of the head, which is not curly, falls in rusty, tangled masses about the face," making the head appear disproportionately large. Later, he speaks of "their wild shaggy hair." When one sees the people, he says, with their rugged, uncombed locks half-covering their faces, they fully represent a preconceived idea of barbarous savages. Hartshorne‡ calls the hair of the head "coarse" and "flowing," and considers it necessary to add that their bodies are by no means hirsute, and that there is no tendency of the hair to converge towards the elbows, or to diverge from the chin, or *vice versâ*.

Through the kindness of Mr. Bastian, two photographs have been sent me of a company of Vēddás, which he obtained in Colombo. They represent three men and three women in full figure, but unfortunately of too small a size to give a clear idea of them. This was the party, it seems, presented to the Prince of Wales on the occasion of his visit to the Island. Mr. Hartshorne, who, to be sure, only speaks of two men and three women, is of the opinion that they came from the district of Batticaloa, where the few Vēddás still remaining, partly through the influence of the missionaries, partly through

* Tennent, *l. c.*, vol. II., p. 449.

† H. Ch. Sirr, *Ceylon and the Siphalese*. London, 1850, vol. II., p. 210.

‡ Hartshorne, *l. c.*, pp. 408, 409.

marriage with the Tamils, have lost many distinctive features of their primitive state. "Two of the women," he says, "were very gentle in appearance, and one is reported to have been decidedly pretty; the two men were described as small and rather ape-like." To these descriptions the photographs aforementioned correspond pretty well.

Though these may not be examples of the purely savage Veddás, I have nevertheless, in lack of any other representations, asked Mr. Mützel to make a drawing of two men and one woman, from which a woodcut* has been prepared. It shows plainly the growth of the hair; the noses comparatively short, broad at the end, and flattened; the eyes apparently deep-set, and the lips of the younger persons full and bulging; so that it gives a far more vivid idea of the people than any description could furnish. One only of the men has anything like a beard. We see the little apron worn by the men, the great bows they carry, the arrows with the leaf-shaped points, and finally the iron axe stuck in the girdle.

As regards the hair, it is comparatively long with all the six persons, but evidently put into some shape by the help of a comb. The women wear their smooth, slightly waving hair parted in the middle, and so does one of the men, who certainly exhibits his *chevelure* in a somewhat disordered condition. Two of the men have curly hair, which forms a bush about the head, sticking out widely and falling down upon the neck, exactly corresponding to all the known descriptions of them. This makes the head appear very large, especially in proportion to the lean body and limbs. But it must here be particularly remarked that this curly hair is never in small, tight rolls as among the Negritos, and the bush of hair does not in the slightest degree approach the peruke, such as is generally worn by the Viti people, or the Abyssinian tribes; on the contrary, the curly hair is very long, and falls down pretty low upon the

* Not reproduced here.—Hon. Sec.

neck, and it is therefore out of the question to talk of woolly hair. It is a comparatively smooth, simply wavy hair, occasionally curly, but remarkable for its length, and just as Palladius describes it, in a most pregnant manner, *ἀκαπα καὶ ἀπλότριχα*. We must here add that he expressly contrasts these smooth-haired people with the Indians (Negroes), whom he calls *φριζότριχες*. Of the eyes, Davy only mentions that they are lively, wild, and restless. Valentijn calls them burning. Bailey speaks of them as "good, and often full." Only Mr. Bennett asserts that they are small, which probably means deep-set. With regard to their colour, I find nothing said. But the statements are sufficient at any rate to prove to us *that the Vēddás are a dark, but not actually black, race, and not woolly-haired like the Negro.*

Hartshorne says of the noses, like Sir E. Tennent, that they are flat; and of the lips, that they are sometimes thick. If we add to this their short thumbs and sharp-pointed elbows, there are indications enough by which to distinguish them in a noticeable degree from the Oriental races living in their neighbourhood. Bailey calls the nose "well-shaped, though inclining to be flat; the nostrils wide; the mouth sometimes large; and the lips firm, but rather thick;"—the features of the face, on the whole, "tolerably regular." Sir E. Tennent describes the mouth as "projecting," and the teeth as "prominent."

Before comparing this picture with that of any other of the neighbouring people, I will add some craniological observations. By an especially happy accident I was enabled myself to examine three Vēddá skulls. I had applied to the German Consul in Colombo, Mr. Ph. Freüdenberg, when he was here, to obtain, if possible, skulls from Ceylon, and especially of the Vēddás. He wrote to me on February 27, last year, that he was sorry he himself could not do this; but that the Governor and Committee of the Museum in Colombo had declared themselves ready to send here as a loan for six months any skulls I might wish to have from their Museum.

These arrived in the summer, accompanied with a note from Mr. A. Haly, the Director of the Museum in Colombo. To all these gentlemen I would express my most sincere thanks for their very great kindness in thus furthering my wishes. I will proceed to give a brief description of the skulls.

Skull No. 1.

Mr. Haly appends to it the following note :—

“Presented by Mr. W. W. Hume, Government Agent, Southern Province.

“This skull is said to be that of a Veddá woman, and was found at Dewilané near Batticaloa, but there seems to be no evidence to show that it is a Veddá skull.”

Plainly a woman's skull, very white, smooth, and of little capacity (1,250 cub. cm.), with teeth much worn away. Whether an under-jaw belongs to it is questionable, for although the condyloid processes of the one fit tolerably, it yet appears somewhat too short; hence it is omitted in the drawing.* The capsule of the skull is long, narrow, and flat, of a pronounced dolichocephalous index (70·9). The brow is quite straight, but not high, without marked orbital prominences, but with strong *tubera*; the *glabella* not much sunk, and at the nasal process remnant of the frontal suture one centimetre long. The curve of the parietal bone appears long at a side view; so also the narrow backhead. The *norma occipitalis* shows a slightly ogivalous form, but has, on the whole, a rounded outline narrowing toward the bottom. On the high and pointed *squama occipitalis* we find no distinct *protuberantia externa*, but strong cerebellar arches.

The sutures are well preserved and pretty deeply indented. On either side are temporary interpolations of bone; to the right an oblong bone extending the whole length, with a slight degree of stenokrotaphy and low *angulus parietalis*; to the left an imperfect bone, but only in the posterior half of the sphenoparietal suture, beside which the point of the

* The drawings of the skulls are not reproduced.—*Hon. Sec.*

ala sphenoidealis comes up high, whilst the *angulus parietalis* is low; likewise in the under part of the lambdoidal suture on either side and on the posterior lateral fontanel interpolation.

A view of the skull from below shows plainly the length and narrowness of the occipital region. The very large *foramen magnum* is injured at the posterior edge, but can be measured approximately. The articular processes of the occipital bone are situated quite anteriorly, and their fascets turned rather to the outside. Small mastoid processes.

In the front view the forehead appears comparatively broad, the face short and of moderate breadth. Index 83.1; therefore chamæprosopic. The very large orbits are likewise broad and extended toward the outside and the bottom, but on the whole rather round in form. Their index amounts to 84.6, and therefore mesokonch. The cheek bones project, and the canine *fossæ* are correspondingly very deep; on the other hand, the zygomatic arches are not very prominent. The nose is rather high on the face, and somewhat to one side, narrow at its root, the ridge bent in, the aperture large. Index 50, therefore mesorrhine. The upper jaw is, on the whole, low, especially at the alveolar process, which is slightly prognathous; the facial angle (brow-nasal spine and auricular orifice) measures 82. The palate long and broad toward the back, the alveolar line somewhat in the form of a horseshoe, and the teeth and the alveolar cavities, especially in the front, large. Index leptostaphyline, 75. The (questionable, therefore omitted in the drawing) under jaw, small and low, the rami slanting and feeble, and particularly narrow. The distance of the maxillary angle amounts to only 85 mm., or 10 mm. less than the lower frontal breadth.

(2).—*Skull No. 4.*

Mr. Haly designates it as evidently abnormal, and says of it and the following (No. 5): "They were procured by the Rev. S. Somanader, the Veddá missionary at Batticaloa. There is a lower jawbone, but I do not know to which skull

it belongs. Mr. Somanader guarantees these as being the skulls of absolutely pure-blooded Veddás, a race, he says, now almost extinct."

The skull, in all probability female, is without a face. Perhaps there belonged to it a senile under-jaw with totally obliterated alveolar cavities, perpendicular and delicate rami and condyles, which, by *arthrititis chronica senilis*, are changed; the skull, however, does not give the impression of having belonged to such a very old person. This skull is unusually small; its measure inside is only 1,025 cub. cm.; it is therefore almost nannocephalous. It is, beside being very crooked, especially depressed on the left side posteriorly, short, though rather broad and high. The index amounts to 80.6; it is therefore brachycephalous. The reason for this abnormality is probably an artificial, or accidental, deformation; for although it has a *synostosis* of the under coronal and the spheno-frontal suture, the main aberrations are in the occipital region. The other sutures are much indented. The *squama occipitalis* is very high, and the lambdoidal angle acute; no *protuberantia externa*. *Tubera* on the brow and parietal bones strongly developed; the brow much arched. *Orbitæ*, so far as their form is recognisable, very large.

Skull No. 5.

This is a male skull, unfortunately also without a face, but in all other respects quite uninjured. Its capacity is considerably greater (1,360 cub. cm.) than that of the two female skulls, but in itself not large. The surface is covered with distinct traces of muscle, especially the back head, where the *facies (muscularis squamæ occipitalis)* show very deep impressions: the *protuberantia externa* is unusually strong and hooked in form, and the *linea semi-circularis superior* makes a strong V-shaped projection. Also the nasal and orbital prominences are strong, although not specially large. The capsule of the skull is distinctly dolichocephalous, with an index of 73, showing in a side view a long finely-

arched curve, with full high brow and round, strongly projecting back head. The sutures are well preserved; only the under portions of the coronarie and the *spheno-frontalis* are synosteotic. In spite of this the temporal regions are on the whole well formed. From a posterior view this skull also has an ogivalous form, yet with greater breadth of basis. The *squama occipitalis* is high, and the lambdoidal angle very acute. The cerebellar arches large. At the basis the occipital region appears unusually long. The *processus condyloides* are very prominent, and the articular facets turned decidedly outward. The mastoid process strong. In a front view the forehead appears broad; the nasal root somewhat deep, but narrow; the bridge of the nose erect; the *orbita* large and slightly rounded; the zygomatic arch not prominent.

Although Mr. Haly says there is no proof that skull No. 1 is a Veddá skull, yet I see no reason why it should not be considered as such. Batticaloa is, as we learn from the preceding accounts, known to be the old Veddá region; and the statement of Mr. Hume that it is the skull of a Veddá woman must have been founded on distinct circumstantial evidence. Certainly it is the skull of a woman; and since also it coincides with other Veddá skulls, I do not scruple to accept it as such. The circumstance that there is nothing about it corresponding to the usual idea of the skull of a savage cannot be of any weight, since the rest of the skulls also impress us as being comparatively delicate, not to say civilised. This is a peculiarity which belongs to different unquestionably savage inhabitants of the Eastern Archipelago, and which is especially conspicuous among the Andamanese, the Negritos of the Phillipines, and many other savage tribes in the mountains of Hindústán. The origin of the two other skulls is so clearly testified to by the missionary of that region, Mr. Somanader, that there is no room for doubt.

For comparison we have a not inconsiderable number of apparently well-ascertained skulls now to be found in

England. Of these, eleven were in possession of Mr. Barnard Davis, who has given notices of them in his "Thesaurus Craniorum": London, 1867, p. 130. Among them are four, likewise from Batticaloa, two from Badulla, and two from Uva. Some are damaged, and must therefore be set aside in our examination. Nine other Veddá skulls are found in the great anthropological collection in the Hunter Museum; their measures have lately been published by Mr. W. H. Flower in his "Catalogue of the Specimens Illustrating the Osteology and Dentition of Vertebrated Animals contained in the Museum of the Royal College of Surgeons of England": London, 1879, Part I., p. 111. Among them are also those which Mr. George Busle (Proc. Linn. Soc., 1862, vol. 6, p. 166) has earlier described. Of two of these it is stated that they are from Nilgala. The two last and the one from Bintenna (Badulla) are furnished by Mr. Bailey. A picture of one of the men's skulls from Bintenna (No. 675) is given in the work of the Messieurs de Quatrefages and Hamy, "Crania Ethnica," Paris, 1876-77. Of two others (Nos. 681 and 682), it is especially said that they may be considered authentic specimens.

In all, we have then, twenty-three skulls for comparison. Among them there is, beside the above-mentioned deformed skull (No. 4) from the Museum at Colombo, another from the Hunter Museum (No. 676), one from the Bailey collection, brought from Bintenna, of which it is expressly asserted that "it has been unsymmetrically distorted by occipital pressure." These two must, therefore, be excluded from certain examinations. The rest of the anomalies, however important they may be, can in the main be passed over. I will only briefly call attention to the fact that the skull I have described, No. 1 from the Colombo Museum, shows some temporary aberrations, especially interpolations of bone, and also that the skull represented by the Messieurs de Quatrefages and Hamy, No. 675, out of the London Museum, shows distinct stenokraphy.

The total result obtained is, first, that the Vēddá skull is uncommonly small, and that occasionally genuine nannocephaly appears in the race.

Of the deformed skull out of the Colombo Museum (No. 4) I have already pointed out that it possessed only a capacity of 1,025 cub. cm. Mr. Flower has discovered even a smaller one, that of an adult woman (No. 679), which measures only 960 cub. cm., and of which he says "that is the very smallest in the whole collection." Here we must particularly remark that it is not a question of microcephaly, in the pathological sense, but of crania justo minora. In order to avoid confusion, I have therefore chosen the name, which I have suggested in an earlier essay, of nannocephalous.

I give in the following a list of some of the measurements, as the fact just signalled is of special importance for the cognisance of races. Regarding the skulls of Mr. Bernard Davis, the first column shows the weight of the sand used in measurement, as given by him; the second and third columns give the reduction of the weights into measures, according to the table made by Mr. Weleker:—

I.—Statements of Mr. Davis.*

No.	Weight. oz.	Men. cub. cm.	Women. cub. cm.
1	64	1,275	—
6	70	1,394	—
7	56	—	1,115
8	65	—	1,295
9	64	—	1,275
10	81	1,614	—
11	59	—	1,175
12	72.5	—	1,444
Average of	3 men's skulls	...	1,428 cub. cm.
Do.	5 women's skulls	...	1,261 „
Do.	8 Vēddás' skulls	...	1,323 „

* Virchow, "Gesammelte Abhandlungen zur wissenschaftlichen medicin." Frankfurt, A.M., 1856, s. 901.

II.—Statements of Mr. Flower.*

No.	Men. cub. cm.	Women. cub. cm.	Uncertain. cub. cm.
675	... 1,140	...	—
676	...	1,225	...
677	...	—	1,235
678	...	1,250	...
679	...	960	...
680	... 1,225	...	—
681	... 1,260	...	—
682	... 1,420	...	—
683	...	—	1300
Average of: 4 men's skulls ...			1,261 cub. cm.
Do. 3 women's skulls			1,145 „
Do. 2 uncertain skulls			1,269 „
Do. 9 Veddás' skulls			1,224 „

III.—My own Statements.

No.	Men. cub. cm.	Women. cub. cm.
1	... —	1,250
4	... —	1,025
5	... 1,360	—
Average of 3 Veddás' skulls...		1,211 cub. cm.
Do. 20 Veddás' skulls...		1,261 „
Do. 8 men's skulls ...		1,336 „
Do. 10 women's skulls		1,201 „

Only two men's skulls, viz., No. 10 among Mr. Davis's and No. 682 among Mr. Flower's, exceed 1,400. The first measures 1,614 cub. cm., and is called by Mr. Davis himself "abnormally large"; the other measures 1,420 cub. cm. All the rest of the measurements given are much less,—three between 1,100 and 1,200 cub. cm. and eight between 1,200 and 1,300 cub. cm. The average of 1,261 computed above may, therefore, be esteemed a pretty fair measure.

The amount of the variation is particularly worthy of attention. If we take the two extremes, the woman's skull

* Archiv. für Anthropologie. Bd., l. s., 272.

of 960 and the man's of 1,614 cub. cm., we have a difference of 654. The different ways of measuring may possibly have increased the difference a little, but not enough to be of any importance.

The length measures stand in a close, but nowise simple, relation to the capacity. In regard to the horizontal extent from the reports of Mr. Davis, I calculate as the average of three male skulls 19·9 English inches = 506 mm., the average of eight female skulls 19 in. = 483 mm., and the average of thirteen skulls altogether 19·2 in. = 488 mm. From the figures given by Mr. Flower accrues an average from five male skulls of 485, of two female skulls of 454, and of seven skulls altogether 476 mm. From my measurements accrues for three skulls an average of 486 mm., a figure pretty near to the others. From all the twenty-three skulls I calculate an average of 484 mm.; from Mr. Davis's skulls and mine, sixteen altogether, an average of 487 mm. The lowest measure (448) was found by Mr. Flower with the nannocephalous girl, the highest (512) with a man; so here too we have a difference in the extremes of 64 mm. The skulls I have described prove here also absolutely typical.

The measurement of the vertical line (right across the head) admits of no exact comparison, since my measure extends from one auditory passage to the other, that of Mr. Davis from the base of one mastoid process to the base of the other. Mr. Flower has not given any vertical lengths whatever. According to my measurements the vertical extent is comparatively small, on the average only 289 mm., which is 197 mm. less than the horizontal extent, of which it is only 5·94 per cent. This figure shows most clearly the narrowness of the skull.

It is very difficult to measure the upper vertical extent (sagittal from the root of the nose across the parietal bone to the *foramen occipitale*) which differs, according to our two statements, in the whole as well as in the single parts. It amounts on the average :—

	Davis. mm.		Virchow. mm.
Frontal vertical extent	124·5	...	123·0
Parietal ...	127·0	...	121·0
Occipital ...	114·3	...	111·0
<hr/>			
Whole sagittal arch ...	365·8	...	355·0

Average ... 360·4 mm.

or reckoned by the percentage of the entire sagittal arch :—

	mm.		mm.
Frontal vertical extent	34·0	...	34·6
Parietal ...	34·7	...	34·0
Occipital ...	31·2	...	31·2
<hr/>			
	100·0		100·0

Here the figures agree at least as far as regards the share of the *squama occipitale* in the formation of the roof of the skull : they show that to the *squama* belongs a considerable share, almost a third, and this may well be looked upon as a characteristic.

The relation of the extent in length to the horizontal extent varies only a little in the two measurements. It amounts by mine to 73·0, by Mr. Davis's to 74·9, on the average 74·5 per cent. of the horizontal extent, which, compared with relation to the vertical extent, is a very considerable figure.

Much more homogeneous are the results of the measurements in regard to the form of the head.

The average index of ratio between length and breadth is decidedly dolichocephalous. It amounts with :—

			mm.
Mr. Davis, from 10 skulls, to	71·3
Mr. Flower, from 8 skulls, to	71·9
Myself, from 2 skulls, to	71·9
<hr/>			
Total from 20 skulls	71·6

We have here omitted to bring into the account the two before-mentioned deformed skulls, which have a brachycephalous index ; the one in the London Museum has an index of 82·9, the other from the Colombo Museum of 80·6.

To these must be added the skull of a girl of Batticaloa, about eighteen years of age, and now in the possession of Mr. Davis (No. 803), which he himself calls an "aberrant example," with an index of 78. To what cause due one cannot conceive from the description, since the only thing mentioned about it is that it has a *processus papillaris* before the *foramen magnum*.

Possibly deforming influences were at work among the female Veddás to a greater extent, though in a less noticeable manner. At least we calculate from the figures of Mr. Davis, even omitting the probably deformed skull, a higher index for the female than the male skulls. Mr. Flower and myself, however, arrive at the opposite result, excluding the deformed skulls, viz.:—

		Davis.		Flower.		Virchow.
		mm.		mm.		mm.
For Men	... (3)	69·6	... (5)	70·9	... (1)	73·0
For Women	... (6)	71·0	... (1)	69·9	... (1)	70·9

In taking the average of the two sexes together, however, the difference disappears, as then Mr. Flower's and my own lower figures count for something, viz.:—

			mm.
Men	... 9 skulls	... 70 7	
Women	... 8 skulls	... 70·8	

At any rate, we have among the number (twenty in all) which come into the calculation, only four belonging to mesocephaly (index of 75 : 1—80). Among the remaining sixteen, however, are seven whose index amounts to something under 70, which are therefore hyper-dolichocephalous. The minimum amounts to 66 (Davis). Quite correct also was Mr. Davis in saying (*l. c.*, p. 132) that the Veddá skulls are narrower than those of African Negroes, and sometimes as narrow as those of the New Caledonians. The relation of the single parts of the skull to the whole length = 100 is somewhat different. With the male skull No. 3 the horizontal length of the occipital region is greater, and the frontal basilar length less. If we indicate the relation of the

occipital length to the whole length by *a*, and that of the basilar length (outer edge of the *foramen magnum* to the root of the nose) by *b*, we obtain for the skull :—

		No. 1.		No. 2.		No. 3.
		mm.		mm.		mm.
<i>a</i>	28.2	...	27.8	...	32.4
<i>b</i>	51.9	...	55.1	...	48.6

Corresponding to the smallness of the skull, the greatest length is throughout little : dolichocephaly is less indicated by great length than by want of breadth. Among all the skulls there is only one—a male skull (Davis, No. 805)—which has a length of 190 mm. (7.6 English inches). With all the rest it is less, with the majority not more than 180. The greatest breadth, likewise, comes up in only one skull to 140 mm. ; the next highest figure is 135—the measure of the male skull from the Colombo Museum. But the majority do not even reach 130. All the more extraordinary is the relatively considerable height. Only twice do we find height less than the breadth. The skull (No. 683, Mr. Flower's) which shows some other aberrations as well, has a breadth of 140 mm. and a height of only 135 mm. ; and a male skull (Davis, No. 804) that shows various synosteoses, and is clinacephalous, has a height (5 in.) a little less than the breadth ; in all the other cases the height exceeds the breadth, and not set down very considerably—in one case (Flower's, No. 680) by 14 mm. The greatest height (136 and 137 mm.) is that of two male skulls—one of Mr. Flower's and one of mine.

The index of ratio between the length and height is, therefore, greater than between the length and breadth. After excluding the two deformed skulls, it amounts to an average of :—

		Men.		Women.
Mr. Davis	...	(3) . 73.6	...	(7) . 76.2
Mr. Flower	...	(5) . 75.0	...	(1) . 71.1
Mine	...	(1) . 74.1	...	(1) . 72.9
In the whole		(9) . 74.9		(9) . 75.3

The average from the collection amounts to 74.9. We

cannot therefore exactly speak of lypsiccephaly, though the form comes very near to this type. If we reckon orthocephaly at 75, or even at 74·9, the Vēddá skull on an average falls below this category.

The height of the ear, which has only been taken by me (vertical distance of the upper edge of the outer auricular passage from the parietal bone), is likewise considerable, particularly in the male skulls, amounting to 120 mm. In this case the index of the height of the ear amounts to 64·9, whilst in the female skull No. 1 it reaches to only 60·4, and even with the deformed one (No. 4: only to 63·0.

As regards the formation of the face, I find, except the already-given descriptions, little osteological support. Of single regions I mention the eye-cavities and the nose.

The orbital index was, in the one case which afforded me an opportunity of taking the measurements, 84·6, exactly the same figure which gives the average in the statements of Mr. Flower. The single cases certainly show very considerable differences, for, according to Mr. Flower, we have among eight skulls: two indices below 80, two between 80 and 85, and four over 85 up to 91·7. Separating the sexes, we have from four male skulls an average of 85·1, from two female 84·3, a difference scarcely worth mentioning. On the whole we may therefore assume that the orbital formation is mesokonch.

The nasal index, which I stated at 50, is, according to Mr. Flower, who compared seven cases, 52·2; it is therefore mesorrhine, bordering on platyrrhine.

There certainly seems to be a not inconsiderable difference in sex, since the two female skulls cited by Mr. Flower were platyrrhine (56·1 and 57·8): and, on the other hand, among the male skulls one, if not two, were leptorrhine (46·5 and [?] 46·7), and only two platyrrhine (54·0 and 54·3). The depressed form of the bone of the nose is plainly seen in Table 1, Fig 3, and in the profile drawing by Messrs. De Quatrefages and Hamy. The previously given descriptions

of Sir E. Tennent, Bailey, and Hartshorne, which emphasise the flatness of the nose, are in unison with this; and the pictures I have given, taken from photographs, also show plainly the depressed form of the root of the nose and the breadth of the rings.

The face altogether seems to be low, flattened throughout. The front view of the skull given by the Messrs. de Quatrefages and Hamy in their pictures exhibits this in a splendid manner. I obtained an index (relation of the entire facial height to the breadth of the zygomatic bone) of 83·1.

From the measurements of Mr. Davis I calculate as an average of five skulls almost the same figure, viz., 83·8. According to this the type is therefore, on the whole, chamæprosopous; and, as far as I can now discover, with the women more than with the men. The skulls of Mr. Bernard Davis show :—

No.		Men. mm.		Women. mm.
313	...	88·2	...	—
801	...	87·5	...	—
802	...	—	...	82·9
803	...	—	...	80·8
804	...	—	...	80·0
Average ...		87·8	...	81·2

Notwithstanding the depression of the faces, they are not actually broad. It is because of the slight prominence of the zygomatic arches and bones which Mr. Bernard Davis has already mentioned in contrast to the African races. Only the London skull, of which Messrs. de Quatrefages and Hamy have given us a picture, appears comparatively broad, and chiefly, it would seem, owing to the strong development of the *processus zygomaticus* of the maxillary bone, and the consequently increased size of the lower zygomatic protuberance.

Mr. Flower calculates, besides the alveolar index, the means by this, the present relation of the “basilar alveoli” length

(distance of the anterior edge of the alveolar process from the *foramen occipitale magnum*) to the "basinasel length" (distance of the root of the nose from the *foramen magnum*): the latter, supposed, = 100. The average of six skulls gives a figure of 96·3. I obtain only 93·4 for the female skull from the Colombo Museum. Separating the sexes the computation of Mr. Flower is :—

No.		For Men. mm.		For Women. mm.
675	...	93·5	...	—
676	...	—	...	93·0
678	...	101·0	...	—
679	...	—	...	96·5
680	...	96·9	...	—
681	...	97·1	...	—
Average ...		97·1	...	94·7

According to this it might appear as if prognathy was greater among the men than among the women, but we must reserve a final opinion on this point, since the measurements of individual skulls show such considerable differences, especially with the males. At anyrate, prognathy is very slight. Mr. Bernard Davis goes so far even as to call the Veddá skulls tolerably orthognathous.

With regard to the proportions of the rest of the body, I have a few more statements from Mr. Hartshorne about two Veddás, which I subjoin, after having changed them into metre measure :—

		Latty, about 18 years old. mm.		Bandiey, about 25 years old. mm.
Height of the body	...	1,631·91	...	1,517·59
Circumference of the head around middle of the brow...		514·33	...	514·33
From top of forehead to end of chin	168·25	...	177·80
Across face	...	133·34	...	171·42
Shoulder to elbow	...	279·39	...	323·81
Elbow to wrist	...	254·00	...	219·05

	Latty, about 18 years old. mm.	Bandiey, about 35 years old. mm.
Wrist to point of middle finger	196·82 ...	174·59
Size of upper arm { right ...	260·34 ...	241·28
around the biceps { left ...	263·51 ...	241·28
Size of forearm { right ...	222·22 ...	222·22
{ left ...	222·22 ...	222·22
Chest, breadth	... 787·39 ...	749·27
Length of upper thigh	... 425·41 ...	419·07
From knee to ankle	... 412·73 .	393·67
Size of the calf	... 298·41 ...	292·07
Sole of the foot	... 241·28 ...	222·22

It is very probable that errors have crept into some of these measurements, especially with regard to the upper arm (shoulder to elbow), which, with the smaller man, is stated to be 44 mm. longer, whilst the whole arm is almost 13 mm. shorter. The breadth of the face also given for Bandiey, the smaller man, is not only 38 mm. more than for the much larger Latty, but of an incredible size altogether. We must, therefore, be very cautious in using these figures. Tolerably constant is the relation of the sole of the foot to the height of the body : with Latty it is 6·7, with Bandiey 6·8, contained in the height of the body. This is quite a normal relation. Mr. Bennett says the hands of the Veddás are small, but their feet long and flat. This may be so : one would hardly think it, however, from the measures given. Of the remainder of the measurements I have not much to say, especially as with some of them, *e.g.*, the length of the upper arm, it is not said where the measure begins and where it ends. This much at least we may conclude from the statements, that the single parts may be assumed to be well proportioned. Of special interest is only the size of the arm, whilst there is a marked difference in general between the right and the left arm. We find here on both sides the same figures—indeed, with Latty the size of the left upper arm is a little more than 3 mm. larger than that of the right. This is to be accounted for by the greater exercise of the left arm.

which is specially strained in drawing the very heavy bow, as has been described by various travellers. Mr. Bernard Davis has in his collection the upper thigh and upper arm of a Veddá: the former is 17·2 in. = 436·8 mm. in length, the latter 12 in. = 304·8 mm. This was evidently a very strong individual: the length of the upper thigh exceeds even that of the two men measured by Mr. Hartshorne (425 and 419 mm.). On the other hand, the length of the upper arm, according to Davis, does not coincide with the figures given by Hartshorne, and this is additional proof of the inexactness of his measurements.

The comparison of the Veddás with their neighbours on the Island is not a little increased in difficulty from the lack of sufficient information with regard to the relative physical condition of the latter. Even the best describers limit themselves in the main to a few words. Regarding the more civilised tribes, as already well known, they at most therefore institute only comparisons with the continental tribes of Hindústán or with the European. Osteological material is also comparatively scanty in the European collections, and even what there is appears to me as rather unsafe. I have, through the kindness of Consul Freüdenberg, received three skulls of Sighalese and three of the Tamils; but examination proves one designated as the skull of a Sighalese child to coincide so exactly with the Tamils, that it seems very doubtful indeed if this is correctly stated. The inhabitants of the low lands upon the Island have so frequently trespassed on each other's territory, and become so intermingled in life, that their skulls may have been confounded after death. Hence I offer the following remarks with all reserve, and principally with the aim of provoking, if possible, more exact information and the sending of better material. In particular I must indicate, as the greatest desideratum, the need of satisfactory photo-

graphs,—especially half-lengths,—not too small (profile and front face), in the right horizontal position.

In our comparisons the genuine Siphalese and the Tamils come chiefly under consideration. Only collaterally can the descendants of the immigrant Arabs (Moors, Moormen), Malays, and still less Chinese, Burmese, Aryan Indians, African Negroes, and Europeans, be brought in. The two first-named tribes are so predominant, through the extent of territory they occupy, as well as from their numbers, that, apart from their almost exclusive historical claims, they must be specially considered.

The Siphalese.

They occupy in the main the south and south-west of the country. According to Sir E. Tennent* the inhabitants of the south coast from Galle to Hambantota are the purest Siphalese. This part formed an important division of the old province of Ruhuna, which was very early colonised by the descendants of Wijayo ; they neither intermingled with the Malabars nor had any intercourse with them whatsoever. Unfortunately Sir E. Tennent gives no actual description of the people. He only speaks incidentally of their build, and their hair ; what chiefly caught his attention was their inclination to an effeminate mode of arraying themselves. This is especially conspicuous in the way of wearing the hair, of which he gives a picture ; but adds, this applies only to the people of the south-west coast, and not to those in the interior or in the north or east. They let the hair grow long, comb it *à l'impératrice*, high from front to back, and bringing it up from the nape of the neck form a roll (*kondé*) on the protruding part of the back head, fastening the whole with combs. Even Ptolemy has mentioned the long hair in Taprobane, and Agathemerus asserts that the men of Ceylon let their hair grow as long as it will, and roll it into a coil on the top of the head in the fashion of women.

* Tennent, *l. c.*, vol. II., pp. 106-112.

Of the children Sir E. Tennent says they are beautiful, with wavy shining hair. He says a group of children in their nakedness look like living bronzes. The men also have delicate features and slender limbs, are frequently beardless,* and wear around the hips a piece of cloth (*comboy*) like an under petticoat, so that altogether the impression they make is womanish. Finally, he adds a notice of them from a Chinese book of travel by Hiouen Thsang, in which the Mongolian expresses his amazement at their prominent noses, by saying the Sighalese have a bird's beak on a human body.

This is about all that I find in Sir E. Tennent concerning the Sighalese. The few paragraphs devoted to the inhabitants of Ceylon by Mr. Von Schlagintweit† coincide with this. Somewhat more definite, though very superficial, are the reports of earlier authors. Valentyn‡ says: "De Cingaleezen zijn niet heel swart, maar bruyngeel, lang en open van ooren, niet klok van gestalt, door de bank wat mager, zeer zwak van leden, geschwind van licham en vrijser ruf tig van geest." Wolf§ declares outright "the Sighalese have a black skin." Percival|| ascribes to the Ceylonese a stature of middle height, about 5 ft. 7 in., and says the colour of the women approaches to yellow. Selkirk¶ calls the eyes of the Sighalese bright black, and says the hair is long, black, and fastened into a knot. The insides of the hands and feet are white, the rest of the body black. The people in the interior seldom shave the beard, but those on the coast do. Sirr** says the men are under middle height, something like 5 ft. 6 in. on an average, and well propor-

* These statements are said to be found in the history of Tambulus, Diodor, Lib. 2, cap. 36.

† Herman von Schlagintweit, Saknnlunski. Reisen in Indien and Hoch Asien. Jena, 1869. Bd., *l. s.*, 213.

‡ Valentyn, *l. c.*, Bl. 43.

§ Wolf, *l. s.*, 155.

|| Percival, *l. s.*, 222.

¶ Selkirk, Recollections. London. 1884, pp. 58-59 of Ceylon.

** Sirr, *l. c.*, vol. II., p. 38.

tioned. Their colour varies from clear yellow-brown to black; hair and eyes the colour of ebony. The Kandians are darker, more powerful, and of better growth. Philalethes,* who specially refers to Valentyn, says the colour of the Singhalese is not quite black, but of a deep chestnut, suffused with a yellow tint. Their ears are long and open, their bodies not powerful, but slender and agile.

Much more exact is the description which Mr. Davy† gives. He divides the Singhalese race into three great tribes: the genuine Singhalese, the Kandians, and the Veddás. In describing chiefly the inhabitants of the interior of the Island, "the highlanders," he says that they are in build, speech, manners, customs, religion, and government complete Indians. Like them they are distinguished from Europeans less in the features than in some trifling characteristics of colour, size, and form. The complexion ranges from light brown to black. Also the colour of the hair and the eyes varies, although not so often as that of the skin; black hair and eyes are most common, and brown hair and eyes less uncommon than gray eyes and red hair, and the light-blue or red eyes and flaxen hair of the Albinos. In size, the inland people exceed the low-land Singhalese and the most of the natives born on the coast of Coromandel and Malabar, but they do not attain the height of the European. Their average is somewhere about 5 ft. 4 to 5 in. They are clean-made, with neat muscle and small bone. For Indians they are stout, and have, as a rule, well-developed chests and broad shoulders, especially in the mountain districts, where they, like other highlanders, have rather short but strong and very muscular thighs and legs. Hands and feet are in general very small,—indeed disproportionately so compared with ours. The form of the head is good, but perhaps rather longer than among Europeans. Their features are commonly neat and often handsome, their countenances intelligent and

* Philalethes, *l. c.*, p. 231.

† Davy, *l. c.*, p. 109.

animated. Nature has given them a wealth of hair, which, in general, they allow to grow to considerable length on their faces, as well as heads, since in their opinion a beard, so far from disfiguring, adorns the face. The women as a rule are well formed and good looking, often handsome. According to their opinion a beautiful woman should have the following attributes:—Hair luxuriant, like the tail of a peacock, long, reaching to the knees, and terminating in graceful curls; eyebrows like the rainbow, and eyes sapphire blue, or like the petals of the blue *máníl* blossom; nose like a hawk's beak, and lips bright and red as coral or the young leaves of the *ná* tree; teeth small, regular, and closely set as the buds of the jasmine; neck full and round; chest capacious, and breasts firm and conical, like the yellow cocoanut; waist almost small enough to be spanned by the hand; hips wide; limbs tapering; the soles of her feet without hollows, and the surface of her body soft, delicate, smooth, and rounded, without protruding bones and sinews.

Davy has the great merit of having added to his work a series of pictures, which illustrate more clearly many of these particulars. On Plate 6 is found a coloured group of Kandyans, after a drawing by Lieut. W. Lyttleton, which shows very clearly the dark-brown complexion of the common people by the side of the lighter yellowish-brown tint of the Disávés: the faces are comparatively long and narrow, the noses arched and very prominent, the upper lips short, and the muscles about the mouth delicate. On Plate 4 likenesses are given, which were drawn from ivory figures carved by native artists; here the faces are shorter and somewhat broader; the noses very prominent and arched, having an almost Jewish expression; the lips (especially of the women) full and bulging, but without any approach to prognathism.

Cordiner* describes the Siphalese as of a slender make, rather below the medium height, with slight but well-shaped

* Cordiner, *l. c.*, vol. I., p. 94.

limbs, and with regular features of the like form with the Europeans; their colour, although varying in shade, not so dark as that of the Indians on the continent; the eyes black, but the whites of them strikingly clear; the hair long, smooth, and black. Among the higher classes the complexion is so light that it seems lighter than that of brunettes in England. In all classes the inner surface of the hands and feet is uniformly white. Of the Kandyans Cordiner* says that they differ no more from the Siphalese than the mountaineers of other lands from the dwellers on the coast. They are of a stouter make and fairer complexion, but not taller. Their manners are less polished, and the custom of wearing a beard increases the natural wildness of their appearance.

If we compare these descriptions with those already given of the Vēddās we find in reality but few points of difference. The complexion of the last may be on the average somewhat darker, but it varies apparently within the same limits. In regard to this the testimony of Dr. Davy especially is of the highest importance. The swarthiness which Mr. Bailey emphasises of the Vēddās is to be ascribed at least in part to their lack of cleanliness. It is equally doubtful if the hair differs; put the well-dressed, carefully-combed, smooth hair of the Siphalese, which is only curly at the ends, beside the neglected, dishevelled, entangled, but not curly hair of the Vēddās, which hangs down so far and sticks out all round, making the head appear very large, and one is inclined to conjecture that the difference here is owing to culture rather than to original peculiarity. The average height of the Siphalese seems to correspond to about the height of the tallest Vēddā: they are somewhat shorter than Europeans.

Among the characteristics cited there is in reality only one which seems to have made a very decided impression on every observer, namely, the form of the nose, about which even the old Chinese furnish reports. Whilst with the Siphalese it is

* Cordiner, *l. c.*, p. 131.

very prominent, resembling an eagle's beak, and therefore rather thin and narrow, with the Vĕddás it is always described as flat, and with widely-distended nostrils. Add to this the thick and projecting lips and the large mouth, and perhaps also the comparative shortness of the Vĕddá face, there then remains, as Mr. Hartshorne* has already pointed out, only a few facial characteristics for diagnosis. Whether this is correct the future may teach us, provided exact descriptions (and above all large photographs) of the Vĕddás are furnished in time. Meanwhile we may state that the *Sinhalese also belong to a dark—perhaps best described as a brown—smooth-haired, and not (or only a very moderately) prognathous race.*

How is it now with the osteological indications? Literature in this regard offers somewhat more explicit statements, although exclusively for skulls. Here also it is the merit of Davy to have furnished us with exact information. He asserts the Sinhalese skull to be longer than the European. As proof of this he gives on Plate 3 the drawing, side and front view, of the skull of a Sinhalese chief from a secluded region inland. This skull is long, moderately high, with abruptly rising forehead, and broad, square back head, flattened at the sides up to the temples; the zygomatic arches prominent, the eye-cavities rather broad and low, and tending to square, but widening towards the bottom and the outside; the nose narrow and prominent, with bridges slightly bent in; the face short, with a low, slightly projecting upper jaw.

A more recent description of a *cranium Cingalensis* is given by Gerard Sandifort.† The skull was furnished by Van Hassem an Brugmans, and is at present in the Anatomical

* Hartshorne, *l. c.*, p. 409, says: "The general appearance of the Weddas may be described as distinctly non-Aryan. The comparative shortness of their thumbs and their sharply-pointed elbows are worthy of remark, as well as their flat noses, and in some cases thick lips, features which at once distinguish them in a marked degree from the Oriental races living in their vicinity."

† Gerard Sandifort. *Tabulæ Craniorum Diversarum Gentium. Lugduni Batav. 1838 (c. f. Mus. Anat. Acad. Lugd. Bat., 1827, vol. III., p. 39, No. DLXXXIV.).*

Museum at Leyden. There is also a great number of measurements given, but unfortunately the greater part of them are of no use for our purpose. The capacity is stated at 39 ounces of millet. Judging from the picture it is a very powerful skull, with a long, strong face, very prognathous, having large, very prominent teeth, large and broad lower jaw, the nose long, high, and thin, the eye-cavities low, imperfectly rounded, and very much aslant. As their height is given at '031, the breadth at '041, the orbital index 75·6 would be chamaekonch. The inter-orbital distance is mentioned as '024. The author himself describes the cranium as oval, with a very high crown, sides very much flattened, with slightly projecting *tubera*, the back head oblong and by no means spheroid, the under parts rather flat; the eye-cavities oblong in the tranverse axis, the *fissura orbitalis posterior* wide, the ends (*vertices*) of the upper jaw hollowed out (*excavatus*), on the lower rims cut out (*exsectus*), and passing obliquely into the likewise oblique and projecting alveolar process of the maxillary bone; the palate much arched (*fornicatum*) and oblong. I remark that its length is stated at '059, its breadth in the region of the third molar at '041, in the regim of the præ-molars at '039; out of the first two measures would result a palatal index of 69·4: consequently an extremely leptostaphyline measure, which indeed does not afford an exact comparison with my measure taken in the region of the second molar. The vertical height of the skull is stated at '145, the tuberal parietal breadth at '126, the jugal breadth at '138, and the distance of the maxillary angle at '110.

I find another statement in the catalogue of the Vrolik Museum in Amsterdam,* where, under No. 66, is mentioned the skull of a native of Ceylon, which Professor Bernard had furnished. It is compared with the *cranium Cingalensis* of Sandifort, from which it is said to be distinguished chiefly by its less prognathous jaw. It is described as a fine, strong, dolichocephalous and somewhat prognathous skull, the

* Musée Vrolik. Catalogue par J. L. Dusseau. Amsterdam, 1865, p. 22.

forehead long, but of little height, considerably flattened at the sides, the cheek-bones strong, and all the muscle *epiphyses* well developed. From the measures given we calculated an index of ratio between length and breadth of 72·2, between length and height of 75, and a palatal index of 73·7.

Mr. Welcker * gives in his craniological tables the average index figures for five Singhalese skulls, without, however, saying where these are at present to be found; probably the above-mentioned Dutch specimens are among them. He states the breadth to be 73·4, the height 77·2.

A large number of Singhalese skulls are brought forward by Mr. Davis, † in fact, a whole dozen. One of these, however, is expressly said to be probably a hybrid of Malabar and Singhalese, and must therefore be excluded. Of the remainder one is from Panaduré, one from Kandy, one from Negombo, one from Colombo, the others unascertained. Half are male and half female. The one (No. 982) which is called klinocephalous and has a *processus papillaris* before the opening of the back head, according to Mr. Davis shows "a degree of mikrocephaly," but as its capacity amounts to 1,474·6 cub. cm. we are not quite justified in such an assumption. I give below a short list of the main results obtained:—

The number of the skull.		Capacity.		Index of Longitudinal Breadth.		Index of Longitudinal Height.	
		♂	♀	♂	♀	♂	♀
315	...	—	1175·7	—	72	—	70
979	...	—	1394·9	—	74	—	78
980	...	1235·5	—	76	—	84	—
981	...	—	1355·1	—	75	—	74
982	...	—	1474·6	—	65	—	72
983	...	—	1494·6	—	70	—	80
984	...	1673·9	—	75	—	76	—
1007	...	1614·1	—	72	—	70	—
1008	...	1693·8	—	73	—	74	—
1009	...	1275·4	—	72	—	76	—
Medium	...	1498·5	1378·9	73·6	71·6	76	74·8
Total average 10)...		1438·8		72·4		75·4	

* Archiv. für Anthropologie, 1886, Bd. s. 154, 157.

† J. Barnard Davis. Thesaurus Craniorum, p. 132.

The average indices agree very nearly with the indices of the skulls in the Vrolik Museum. Dolichocephaly is very pronounced, though not so strongly as with the Veddás; the height agrees pretty well with the Veddás, but the capacity is much greater.

A wholly different description of the skull of a Sighalese is given by Mr. Zuckerkandl.* This skull was brought over by the Novara expedition without any statement whatever of its origin. It has a capacity of 1,505 cub. cm., and an index of ratio between length and breadth of 86·1. It is therefore hyper-brachycephalous. We may assert without hesitation that it is either in a high degree pathological or outright not the skull of a Sighalese. The latter assumption is supported by the fact that the incisors and canine teeth of the upper jaw are filed flat,—a phenomenon nowhere mentioned as seen among the Sighalese, but which points very clearly to a Malayan origin. The assumption of a pathological, perhaps deformed formation, is supported by the fact that the cranium is asymmetrical, the forehead flat and retreating, while the *squama occipitalis* is pressed flat to such a degree that the upper half is sunk in “almost in the form of a wave.” We may therefore exclude this skull from comparison.

With regard to my own skulls, I have already said that probably a child's skull, marked as Sighalese, will have to be excluded; but as it is so distinctly stated to be Sighalese I will here describe it with the rest.

Skull No. 1 (Table II.).

A juvenile male skull, seemingly rather large, but without under jaw. *Synchondrosis speno occipitalis* closed. Wisdom teeth broken out; the front teeth have later fallen out; the remaining molars and the first premolars are very large, and only a little worn on the crowns, but covered with a thick black crust (betel). The points of attachment of the

* Reise der Oesterreichischen Fregatte Novara. Anthropologischer Theil. Erste Abtheilung. Cranien der Novara Sammlung, beschrieben von E. Zuckerkandl. Wien, 1875, s. 24.

muscles strong, but the frontal eminences not very prominent. The bones are yellow-brown, smooth, shiny, and hard.

The skull is in reality smaller than it appears ; it has only a capacity of 1,110 cub. cm. The index of ratio between length and breadth is 71·3, and is strongly dolichocephalous, between length and height 72·5, orthocephalus.

In the *norma verticalis* the roof of the skull appears long and narrow, tapering toward back and front, moderately phænozygomatic, the *tubera parietalia* spreading out broadly. The skull is unsymmetrical (plagiocephalic), especially behind and below, where upon the left side, but still on the parietal bone, there is to be observed an oblique flattening, whilst the right side is more fully rounded out. In front the form is more regular, although the right half of the forehead is somewhat awry, and the right zygomatic arch shorter than the left ; the nose diverges a little to the left, and the palatal suture at the back part turns a little to the left. The sagittal suture, also, is not exactly median. Many signs are visible of premature *synosteosis* : thus, on either side, but more extensively on the left, in the midst of the side parts of the coronal suture, and at different points of the sagittal suture, of which the right emissary is wanting and the left very small. The lower side parts of the coronal suture are quite obliterated on the left for a length of 30 mm., and on to the right of 22 mm. The open sutures are comparatively simple, yet the sagittal suture in its middle, and the lambdoidal suture, have pretty large and broad indentures. The latter at the point is very much depressed, and at the sides, especially the left, there are several wormian bones. On either side, in the region where usually the *sutura transversa occipitis* begins, we find a wormian bone reaching to the parietal bone, larger on the left side, but in its middle and upper part synosteotic.

In a lateral view of the skull it appears long and low, the brow itself low and rather sloping, the *tubera frontalia* only tolerably distinct, the front of the skull long and

rising abruptly. It reaches its height at the coronary suture ; behind this is a slight depression ; the vertical height, a finger's breadth behind the *coronaria*. The back slope of the parietal curve begins in the region of the *tubera*, and is very long ; the *squama superioris* is strongly convex. The temporal *fossæ* large, and reaching to the *tubera parietalia*, and beyond the lambdoidal suture. The front part of the temporal *fossæ* uneven and rugged. The *squama temporalis* on either side flat and high, especially on the left. On either side a strong *processus frontalis*, which is only somewhat indistinct because of the extensive *synostosis* of the *coronaria*. The *ala temporalis* low and quite overlaid by the very broad process, which extends from the *squama temporalis*, pretty regularly on the right, somewhat jagged on the left, but on both sides pointed in front. In consequence of this stenokrotophy we find, however, that the very much depressed place is pretty low down upon the *ala*, indeed, immediately at the juncture of the *sutura spheno frontalis*, *zygomatiko frontalis*, and *spheno zygomatica*. The process appears more pointed on the left, on the right almost trapezoidal. The measures amount to :—

		Right.		Left.
Length of <i>proc. temp.</i>	upper	... 15 mm.	...	12 mm.
Do.	under	... 10 mm.	...	9 mm.
Breadth of <i>ala temp.</i> 19 mm.	...	18 mm.

In the *norma occipitalis* the contour of the skull is almost pentagonal, the side parts going almost straight down, only diverging at the base, the roof with slightly arched lateral parts, the base tolerably straight. The *squama superioris* strongly prominent and flattened at the sides. No *protuberantia occipita externa*. The *linea semicircularis superior* and *inferior* strongly marked : *linea suprema* very faint. We find on either side, however, and especially strong on the left, a deep abrupt break between the *facies muscularis* and the *facies laevis*, which in its lower part follows the direction of the *linea superior*, then makes a deep bend toward the mesial line, and ends parallel to the *linea suprema*, right underneath it. In this way is formed on either side a long

deep-lying tongue of the *facies laevis*, which reaches the *sutura transversa*. The cerebellar *fossæ* are tolerably rounded out, the *facies muscularis* more deeply marked. No large *emissaria mastoidea*, but instead of this a larger *foramen* on either side, near the *crista perpendicularis*. The *foramen magnum* is rounded posteriorly, more oval anteriorly, 31 mm. in length, 26 in breadth, therefore 83·8. The articulation prominent and bent; *processus mastoïdes* poorly developed, with a deep depression; *processus styloïdes* large. *Apophysis basilaris* lying somewhat flat; *processus pterygoïdes* with spreading *lamina externa*; deep *fossæ* for the lower jaw.

In the *norma frontalis* the middle and anterior part of the head seems high, the region of the fontanelle raised, the face, however, short and narrow. Orbits low and almost four-cornered; index 76·9, therefore strongly chamaekonch. *Fissura spheno maxillaris* spreading out in front. The outer edge of the orbits bent inwards a little just below the *sutura zygomatico frontalis*, inasmuch as here the *processus frontalis* of the malar bone is somewhat bent inward posteriorly. The nose low, narrow above where it articulates with the broad nasal process of the frontal bone, the bridge bent in and somewhat rounded, but prominent and aquiline, the aperture broad below, narrow above, hence triangular; index 57·7, therefore platyrrhine; *canine fossæ* full, *foramina infraorbitalia* large, and especially the left one, communicating with a roundish depression on the surface of the *canine fossa*. Alveolar process short, in the middle 13 mm. long, obliquely prominent. *Alveolæ* broad, palate large, especially long; index 75·4, therefore leptostaphyline. The *sutura transversa palati* very much forward, 17 mm. in front of the *spina nasalis posterior*, which is short and rounded away. The alveolar process is widely curved in front, almost straight at the sides, slightly converging behind. Hence the palate long, of prognathous character, and somewhat pithecoïd in form. The malar bones on both sides have a fissure posteriorly beginning at the *sutura*

zygomatico temporalis, 6 mm. right, 5 mm. at the left, and 3 *foramina zygomatica*. The *tuberositas molaris* is of moderate size, and belongs mainly to the upper jaw; the *tuberositas marginalis temporalis*, especially the left, is very strongly developed, and the bone very much bent inward below.

Skull No. 2.

A senile, wholly toothless, probably male skull, without lower jaw, of very moderate capacity (1,200 cub. cm.), but strongly dolicho-orthocephalic (ratio of length and breadth 70·2, of length and height 73·2).

It shows throughout a tendency to *synostosis*; the sagittal suture is wholly obliterated—not a trace of it; in the region of the fontanelle a broad projection above the frontal bone, as sign of early obliteration. The *emissaria* are present, but very near together (distance 10 mm.), the right considerably enlarged. The coronal suture obliterated in the lower part to a considerable extent on the right; on the left it is perfectly simple, and in process of obliteration. At the right the posterior part of the *spheno frontalis* is overgrown; the *spheno parietalis* on both sides indistinct. The lambdoidal suture at its angle shows traces of obliteration.

In the *norma verticalis* the skull is very long and narrow, strongly arched in front, narrowed behind, with very prominent lambdoidal angle, for the rest phænozygomatic. The tuberosities very broad and prominent, therefore somewhat klinocephalic in form. At the right, on the parietal bone, just behind the coronal suture, several flat *exostoses*.

In the *norma temporalis* the skull appears rather long than high. The middle of the parietal curve is flat, its frontal division strongly arched, the posterior obliquely sloping downward to the lambdoidal angle; then, however, much arched at the *squama superioris*. Eminences rising even to the parietal prominences and the lambdoidal suture. *Squama temporalis* flat. *Alæ* depressed towards the centre, especially the right one, which is very much narrowed

below. At their extremities posteriorly an irregular, trapezoidal *epiptericum*, 11 long, 8 high, with indented edges, which towards the front are somewhat indistinct. The *angulus parietalis* is very short, and as far as can be judged with the *synostosis* of the lower part of the coronal suture, and the adjoining part of the *spheno frontalis*, is prevented from coming in contact with the *ala* up to a distance of 4 mm.

	Right.	Left.
Direct breadth of the <i>ala sphen.</i> above ...	21 mm. ...	24 mm.
Do. do. below ...	12 mm. ...	15 mm.

The *norma occipitalis* shows very high straight sides, with simple flattened arching of the roof, and a straight base. Lambdoidal sutures jagged. *Squama superioris* strongly arched, but short, somewhat flattened laterally and below. Plainly marked *linea semicircularis suprema*. At the upper end of the *crista perpendicularis* a large irregular protuberance, very deep depression below the *lineæ semicirculares superiores*. Large cerebellar archings with depressions between well-developed *emissaria mastoidea*.

Basis cranii long, and protruding behind. Mastoid process small, with deep fissures. The *foramen magnum* small, 31 mm. long, 28 mm. broad, index 90·3, very prominent articulating surfaces, very long and strong styloid processes. In the centre of the basilar *apophysis* a large basilar *foramen* entering obliquely posteriorly, which corresponds to a deep irregularly sinuous *sulcus* on the surface of the *clivus Blumenbachii*, which, above and at the left, seems to have communicated with the *sinus cavernosus*. Deep and wide articular surfaces for the under jaw, very large *laminæ externæ* on the alar processes, especially on the left. At the left a very large *foramen ovale*.

From the front the middle of the head appears high and broad, the face delicate, short, and broad. The orbits rather high and oval, widening somewhat as well to the inner and upper, as to the outer and lower aspect, yet almost four-cornered; index 82·9, therefore mesokonch. Remarkably wide *fissura spheno maxillaris*. The nose narrow above as well

as below, the bridge very prominent, bent in at the middle, almost aquiline; index 46, therefore leptorrhine. The *sutura naso frontalis* fits convexly above into the nasal process of the frontal bone. *Spina anterior* and *inferior* well developed and prominent; *crista* and *septum* very thick. On the cheek-bone either side a short indication of a posterior fissure, which, however, lies very high; on both sides three small *foramina zygomatica*. Canine *fossæ* are little depressed, but, on the other hand, run from the immensely broad *foramen infraorbitale* on either side to the alveolar process, which is more strongly developed on the left, making a very deep fissure. The alveolar process is entirely toothless, but there are still single open *alveoli*, especially at the left in the region of the bicuspid and first molars; most of the *alveoli*, especially those of the incisors, are entirely obliterated, and the process has disappeared, so that the shape of the very much shrunken palate is uncertain. Here also the position of the transverse suture is remarkable, because it is pushed so far to the front as to be at a distance of 14 mm. from the posterior edge. The *spina nasalis posterior* is wholly wanting; a short bifid projection larger on the left than on the right.

Skull No. 3.

A child's skull, perhaps female, with the not yet exchanged milk teeth. The outer upper cutting teeth are still enclosed in their cavities. The *sutura incisora* of the palate very plain. The bicuspid and first molars developed, and very large. The first bicuspid with three fangs, two outer and one inner, the right one, moreover, with an *exostosis* of enamel. The *alveoli* of the second molars are open very wide, and empty, but the teeth, to be sure, had not yet erupted. The openings of the *alveoli* of the wisdom teeth still lie very deeply, and far back. The *synchondrosis spheno occipitalis* very widely open. To the right, at the *squama occipitalis*, is a *sutura mendosa* 24 mm. long, in the direction of the *sutura transversa*; at the right only a slight indication of one.

Notwithstanding youth, this skull is larger than the two

preceding ones; its capacity amounts to 1,250 cub. cm., therefore it is mesohypsicephalic (ratio of length and breadth 76·7, of length and height 77·3): therefore in its form it is wholly irregular.

Looked at from above it appears cut off short behind and somewhat unsymmetrical; broadly arched in the region of the parietal eminences, towards the front lessened, but still more broad. It is scarcely phænozygomatic. The sutures are open, but the lower parts of the coronal and the posterior division of the sagittal are very simple. The left *foramen parietale* is obliterated up to an almost invisible point, the right distinct, but moved very near to the suture. The lambdoidal has deep indentations with wormian bone near the angle, and in the vicinity of the side fontanelle., Parietal and frontal emissaries broadly prominent.

At a side view the skull has a wholly female form; the low brow passes with a sudden turning into the long slight parietal curve, from which, posteriorly, there is a very sudden fall, with slight arching of the *squama superioris*. Yet the skull appears high. In the right temporal region is a very large *epiptericum*, 25 mm. long, 10 mm. high, obliquely quadrangular. This completely interrupts the union of the *ala* with the *angulus parietalis*, at the expense of which it is principally developed. The ring is depressed, and in its middle part shows stenokrotaphy. To compensate, the temporal part of the frontal bone is arched forward, bomb-shaped on the left. The conditions are almost normal; but here also is an arching of the orbital portion of the frontal bone, and the *ala* is set more deeply into the latter:—

		Right.		Left.
Breadth of the <i>ala</i> above	...	13 mm.	...	20 mm.
Do.	in the middle	10 mm	...	12 mm.

At a back view the skull is very high and broad, the sides straight, slightly converging below, the roof slightly rounded. The back part of the head high, the *squama superioris* arched out, almost like a ball. No protuberance, *linæ semicirculares* scarcely visible. Cerebellar archings well developed over

the *sutura mendosa*, a deep transverse impression (einschnürung?) which in a manner cuts off the ball-shaped *squama superioris*, and is deepest at the lambdoidal suture.

A view of the skull from below gives the impression of breadth, principally in the mastoid region, whilst the laterally narrowed and very small occipital part seems rather long. The mastoid processes small, with a deep fissure. *Foramen magnum* very large, especially long and posteriorly—in the middle of the border having a secondary curving out (indication of *spina bifida occipitalis*?) ; on either side in front of this a thickened place forming a smooth articulating surface, evidently for the reception of the ring of the *atlas*. Length of the *foramen* (with the curving out) 36, breadth 25.

From a front view is seen a low, broad forehead, with very distinct eminencies and large nasal process. At the lower part of the latter a short remnant of the frontal suture. The orbits high and large diagonally, widened above and outwardly ; index 83·3, therefore mesokonch. The root of the nose broad and somewhat flattened, the bridge slightly arched and short, bent forward and downward at the end ; the *sutura naso frontalis* flat, and only slightly projecting above the plane of the *sutura maxillo frontalis*. The aperture high and triangular, with rounded corners ; nose index 55·5, therefore platyrrhine. Alveolar process not at all prognathous, but the teeth somewhat obliquely directed forward. Palate short and broad, almost the shape of a horse-shoe, with a large (17 mm. long, from front to back) palatal plate ; index 86·8, therefore brachystaphyline. The curve of the teeth short and wide, diverging behind.

From this description it is manifest that the last of the three skulls differs in the chief respects from the two others, and it is easy to understand that this difference would have become very much greater if the child had lived and completed its development. It will appear later that in these main points it approaches the skulls of the Tamils, although these, among themselves, present no small differences. I

will not go quite so far as to declare outright that it is a Tamil skull, but it may have belonged to a bastard, and the fact (already mentioned) that the skull No. 316, from Mr. Davis's collection, which is distinctly marked as that of a hybrid of Malabar and Singhalese, corresponds with this one almost entirely in the indices (ratio of length and breadth 77, of length and height 78), speaks strongly in favour of the assumption. It would seem at least wiser for the present to exclude it from the collection. But I may at the same time add that the same reasons may be urged against the admission of the skull No. 980, from Mr. Davis. This has a ratio of length and breadth 76, and an index of height 84, although it belonged to a senile individual, with total disappearance of the alveolar processes. If then we withdraw this, as well as my skull No. 3, there remains tolerably homogeneous material, which offers great probability that it fairly corresponds to the typical conditions. To the support of this view the fact is of value, that the drawings which Davy, and even those which Sandifort has given, coincide not only with those I have furnished (Table II.), but also, in the main, with all the other descriptions and measurements. Nevertheless I am sorry to say that the existing material is nowise sufficient to enable us to decide all the questions. The absence of the lower jaw in all my skulls is a very serious loss, and the senile condition, as well as the extensive *synostosis* of one of the two apparently pure skulls (No. 2), makes even the use of this, in regard to all the points in which it varies, questionable. Even the third still remaining skull (No. 1) is not free from great and plainly individual aberrations, for it not only shows, in spite of the youth of its owner, very numerous obliterations, but also on either side a large *processus frontalis squamæ temporalis*.

This discussion is in the highest degree instructive, as showing how unsafe it is to make race definitions on the ground of single, or of a few skulls, and how necessary it is, especially for such complicated ethnological conditions as

those of Ceylon, to have ample and historically sure material at our disposal. In the present case, I consider myself justified in not foregoing the use of the skulls sent to me, because through the comparison with the skull measurements from other collections I have sufficient material under control afforded me. Setting aside the not measured but simply represented skulls in Davy's work, and also those of Mr. Welcker (five) mentioned without any detailed statements, and Sandifort's skulls given with a wholly different method of measurement, we can use for our comparison twelve Siṅhalese skulls, viz., one from the Vrolik Museum, nine from Mr. Davis's collection, and two from mine. These would make a good broad basis for the decision, if important numbers were not lacking in Mr. Davis's: for instance, measures of the orbits, of the nose, and of the palate. Hence my work in several respects can only serve as preparatory.

Our study of details thus far has proved, first, that the Siṅhalese skull is considerably larger on the average than the Vēddā skull. Leaving out the two doubtful ones from nine skulls of Mr. Davis's, and two of mine, we obtain an average of 1,406 cub. cm., which exceeds the measure of the Vēddā average by 145 cub. cm. To be sure, the fluctuations here also are very great: the extremes of 1,110 and 1,694 cub. cm. afford a difference of 584, almost as great as we meet with among the Vēddās. A comparison of them, however, immediately shows that the numbers much more frequently range high among the Siṅhalese:—

cub. cm.		Vēddās.		Siṅhalese.
901-1,000	...	1	...	—
1,001-1,100	...	1	...	—
1,101-1,200	...	3	...	3
1,201-1,300	...	10	...	1
1,301-1,400	...	2	...	2
1,401-1,500	...	2	...	2
Over 1,600	...	3	...	3

Corresponding to the greater capacity, the measurements are also larger with the Siṅhalese.

And first, for the extent horizontally I have, in like manner, as with the Vēddás, after putting the figures of Mr. Davis into metre measure (leaving out here also the skull No. 980), received as an average of—

4 Male skulls	532 mm.
5 Female skulls	494 mm.
<hr/>			
9 Sighalese skulls	511 mm.

Compared with the Vēddá skulls of Mr. Davis, the difference in favour of the Sighalese amounts to 26·11 and 23 mm. My two Sighalese skulls, whose small capacity is clear from the previously given numbers, show only 482 and 493 mm. extent horizontally: consequently, in the one case it is somewhat less and in the other somewhat more than the average of the Colombo skulls which I measured. On the other hand, the size vertically (398 and 293 mm.) proved greater with my Sighalese than the average of the Colombo skulls (298 mm.). One of the latter, however (No. 5), has a higher measure (300 mm.). In the average, the vertical compass of my two Sighalese skulls is 192 mm. less than the horizontal, of which it is 60·5 per cent.; therefore somewhat more than with the Vēddás.

I have likewise calculated the length of circumference of Mr. Davis's skulls, taken with the sagittal suture. I receive an average from—

4 Male skulls	393 mm.
5 Female skulls	370 mm.
<hr/>			
9 Sighalese skulls	380 mm.

whilst my own measurements amount to 354 and 365 mm. The corresponding average with the Vēddá skulls amounts to 366 (Davis) and 355 (Virchow) mm.

As regards the single segments of the sagittal arch, I find the following average from Mr. Davis's figures:—

	Frontal.	Parietal Segment.	Occipital.
4 Male skulls	... 136 mm.	... 136 mm.	... 120 mm.
5 Female skulls	... 128 mm.	... 131 mm.	... 110 mm.
<hr/>			
9 Sighalese skulls	... 132 mm.	... 133 mm.	... 115 mm.

or, according to the per centage of the whole sagittal arch :—

4 Male skulls ...	34·6	...	34·6	...	30·5
5 Female skulls...	34·5	...	35·2	...	29·7
9 Singhalese skulls	34·7	...	35·0	...	30·2

Here, as contrasted with the Veddás, we notice in a very striking way the important part taken by the frontal and parietal bones, especially the first, and the insignificant part, on the contrary, assigned to the occipital bone.

With my two skulls the proportions for the middle of head appear most favourable, and therefore rather according to the female type of Mr. Davis's skulls :—

No. 1	...	33·6	...	35·3	...	31·0
No. 2	...	33·9	...	35·6	...	30·4

The proportion of the sagittal vertical extent to the horizontal amounts in Mr. Davis's skulls to 74·3, in mine to 73·7 : hence almost the same numbers as with the Veddás.

As regards the form of the head, I have already given the particulars of Mr. Davis's skulls. The ratio of the average of length and breadth is, according to index, the following :—

		Skulls.		
Dusseau	...	1	...	72·2
Davis	...	9	...	72 0
Virchow	...	2	...	70·7
On the whole, from	...	12	...	71·8

This excellent dolichocephalous measure accords almost exactly with the Veddá average (71·6). Even if we take into consideration the five skulls measured by Mr. Welcker, and omit the one mentioned by Mr. Dusseau, the average for sixteen skulls only amounts to 72·2. I will not lay any particular stress upon the difference in sex, since even with the Veddás contradictory numbers have been shown. I can only say authoritatively that Mr. Davis's figures for the female Singhalese heads show a smaller proportion (71·2) than those of the men (73). But here I must say that the previously described skull (No. 982), which Mr. Davis, for some reason

not apparent, calls mikrocephalic, has only an index of 65. Omitting this one we get from Mr. Davis's four female Siphalese skulls an average index of 72·7.

It is especially noteworthy that all the particularised Siphalese skulls (with the exception of skull No. 980 belonging to Mr. Davis, several times mentioned, but left out of the computation) vary within the limits of dolichocephaly, whilst among twenty Veddá skulls (even after the exclusion of the deformed one) there were found four mesocephalic. Were we perfectly sure of the correctness of the preceding statements, we must infer from them certainly a special similarity of the Veddá race to the Siphalese.

As regards the proportions of the single parts of the skull to the length of the whole, I have made a like calculation to that of the Veddás :—

		No. 1.		No. 2.
Index (a)	...	29·7	...	29·8
Index (b)	...	55·6	...	53·5

On the whole, these measures also are somewhat greater than with the Veddás, while yet nowise in a constant or characteristic way.

The absolute figures for the greatest length and breadth of the skulls on the whole run higher for the Siphalese than for the Veddás. I will next give a list of the length, breadth, and height measures of all the Siphalese skulls :—

			Length. mm.		Breadth. mm.		Height. mm.
Dusseau	180	...	130	...	135
Davis,	No. 315	...	172·7	...	124·5	...	121·9
	" 979	...	177·8	...	132·1	...	139·7
	" 981	...	175·2	...	132·1	...	129·5
	" 982	...	182·8	...	119·4	..	132·1
	" 983	...	180·3	...	129·5	...	144·8
	" 984	...	193	...	144·8	...	147·3
	" 1,007	...	195·6	...	142·2	...	134·6
	" 1,008	...	198·1	...	144·8	...	147·3
	" 1,009	...	182·8	...	132·1	.	139·7
Virchow,	No. 1	...	178	...	127	...	129
	" 2	...	181	...	127	...	132·5

We see from these that the greatest length of three male skulls is over 190 mm., and of only four skulls (chiefly female) less than 180 mm. Of the twelve skulls, seven have a length of over 180 mm. The Sinhalese skulls, according to this, exceed the Veddá skulls in length. The result is the same with the greatest breadth. Of the twelve skulls half show a breadth of over 130 mm., three are over even 140 mm. in breadth, only five are under 130 mm.

As regards the vertical height, it is the same with the Sinhalese as with the Veddás, and greater on the whole than the greatest breadth. Only with three (two female and one male) does the breadth exceed the height. On the other hand, in two skulls of women the height is considerably greater than the breadth, viz., about 12·7 and 15·3 mm. In three cases the height reaches a measure over 140, rising in one to 144·8 and in two to 147·3 mm. This is considerably more than with the Veddás. Nevertheless, the ratio of length to height reckons for :—

	Index.		Males.		Females.
Dusseau	...	(1)	...	75·0	...
Davis	...	(4)	...	74·0	...
Virchow	...	(2)	...	72·8	...
Total			(7)	...	73·8
Average of the whole twelve				...	74·2

The result, therefore, is a little below the average of the Veddás (74·9), and within that of orthocephaly. The figures given by Mr. Welcker (77·2) exceed considerably the above estimate; but if we include them in taking the average, and leave out the estimates of Dusseau, the result obtained for sixteen skulls is 75·1, which is only a minimum over the amount of the Veddá index.

The auricular index is likewise less than with the Veddás (63·5 and 58·5)—in the latter case less than with any of the Veddás.

The total result as regards the formation of the skull is, hence, *that a great correspondence exists between the proportions of the Sinhalese and the Veddás, while the absolute*

figures show the Sinhalese to exceed the Vēddás, as a rule, in height. These differences would in the average be of still more importance if the two skulls I have measured had not suffered from a great variety of impediments to their perfect development. I therefore call attention to the description, and will here only say that there is certainly premature *synosteoses* and much irregularity in the temporal region, especially in the one case, where there is stenokrotaphy, and where the squamous portion of the temporal bone overlaps the frontal bone; and in the other case owing to a great *epiptericum*.

In the latter condition was also found the Vēddá skull from the Colombo Museum; and a Vēddá skull from the London Museum shows (as before mentioned) stenokrotaphy.

In examining the form of the face, I follow the same method as before with the Vēddás, and begin with the orbits.

Unfortunately, a great difference appears in the orbital index of the two skulls I measured, which it is difficult to reconcile, the first being 76·9 the other 82·9—consequently, one chamækonch the other mesokonch. The last will therefore correspond nearer to the Vēddá skulls. Here I must suspend judgment, for no other observer has recorded orbital measurements of the Sinhalese, or made any statements about the shape of the orbits. Whether the shape which I have spoken of as inclining to quadrangular is of any significance, must be decided by further observations.

It is the same with the nose index. In the first of my Sinhalese 57·7, therefore platyrrhine; with the second 46, therefore leptorrhine. Like differences are found, to be sure, in the Vēddá skulls, whose average shows a mesorrhine measure (52·2), while we might have expected, according to the descriptions of the observers before quoted, a greater uniformity in the shape of the nose. The bony structure of the nose in the Sinhalese skulls is narrow, prominent, and with a slightly aquiline bridge; and I have the impression that the form, as it exists in skull No. 2, is really the typical

one. I have earlier expressed my idea* about a form which is determined by two wholly different factors, not necessarily united to one another, viz., the height of the nose and the breadth of the aperture. But it is not worth while to continue this discussion at present, with so little material.

Only six of Mr. B. Davis's skulls offer material for determining the index of the face, and of these five are female. I have computed them as follows :—

Skulls.		Height of whole Face. mm.		Transverse Diameter. mm.		Index.
No. 315 ♀	...	109	...	114	...	95·6
„ 979 ♀	...	91	...	117	...	17·7
„ 981 ♀	...	104	...	117	...	88·8
„ 982 ♀	...	102	...	125	...	81·6
„ 983 ♀	...	117	...	127	...	92·1
„ 1,007 ♂	...	130	...	132	...	98·4

Here a very considerable contrast appears to the Veddás. Whilst the highest measure of the male Veddá was 88·2, with the Siphalese we have a male skull of 98·4 and two female skulls of 92·1 and 95·6 ; a third female skull has an index of 88·8. There remain only two female skulls with low measures, one 81·6 and one of a weak-minded person, which is 77·7. Whilst the total average with the Veddás was only something over 83, I find for the Siphalese 89.

If we now reflect that of the female skulls, as a rule, the measure is lower, and that here, of six skulls, five are female, among which is included the abnormally low measurement of the skull of a weak-minded person, we may assume as very probable that the Siphalese face index in the classification suggested by Mr. Kollmann (which, however is based upon a somewhat different computation) is leptoprosopic. The smallness of the yugal distance is decidedly in favour of such an assumption.

* Virchow. Beiträge zur physischen Anthropologie der Deutschen mit besonderer Berücksichtigung der Friesen. Abhandlungen der Akademie. B erlin, 1876, s. 143, 350.

Since in both my skulls the lower jaw is wanting, I cannot arrange a corresponding calculation. Added to this, one of them is so greatly changed on the edge of the jaw by age, that it could not even be used for the middle face index. I can therefore simply institute a comparison between one Vēddá skull (No. 1) and one Sinhalese. In the following I give an index (*a*) calculated from the proportion of the height of the middle face (root of the nose to the alveolar edge) to the zygomatic diameter, the latter = 100; and a second (*b*) calculated from the same height, and from the molar breadth (lower end of the *sutura zygomatico maxillares*), the last = 100:—

		(<i>a</i>)		(<i>b</i>)
Vēddá	...	50.0	...	70.1
Sinhalese	...	52.6	...	60.5

Here the result is, as before, less breadth of the whole face with the Sinhalese, but greater width of front face. The alveolar index of the Sinhalese No. 1 shows a comparatively high figure, viz., 99, but the facial angle (external meatus, nasal spine, root of the nose) only 75, whilst in the case of the Vēddás amounting to 82.

With regard to the palate, I have unfortunately neglected to take the measure of it in the Vēddá skull. I have, however, stated that it was broad, and the alveolar ridge in the shape of a horse-shoe. Contrasted with this, the Sinhalese palate exhibits considerable difference. According to Dusseau's figures, I reckon a palatal index of 73.7; according to mine, for skull No. 1, of 75.4. Result, a leptostaphyline measure. If we compare the two skulls upon Tables I. and II., below fig. 5, the difference is obvious. Whether it is to be regarded as universal I am not able to say.

On the whole, the osteological investigation of the Sinhalese face, therefore, confirms what has already become conspicuous from the physiognomical observations of individual reporters; *the skeleton face of the Sinhalese differs far more from that of the Vēddás than the skull of the former from that of the latter.* It is distinguished, as a whole, in that it is much

narrower. The same is true of the palate, and probably of the nose. On the other hand, the orbits—at least of my Sinhalese skull—are by no means high. The greatest uncertainty is regarding the form of the jaw-bone. One Sinhalese skull I have pictured on Table II. is decidedly more prognathous than the Veddá skull, Table I., but also more than the Sinhalese skull, according to Davy. The Veddá skull of Messrs. Quatrefages and Hamy, as well as the Sinhalese skull of Sandifort, has, however, a very prominent alveolar process.

Before pursuing this comparison farther it will be expedient to discuss the other races of people who must later on be brought into comparison.

The Tamils or Malabars.

As already explained, we understand by this name the Dravidian immigrants who, in historic time, came from many different points on the peninsula of Hindústán, and in the course of over two thousand years multiplied so greatly that they almost exclusively peopled the north and a large portion of the east of the Island, more especially along the coast. When the Portuguese, the first pioneers of European civilisation, obtained a firm foothold upon the Island, the Malabar rule was firmly established in the old *Rájaráta*, or *Pihitiráta*. Moreover, Valentijn* defines their seat in his time as extending up to the river Corunda Waye, which it seems is identical with the Koorinda, or Kirinde-oya ("cinnamon river"), of Sir E. Tennent,† a little river which toward the south-east, near Mahágan, empties itself into the sea. Davy‡ also designates the northerly and eastern coast provinces as the principal seats of the Malabars.

Pridham§ speaks of them as inhabitants of the land from Batticaloa even to Jaffna in the north, and from there as far

* Valentijn, *l. c.*, Bl. 49.

† Davy, *l. c.*, p. 108.

† Tennent, *l. c.*, I, p. 41; II, p. 417.

§ Pridham, *l. c.*, p. 463.

south as Puttalam. It is not to be understood from this, however, that they live even now wholly separated from the Singhalese. On the contrary, they are found in no small numbers mixed with other races, especially in the towns, as the description of Colombo by Sir E. Tennent* very clearly testifies. In this city they form a large fraction of the labouring population. It is of special interest to us that in the east they are immediate neighbours of the Vēddás.

In fact Wolf,† who found no sort of resemblance between Malabars and Singhalese, calls the Vēddás “another species of Malabar.” He describes the Malabars as black, long-haired, and without calves to their legs. Beyond this I find very few statements regarding their physical peculiarities. Most of the writers limit themselves on this point to ascribing to them a stouter physique and greater activity than the Singhalese.‡ Mr. Pridham says they either wear the hair carelessly fastened up in a coil upon the crown of the head, or on one side above the ear; sometimes the whole head is shorn with the exception of a single lock upon the crown. Sir E. Tennent§ describes the children of the Tamils as perfectly naked, with glossy black hair and graceful limbs.

To the Tamils, as already stated, belong “the Mookwas, or, as they call themselves, Mukuger.” If we may really impute to them a separate origin, as Pridham|| does, who traces their descent from the Nairs and Mookwas of the Malabar coast, all observers nevertheless agree that from their physical appearance they must be very nearly related to the Tamils, if they are not actually Tamils. The fact that the Mukkavar are Christians, and part of them also Muham-madans, whilst many of the Tamils adhere to the teachings of Brahma, has made the first a special object of attention.

* Tennent, *l. c.*, II., p. 156.

† Wolf, *a. a. O.* II., s. 156, 167.

‡ Selkirk, *l. c.*, p. 68. Pridham, *l. c.* I., p. 465.

§ Tennent, *l. c.*, II., p. 514

|| Pridham, *l. c.* I., p. 466.

Until of late only a single skull of a Tamil or Malabar was known in Europe. This I found in the collection of Mr. B. Davis. Besides this there was in the same collection the skull of a hybrid of Malabar and Singhalese (No. 316). Through the kindness of Mr. Freüdenberg, Consul, I have received three Tamil skulls, unfortunately all without the lower jaw, and with these a child's skull, marked Singhalese, which I have already described, and of which I entertain the suspicion that it belongs to the group of Dravidas. Properly speaking, we have accordingly only four specimens, in a broader sense we may say six. The first four are recognisable as male, the two last have so slight sexual characteristics that their distinction is doubtful.

The following is a detailed description of the skulls which are at present in my possession.

Skull No. 1.

A still youthful, apparently male skull, without lower jaw, in which all the teeth are erupted, but so far as they are present (the incisors, the right cuspids, and three bicuspids are wanting) are very little worn off; the *synchondrosis spheo occipitalis* is closed. Capacity small (1,155 cub. cm.), ratio of length to breadth (72) decidedly dolichocephalic, ratio of length to height (79·4) quite as certainly hypsicephalic.

Looked at from above the skull seems somewhat unsymmetrical, especially the left parietal eminence, which is lower and flatter. On the contrary, the left half of the *squama occipitalis* is higher and fuller, the right flattened laterally, the lambdoidal angle very irregular, the right leg falling down abruptly close to the continuation of the sagittal suture; the left, on the contrary, extending almost horizontally. The latter, moreover, contains in its lower part, near the side fontanelle, long *ossa wormiana*. The shape of the skull is decidedly long, mainly owing to the very narrow prominent occipital portion. In front, up to the *tubera parietalia*,

* Barnard Davis. Thes. Cran., p. 134.

rather broad, broadest in the region of the latter. Sutures perfect, no trace of *foramina parietalia*. In this region the sagittal suture is rather simple. Strongly marked phænozygy.

At a side view we get the impression of height, and hence also of the shortness. The brow tolerably straight, orbital ridges hardly developed. The upper part of the forehead above the eminences greatly arched, and rising up just in front of the *coronaria*. The descent of the parietal curve toward the occiput is abrupt. High *plana temporalia* intersecting the *tubera squama temp. platt.* Large *alæ*, with very short *anguli parietalis*: at the right 35, at the left 34 cm. broad.

The *norma occipitalis* shows a very high pentangular contour, rather flattened above, horizontal below, with very high and perpendicular sides, only diverging a little below. High and, as mentioned above, very irregular *squama occipitalis*, with somewhat compressed sides, no protuberance; *lineæ semicirculares* well defined, sharp *crista perpendicularis*, slight cerebellar archings, short *facies muscularis*.

In the *norma basilaris* the skull appears broad, especially in the jugular and mastoid region, whilst the occiput is very narrow and prominent. The *foramen magnum* a long oval, somewhat oblique, 34 mm. in length, 26 in breadth, index 76·4. Articulations prominent toward the front. Mastoid processes thick, but not long on either side, with large secondary eminences on the posterior surface, especially prominent on the left side. The styloid processes well developed, the articular surfaces for the lower jaw very deep. *Hamulus pterygoideus* and end of the *lamina externa* very large.

At a front view the head seems high, forehead full, nasal process very broad. Orbits high, with a diagonal widening below and externally; index 84·4, hence mesokonch. *Fissura orbitalis inferior* very wide and hollowed out at the end. Nose narrow above and below; bridge prominent and somewhat rounded; index 48·8, hence mesorrhine. *Fossa canina* a little depressed on the molar bone on both sides; a posterior superior fissure, and a large marginal tuberosity. Alveolar

process strongly prognathous, but only 18 mm. long, with very large *alveoli*. Palate deep and broad behind, with slightly horse-shoe shape. Alveolar ridge 90, therefore brachystaphyline. Horizontal plate of the palate bone more prominent anteriorly in the middle; short *spina nasalis posterior*.

Skull No. 2.

A senile male skull without lower jaw, of small, but yet, beside the others, of relatively larger capacity (1,260 cub. cm.), still dolichocephalic (74·8), and of moderate height (length to height index 73·7); very marked places of attachment for the muscles. Occipital protuberance large, almost hook-shaped. The nasal prominence of the frontal bone broad, protruding greatly, and with jagged traces of the lower part of the frontal suture. The right malar bone, with the contiguous part of the upper *maxilla* and zygomatic arch wanting; right side of the skull slightly eroded by decay.

In the *norma verticalis* the skull seems a pretty regular and broad oval, with its greatest extent in the region of the parietal eminences, and slightly phænozygomatic. The middle part of the sagittal suture rather simple, the left *foramen* wanting, the right lying very near to the suture. The lower side divisions of the coronal and of the *sutura spheno frontalis* obliterated; beginning of *synostosis* of the *spheno frontalis*.

In the *norma temporalis* we see very high planes, which reach above the *tubera* and up to the lambdoidal suture, ending posteriorly on the left in a thick sclerotic surface whose edge overlies the lambdoidal suture; *ala* broad and indistinct on the right, 26 mm. broad on the left.

In the *norma occipitalis* the section is seemingly nearly pentangular, broad, moderately high, with a somewhat flattened roof. The *squama* are large, especially broad; the lambdoidal angle about 160 degrees. The protuberance well developed, as also the *linea semicircularis superior*; in place of the *linea suprema*, however, a flat ridge. *Facies muscularis* strongly marked; cerebellar archings only slightly developed, middle

portions rather depressed, near the *crista perpendicularis* two *foramina*.

In the *norma basilaris* the breadth of the middle and posterior regions very evident. *Foramen magnum* very large, long, and somewhat oblique, 38 mm. in length, 28 in breadth, index 73·6. Articulating surfaces very prominent; behind them, on either side, a thickened portion of the edge, especially on the left, which corresponds to an articulating surface on the arch of the atlas. Mastoid processes large and long, with a very deep fissure; very large styloid processes; enormously developed *lamina externa pterygoidea*, larger but thinner Hamular process; to the right quite a long *foramen civinini*; deep glenoid cavities.

In the *norma frontalis* head appears moderately high; face, however, rather short. Large frontal sinuses; nasal eminence prominent, with broad jagged remains of the frontal suture. Orbits high and wide, principally hollowed out diagonally below and externally; index 83·3, mesokonch. Malar bone small; nose above quite small, with sharp and only slightly bent bridge; index 51·1, on the borders of mesorrhine. *Sutura naso frontalis* rather strongly inclining upward, and articulating with the very moderately broad nasal process of the frontal bone. *Fossa canina* full; *foramen infraorbitale* small and flat; alveolar process strongly prognathous: side parts obliterated, only the middle and front still remaining and prominent; palate atrophied.

Skull No. 3.

A still youthful male skull, without lower jaw. All the teeth were fully formed, but the incisors, cuspids, and bicuspid have fallen out; first molars very large, and the crowns greatly worn; only the wisdom teeth without traces of wear, and small; dark betel-colouring of all the teeth. *Sutura spheno occipitalis* closed. Muscular attachments strong, although the bones on the whole delicate. Capacity small, 1,200 cub. cm. Form hypsimesocephalic, although bordering upon

dolichocephaly; index of length to breadth 75·3, to height 80·9, strongly prognathous.

Top view: short, especially posteriorly; moderately broad; phænozygomatic; sutures open; sagittal suture in the region of the *foramina* wanting.

Side view: short and high; greatest height behind the line of the ear and two fingers' breadth behind the coronal suture. High, straight forehead, strongly incurvated, with large orbital ridges, deep *glabella*, and well-marked eminences; posterior part long and rising; coronal suture pressed far back. Middle of the head short, and much arched. From the crown a sudden descent, with short arching. High *plana temporalia* reaching to the lambdoidal suture, and here forming a large prominence; *squama temporalis* very flat; on the right stenokrotaphy, with *epiptericum spheno frontalis*. The *angulus parietalis* entirely wanting, the *portio orbitalis ossis frontis* in compensation, slightly arched forward. The *ala* is almost wholly prevented from articulating with the parietal bone: it only touches it at its posterior end, under which the *epiptericum* is pushed. Coronal and spheno temporal sutures run almost in a direct line. *Spheno frontalis* long, in a line with the *squamosa*, which is posteriorly lancet-shaped, 11 mm. long, 5 high; *epiptericum* articulating with the *ala*. *Ala* itself strongly incurvated in the middle, yet broad; on the left the *spheno parietalis* short, the angle little developed, so that the *squamosa* and the *spheno parietalis* and *spheno frontalis* run almost in a line; *ala* flat and broad.

		Right.		Left.
<i>Spheno parietalis</i>	...	1 mm.	...	7 mm.
<i>Spheno frontalis</i>	...	23 mm.	...	20 mm.
Breadth of the <i>ala</i>	..	25 mm.	...	25 mm.

Back view: very high, sagittal region quite prominent, only the suture itself somewhat depressed. The form of an assumed section, about pentangular, but the upper and lateral surfaces slightly arched. Eminences prominent, *squama* high, lambdoidal angle acute, *squama superioris* strongly

arched, protuberance small. *Facies muscularis* large, and, on the whole, arched; cerebellar archings, instead, slight.

Lower view: short, rounded behind; *foramen magnum* short, 34 mm. long, 29 broad, index 85·2; very strong articulating surfaces, placed rather far to the front and near together. Mastoid processes large; left divided, but has a slighter fissure. Deep and large glenoid cavities.

Front view: high, arching pretty regularly above; well-developed nasal eminence, with somewhat porotic surface; in the middle of it a finely indented remnant of the frontal suture, at either side of it an arching forward, owing to the frontal sinuses. High, somewhat oblique orbits, with rounded roof; index 86·4, hypsikonch. Anterior part of the spheno-maxillary fissure broad. Nose narrow above, bridge almost sharp, somewhat deeply incurvated and arched; aperture broad and high; index platyrrhine. *Spina nasalis anterior* large. *Fossa canina* moderately depressed. *Foramen infra orbitale* flattened. Cheek bones projecting greatly, with rather short posterior superior fissure. Alveolar process short, 14 mm., still strongly prognathous, because of the large *alveoli*. Palate very broad; index 87·1, brachystaphyline. Alveolar ridge slightly converging posteriorly, yet somewhat in the shape of a horse-shoe. Teeth on the whole very large. The anterior part of the palate surface forms an oblique descent. Slight *spina nasalis posterior*; large (14 mm. long) palatine plate.

The single skulls present certain peculiarities which impair their typical value. This is especially true of the first, which shows a considerable degree of plagiocephaly, with great irregularities in the lambdoidal suture. In all probability the obliquity has operated as a pressure, which has affected one side of the occiput, but it is difficult to say whether this pressure has been an artificial one, and if it came first after birth. The extent of the aberration in the configuration of the lambdoidal suture appears to indicate rather a disturbance during foetal life. We found something

resembling this in the Sinhalese skull No. 1, in which the disturbances even extend to the skeleton of the face, and it had better therefore be omitted in the comparison.

The irregular formation of the *processus pterygoideus* in the second case, where is found, on the right side, a hyperplasia of the *lamina externa* and a large *foramen civinini*, renders this one also unsatisfactory for an entire comparison. Somewhat more considerable are the temporal deviations in the third case, where at the right is found separating *epiptericum*, and at the left a shortening of the *angulus parietalis*; but we found something similar with the Sinhalese, for in No. 1 we encountered on either side a frontal continuance of the *squama temporalia*, and in No. 2 a right-sided *epiptericum*. It would indeed be very desirable to have skulls without these individual peculiarities (although possibly somewhat common to the race), but at present they are not to be obtained.

Turning now to the comparison, we find that the average capacity of the skull is very moderate. The skull out of the Davis collection is the largest; its capacity 1,375 cub. cm. Mine have 1,155, 1,160, and 1,200 cub. cm. The average amounts to 1,247 cub. cm., hence somewhat less than the average of the Veddás (1,261 cub. cm.), and very much less than that of the Sinhalese (1,406 cub. cm.). Considering the small number of Tamil skulls, I should not be willing to take this proportion as the standard, but it shows that the low figures of the Veddá skulls must not be looked upon as wholly exceptional. The skull of a hybrid in the Davis collection has a somewhat higher measure, viz. (according to Mr. Welcker's tables), 1,325 cub. cm. My doubtful Sinhalese skull, No. 3, although belonging to a child, is also comparatively roomy, its capacity being 1,250 cub. cm. But these specimens cannot be taken into consideration in computing the average.

The horizontal circumference of the skull out of the Davis collection amounts to 495 mm.; mine measure 477, 490, and 473 mm., giving an average of 483 mm., differing little

from that of the Vēddás and the Siḥhalese, though somewhat smaller than with the latter. The hybrid, No. 316, of Mr. Davis has only 475, not much more than the Siḥhalese (?) child, 472 mm.

The vertical circumference, on the other hand, constantly rises above that of the Vēddás as well as the Siḥhalese. It amounts in my three skulls, in the average, to 306 mm., against 289 with the Vēddás and 295 with the Siḥhalese. This average is only 174 mm. smaller than that of the horizontal circumference of the corresponding skulls (480 mm.), which is 63·7 per cent., against 59·4 with the Vēddás and 60·5 with the Siḥhalese. This difference is very noteworthy. It is found also with the child (Siḥhalese No. 3).

The circumference of the skull from Mr. Davis's collection, taken through the sagittal suture, measures 353 mm.; that of mine 359, 351, and 352; therefore, in the average, 353 mm., against 376 with the Siḥhalese and 363 with the Vēddás. Plainly the question here, however, is as to the complementary relation to the vertical measure, for the sagittal circumference in length amounts in the case of the—

Tamils, to	73·0 per cent.
Siḥhalese, to	74·3 „
Vēddás, to	74·5 „

of the horizontal circumference.

In an investigation as to the share of the individual portions of the roof of the skull to its whole circumference (*scheitelbogen*), the striking anomaly is directly presented of the plagiocephalic skull (No. 1 in my collection), which is remarkable for the great development of the middle and back parts of the skull-roof, owing to which there is a perfectly abnormal shortening of the frontal portion. This will be best understood by a comparison of the figures.

			Frontal. mm.		Parietal. mm.		Occipital. mm.
Davis, No. 314	129	...	122	...	102
Virchow, No. 1	117	...	132	...	110
Do. No. 2	134	...	120	...	97
Do. No. 3	130	...	122	...	100
<hr/>							
Average	127	...	124	...	102
Average (omitting No. 1)...			131	...	121	...	99

Calculated according to the percentage of the whole sagittal arch : —

			Frontal. mm.		Parietal. mm.		Occipital. mm.
Davis, No. 314	36.5	...	34.5	...	28.8
Virchow, No. 1	32.5	...	36.7	...	30.6
Do. No. 2	38.1	...	34.1	...	27.6
Do. No. 3	36.9	...	34.6	...	28.4
<hr/>							
Average	36.0	...	34.9	...	28.8
Average (omitting No. 1)...			37.1	...	34.4	...	28.2

It is clear from this that for a precise comparison No. 1 must be left out entirely. The two others, however, previously mentioned, viz., that of the hybrid (No. 316) from the Davis collection and that of the child marked Singhalese No. 3 from mine, very decidedly approach the Tamil type. They coincide so exactly with one another that the suspicion of the child's skull being really a Tamil skull, or at least a hybrid, grows upon me strongly. The figures for these are the following :—

			Frontal. mm.		Parietal. mm.		Occipital. mm.
Davis, No. 316	122	...	125	...	104
Virchow, No. 3	121	...	125	...	103
<hr/>							
Or per centage :—							
Davis, No. 316	34.7	...	35.6	...	29.6
Virchow, No. 3	34.6	...	35.8	...	29.5

Contrasted with the Tamils proper the brow here recedes somewhat, whilst the occiput and parietal portions are more developed, and owing to this all the Tamil relations are a little changed.

If, on the other hand, we compare the Tamils with the Vēddás and the Singhalese, a radical contrast appears, especially as regards the share of the brow and the upper part of the occipital bone in the forming of the skull-roof. Whilst with the Tamils it culminates in the frontal division, with the Singhalese, and still more with the Vēddás, the occipital is strongly developed. The hybrid, in the stronger parietal development, comes nearer to the Singhalese.

Still more striking are the variations in regard to the form of the head. To be sure, my plagiocephalic Tamil skull, No. 1, here takes an exceptional place, because owing to its surprisingly little breadth (126 mm.) it gives a low dolichocephalic index (72). On the other hand, the skull out of the Davis collection has a high mesocephalic index (79), and of my two Tamils, one (No. 2) is at the extreme boundary of dolichocephaly (74·8), the other (No. 3) even beyond this, and at the beginning of mesocephaly (75·3), the average being 76·3, therefore mesocephalic. The two hybrids show the same relations; skull No. 316 of Davis has an index of 76·7, the child's skull in my collection has one of 77. This, contrasted with the excellent dolichocephaly of the Singhalese, and, with a few exceptions, of the Vēddás also, is a very important result.

The smaller occipital development of the Tamil can be seen from this, that the horizontal length of the occiput in relation to the entire length (*a*) is less; on the other hand, the basilar length in the same relation (*b*) is greater.

	No. 1.		No. 2.		No. 3.
(a)	27·4	...	23·4	...	27·0
(b)	57·1	...	54·1	...	55·8

The greatest length on an average is small. With Davis it amounts to 173, in my skulls to 175, 179, and 170; hence in no case reaching even the moderate measure of 180 mm. The hybrid from the Davis collection measures only 168 mm., while my child's skull measures 172. The greatest breadth, which is always in the parietal region, is found in a skull of

Mr. Davis's, 137 mm. ; in mine it is 126, 134, and 128 ; in that of the hybrid 130 ; in the child's skull 132 mm. ; hence in none of them anything considerable. In comparison with these the measures of the vertical height are 137·5,—remarkable : in the same order they are 132—139, 132, 137·5,—132,—and 133. The greatest number here, therefore, is that of the plagiocephalic skull, No. 1, which must be left out of consideration. All the remaining figures are very moderate, even small as contrasted with the Singhalese, in fact almost on the borders of the Vēddā figures. The breadth is greater than the height in two out of the three typical Tamils.

The matter takes another aspect if we consider the figures of comparison. The length to height index amounts with Mr. Davis to 76, with my three skulls to 79·4, 73·7, and 80·9, with the hybrid 78, with the child's skull to 77·3. From this the average of the three typical Tamils is 76·8, which corresponds with the hybrids. This is a decidedly hypsicephalic measure, larger than that of the Vēddās (74·9) or of the Singhalese (74·2). This, then, may be included among the diagnostic points.

The auricular index is also correspondingly high. I found it 66·3, 63·1, and 68·8, and with the child 67·4.

Whilst a comparison of the bony skull of the Vēddā with that of the Singhalese proves great similarity, as compared with the Tamil, on the contrary, a great difference is observed. The skull of the latter is hypsimesocephalic, and even when the measure of the contents shows very slight variations, great differences appear in the circumference measures. How much the latter were to be seen in the sagittal circumference and in the share of the different parts of the roof of the skull, has been previously explained in detail.

If we now turn to the shape of the face, we find that with the Tamils it is quite regular.

The orbital index amounts to 84·4, 83·3, and 86·4, hence in the average 84·7, a high mesokonch measure. The child's

skull also gives 83·3. Very similar is the index of the Vēddás, while, on the other hand, that of the Sīghālese seems to be lower. On the whole the orbits are high, in one case (No. 3) even hypsikonch, the upper edge in most somewhat bent, and the diagonal from within and above downward and outward lengthened.

The nasal index of my three skulls shows 48·8, 51·1, and 53·1, —an average of 51, hence on the extreme verge of mesorrhiny. No. 3 only is platyrrhine. The child's skull alone gives the high platyrrhine measure, 55·5. In so far the Tamil nose probably resembles the Vēddá nose more than the Sīghālese. But here also the index gives no distinct idea of the shape of the nose. In its bony parts it is throughout narrow and prominent, although the nasal process of the frontal bone is very broad. The bridge is a little bent in, rather sharp and aquiline. The nose, however, with them all is of little height, which may in the living have rendered it quite different from the Vēddá nose.

The face measures are scarcely satisfactory. Only the skull in the Davis collection has a lower jaw, and in this the index is 85·7, a mesoprosopic measure. Of my skulls, the senile (No. 2) must be omitted because of its defective alveolar processes; the other two have middle-face indices of 51·6 and 53·4. The relation of the molar breadth to the middle-face height amounts to 68·8 and 62·3. The Tamil face occupies a middle position between the Sīghālese and the Vēddá face: it is shorter than the first and longer than the second.

As regards the alveolar index, this amounts to 90, 94·8, and 97·8, therefore in the average 94·2. The degree of prognathy, which is quite clear with the Tamils, is with no more certainty to be ascertained from this than from the (nasal) facial angle. The size, especially of the *alveoli* of the incisors, necessitates a strong projection forward of the alveolar process. But the palate also is decidedly broad; hence we have a palatal index of 90 and of 87·7, a brachystaphyline measure. And herein lies a very striking contrast to the Sīghālese. The size of the

palatine plate of the *os palatinum*, on the other hand, shows a certain similarity to theirs.

The Moors, or Moormen.

According to the information which I have already given Arabian colonies were at a very early period established in Ceylon for commercial purposes. Even at the present day a large part of the smaller traffic is in the hands of these people, who are still engaged in maritime intercourse with the Continent. Sir Emerson Tennent* deduces from this the appellation "*Marakkala-minisu*," or "Mariners." There are, however, "Moorish" villages and settlements also upon the Island. About Batticaloa especially, they seem to have introduced, or at least to have here brought to greater perfection, the culture of the palm, in the same way as in the south of Spain.† But in spite of this their number is small, and their effect upon the rest of the population even less highly to be estimated, because of their religion, which necessitates a sharply-defined separation, so that they rarely intermarry with the Sinhalese or other natives.‡ I would not, however, omit them, since in a very characteristic way they occupy a distinct place under the caste organisation. As mentioned they are "attached" to the *Kshudrawansa*, and among them to the Fisher caste (*Karawé*).

Unfortunately we have scarcely any descriptions of their physical peculiarities. Wolf,§ who certainly seems to include all sorts of people under the name of "Black Turks," says the Moors are black, but have strong limbs, thick calves, and shorn heads. Thunberg|| describes them as large of stature, darker than the rest of the islanders, and well clothed. Pridham¶ declares them to be the handsomest race in the Island, after the European, of martial appearance, and almost without exception tall and well formed. Davy says, "In dress,

* Tennent, I, p. 632.

† *Id.*, II, pp. 456-58.

‡ Pridham, I, p. 479.

§ Wolf, a. a. O. I. S. 169.

|| Thunberg, vol. IV., p. 188, quoted by Philalethes, *l. c.*, p. 244.

¶ Pridham, *l. c.*, I, p. 479.

appearance, and manners they differ but little from the Singhalese."

So far as I can learn there is only one skull of a "Moor" in Europe, and that is in the possession of Mr. Barnard Davis.* This one (No. 317 of his collection) came from Colombo. It is a male skull of 1,495 cub. cm. capacity, therefore tolerably large, with a length and breadth index of 70, length to height index of 71, and a face index of 85·7; it is accordingly orthodolichocephalic and chamæprosopic.

A farther comparison is scarcely desirable, because from a single skull no judgment can be formed as to whether it is really typical of the race.

Malays.

We have earlier discussed the existence of a scattered Malay element. A few statements as to their physical condition have come to us.

Cordiner† describes them, as in contrast to the other races, lighter, more inclining to copper-colour than any other of the Indian races. Selkirk‡ speaks of them as nearly of a copper colour, rather below the middle size, with "flattened foreheads, broad faces, large flat noses, and sharp, fierce revengeful eyes." Pridham§ describes them similarly, and calls them by no means agreeable specimens of humanity. They are active, of a slight yet muscular form.

In the Davis collection there is a Malay skull from Colombo. It is marked male. Its capacity amounts to 1,435 cub. cm.; the length to breadth index is 79, length to height index 76, face index 108. It is therefore hypsimesocephalic and leptoprosopic.

Mutual Relation of Races.

It is conceivable that the question of the origin and relationship of the different tribes existing close to one

* Davis. *Thesaurus Craniorum*, p. 134.

† Selkirk, *l. c.*, p. 74.

† Cordiner, *l. c.*, p. 143.

§ Pridham *l. c.*, I., p. 483.

another in Ceylon should very early have interested the visitors to the Island.

In 550 B.C. Cosmas Indicopleustes, who lived under Justinian, states, upon the ground of reports from the Greek traveller Sopater, that the natives of Ceylon belonged to different races: he calls them expressly *ἀλλόφυλοι*.^{*} Even the Chinese were aware that the north of the Island was inhabited by quite a different race from that of the south; the men in the north (the Tamils) they compare to the Hu (Hoo), a people of Central Asia; in the south (the Siphalese) to the Liao (Leaou), a mountain tribe in west China, to whom they ascribed "large ears, long eyes, purple faces, black bodies, moist and strong hands and feet," with a long life of a hundred years and more, adding that the men, as well as the women, wore their hair "long and flowing."[†]

Evidently these old Chinese reporters found no analogy between the Siphalese and the Chinese themselves. Nor have they, so far as I know, left behind any accounts from which to conclude that a Chinese colonisation of the Island had ever taken place. All that is gathered from their reports[‡] is confined to information about the mercantile and religious institutions, and to one warlike enterprise of the Chinese; but the reports do not come down further than the fourth century of our era, and the defeat of a king of Ceylon by a Chinese army, which occurred as late as the year 1408. Except the statement that in the year 1266 Chinese soldiers entered the military service of king Parákrama, there is no mention made of any longer stay or actual settlement of the Chinese in Ceylon. Notwithstanding this, the Portuguese writer Ribeyro[§] has expressed his opinion that the original population of the Island may have been Chinese. Knox^{||} also

^{*} Tennent, *l. c.*, I., p. 568.

[†] Cited by Sir E. Tennent (*l. c.*, p. 611) from Chinese works.

[‡] Tennent, *l. c.*, I., p. 607, *et seq.*

[§] *Id.*, *l. c.*, I., p. 327, note 2.

^{||} Knox, *l. c.*, p. 61.

heard this story from some Portuguese, but says very decidedly: "But to me nothing is more improbable than this story. Because this people and the Chinese have no agreement nor similitude in their features, nor language, nor diet," and adds: "It is more probable they came from the Malabars, their countrey lying next, tho they do resemble them little or nothing. I know no nation in the world do so exactly resemble the Chingulays as the people of Europe." Here we must remember that he looks upon the Vēddās and Sīghalese as belonging together: "Of these natives there be two sorts, wild and tame."

This certainly ingenuous statement is of great value. The reference to the Malabars is, as we see, purely speculative. In reality Knox denies any resemblance of the Sīghalese to the Malabars, and finds them much more like the Europeans. This is the first unequivocal testimony to the Aryan origin of the Sīghalese, which since then has been assumed by so many visitors. Davy* says: "The pure Singalese of the interior are completely Indians in person, language, manners, customs, religion, and government." He leaves it indefinite which division of Indians he has in mind, and his mentioning the religion seems to exclude the Aryan or Brahminic division. Certainly he did not refer to the inhabitants of the peninsula of northern India—the so-called Indo-Chinese.

Philaethes† and Pridham‡ alone among the more recent reporters express their conviction of the Chinese origin of the Sīghalese; both, however, not from anthropological reasons, but on historical grounds, and the latter with reference to the system of drainage and terrace building of the Sīghalese, which he traces back to China. The historical grounds are of little importance. With regard to drainage, though the invention of this system may unquestionably be ascribed to

* Davy, *l. c.*, p. 109.

† Philaethes. *l. c.*, p. 15, note †.

‡ Pridham, *l. c.*, I., p. 21.

the Chinese, Sir E. Tennent has proved that "the tank system" in Ceylon is of Tamil origin, and was introduced from Hindústán in the fourth century of our era.

After the previous statements no elaborate proof is needed that neither Siphalese nor Veddás, at least in the form of their skulls, present the slightest indication of any relationship to the Mongols. Such a remarkably dolichocephalous tribe has never yet been found among the Mongols. What truth there is in the old Chinese story of the similarity of the Siphalese to the Liau in west China I cannot judge; but it is not even proved that this people is to be regarded as belonging to the Mongols proper. We might rather connect them with the present Laos (on the boundary between China and Siam), whom Gützlaff,* according to their complexion, distinguishes as black and white. According to the opinion of Mr. Schott,† however, the Liau are rather identical with the Ljaos, of whom he states only that they were "south-western aliens," therefore, at any rate, not Chinese. Until we have more precise information about this south-western people, which happily is now in prospect, we cannot draw

* Prichard, *l. c.* Third edition, London, 1884, vol. IV., p. 503.

† Professor Schott communicates to me the following: "The word *Ljao*, of which I thought at first, is the name of a river in the present Mandshooria, after which a Tartar dynasty was named, who for some time ruled over north China. Another *Ljao* (in different dialects *lao*, *lio*, *liu*, formerly even *lot*), which indeed is the one for us to consider, is written very like the former. This signifies, with an added *ja* ('back tooth'), 'prominent teeth,' and is besides, in itself alone, the name for certain south-western outlandish tribes, as I see from the original dictionary, named after the Emperor Kang-hi. The tribe southward from Yun-nan, called by the Europeans *Laos*, is, as far as I know, by the Chinese never called anything but *Lao-tschua*, from *lao*, 'old man,' and *tschua*, 'to beat the drum.' This drum-beating old man is evidently a mere counterfeit of a non-Chinese word, as, for instance, *lang-ja*, 'wolf-teeth,' is the Chinese rendering of *Langka*, that is the Indian name of the Island of Ceylon. Corresponding to the old name for a people or peoples, *Hu*, which designated, in general, the population of central Asia to the north of China, and among these the *Hjün-nu*, or *Hjung-nu*, who have often been confused with the *Huns*, and are certainly in name identical with them, is a word signifying, in its appellative sense, the dew-lap of an ox. Another *Hu*, differently written and distinctly national, I cannot trace."

from this citation any important conclusions regarding the physical constitution of the Sīḥalese. I will not, however, pass over in silence the fact that according to an old tradition already mentioned by Valentyn, the Sīhala dynasty, from which Wijayo the conqueror was descended, had their residence in Tenasserim; so that according to this a Siamese origin is ascribed to the Sīḥalese. Since, however, all the more recent investigations agree in this, that the dynasty, as well as the language of the Sīḥalese, is derived from Magadha, the present Behar, that is, from the very midst of the Ganges land, there is no need of our following up the tradition. Besides, it is not the search for the Sīḥalese origin which claims our first interest, but fathoming the derivation of the Vēddās.

Even in case we consider the Vēddās to be, as some say, savage Sīḥalese, or the Sīḥalese to be tame Vēddās, as others say,—thus deducing both from one and the same original stock,—we cannot but begin our investigations with the Vēddās. A reverse order would be justified only if we assumed that the Vēddās had sunk back from a condition of higher civilisation to the most absolute savagery, in which condition all travellers have found them for many centuries. The theoretical objection to such an assumption I have pointed out already, and will not bring it up again. But I ask, what signs of an earlier civilisation have actually been found? Have the remains of a higher culture been discovered anywhere upon the Island, which, with any show of probability, might be attributed to the Vēddās? To my knowledge there is nothing of the kind, not even rubbish-heaps (*kjökkenmöddinger*) such as are found in an excellent state of preservation in the neighbouring Andaman Islands. Not one stone implement, such as even the Australian possesses in manifold forms, has been found. Now it is just conceivable that these gaps may be filled by further researches, especially since the above-mentioned remark of Mr. Hartshorne awakens at least a hope of stone axes. But what will be gained

even by this? At best the possibility of placing the Vēddás on a level with the Andamanese and the Australians, whilst, according to the present facts, they must be placed decidedly lower. A people who do not even possess clay vessels, who have no knowledge of domestic animals beyond the dog, who are unacquainted with the simplest forms of gardening and agriculture, who lack almost every kind of social institution, who are not even counted among the outcasts by their civilised neighbours, cannot possibly ever have had the means which make a higher culture of any kind possible. *The hypothesis of a return to barbarism must hence be definitely given up.*

The ground for such an assumption could only be found in the language. How great the difference of opinion with regard to the place which should be given the Vēddá language I have already shown. That it is no Dravidian idiom fundamentally seems to me proved beyond a doubt from the testimony before us. A great number of high authorities, among them some of the first linguists, declare it to be rather a Sinhalese than an Aryan dialect. But whether the Sinhalese itself corresponds to one of the other Indo-Aryan languages is again contested. But even if, with the well-informed Childers, we take it for ancient Páli, or rather a primitive sister dialect of the Páli, it will then truly be very difficult for any one to argue from it, and still less from the Sanscrit words intermingled with it, the derivation of the Vēddás from the valley of the Ganges.

For centuries they have been surrounded by more highly cultivated people, and even if they, from shyness, have remained hidden in their forests, a certain intercourse with their neighbours has yet been unavoidable. Where the Tamils have continuously pressed on nearer to them, as in the vicinity of Batticaloa, a part of the Vēddás have adopted the Tamil language.* But during a very much longer period, and

* Cordiner, *l. c.*, I., p. 91. Bailey, *l. c.*, p. 305, note.

in the greater number of places, they were in immediate contact with the Siphalese, to whose kings they stood in a kind of subjection, and from whose line their own chiefs were appointed. What wonder, therefore, if they adopted more and more Siphalese words and forms? The question is only whether, beside these, as I suppose, borrowed words, their language has not preserved some individual elements? To this point the collectors of vocabularies and comparative linguists seem to have given very little attention. And yet the words of doubtful origin, as Mr. Hartshorne has designated them, should be most carefully collected and tested. Thus far we are not even informed positively whether the Vēddá language contains any words designating numbers. What use is it for our investigation that Mr. Max Müller declares more than half the Vēddá words (that is, of those noted down by travellers) to be corrupt Sanscrit? Where belongs the other half, even if smaller, which perhaps with greater attention might be enlarged? If we cannot class it among the Tamil languages it is very possible that it may prove specific. Nothing hitherto justifies us, it seems to me, in any such one-sided statement as that of Mr. Edward Tylor, who calls the Vēddá language, without hesitation, Aryan.

The matter would take a rather different aspect if we might assume that originally the Vēddás alone inhabited the whole Island, and that they were not only forced back into the forests by the immigrants, but had intermingled with them. Of the Tamils, who did not immigrate until later, we may say that in the north they have, in fact, supplanted the original population, but that in the east they have not merely mingled with the Vēddás, but have accomplished a veritable Tamilisation of the Vēddás. This appears, however, unimportant for the essential point. Not so with the Siphalese. If we follow the statements of the native analysts, the origin of the Siphalese is to be traced back to the followers of king Wijayo, a victorious host of immigrants from the valley of the Ganges. It will not be necessary to

take the number of seven hundred people from Magadha (Behar), as the annals give it, quite literally, but whatever it was, the proportion must have been something like that of the Danes and the Normans in England. The larger part of the Island was divided into fields and gardens, and a patriarchal system introduced which has lasted for thousands of years. A series of facts testify that the aboriginal population was not wholly excluded from this system; even the circumstance that the Vēddās were reckoned among the high caste of agriculturists (*Goyiwaṇsé*, or *Vellāla*) clearly indicates that an established position was early insured to them in the political organisation of the country. Upon such a foundation the intermingling of the Magadha people with the aborigines would most naturally take place, and if we look upon the Sinhalese race as the result of this commingling, the experience of so many other countries where a similar intermingling took place would make it perfectly explicable that the Magadha people made their language, the old Pāli or Eḷu, the ruling one, while in their physical conformation the aboriginal element won lasting influence.

With such a view of the matter the Vēddās and Sinhalese would neither be identical nor distinguished from one another simply by a degree of culture. The Vēddās would appear rather as representatives of the aboriginal race; the Sinhalese, on the other hand, as hybrids, produced by a union of immigrant Indians with Vēddās, and therefore varying according to the measure of the participation of either of these elements. This indeed strikes me as being the solution of the anthropological problem before us, so far, at least, as the material at present reaches. The linguistic difficulty, that also the unmixed natives adopted the Aryan language of the conqueror without, as far as we can judge, having been forced to do so, appears to me no longer insurmountable, since from personal experience I have established the fact that in the Baltic provinces of Russia one part of the Finnish population after the other, through

imperceptible but steady progress, has become Letticised to such an extent that the Courland language has wholly, the Livonian almost wholly, disappeared, and only the Esthonian still offers any resistance.*

Considered simply on anthropological grounds, the differences between the Vĕddás and the Siphalese are not so great as to oblige us to assume an absolute contrast in the two tribes. I will not deny that the number of skulls we know to be authentic, which I could personally test by comparison, is too small to lead to a definite conclusion ; but they seem sufficient to enable us to ascertain whether any reason exists for distinguishing results obtained in other ways. Such reason I do not find. After having with the greatest caution excluded the skulls which were of doubtful origin, as well as those which through peculiar malformation showed great aberrations, there still remains, with the addition of skulls found in foreign collections, so great a number of useful specimens that they much exceed what stands at our disposal relating to other tribes.

Comparing briefly what has been arrived at, the result is first, that the Vĕddás, as well as the Siphalese, are dark tribes, whose complexions vary between yellow-brown and black. The greater number of observers describe the Siphalese as not actually very dark, but rather of a chestnut-brown, or brown with a yellow undertone. Percival describes the women as of a yellow colour ; Cordiner and Selkirk assert that the insides of the hands and feet are white. The accounts do not attribute to the Vĕddás such fair skins ; the report of Percival that the Vĕddás are copper-coloured and fairer than the rest of the Siphalese is wholly unsupported.

But even allowing that a considerable amount of difference in colour exists between the two tribes, it may at least be taken into consideration that the Vĕddás are naked, exposed

* Zeitschrift für Ethnologie. Verhandlungen der Berliner Anthropologischen Gesellschaft, 1878.

to all the inclemencies of the weather, without regular habitations, and, moreover, dirty in the extreme—conditions which, even in our climate and under much less trying circumstances, would be enough to bronze the skin very deeply. The Singhalese, on the other hand, are more or less completely clothed, wearing something at least on the lower part of the body, live in regular houses under relatively favourable conditions, and are often distinguished for great cleanliness. If then, as reported by travellers, very dark, almost black individuals are by no means uncommon among them, it is certainly a noteworthy fact.

The character of the hair also is plainly similar, only that here the effect of culture is conspicuous to a much higher degree. Whilst the Veddās never comb theirs,—perhaps, in general, do not interfere with it in any way,—so that from year to year it becomes more and more dishevelled, and in a bushy matted mass covers head, face, and shoulders, the Singhalese exercise a quite unusual womanly care in smoothing and arranging their hair. Both tribes, however, wear the hair long; it is black, luxuriant, and a little wavy; only with the Veddās, owing to neglect, it hangs down in a tangled but not curly manner; the tresses, properly speaking, notwithstanding, are neither curly nor woolly. We will add that in single cases a more curly kind of hair is seen, as in that of the elder man among the drawings given,* though even in his case the hair is long and wholly different from the little close rolls and woolly hair of the real Negroes and Negritos. Had it early been cleaned and combed it would probably be like that of the Singhalese, glossy as ebony. The picture of the young girl in the drawing* seems to exhibit just this improvement.

A very remarkable statement, looking at the matter as it were from the other side, is to be found in d'Albertis.† This traveller had engaged in Point de Galle, two Singhalese for

* No drawings are reproduced.—*Hon. Sec.*

† L. M. d'Albertis. *New Guinea*. London, 1880, vol. I, p. 259.

his researches upon New Guinea. When these Siphalese had become acquainted with the natives of Yule Island (in the Gulf of Papua, at the south of New Guinea) they told him these people resembled their own country people, only that their complexions were not so dark. When he called their attention to the fact that the hair of these natives was "fuzzy" they replied that the Siphalese also would have "fuzzy" hair if it were not daily combed and carefully oiled. M. d'Albertis mentions in connection, that the hair of one of the Siphalese, who wore it short, was crisp, and that of the other, who wore it long, was smooth; he also does not deny that many of the natives resembled the type of his Siphalese. Even setting aside this analogy, as drawn from only two persons, still this statement, so wholly impartial, pretty conclusively proves that the Siphalese hair, when uncared for, strongly resembles that of the Vēddás. A marked contrast is, at any rate, implied to the smoothness of hair of the Malays and Mongols; and the ἀλότριχα of Palladius must not be understood in the sense that the hair of the Vēddás is called smooth without any reservation.

Reports with regard to the colour of the iris are less complete, but we gather from the descriptions that, as a rule, it is dark. As to the Siphalese, Davy makes more explicit statements, and from these we learn that the eyes are generally black, seldom hazel, rarer still grey, but only among the Albinos light blue or red. To be sure, in the poetic description of an ideal Kandy beauty given, "eyes, the blue sapphire and the petals of the blue manilla flower" are considered desirable, but this can hardly be said to refer to a typical peculiarity. Nowhere is anything of the kind mentioned of the Vēddás, and we may therefore assume their iris to be really black or dark brown.

As regards size, plainly both races are of moderate stature, rather short than tall. If the height of the Vēddás on the average is 1,537 for the men, and for the women 1,448 mm., with the Siphalese, on the other hand about 1,625

to 1,650 (men), the significance of the shorter measure of the Veddás cannot be doubted, and much less since we find the minimum measures for the men amounting to only 1,245 mm.

The information about the Sighalese is unfortunately very incomplete ; in one thing, however, all observers agree, that they are smaller and less vigorous than the Europeans. Whether there is only a relative difference in size between Sighalese and Veddás, whether the latter were stunted in growth in consequence of their wretched life, or whether their shortness is a typical race peculiarity, is still doubtful ; yet the fact that they are not all dwarfs, but that comparatively large Veddás are met with (for the very scrupulous Mr. Hartshorne gives the measure of one man as 1,638 mm.), may be adduced in favour of the hypothesis that their often dwarfish size is a result of long-continued unfavourable conditions for development. Nevertheless, the fact in the main is well established that the Veddás belong to a small, indeed to one of the smallest known races. If we add that the *Veddirata* is extremely rich in game, that the Veddás are skilful hunters and fishers, that honey and edible fruits and roots stand in plenty at their command, we cannot say that, like the Australians, they suffer from enforced deprivations. If, notwithstanding, they are much smaller than the Australians, it seems to me we must recognise their smallness of stature as constitutional.

Concerning their development of muscle and strength of body, the witnesses testify loudly in favour of the Veddás. Though the fleshy parts are rather slender, perhaps even lean, the Veddás seem to possess, in general, great capacity for active effort, and limbs of good proportions. Compared with the Sighalese in the lowlands they may be said to show a certain superiority in all work requiring muscle, for it is the Sighalese of the mountains only, especially the Kandyans, who are renowned for physical strength. The shortness of the thumbs and pointed elbows, emphasised

by Mr. Hartshorne, may be explained among the Veddás, perhaps, by their shortness and leanness ;—at any rate, only the first would be of any importance if it should be proved by measurement to be altogether disproportionate. Perhaps we meet here, however, with a deception similar to that of Mr. Bennett's, who lays such stress upon the length of the foot, whilst direct measurement shows perfectly fair proportions. It may be true that the Veddás are flat-footed, but this would not be sufficient to constitute a race-distinction.

Similar observations, only still less distinctive, we find in regard to the size of the head, especially the capacity of the skull. The single numbers, as well as the averages, I have already given, and compared with one another. The result proves that the Veddá skulls on the average are much smaller than the Sighalese ; in fact, that a certain number of them can be called positively nannocephalic. The Sighalese skulls, however, have only a capacity on the average of 1,406 cub. cm., and among eleven examples only three between 1,100 and 1,200 cub. cm. If we weigh against this that also among the Veddá skulls were two of 1,614 and 1,420 cub. cm., it follows that (supposing these skulls to be genuine) not only is nannocephaly no constant characteristic, but skulls of even great capacity are found among the Veddás. The numbers slide over from both sides ; the highest average of the Sighalese does not prevent the occurrence of very small examples ; and *vice versâ*, the certainly very low average of the Veddás includes some pretty large specimens.

I will not rehearse the length measurements and the relations deduced from them. In this way certain differences between the two tribes have come to light, but we shall be able to represent them parallel to each other in the indices. To only one of the proportions will I here call attention, because this may be of considerable importance, viz., that with the Sighalese the front and middle head have a larger share in forming the roof of the skull, while with the Veddás it is the occipital region. Yet I am bound to mention

that the frontal breadth (lower) of the Veddá skulls from the Colombo Museum was by no means less than that of my Siphalese.

Of special interest is the comparison of the skull indices. The average ratio between length and breadth which I have ascertained is for both tribes almost identical: 71·8 for the Siphalese, 71·6 for the Veddás. This is a highly dolichocephalic measure. If by this is proved that all the Siphalese skulls we have for examination are dolichocephalic, and that among twenty-eight Veddá skulls four were mesocephalic, we might suspect Tamil skulls had been intermingled with the latter. This cannot be decided without new and very sure material. For our present comparison we can only assume that these important relative measures do not point to any radical difference in race between Siphalese and Veddás. With both the skull is long and narrow, yet among the Veddá skulls there is a greater number in which the narrowness is extreme than among the Siphalese.

It is the same with the ratio between length and height. This is orthocephalic with both tribes—with the Veddás indeed even to the border of hypsicephaly (74·9), with the Siphalese somewhat less (74·6). But we must, in both kinds of skulls, calculate from those of medium height. With reference to the height measurements the ratio is somewhat different, in so far as here the larger figures are on the side of the Siphalese.

These coincidences of the main indices are so great that they could not be greater within the limits of a single race. The configuration of the capsule of the skull may, aside from the share of the separate bones in it, be considered as identical. In fact, according to the testimony of travellers, the difference of race is more conspicuous in the face than in the skull. It is chiefly in the form of the nose, particularly the flatness of its ridges and the breadth of the nostrils, but likewise to the form of the lips and jaws, which are throughout described as prognathous, the various authors call

attention, as being characteristic features of the Vēddá face. Contrasted with the Singhalese nose, which the old Chinese reporters call a bird's beak, and in the description of the Kandy beauty is compared to a hawk's bill, contrasted with the delicate lips and orthognathous jaw, which we perceive in Davy's drawings, we find certainly very striking differences.

Osteological investigation has, regarding the main facts, confirmed these observations made among the living. Unfortunately we have not been able to turn the skulls found in Europe to much account in this direction, owing to the difference in the published measurements, and least of all indeed with the Singhalese; moreover, it is very unlucky that the two skulls in my possession, of which one has belonged to a young, the other to a very old man, show great individual differences.

In general the skeleton face of the Singhalese is narrower and longer than that of the Vēddás. The former prove to be leptoprosopic (index 89), the latter chamæprosopic (index 83-84). Corresponding to this the palate with the Singhalese is more long and narrow, with the Vēddás rather short and broad, with a prognathous jaw. In this last particular the contrast to the Singhalese is not so clear, since Mr. B. Davis has made no reports concerning it, and of my skulls, one is a strikingly prognathous one, although not having a long alveolar process. Moreover, with the Vēddás occurs mesokonchy (84.6) and mesorrhiny (52), with many individual aberrations, it is true; so that with the women we have more platyrrhine, with the men more leptorrhine forms. On this point the Singhalese material is very unsatisfactory and quite inadequate. I will return to this latter, although pretty much all concerning it is conjecture. I add here only the comprehensive judgment of Mr. B. Davis* in respect to the type of the Ceylonese and Indian population.

* Davis. *Thesaurus Craniorum*, p. 153.

"In Ceylon and the plains of India we have found the people (Veddahs as well as the more elevated races), as far as our material extends, characterised by small, narrow, long, and rather tall crania, having prominent nasal bones and well-expressed faces when we refer to the typical skulls. As soon as we ascend the southern slope of the Himalayas we meet with races of a very distinct cranial type." Whether this judgment refers to the non-Aryan tribes of India is far from clear; certainly in this generalisation it may remain an open question.

If we now draw into comparison the Tamils or Malabars, we come in contact with a much more widely diffused prejudice, although it has only found expression in recent times. Ribeyro had early the opinion that the Siphalese originated in a mingling of Chinese and Malabars (Gallas*). Knox† also, although he found little or no similarity between Malabars and Siphalese, on historical grounds considered a relationship possible. The later writers have (chiefly from outward observation) looked upon the Siphalese as Aryans, and sought to find a Dravidian origin for the Veddás. Lassen‡ only, who considers the Veddás as that portion which had remained unchanged, traces back, on linguistic grounds, the entire "people of the Cingalese" to Dekkan tribes. Sir E. Tennent§ also alludes to the existence of linguistic and religious (if we may use such an expression) affinities which seem to point to the people of the Dekkan; he assumes|| that the Veddás have the same relation to the Aryan Siphalese as the mountain tribes of India to the later Aryan immigrants. He mentions especially the Koolies in Guzerat, the Bheels in Malwa, the Puttooas in Cuttack, the Khoonds in Gundwana, the Bedas in Mysore, and the wild

* Pridham, *l. c.*, I., p. 21.

† Knox, *l. c.*, p. 61.

‡ Lassen. *Indische Alterthumskunde*, I., s. 199.

§ Tennent, *l. c.*, I., p. 328.

|| *Id.*, *l. c.*, II., p. 438.

hordes in the mountains to the east of Bengal. Mr. Bailey* concurs with this view. He not only brings forward the Khonds, the Puttuwas or Juanguas, the Pulindas (in Orisa), the Meekirs (in north Cachar), &c., but extends his comparisons even to Assam, Tenasserim, and east Burmah. But his proofs also are drawn wholly from the social and religious life of these peoples. Without any special evidence is the statement of Mr. Tagore† that a wandering tribe known to the Ptolemies in the northern part of India, the Vaidehas, and who were later encountered by Tippoo Sahib in Mysore under the name of the Bedas, are still extant in their wild and savage condition in the Vēddás of Ceylon. Mr. Jagor‡ mentions that the Bedas who live in little groups in the woods of Travancore and Cochin are considered by some to be a branch of the Vēddás of Ceylon. However interesting these suggestions may be, they still appear to me to assist very little toward the settlement of the disputed question.

Anthropological comparisons have until now hardly been undertaken. Neither have I the intention so far to extend the present investigation, although a variety of material for it is before me. I shall certainly make some references to such, but a full discussion of all the points to be considered would require a much more extensive work. In the first place it will be necessary to take the Tamils of Ceylon into comparison, and chiefly because the historical accounts, going backward as far as Wijayo, inform us of numerous marriages, not merely of the kings, but of their retainers, with the Malabar women, not to mention the very early invasions and settlements made in the Island by Tamil hordes.

* Bailey, *l. c.*, p. 307.

† Transactions of the Ethnological Society of London. New series, 1863, vol. II., p. 381.

‡ Zeitschrift für Ethnologie, 1879, Bd. XI. Verhandlungen der Berliner Anthropologischen Gesellschaft, s. 167.

In spite of the meagre reports with regard to the physical characteristics of the Tamils we cannot doubt that they, likewise, are very dark, more or less black, and have long black hair. For the rest, observers lay much stress on their great strength and activity, nothing more. Hence there remains to me only the scant craniological material found in the collection of Mr. B. Davis and in my own. This is all insufficient for a final authoritative answer to the question of the ethnological relation of the Tamils to the two other Ceylonese tribes, and hence my conclusion is only to be accepted with great reservation.

All these skulls are comparatively small, and certainly no one would infer from them that they belonged to a powerful race. As already stated, the average capacity of a Tamil skull is 1,247 cub. cm., which is even less than the average of the Veddás and of the Sighalese. It is scarcely possible to look upon this number as the typical one for the race, in my opinion, and it is only interesting as showing that small skulls may be found among all the tribes of the Island. Still there is none among them which reaches the minimum number of the Veddás.

More important, however, is the difference in the form of the head. The Tamil skull, to judge from these specimens, is hypsimesocephalic, in fact wholly different from the Sighalese and the Veddá skull. Its index of breadth is 76·3, of height 76·8. Corresponding to this its transverse vertical length is greater than its sagittal circumference length. With reference also to the shape of the single bones in the formation of the roof of the skull we find a considerable difference; the *squama occipitalis* is much smaller; the frontal bone, however, considerably larger than with the Sighalese, and still more emphatically with the Veddás. The basilar view shows plainly the extraordinary shortness of the occipital region.

I must say after this, that the skull of the Tamils, so far as recognisable from those we have under consideration, exhibits

no relationship either with the Vēddás or with the Sinhalese. The proportions of the face may briefly be stated in the following formula : mesokonchy, mesorrhiny, mesoprosopy, prognathy, and brachystaphyly.

This positively distinguishes the Tamil face from the Sinhalese, and brings it nearer to the Vēddá face. But as I have already said, the almost complete identity of the nasal indices (Tamils 51, Vēddás 50-52) does not prevent the greatest variety in the formation of the nasal bridge. Owing to the greater narrowness of the nasal bone, as well as to the prominent, slightly bent in, and comparatively sharp nature of the bridge, we perceive a certain resemblance to the Sinhalese nose. Therefore, should we least of all be justified in representing the flat, and, toward the lower part, broad nose of the Vēddás as a Tamil inheritance? A comparison of the profiles of the faces at a lateral view in Fig. 3, upon my three skull Tables, will show conspicuously the difference in the formation of the noses.

I might in like manner refer to Fig. 1 about the formation of the orbits, and to Fig. 5 in regard to the formation of the palate. Considering the difficulty, however, of showing these relations with perfect distinctness in a drawing, it seems to me that it will tend materially to facilitate a clear understanding of them if I show the principal lines by themselves, and of their natural size. I aim at the same time to draw attention more particularly to some hitherto rather neglected points, and to put sharply defined questions for later discussion. For, to my great regret, I am not in a position to assume any responsibility as to the ethnological significance of my lines. I can only say that I have chosen from the three series those skulls which, after mature consideration and testing, seem to offer the best guarantee that they, to some extent, positively exhibit the race type.

The wood-cuts,* for which the three skulls represented

* Not reproduced—*Hon. Sec.*

in my tables have been used, show the exterior outlines of the noses and orbits. The horizontal line, after which these skulls as well as those on my Tables have been arranged, is the so-called German horizontal line, which is drawn from the lowest point of the inferior edge of the orbit to the highest point of the superior circumference of the outer ear opening. The difference in the form of the entrance to the orbit is in this way quite as perceptible as the difference in the distance of the orbits from each other, and in the position of the edges of the orbital entrance toward the horizontal line.

The measures and indices of the orbits in question are as follows :—

		Breadth.		Height.		Index.
Veddá	...	39 mm.	...	33 mm.	...	84·6
Singhalese	...	39 mm.	...	30 mm.	...	76·9
Tamil	...	37 mm.	...	32 mm.	...	86·4

According to this the Veddá orbit is mesokonch, the Singhalese chamækonch, the Tamil hypsikonch. The difference between the first two rests solely on the lesser height, whilst both differ from the Tamils in their greater breadth.

But with this difference is associated a real divergence in the curvature and sloping off of the edges. The curve is slightest with the Singhalese, where the upper and under edges are almost straight, and run parallel to each other, so that as the outer edge also is very slightly convex, a flattened quadrangular face with rounded corners is the result. In the case of the Veddá, where the orbits themselves are largest, the edges have a tolerably regular curve, so that the shape of the orbital entrance is almost round, only the diagonal from the top and inside to the bottom outside is longer because of the greater expansion about the cheek bones. Finally, with the Tamil, which exceeds the rest in height, the upper edge is but slightly convex, and the widening toward the zygomatic bone more distinct; owing to this the shape of the orbital entrance becomes an oblique oval.

To this dissimilarity is to be added the very different

formation of the naso-frontal region, as may be seen from the following figures :—

	Veddá. mm.		Sinhalese. mm.		Tamil. mm.
Distance of exterior orbital edges (diam. biorbitaire) ...	95	...	93	...	90
Distance of the inner orbital edges (diam. interorbitaire)...	28	...	19	...	17
Inferior breadth of <i>processus nasalis ossis frontis</i> ...	23	...	25	...	21
Direct length of <i>sutura naso frontalis</i> ...	9	...	13	...	12

With the Tamil the two orbits stand nearest to each other ; the root of the nose is narrow but very prominent ; the *sutura naso frontalis* lies deep, taking a straight horizontal course, and the nasal process of the frontal bone, though very protuberant and bearing traces of an extremely jagged frontal suture, is stunted in its transverse development. With the Veddá it is exactly the reverse, and the distance of the orbits from one another greatest ; the nasal process of the frontal bone, in which also a remnant of the *sutura frontalis* persists, is broad and full ; the *sutura naso frontalis*, although short, pushes right up into the frontal bone, and is therefore very high, so that the *sutura maxillo frontalis* takes an oblique course on either side ; the root of the nose itself is small and depressed. With the Sinhalese the proportions are again different, but resembling nearer those of the Veddá ; the nasal process of the frontal bone is even more broad and full, the nasal frontal suture more symmetrically curved and bulging out at the top, therefore reaching higher than with the Tamil ; the distance of the orbits most considerable, the root of the nose itself broader than with the Veddá, but the bridge at its starting point more incurvated than with the Tamil.

The form of the aperture of the nose is with the Tamil more like that of the Sinhalese than that of the Veddá. The former has a breadth of 25 mm., the latter of 24 mm., that of the Sinhalese 26 mm. Hence the nose of the Tamil and of the Sinhalese is platyrrhine, that of the Veddá mesorrhine ; the

indices are 53·1, 57·7, 50. In spite of this the Veddā nose at its *epiphysis* is flatter and more depressed, the Sighalese and Tamil protuberant, the Tamil in fact more than the Sighalese. The impression of greater breadth in the root of the nose with the Sighalese is only an illusion, and caused by the retreating of the nasal bone into the plane of the frontal processes of the upper jaw, and hence the whole space between the corners of the eyes is flatter and more even. In reality, not only the root of the nose but the entire bony structure of the nose of the Veddā is narrower than in that of the other skulls. With regard to this I may once more remark that the nasal indices taken in this way from the relation of the breadth of the aperture to the height of the whole nose, gives no idea of the protuberant parts of the nose. As to the aperture itself, in the case of the Veddā it corresponds somewhat to the European type—is pear-shaped: with the other two, especially the Sighalese, rather triangular.

An exhibition of the Veddā, Sighalese, and Tamil palates may render a further comparison of the linear boundaries possible.*

I begin here also with the figures :—

		Length. mm.		Breadth. mm.		Index.
Veddā		48	...	36	...	75·0
Sighalese	...	53	...	40	...	75·4
Tamil	...	49	...	43	...	87·7

Consequently the palates of the Veddā and of the Sighalese are leptostaphyline, those of the Tamil brachystaphyline. The last varies most in form; its great breadth and shortness stand in correct relation to the form of the skull. Next to this, not in the index, but in the shape of the tooth-curve, comes the Veddā palate, the chief distinctive feature of which is that the tooth-curve towards the back draws partly together, and has very nearly the outline of a horse-shoe. Wholly different from the Tamil, and also somewhat differing

* Drawings not reproduced—*Hon. Sec.*

from the Vēddá, is the Siṅhalese ; with the latter the palatal plate is unusually long, and at the same time of considerable breadth, so that it is very large, but the tooth-curve does not form, as with the other two, a more symmetrical curve, but the side parts stretch out in a pretty straight line parallel to one another, whilst the region of the incisors forms a broader, flatter curve, jutting out in front. The relatively large share which the *os palatinum* has in the formation of the palatal plate with the Siṅhalese has been already pointed out. It may be further mentioned that the teeth in the Siṅhalese are most largely developed, and that especially the first molars have unusually large crowns. In the Tamils the *alveoli* of the cutting and canine teeth are very large, so also the first molar, which by far exceeds the rest in size.

The facts given in respect to three of the most important regions of the skeleton face may suffice to show what great difficulties are encountered in attempting to fathom the degree of affinity existing between these three tribes. If we take, as usual, the indices as guides, we gain for each region another combination. Most closely related are :—

- (1) according to the orbital index, the Vēddá and the Tamil ;
- (2) according to the nasal index, the Tamil and the Siṅhalese ;
- (3) according to the palatal index, the Siṅhalese and the Vēddá.

We must not forget, however, that here only one individual is taken from each tribe, and that the examinations I have cited prove that the individual selected by no means corresponded in every single particular to the average of his tribe. Thus the Tamil is platyrrhine, whilst the Tamil average was found to be mesorrhine. If this average corresponds to the typical tribal conditions, then the Tamil nose stands at least as near to the Vēddá nose as to the Siṅhalese. And yet, as I have shown at some length, it is distinguished in all other respects as well from the Vēddá as from the Siṅhalese nose.

Considering the small number of skulls immediately at my disposal, and the very defective or otherwise doubtful condition of some of them, I was obliged to take my pictures from such of them as gave the best indications of regular development. But I can by no means assert that in all respects they represent typical forms, or that my statements do not admit of great corrections. This the future only can decide, and my work will have fulfilled its aim if it hastens the bringing on of new and better material.

For the present I can only make the single assertion that, so far as we have a distinct view of the physical relations, *as few evidences appear of a real affinity between the Tamils and the Vēddás as between the Tamils and the Sinhalese.*

This, however, does not decide the question as to whether there is a Dravidian element either in the Vēddás or the Sinhalese. The present Tamils of Ceylon are in nowise typical representatives of all the tribes of Hindústán which are usually embraced in the term "Dravidas." Indeed, we find that in the further pursuit of a study of the latter so many varieties among them have come to light, that it has not yet even been proved with certainty which of the so-called Dravidian tribes are most closely related, and which are to be looked upon as the purest. But we now know that in the course of centuries "Malabars" from different regions on the coast of the peninsula of Hindústán, who made invasions and settlements in Ceylon, came, not alone from the nearer points on the coast, but also from quite northern districts. Before expressing a decided judgment all these tribes must be compared in turn.

It would not be here in place to institute a comparison of this kind, and the material at present is not sufficient. I will limit myself to calling attention to the statements of Mr. Callamand* regarding the Maravars, and the introduction of a single example. Through the mediation of Mr. F. Jagor

* *Revue d' Anthropologie*, 1878, sér. II., T. I., p. 607.

I received from Dr. Burnell three skulls from the lower castes of Tanjore, therefore directly from the region corresponding to the Chóla or Solí of the Siphalese annals.

Of these three the one which is distinguished by a large back palatal fissure proves so aberrant in form that it must be excluded as pathological. The other two, however, are very similar, except in the certainly very different form of the palate, as we see in the main indices :—

Index of breadth	...	73·3	...	75·4
Index of height	...	76·1	...	78·2
Orbital index	...	85·3	...	80·4
Nasal index	...	51·0	...	50·0
Palatal index	...	73·0	...	90·0

Strictly speaking, only the height and the indices of the nose agree well, both skulls being hypsicephalic and mesorrhine. On the other hand, we find in all the other indices differences which make it necessary to assign these skulls to other categories, according to the special relations considered. One is dolichocephalic the other mesocephalic. Which is here typical? One is hypsikonch the other mesokonch, one leptostaphyline the other brachystaphyline. According to which shall we decide?

To be sure we may say that in such limited comparisons chance figures often acquire a higher importance than belongs to them. The difference of the indices of breadth, for example, is just exactly as great (viz., 2·1) as the difference in the indices of height, and yet we are obliged to classify one skull as dolichocephalic and the other as mesocephalic, because accidentally the border figure between the two classifications is 75, and this is just between the two indices 73·3 and 75·4. On the other hand, the equally great difference in the indices of height does not prevent both skulls being assigned to the same category, viz., the hypsicephalic, since the number 76·1 as well as 78·2 is within the recognised extreme. Which of these figures is more, which less accidental I am unable to decide, and the calculation of an average from the single cases would not aid in the decision.

Nevertheless, I may say that the Tanjore skulls approach comparatively near the Tamils of Ceylon. In these I found also no small individual differences, and in the index of breadth, in fact, exactly the same, for the latter in the Tamil skulls amounted to 72, 74·8, and 75·3. But for the rest so many analogies present themselves between the two groups that in spite of the aberrant pathological skulls of Tanjore I consider it very probable that the people of Tanjore and the present Tamils of Ceylon are connected together.

But the kingdom of Chóli, or Solí, was even in ancient times a civilised state. Among its near neighbours early appeared the wild mountain tribes of the Nilagiris, remnants of which exist even to this day: as, for instance, the Kurumbas (Curumbars, Kurubas). They were subjugated by the kings of Chóla, and are found at present only in sparse numbers.* For a series of measurements and other investigations regarding these people we have to thank Mr. F. Jagor,† and also for some account of the half-savage Naya-Kurumbas living in the forests. Of the latter, Mr. Jagor has brought with him a skeleton, which is in the possession of the Berlin Anthropological Society. It belonged to a woman, and is remarkable for its extraordinary smallness and delicacy. It is 1,310 mm. in height, and of the skull we have the following indices:—

Index of breadth	74·6
Index of height	74·6
Index of face	81·8
Index of orbits	91·1
Index of nose	63·8
Index of palate	64·0

It is therefore an orthodolichocephalic chamæprosopic skull. Its capacity amounts to only 960 cub. cm., precisely the same nannocephalic measure which Mr. Flower gave of the smallest Veddá skull from Hunter's Museum, and which

* James Wilkinson Breeks. *An Account of the Primitive Tribes and Monuments of the Nilagiris*. London, 1873, p. 55.

† *Zeitschrift für Ethnologie*. 1879, Bd. XI., s. 54 *et. seq.*

he declares to be altogether the smallest human skull in this collection. In fact, this skeleton challenges comparison with the Veddás. The skull measurements show great similarity, whilst the Tamils from Ceylon as well as from Tanjore, especially in the index of height, vary essentially. The form of the face is different from both, as well from the Veddás as from the Tamils, but not different enough from the Veddás to justify an ethnological separation.

The measurements of Mr. Jagor among the living showed in the main similar proportions, although considerable single deviations appear which it is now impossible to account for. He found the Naya-Kurumbas throughout small in stature, and although among them were some very young individuals, the elder ones, especially the women, proved to have even smaller figures. I put the numbers briefly together :—

		Height of body. mm.		Skull index.
A man of 19 years	...	1,435	...	69·4
A girl of 15 years	...	1,402	...	71·0
A woman of 25 years	...	1,345	...	—
A woman of 45 years	...	1,305	...	82·4
Average of the women	...	1,350	...	—

The result in the case of the few wild Kurumbas is :—

		Height of body. mm.		Skull index.
A man of 18 years	...	1,492	...	72·6
A man of 23 years	...	1,515	...	73·1
A man of 27 years	...	1,529	...	80·2
A man of 30 years	...	1,523	...	69·8
A man of 50 years	...	1,589	...	—
Average of the men	...	1,529	...	—
A woman of 22 years	...	1,470	...	—
A woman of 50 years	...	1,410	...	—
Average of the women	...	1,440	...	—

How far the difference in bodily height is universal we cannot judge. At any rate, the women of both tribes are not

only smaller, but absolutely small. But the Kurumbas altogether must be called small. Mr. Ross King,* in his description of the aboriginal tribes of the Nilagiris, points out the Kurumbas as especially stunted creatures, "low in stature, they are also ill-made. They are among the most debased types of mankind." The indices of the head are, in both of the columns just given, dolichocephalic, and indeed to a very pronounced degree. The fact that we have in each column a brachycephalic head is perhaps to be ascribed to the difficulty in taking the measures of the living.

I do not enter any further into these investigations. For the present I only wished to show that the physical condition of the Tamils, including even those of the Coromandel coast, is not sufficient to represent perfectly the Dravidian type. Close beside them in the mountains of Hindústán we come upon other Dravidas who, to all appearance, are essentially different. Therefore, if one will search out the connection of the Veddás, and perhaps of the Sîphalese themselves, with Dravidian India, it would be advisable to go beyond the inhabitants of the coast and bring the mountain tribes into comparison.

But even here the researches will not end, for according to all probability the present mountain tribes are not the real aborigines of Hindústán. In the tradition, together with the Kurumbas, the Vedars are called the oldest inhabitants of Tondamandalam (Madras); and of them, it seems, it was said: "There were then no forts, only huts; no kings, no religion, no civilisation, no books; men were naked savages; no marriage institutions."† I will lay no weight on the name of the Vedars, which probably likewise signifies "hunters," although the mention of such aborigines is certainly noticeable. Further, in the oldest Indian epic, the Rámáyana, we are told of the fights of Vishṇu with fabulous Asurs, who we must imagine to have been the aborigines of Hindústán

* Journal of Anthropology. London, 1870-71, p. 46.

† Breeks, *l. c.*, p. 55. Prichard, *l. c.*, IV., p. 182.

and Ceylon. Ráma himself, who is said to have come from Oude, makes war upon Ráwaná, king of Ceylon (Lańká), champion of the Yakkho and Rákshasas worship, and conquers him. Curiously enough a tradition has been preserved among the Hayas (Vayas, Haius) in Nepál that at the time when Ráwaná was slain they immigrated from Ceylon to the Dekkan, and later from thence to Samroanghar, and finally reached the mountains, which are their present home.* The Varalis, who inhabit the mountains of Konkan,† tell the same tale of their tribe. All these traditions are of course of no positive value for the diagnosis of the different tribes, but they must warn us not to decide our investigations among the aboriginal races of India and Ceylon simply on the ground of some crude linguistic indications, or the physical characteristics of a few better known tribes. All the same, whether the earliest inhabitants of Ceylon immigrated in boats over the small extent of sea which separates the Island from the mainland, or whether, as has been so often conjectured, and is rendered highly probable by the fauna of Ceylon, the Island was once a part of the continent, and as such inhabited by the same tribes, we cannot avoid the conviction that they stand in a close affinity to the aborigines of India.

Whether these were proto-Dravidian or even pre-Dravidian tribes we cannot with certainty decide at present.

The traditions, however far back they may go, with regard to this give very little light. Mr. Zimmer‡ has lately compiled from the books of the Vedas comprehensive accounts of the condition of the Indian people in past ages, but they hardly afford sufficient foothold to enable us to judge

* Dalton. Ethnological Description of Bengal, re-published by Oscar Flex. Zeitschrift für Ethnologie, 1874, bd. VI., s.

† Louis Rousselet. Tableau des Races de l'Inde Centrale. Révue d'Anthropologie. Paris, 1873, t. II., p. 69.

‡ Heinrich Zimmer. Altindisches Leben. Die cultur der vedischen Arier. Berlin, 1879. s. 100 *et seq.*

of the Aryan condition. When the light-skinned Aryans from the Punjáb invaded the land, later called Hindústán, they found it already in the possession of numerous tribes of "dark-skinned" people. In the Vedas these same tribes are designated by the generic name of *Dasyu* or *Dasa*. A greater part of them, in proportion as the conquerors penetrated farther into the valley of the Ganges, were forced back on both sides to the mountains, northward into the Himálaya and southward into the Vindhya; those who remained behind were adopted as Sudras, thus becoming a part of the Aryan organisation. Hence nothing stands in the way of the assumption that the mountaineers in general belong to the aboriginal tribes. But neither does anything compel us to consider all these tribes of the *Dasyu* as homopholic. Indeed, one has recently begun to separate the Dravidian from the Kolarian* tribes, chiefly on account of language. Should we, in the face of such an important linguistic contrast, assume a physical similarity? In this matter the French anthropologists have advanced most audaciously. M. Rousselet† speaks most positively of an immigration of Thibetan tribes of the yellow race from the east, and another of Turanians from the west, before the Aryan invasion; but he assumes, as anterior to both, a population of Negritos. To the admixture of the latter with yellow tribes he first of all ascribes the origin of the proto-Dravidians, counting among these the Malers, the Konds, perhaps the Gonds, and only when fresh troops of invaders had again mixed with the proto-Dravidians, arose, in his opinion, the Dravidas or Tamils. They brought the snake-worship (Nagas) with them. On the other hand, from the immigration of the Turanians arose in the plains the Jats, in the mountains the Bhils, Minas, and Mhairs. He regards as the last remains of the primitive black population the scattered remnants of a small black people upon the high

* Dalton. *Zeitschrift für Ethnologie*. a. a. O. S. 252.

† Rousselet, *l. c.*, pp. 55, 279, pl. III.

plateaus of the Amarkantak, who have become known under the names of Djangals, Puttuas, and Juangas. Curiously enough these are precisely such tribes as Sir E. Tennent and Mr. Bailey had already brought into comparison with the Veddás. But with regard to the Juangas (Dschuangs), Colonel Dalton states that they belong to the Kolarians; that their hair is rough, curly, and of a reddish brown colour, their cheek-bones prominent, faces flat, noses depressed, brows vertical but low. He gives the average height of the men as below 5 ft. and that of the women as about 4 ft. 8 in.* This description contains quite as many Mongolian as Negritian characteristics.

If I have many doubts, therefore, about admitting the distinctions of Mr. Rousselet, especially with regard to the assumption of a veritable Negrito race as the aboriginal race of India, I yet in nowise oppose the idea that the tribes of "black-skins" which the Aryans found established in the valley of the Ganges were mixed. How much Mongolian, Turanian, or Negrito blood flowed in their veins must remain for the present undecided. But it is certainly not improbable that a part only of the Dasyu were Dravidians, and that, even before the proto-Dravidas of Mr. Rousselet, pre-Dravidian tribes inhabited the land. Neither the Mongols nor the Turanians satisfactorily explain the stunted growth of the tribes of "black-skins," to whom even Pliny† alludes as "the pigmies inhabiting the mountains in the country of Prasîæ." All the information we have of them is unfortunately so imperfect as to permit of its being turned to account for every sort of opinion.

The Messrs. de Quatrefages‡ and Hamy have collected

* The young women wear even now nothing but green leaves held together by a girdle. In so far they resemble the Wannî Veddás. But according to Mr. F. Jagor the women of the Korogars, some of the Gond groups, and the Chauchra in Hindústân, likewise wear no covering but leaves.

† Plinius. Nat. Hist.. lib. VI. c. 22.

‡ A. de Quatrefages et Ernest T Hamy Crania Ethnica. V. p. 1-9.

accounts of the Negritos in India, from which they conclude definitely that genuine Negritos are still living in various parts of the country. I cannot esteem the evidence sufficient, although I will not deny that the question is open to discussion. I will give only one example as ground for my misgivings, which is not, however, taken from the Indians, but from genuine Negritos from the neighbourhood.

The so-called Negrito (or Mincopie) race which inhabits the neighbouring provinces to the east, and principally several clusters of islands and parts of Malacca (though they are in fact only scattered members of the tribe), show unquestionably by their dark complexion as well as smallness of frame, and particularly of the head, a striking approach to the Veddás and Kurumbas. As next to them in point of territory we must mention their near neighbours the "little blacks" who dwell in the Andaman Islands. In truth, Mr. Hartshorne* points to certain analogies between Veddás and Andamanese. But his proofs refer exclusively to single customs and peculiarities,—for instance, to the use of the bow and arrow, to their inability to count,—but nowhere rest upon physical grounds. It cannot be denied, however, that the Andamanese, through previously cited characteristics, are physically pretty closely related to the Veddás. In the measurements of Mr. F. Jagor† from the living I calculate the average height of the Andamanese :—

			mm.
17 males at	1,488
10 females at	1,416
27 Andamanese at		..	1,462

Among these the minimum is 1,350 with a man 20 years old, and 1,320 mm. with a woman of 24; the maximum 1,636 with a man 40 years old, and 1,504 mm. with a woman

* Journal of the Anthropological Institute of Great Britain and Ireland, 1878, vol. VII., p. 468.

† Zeitschrift für Ethnologie. 1876, bd. VII. Verhandl. der Anthropol. Gesellsch., s. 262. Journ. Anthropol. Inst., I. c., p. 437.

20 years old. These are proportions in part even lower than the measure found for the Veddás, on the whole, however, coming to about the same.

As regards the capacity of the skull, it is on the average very small. I can state that according to measurements of Andamanese skulls, for which I am indebted to the kindness of Messrs. Macnamara and Man, they reach and even exceed the measure of nannocephaly which the Veddás and Kurumbas present. One of my skulls has a capacity of only 940 cub. cm., another shows 970, a third 1,050.

As great as the similarity in these figures is the difference in the form of the skulls. The Andamanese, as well as the Negritos generally, are in reality brachycephalic, and this one circumstance distinguishes them definitely from all the Ceylon races. If we add to this that their hair grows in spiral coils, and is to be classed with the woolly hair of the genuine negro, then every possibility disappears of a union with the Veddás, unless we assume that climatic influences have specially affected the hair. The complexion also presents considerable variation. Since most reporters call it pure black with the Andamanese, the Veddás are generally described as lighter, and even by the very trustworthy Davy as resembling the Siñhalese.

Even less analogy is found between Veddás and Australians. We may certainly point out that the hair and even the beard is somewhat like that of the Veddás; but one glance at the skull, and still more at the skeleton, of the Australian convinces us that here a great and unmistakable contrast exists. In spite of this Mr. Topinard* has recently emphasised the relationship of the Australians as well to the Veddás as to the Bhils, Gonds, Khonds, Mundas, Kurumbas, &c. I call attention also in this connection to the sufficient number of reasons to the contrary adduced by his countryman, Mr. Callamand.†

* Paul Topinard. *L'Anthropologie*. Paris, 1877, p. 521.

† Callamand. *l. c.*, p. 624.

Very much more complicated is the question whether Malay elements were not infused into the aboriginal population of Ceylon, which from the peculiar rigging of their boats has been concluded, not without substantial grounds. The fact that the Malays have extended their settlements much further, even as far as Madagascar, suggests the idea that they may have established upon Ceylon a kind of midway station. There are, however, no obvious physical indications of such a relationship, and I would therefore enter into no further discussion of this possibility, the less so since the generally assumed connection of the Malays with the ancient inhabitants of India impedes such investigation very greatly. The single recent statement of a physical resemblance between Singhalese and Malays, which I find is by an American missionary in China, Mr. Williams,* who observed in the former "a Malay expression of countenance."

From the foregoing discussion we assume as proved :—

(1.) *That manifold resemblances exist between the Veddás and the Singhalese, and that the origin of the Singhalese race from a mixture of Veddás and immigrants from India possesses great probability, as well upon historical as also upon anthropological grounds.*

(2.) *That the Veddás as well as the Singhalese in the main features are distinguished from the Ceylon Tamils, and equally from those of Tanjore (Chóla).*

(3.) *That, on the other hand, among the remnants of the old Dravidian or perhaps pre-Dravidian tribes of Hindústán we find even to-day evidence of analogies with the Veddás.*

Have the Veddás remained in the condition of the proto-Dravidians, or possibly pre-Dravidians, or have they in their isolation sunk to a lower state? In other words, are they ethnologically to be turned to account in order to paint anew the picture of this primitive period?

* United States Exploring Expedition during the years 1838-42. Vol. IX. Pickering. The Races of Man. Philadelphia, 1848, p. 136.

In various places I have earlier demonstrated why it is not to be assumed that the Vēddás have ever passed through a state of higher civilisation. If in spite of the reasons for such a conception, which to me seem conclusive, it may nevertheless be assumed that, owing to unfavourable outward circumstances, they have by degrees retrograded physically, and that their present low intellectual condition is the result of this physical deterioration, we should then be forced to represent them as a pathological tribe. The smallness and delicacy of their bones, above all the tiny size of their skulls, and, as a necessary result, the inferior capacity of their brains, might indeed suggest the hypothesis that they are a kind of cretin or microcephyle. Unquestionably the brain of the Vēddá must be very small; direct and definite statements of how small we have not, and computation is very uncertain. Herr L. W. von Bischoff* has called attention in detail to the inexactness of the proposed method by which the weight of the brain is computed from the capacity of the skull. We can, however, by this method arrive at an approximate estimate, and I subjoin a few such calculations. The first is according to the method of Mr. Barnard Davis, who for the meninges and the vessels deducts 15 per cent. from the figures for the capacity of the skull, and claims the remainder as being the weight of the brain. The second is according to the direction of Herr von Bischoff, who ascertained that the capacity of the dry skulls was with males 11·9, with females about 8·8 per cent. cub. cm. larger than the weight of the brains expressed in grams. The weight of brain, therefore, would be with the Vēddás, according to—

Davis's method.		Bischoff's method.	
Males, 1,136 grams	1,177 grams
Females, 1,021 grams	1,105 grams

These numbers, however inexact they may be, still indicate a very striking contrast to the proportions of the brain

* Theodor L. W. von Bischoff. Das Hirngewicht des Menschen. München, 1880. v. 66.

in cultured races ; indeed, the figures for the nannocephalic girl are so small that we have every reason to inquire whether these can be physiological relations. If we add to this the apparently very small capacity of the Vēddās for mental development, the almost entire absence of all ideal forms of thought, the inability to count, and still more to calculate, the want of any sense of colour, the question suggests itself whether this is not mikrocephaly in the pathological sense ? We can distinctly deny this suggestion. The small Vēddā skull is as little to be considered mikrocephalic, in the technical sense, as the intellect of the Vēddās is to be likened to the mental condition of mikrocephyles. The individuality of the Vēddās is psychically fully developed. So far as their needs demand they have matured their capacities, and are able to take care of themselves and their children. They establish families, defend their estates (not very definitely limited to be sure), obtain for themselves, partly by great effort and cunning, the necessary food, and even associate, so far as unavoidable, with neighbours and strangers in a free way and as self-determined men. Enough ; they are distinguished in all the main features from actual mikrocephyles.

Mr. Bailey* testifies expressly that madness and idiocy are rare among the Vēddās, especially the latter. He says it is true they have the notion, that when one curses another madness overtakes the one cursed—a notion which prevails also among the Singhalese, who designate cursing as *katawaha* (“ bad mouth,” or “ poison from the lips ”). But insanity is nevertheless uncommon among them. This testimony is the more worthy of note since Mr. Bailey suggests the idea that, as the result of intermarriages with blood relations, beside a stunted body, diseases of the brain, idiocy, and epilepsy might be expected. But he finds nothing of the kind, and satisfies himself by imputing to the cause mentioned the lack of numerous descendants and dying out of the race, an

* Bailey, *l. c.* p. 295.

explanation which, considering the manifold unfavourable conditions under which the tribe live, may at least in this sweeping sense be open to question.

Real microcephaly in the pathological sense is found among the tribes of India. One of the most noticeable examples we know was communicated to the Berlin Anthropological Society by Dr. J. Wilson.* It concerns a sect of Fakírs, who administer the service in the temple of Shadowla, in the Punjáb, and who belong to the Suní Muhammadans; on account of their abnormal heads they were called Chuas or Chuhas ("rat-heads"). Of one of these Mr. Wilson has given us some measurements, which, though not showing exactly how they were taken, at any rate indicate much smaller proportions than are to be found among the Vēddás. According to him, with one male Chua:—

The diagonal circumference of the head (measured before the ears, across occiput) ...	mm. 19 inches = 482
The horizontal circumference (across occiput, ears, and fron- tal cavity) 17 inches = 431
The vertical circumference (right across from one ear opening to the other) 8 inches = 203

If we compare these figures with those of the Vēddás the difference will instantly be clear. With the Chua the size diagonally amounts to less than the size horizontally of the Vēddá skull No. 1, although the latter is not measured across the frontal cavities, but above them, and of course without any covering of flesh. Although Dr. Johnston asserts the impotence of these people, the sect has still, since the 16th century, continued to perpetuate itself in both sexes, and at some periods so vigorously that their number in the latter half of the 17th century reached a hundred heads. The temple is secretly visited by women, who, because of their

* Zeitschrift für Ethnologie. 1879. bd. XI. Verhandl. der Anthropol. Gesellsch., s. 237. 1880. bd. XII., Verhandl., s. 12.

sterility, pass a night there, and consecrate their first-born, in advance, to the temple service. In the morning "they find a Chua at their side who is supposed to promote conception and beget Chuas." It will indeed be allowable to make another interpretation, and assume direct agency, wherein less impotent individuals than Dr. Johnston saw are employed; however it may be, this example very well illustrates the distinction between microcephaly and nancephaly.

It may, therefore, without hesitation, be admitted that the impaired bodily and mental development of the Veddás is not owing to a really morbid condition, which as such might be hereditary, but rather to be regarded as a race-peculiarity. This, however, by no means excludes the possibility that favourable outward circumstances, especially better food, might produce a more complete development, and the body become larger and stronger, the skull and brain formation more perfect. In fact such cases appear among the Veddás, as is proved by examples previously given. A man of 1,638 mm. in height far exceeds the average, and though the one skull in the Davis collection which has a capacity of 1,614 cub. cm. may be considered as a kind of abnormality, there is still the other out of the collection in the College of Surgeons of 1,420 cub. cm., which (supposing it to be genuine) is a very noteworthy specimen.

It might follow from this that the Sinhalese are civilised Veddás, who simply owe the superiority of their physical development to their better life. The Island of Ceylon had of old the reputation of affording the most favourable conditions for the existence of men, and was celebrated for the longevity of its inhabitants. "In Taprobanem," Palladius* writes, "ubi gens est Macroborum, namque eximia coeli temperie...ad ætatem 150 annorum senes durant." Saint

* Palladius, *l. c.*, p. 3; cf. Plinius, *Nat. Historia*, lib. VI., c. 24. "Vitam hominum centum annis modicam."

Ambrosius even translates the Greek *μακρόβια*, “Beati.” However, climatic and outward circumstances favour the Vēddás too, and if in their peculiar conditions of life they in some degree approach the Roḍiyas, still, as already mentioned, the latter have nowhere sunk to a physical degradation compared with that of the Vēddás. But no one will deny that with good care both might attain to an incomparably more complete bodily development.*

In spite of this possibility of a more perfect growth, the Vēddá race is still in reality, as in ancient days, of small stature—in fact one may even count it among the smallest of the living human tribes, and in a not very strict sense speak of it as a tribe of dwarfs. As a further corroboration of this, such tribes were scattered all over India. I have already referred to the Naya-Kurumbas. But beside these, people of small stature and little heads are not uncommon. Even the Sīḥalese and Tamils of Ceylon have already afforded us examples of this. Herr von Bischoff† speaks of the brain of an Indian from Bukkur of 1,660 mm. in height, which weighed only 973 grams : he quotes at the same time an observation of Peacock’s, who found in a native of mixed origin from Bombay a brain of 1,006 grams, whilst Mr. Clapham ascertains the weight of brain of a Bengalese to be 1,531 grams. In the collection of the Berlin Anthropological Society is the skull of a Poleyar, with a capacity of only 1,040 cub. cm.; that of a young native of further India, belonging to the caste of the oil merchants, having a capacity of 1,150, and his mother’s of 1,100 cub. cm. Of the skulls from Tanjore which I mentioned one has 1,200 the other 1,255 cub. cm.

The naniocephaly of the Vēddás, however little pathological it may be, compels us in nowise to go beyond the province of Indian ethnology to seek out analogies. Possibly

* Davy (*l. c.*, p. 107) states that among the Sīḥalese there are more men than women ; in the fishing towns, where the food is better, we find, however, as in Europe, that the case is exactly the reverse.

† Von Bischoff, *a. a. O. S.* 83.

India in ancient times was inhabited by tribes who bore a close relationship to these. With as little propriety as the present Hindús can be said to have sprung, and progressively developed from these more or less dwarfish aborigines, just so little does such a kind of explanation suit the connection of the Vēddás with the Sīghalese. As they have not descended from the Sīghalese by regressive degeneration, neither surely have they been transformed by progressive evolution into Sīghalese. That no such simple affinity exists is proved chiefly by the difference in the form of the face, to which all observers testify.

In truth, it was just the form of the face which caused all the earlier travellers to associate the Sīghalese with the Europeans. Even Knox, as I have already mentioned, was of the opinion that no people in the world were so exactly like the Sīghalese as the people of Europe. Cordiner asserts this quite as distinctly, calling attention particularly to the features, which means the face. If so fine an observer as John Davy, instead of this, says the Sīghalese are wholly Indian, we can only conclude that all these designations point to the common Aryan character of the face. With Davy this is the less to be doubted since he speaks explicitly of the "Asiatic" form of the Sīghalese skull (that is, of the capsule of the skull); when, directly to the contrary, almost all observers ascribe to the Vēddá face a foreign and very frequently Dravidian type, it becomes clear that genealogical investigation must make the face a main object of study. If we now go back to the history there can be no doubt that *the Sīghalese face is an importation from the Aryan province of the Indian continent*. The Rámáyana, as well as the Wijayo legend, affords direct confirmation of this. The latter, however, conveys at the same time an earnest warning not to be too one-sided in this opinion, for it speaks distinctly of an importation of Tamil women from "Mabar," from whom the king himself and his followers took wives.

If my view be correct that the *Vēddás* are a pure blooded, the *Sinhalese* a mixed race, we may then leave the question out of consideration as to how far Ceylonese intervention, especially soil, food, and climate, has operated to determine the formation of the body. I wish only to touch briefly upon a few facts, the knowledge of which is not without significance in regard to this question. Even in the old document ascribed to Palladius, the sheep upon Taprobane are spoken of : “Oves illis crinitæ omnesque absque lana, lac suppeditant ubertim, latis caudis conspiciendæ (πλαρείας ἔχοντα οὐράς).

Sir E. Tennent,* nearly two thousand years later, made the same observation in Jaffna ; the sheep of the place had long hair, like goats, instead of wool. A similar influence of climate upon the hairy covering of the sheep is also testified of other places. It is asserted† that the native cats of Ceylon have an inferior appearance ; they are said to be small, with thick close-clinging hair, little heads, retreating foreheads, but great pointed ears.‡ Any one disposed to assume a like influence of climate upon men might conclude that human beings also, especially the aborigines, who have dwelt longest upon the Island, have undergone a like change : for example, that the hair was originally woolly, the head and entire body larger. Then might approaches be sought to woolly-haired blacks, to Andamanese and Negritos, to Melanesians and even Africans. Before admitting such great alterations,

* Tennent, *l. c.*, II, p. 531. “The finest sheep in Ceylon are reared upon the dry plains which overlie the limestone and coral rock, on the northern and western coasts. These sheep, instead of being coated with wool, are covered with long hair, resembling that of goats, and the horny callosities that defend their knees, and which arise from their habit of kneeling down to crop the short herbage, serve to distinguish the Jaffna flocks from those of the other portions of the Island.” I do not find it said that these sheep have fat tails.

† Charles Darwin. *The Variation of Animals and Plants in the State of Domestication*. Translated from the English by V. Carus. Stuttgart, 1868, vol. I., p. 122 ; vol. II., p. 369.

‡ *Id.*, vol. I., p. 57.

however, the facts must be assured. The story of the native cats deserves a more strict inquiry; it rests at present upon the solitary testimony of a botanist (Mr. Thwaites). The metamorphosis of the sheep, however, seems more firmly established, as it is supported by the authority of two wholly independent witnesses, separated from one another by quite a long interval of time; but it is confined, according to Sir E. Tennent, to a comparatively small district in the extreme north. Hence it appears to me we should hesitate before making an application of these experiences, gathered from the history of domesticated animals, to the savage inhabitants of Ceylon; at any rate until it is proved that the latter actually possessed in earlier times different physical characteristics. The present state of the hair plainly corresponds to the ἀπλότριχα of Palladius, and must therefore have been just as it now is for at least fifteen hundred years.

It is very certain that if we would pursue the search for the origin of the Veddás genealogically we must first turn our investigations to the savage, or half-savage tribes of India. This once clearly settled, room enough will still remain for conjectural anthropology. Even now speculation has gone pretty far. Mr. Hyde Clarke* brings the Kolarian and other further Indian tribes in connection with the African negroes; Col. Kincaid† places the Bhils with the Mongols; and Mr. Kean‡ strikes the Malays wholly out of the series of independent races, and believes the Caucasians to have penetrated in pre-historic ages not merely to further India, but even so far as Polynesia. It may be of service that such questions should be seasonably presented, especially at a time when the dying out of the savage races is imminent, and admonishes us to hasten the investigation. But after the questions have awakened interest, the warning must be reiterated not to draw any definite conclusions until a greater

* Journal of the Anthropological Institute of Great Britain and Ireland, 1878, vol. VIII., p. 49.

† *Id.*, 1880, vol. IX., p. 406.

‡ *Id.*, 1880, vol. IX., p. 258.

amount of facts have been collected. First of all then, great stress must be laid on the importance of enlarging by every possible effort the ethnology of the Indians, in order to be able to investigate radically the tribe of "black-skins." Since a part of the Dasyu were transferred to the Sudras, and consequently included in the caste system of the Hindús, as the Veddás in that of the Sighalese, it is not even possible to bring to a conclusion the physical anthropology of the Hindús and the Sighalese until we have resolved the evidently very composite group of the Dasyu into its separate members. One such member is plainly the tribe of the Veddás. Their natural isolation upon an island has perhaps tended to preserve in them, rather than in related races upon the continent, their peculiar character, and made them an object by which to test the admissibility of the theories concerning the origin of the black Indians.

May the zeal of the observer know no flagging, that before the utter extinction of this already much depleted race, the language and customs, the physical and mental constitution, of the Veddás, may be in all particulars firmly established.

TABLES OF MEASUREMENTS.

I.—SKULL AND FACE MEASUREMENTS.

		VEDDA'S.				SINHALESE.				TAMILS.			
		1	4	5	6	1	2	3	4	1	2	3	4
Capacity	...	1,250	1,025	1,360	1,110	1,200	1,250	1,155	1,260	1,155	1,260	1,200	
Greatest length	...	177	165	185	178	181	172	175	179	175	179	170	
Greatest breadth	...	125.5	133	135	127	127	132	126	134	126	134	128	
Vertical height	...	Ps. 129	121	137	129	132.5	133	P. 139	132	P. 139	132	137.5	
Auricular, meatus audit. to vortex	...	107	104	120	113	106	116	116	113	116	113	117	
Horizontal circumference	...	485	465	508	482	493	472	477	490	472	490	473	
Trans. vertical circumference	...	283	286	300	298	293	305	305	308	305	308	305	
Sagittal circumference, frontal bone	...	120	115	134	119	124	121	117	134	117	134	130	
Length of sagittal suture	...	115	108	140	125	130	125	132	120	132	120	122	
Sagittal circumference, squama occipital	...	110	109	114	110	111	103	110	97	110	97	100	
Whole sagittal arch	...	345	332	388	354	365	349	359	351	359	351	352	
Inferior frontal diameter	...	95	91	93	93	92	88	88	92	88	92	88	
Temporal diameter	...	107.5	110	117	93	103	102	108	115	108	115	104	
Parietal diameter, <i>tubera</i>	...	119	123	120	122	116	123	115	120	115	120	122	
Occipital diameter	...	102	100	99	103	101.5	103	101	103	101	103	95	
Mastoideal diameter, end	...	96	94	103	96	98	93	105	95	105	95	93	
Mastoideal diameter, <i>basis</i>	...	110	111.5	122	115	115	111	120	119	120	119	112	
Auricular diameter	...	100	108	108	97	103	95	106	115	106	115	106	
Horizontal length of occiput	...	50	46	60?	53	54	52	48	42	48	42	46	
Distance of nose-root from <i>foramen magnum</i>	...	92	91	90	99	97	92	100	97	100	97	95	
Distance of root of the nose from the ear opening	...	96	94.5	99	102	101	95	101	104	101	104	99	
Distance of nasal spine from <i>foramen magnum</i>	...	81	—	—	96	86	83	91	87	91	87	88	

Distance of nasal spine from ear opening	95	—	—	105	101	93	102	103	101
Distance of alveolar edge from <i>foramen magnum</i>	86	—	—	105	82!	83	90	92	93
Distance of alveolar edge from ear opening	100	—	—	100	101!	96	107	111	107
Distance of chin from <i>foramen magnum</i> ...	114	—	—	—	—	—	—	—	—
Distance of chin from ear opening	92.5	—	—	—	—	—	—	—	—
Height of face, A (from nasal root to chin)	101.5	—	—	—	—	—	—	—	—
Height of face, B (from nasal root to alveolar edge)	61	—	—	59	58!	151	62	66	63
Breadth of face, A (jugal)	122	—	—	112	120	07	120	—	118
Breadth of face, B (<i>sub. zyg. max.</i>)	87	—	—	97.5	87	83	90	—	101
Orbits, height	33	—	—	30	34	30	32	35	32
Orbits, breadth	39	—	—	39	41	36	38	42	37
Nasal height	48	—	—	45	51	36	45	45	47
Nasal breadth, aperture	24	—	—	26	23.5	20	22	23	25
Palate, length	48	—	—	53	45!	38	49	48!	49
Palate, breadth	36	—	—	40	33!	33	36	36!	43
Distance maxillary angle	85	—	—	—	87	81	90	—	89
Distance maxillary joint	—	—	—	75	75	76	76	76	75
Facial angle	82	—	—	—	—	—	—	—	—

II.—INDICES COMPUTED.

Length to breadth index	mm.	70.9	80.6	73	71.3	70.2	76.7	72	74.8	75.3
Length to height index	"	72.9	73.3	74.1	72.5	73.2	77.3	79.4	73.7	80.9
Breadth to height index	"	103.5	90.9	101.4	101.5	104.3	100.7	110.3	98.5	107.4
Auricular index	"	60.4	63	64.9	63.5	58.5	67.4	66.3	63.1	68.8
Middle facial index	"	50	—	—	52.6	—	47.6	51.6	—	53.4
Orbital index	"	84.6	—	—	76.9	82.9	83.3	84.4	83.3	86.4
Nasal index	"	50	—	—	57.7	46	55.5	48.8	51.1	53.1
Palatal index	"	75	—	—	75.4	—	86.8	90	—	87.7

* The mark P. signifies that the greatest breadth was taken at the parietal; Ps. at the *tubera* (upper parts); Pl. at the lower parts.

PRINTED AT
THE GOVERNMENT PRINTING WORKS,
COLOMBO, CEYLON.

"Proceedings, 1885."


By an oversight, the pagination was run on from "Proceedings, 1884" (which form part of Volume VIII.).

It is not possible to correct the paging neatly, except in manuscript. Members are requested to do this for themselves.

The pages should run from i—cx.



PROCEEDINGS,
1885.



OFFICE BEARERS, 1885.

Patron.

His Excellency the Hon. ARTHUR H. GORDON, G.C.M.G.,
Governor.

Vice-Patron.

HON. C. CLEMENTI SMITH, C.M.G.

President.

Right Rev. R. S. COPLESTON, D.D., Lord Bishop of Colombo.

Vice-Presidents.

W. R. KYNSEY, Esq., M.K.Q.C.P.L., L.B.C.S.I.
T. BERWICK, Esq.

Honorary Treasurer.

J. G. DEAN, Esq.


Honorary Secretary.

W. E. DAVIDSON, Esq., C.C.S.

Committee.

J. CAPPER, Esq.
Hon. Lieut.-Col. F. C. H.
CLARKE, R.A., C.M.G.
J. B. CULL, Esq., M.A.
D. W. FERGUSON, Esq.
PH. FREUDENBERG, Esq.

S. GREEN, Esq., F.L.S.
W. P. RANASINGHA, Esq.
H. TRIMEN, Esq., M.B., F.L.S.
J. L. VANDERSTRAATEN,
Esq., M.D.



PROCEEDINGS.—1885.

GENERAL MEETING.

29th January, 1885, 8.30 p.m., at Colombo Museum.

Present :

The Hon. J. F. Dickson, M.A., C.M.G., President, in the Chair.	
P. D. Anthonisz, Esq., M.D.	W. Ferguson, Esq., F.L.S.
T. Berwick, Esq.	The Hon. F. Fleming.
F. W. Bois, Esq.	Ph. Freüdenberg, Esq.
H. Bois, Esq.	H. MacVicar, Esq., F.Z.S.
The Hon. R. A. Bosanquet.	W. P. Ranasinha, Esq.
J. B. Cull, Esq., M.A.	J. H. Thwaites, Esq., M.A.
D. W. Ferguson, Esq.	W. H. Wright, Esq.
J. Ferguson, Esq.	

W. E. Davidson, Esq., C.C.S., Honorary Secretary.

Six visitors introduced, and six ladies.

Business.

The Paper for the evening was a translation, by Mr. Philip Freüdenberg, of an account of Ceylon by Johann Jacob Saar, a private soldier in the service of the Dutch East India Company, whose experiences of fifteen years' campaigning in Ceylon were admirably rendered in Mr. Freüdenberg's translation. The naive spirit of the original was capitally caught. The extract read by Mr. Cull, the whole translation being too long to read, was the part relating to the siege of Colombo by the Dutch, and its capture from the Portuguese in 1656.

The recital of Saar's experiences in Ceylon is in the form of an extended diary, with the dates of the various incidents noted very carefully. The translation commences with the fourth chapter of the original work, the previous chapters referring to his travels in other countries. It is dated 1647, A.D. when, with three hundred other soldiers in the Dutch East India Service, the writer left Batavia for Ceylon, arriving at Galle, then regarded as the Dutch capital of the Island, the Portuguese holding possession of Colombo, Negombo, Kalutara, Mannâr, and Jaffnapatam. The account of the country and its people in the early part of this diary is told very much as we find it in Knox, save that the latter referred to Kandyans, whereas Saar speaks of the low-country people. He alludes with evident surprise to the fact of the peasant, or cultivator, being held in higher esteem than the artificers in gold and silver, but so it is not only in all Eastern countries, but amongst the early inhabitants of the West, where the poorest free-born cultivator was, in the Saxon times, held to be

superior to the burgher or artisan. There are several pages devoted to an account of the kraaling of elephants, which was evidently carried on then pretty much as it is in the present time, except in the methods adopted for taming and training the captured brutes. There is an amusing account of a capture of a huge rock-snake whilst in the act of swallowing a young deer, a portion of which protruded from the creature's jaws: the snake was killed, and the young deer removed from it was found to weigh forty pounds. Seeing the natives prepare to cook the snake, Saar bethought him to make a meal or two of the deer, and found that, on being cooked, it tasted remarkably well.

It is made very evident from Saar's recital that the Portuguese had rendered themselves intensely disliked by the King of Kandy, or, as he is termed, the Emperor of Ceylon, who on several occasions made overtures to the Dutch to aid him in expelling the Portuguese from the country, sending on one occasion an embassy to Batavia for that purpose. The Dutch, nothing loth, came to an understanding with the Kandians, who supplied them with fresh provisions of all kinds, as well as with native troops to aid them in their operation, and coolies for carrying supplies, &c.

The hostile proceedings of the Dutch Commander of Galle appear to have been directed, in the first place, against "the great fortress of Negombo," as it was styled. Negombo had at that time four bastions, two towards the sea and two towards the land, each armed with eight guns, with a wall of sods twenty-two feet thick running round the whole, and enclosing a castle protected by two bastions. Outside of all there was a deep and wide ditch lying with sharp stakes. Altogether, it must have been a formidable place in those times against a native enemy. The reason for all this strength was that Negombo was the centre of the cinnamon jungles, into which large bodies of peelers were despatched at the proper season, accompanied by a hundred soldiers to drive off the enemy and wild elephants during the collection of the much-coveted bark.

Negombo was taken by the Dutch, and recaptured from them several times after much fighting and some blood-letting, but, after the taking of Colombo and the establishment of a good understanding with the Kandyan sovereign, it was no longer necessary to maintain a large garrison at Negombo, and the fort and its works were much reduced in size and strength.

The account of the march of Dutch troops to the siege of Colombo is full of interest, as showing the mode of warfare adopted in those days, and the tedious marches undertaken by the troops, all of whom were infantry. Meeting a body of Portuguese troops seven hundred strong, a few miles on the Galle side, the Dutch army, reinforced from Batavia and numbering three thousand, had no difficulty in defeating them and killing a large number. Advancing on the capital they regularly invested it, but met with such a stout resistance that their numbers were considerably reduced by dead and wounded, the latter being cared for in

a monastery at Mutwal. The besieging force was now beginning to feel some discouragement, but the narrative goes on to say :—

“ When, however, on the 2nd of April, three ships with fresh soldiers arrived from Batavia, our spirits rose considerably, and we wanted to have our revenge ; the more so, as, on the following day, 3rd of April, we got hold of the Portuguese provisions which had sailed from Goa under a Dutch flag, in hopes to pass through our fleet into the harbour of Colombo.

“ When the besieged learnt these two facts, they, on the other hand, became despondent, especially as they saw that every day we got nearer to the town. Daily many deserters came to us, and all reported that there was great want of provisions, and that many had died of hunger. This was confirmed by their daily driving out black people, whom we could not allow to get into our camp, and therefore had to shoot between the trenches and the town. At last the famine assumed such proportions that one native woman ate her own child ; others took grass from the ground, and wanted to eat it. As we had no means of driving them away from our camp, we had to strike a still greater terror into them, and when a woman came and brought small children, we forced her to put her child into a wooden mortar, and to pound it dead with the pounder, and then again to go away with the dead child. On the 9th of April we began to dig a mine, and managed to make a gallery on one side across the ditch. When, however, on their side we had dug for two days, they noticed it, made a counter-mine in the direction of ours, so that when we became aware of it and heard it, we had to give up our work.

“ On the 12th of April, our General wanted to reconnoitre whether we could not construct a mine in a different locality. But when we wanted to go into the last trench, a shot from one of the bastions hit him and killed him on the spot, which caused a great terror among our soldiers.

“ On the 2nd of May his body was taken to Galle, and there carried into the church by sergeants and buried, whilst the cannons upon the wall and round the town fired a salute, and two companies of soldiers gave three volleys. On the 6th of May, a Saturday, we were lying all through the night in the trenches, as the Emperor of Ceylon and ourselves had decided to attempt again a general assault. Just then a Portuguese, fully armed, ran over to our camp, and then was conducted before our Governor, who commanded in place of the late General. On close examination he said that those in the town wished for nothing better, but that another storm should be attempted. He told us that in the town passages been made through all the houses, whilst all the streets were provided with double palisades of palm trees, that the cannon had been taken down from the walls, and had been posted in the streets charged with shot ; that below the walls which we should have to pass, big boxes with powder had been put and so arranged that, with a running fire through all their houses, they could be exploded, and by thus separating the bastions

from each other, make it impossible for us to carry our point, because we should all be killed either by fire or by mines. On the other hand, he gave us splendid advice. He said that, as soon as daylight appeared, being Sunday, the citizens, who had been watching during the night, would go with the soldiers to hear mass, and there would be no more than five or six men in the bastions. Altogether, there were only about one hundred real Portuguese soldiers ; the others were burghers and slaves. Now, we were to make our drummers beat and our trumpeters trumpet at the same time, and in the usual way in the morning ; we were to remain quietly in the trenches, that nobody might become aware of our intentions, and then, half an hour afterwards, when they would be all in church, we were quietly to attack the bastion called St. John's. This advice pleased us very much ; three companies with firearms were quietly told off, and a reward of fifty-six dollars promised to him who should first scale the wall. We prepared quickly our ladders, placed them against the wall, and managed to get up without being noticed. We found not more than eight natives, seven of whom were asleep ; the sentinel, it is true, was awake, but he was killed with the others before he had time to escape.

"Soon there was an alarm in the town, all bells were tolled, everybody was up and in arms and ran towards the bastion. The cannons were directed against us, and a strong fire kept up, so that we again had about three hundred dead and many wounded."

Before the Paper was read, some questions were put by the Members, which elicited interesting information. In reply to Mr. Fleming's inquiry as to what publications might this year be expected, the Secretary gave the satisfactory assurance that five or six volumes would be issued from the press during 1885. The Journal for 1883, which had been delayed through many causes, was now nearly ready, and the catalogue, by Dr. Trimen, of plants indigenous to or growing wild in Ceylon was being printed, and was promised by the end of February ; this would form an extra number of the Journal. During March, the Proceedings of 1884 would be printed, while April and May were to be devoted to the publication of the first part of the Journal of 1884 ; the whole of this number would be taken up by the studies of the Játakas, which were now being edited by the Bishop of Colombo. Mr. Parker's Paper on the Archæology of Tissamaharáma is to appear a month later, and is of itself to form a separate and most interesting number. A third instalment of the Journal, comprising the other Papers read during 1884, would be taken in hand later ; and if the funds of the Society would admit, a reprint of one of the back numbers, now out of print, would be undertaken. This assurance shows a most promising harvest, and if the Secretary is able to act up to his promises, the Members will have every reason to be well satisfied.

Mr. Bosanquet put a very pertinent question in asking for news as to the excavations being conducted by the Society at

Anurádhapura. The answer to this by the President was disappointing; nothing of real value was to be found. It has been found that no chapels existed on three sides of the Mirisvęti dágoba, and all that has been laid bare are the mouldings and plaster covering of the dágoba.

The President stated that Mr. Cull had recently paid a visit to Anurádhapura, and could, perhaps, give the Society some information.

Mr. Cull replied that very little had been done, the only interesting objects excavated being some inscribed stones round near what were supposed to have been the royal elephant stables, but which may turn out to be the remains of the Maha Viháre.

The President expressed his opinion that the object towards which the Society should strive in its archæological researches was the discovery of manuscripts, and he gave it as his belief that several of the ancient dágobas of Ceylon—notably the Abhayagiri dágoba, at Anurádhapura—were built for the express purpose of enshrining the sacred books of Buddhism. This belief had received an unexpected confirmation in Mr. Parker's researches at Tissa. He read a letter from Mr. Parker, in which he says:—

“I have been informed by several persons who saw it that a book of two gold leaves was found in the old relic-chamber at the top of the Maharáma here, and replaced in the new relic-chamber, which is now entirely covered up. It is said to have the leaves covered with writing, which resembles the characters on the inscribed bricks.”

There seems some fear now, from what Mr. Freüdenberg said in answer to a question by Mr. Berwick, that the translation of Prof. Virchow's Monograph on the Vęddás, which has been made for the Society through Mr. Freüdenberg's instrumentality, may be lost through a misunderstanding with the translator, an English lady, who has left Germany for America, and taken her manuscript with her. We trust, however, that Mr. Freüdenberg, in his next trip to Europe, will somehow contrive to bring the long-delayed translation with him on his return.

The Meeting terminated with a vote of thanks to Mr. Freüdenberg for his translation, and to Mr. Cull for the reading of it.

COMMITTEE MEETING.

17th February, 1885, 4.45 p.m., at the United Service Library.

Present :

The Hon. J. F. Dickson, M.A., C.M.G., President, in the Chair.

J. Capper, Esq.

W. P. Ranasinha, Esq.

J. L. Vanderstraaten, Esq.,

M.D.

W. E. Davidson, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of Committee Meeting of 19th December, 1884.

2.—Discussed memorandum circulated by the Honorary Secretary, suggesting a systematic division of the year into three sessions, one of which should be devoted to lectures of a popular character, so far as the topics chosen could be held to come within the scope of the Society's *raison d'être*. After some discussion, it was resolved that during June, July, September, and August, a series of lectures on the following topics should be delivered, if the gentlemen invited by the President and the Committee to deliver the lectures would kindly consent to do so:—

- (a) The Colombo Breakwater : its engineering features, by J. Kyle, Esq.
- (b) An account of the Structure and Resources of the Colombo Waterworks, by A. W. Burnett, Esq.
- (c) The Pearl Fisheries of Ceylon, by J. Donnan, Esq.
- (d) The Colombo Fort in the Portuguese, Dutch, and English Times, by J. Capper, Esq.
- (e) History of the Public Health of Ceylon, by W. R. Kynsey, Esq., F.C.M.O.
- (f) Food Products of Ceylon, by E. Elliott, Esq., C.C.S.

3. Discussed the range to which invitation should be limited to contribute to the *Jātaka* studies of the autumn sessions.

Resolved finally,—That the Bishop of Colombo should be requested to draw up a synopsis of work founded on that written by him last year, and that this be circulated by the Secretary to Members of the Society, and to students of Buddhism, among the scholars in various parts of India.

4. Attention was drawn by the Secretary to the want of co-operation and reciprocity in the exchange of publications of certain learned Societies.

Resolved,—That the Secretary do draw the attention of these Societies to the fact, and do request reciprocity in exchange.

GENERAL MEETING.

20th February, 1885, 8.30 p.m., at the Colombo Museum.

Present :

His Excellency the Hon. A. Hamilton Gordon, G.C.M.G.,
in the Chair.

The Hon. J. F. Dickson, M.A., C.M.G., President.

P. D. Anthonisz, Esq., M.D.	Ph. Freüdenberg, Esq.
T. Berwick, Esq.	S. Green, Esq., F.L.S.
W. J. S. Boake, Esq., C.C.S.	Hon. A. C. Lawrie.
H. Bois, Esq.	H. MacVicar, Esq., F.L.S.
Hon. R. A. Bosanquet.	F. H. Price, Esq., C.C.S.
J. Capper, Esq.	W. P. Ranasinha, Esq.
J. B. Cull, Esq., M.A.	Hon. F. R. Saunders.
A. M. Ferguson, Esq., C.M.G.	H. Van Cuylenburg, Esq.
J. Ferguson, Esq.	H. White, Esq., C.C.S.
W. Ferguson, Esq., F.L.S.	W. H. Wright, Esq.
Hon. F. Fleming.	

W. E. Davidson, Esq., C.C.S., Honorary Secretary.

Seven visitors introduced, and twelve ladies.

Business.

After the Minutes were read and passed, Dr. Trimen read a valuable Paper, of which the following is an abstract :—

*Remarks on the Composition, Geographical Affinities,
and Origin of the Ceylon Flora.*

The author commenced by remarking that the Systematic Catalogue of Ceylon Plants which he presented to the Society was as unsuited for reading as a dictionary, a concordance, or an index ; but he would accompany it by some general observations on the flora which it enumerates. The present catalogue includes about 3,250 species, of which the odd 250 may be reckoned to be ferns, and the 3,000 flowering plants or phanerogams.

Of these 3,000, he first called attention to those among them, 285 in all, which, though more or less wild plants, were not native, but aliens, colonists, denizens, or casual waifs and strays. There are numerous foreign fruit trees and many tropical weeds. The tendency of weeds from the New World to spread over the Eastern tropics was noted, and that of the weeds of Europe to colonise in temperate climates ; examples from these two classes were given. There remain 2,715 phanerogams in the native flora.

A comparison with some other areas of this globe, temperate and tropical, was made, and the conclusion arrived at, that,

though less so than was formerly supposed, the Ceylon flora was a rich one for its position, and probably more so than any equal area in India.

Taking as his text a remark of the late Mr. Bentham, that the chief interest of the vegetation of Ceylon would be found to lie in its relations with surrounding countries, the author commenced by an examination of these native species. The remarkably large proportion of *endemic* species, *i.e.*, species peculiar to the Island, viz., 786 (or 29 per cent.), was first remarked as probably larger than that of any other continental island, except Madagascar. Comparisons were made in this respect with other countries, from the British Isles with over 1,400 species and probably none endemic, to New Zealand with 72 per cent. peculiar, and the richness of true oceanic islands in this respect alluded to.

The views now generally held as to the causes of the present distribution of species over the world were briefly passed in review, and Ceylon was seen to have derived the bulk of its flora from Continental Peninsular India, only about 130 species (besides the endemic ones) not occurring there. The separation of the northernmost part of the Island from the mainland was shown to be geologically recent.

The subject of representative species of the same genera in different areas was illustrated by the case of the Ceylon mountains and the Nilgiris, only 400 miles apart. More than half of our mountain species are endemic, and not found in the Nilgiris, though nearly all the genera are identical; the flora may be said to be very similar and yet very different. Examples of different genera were given in illustration. The explanation of a common origin and evolution of new forms in time, under new surroundings, was accepted; more remote affinities in community of distant floras by common possession of natural families were pointed out.

Of endemic *genera* Ceylon only possesses 20, and these contain 48 species. Of the endemic species, all but about 73 are members of genera also represented in Peninsular India. But there are also in Ceylon species of genera, also not met within Peninsular India, identical with those of other countries. Many examples were given. In all, no less than 100 genera of flowering plants are represented in Ceylon which are not found in the peninsula. Nearly the whole of these are natives of the hot, wet districts of S.W. Ceylon; a very few are mountain types, but these are not endemic, though of interest as not occurring in the Nilgiris.

The affinity of these non-peninsular genera was shown to be in the great majority of cases *Malayan* (as opposed to *Indian*), including in the term not the Malay Peninsula and Archipalego, but the Andaman and Nicobar Islands, and the northward extension into East Bengal through Burmah. It was next pointed out that this *Malayan* type was also present in Southern India on the Malabar coast, where it is represented by either the same or

allied genera and species to those in Ceylon, but to a much less marked extent than here.

The question of how this flora reached S.W. India and Ceylon was next considered. Mr. Wallace's view of the elevation of the northern part of the Bay of Bengal, in Miocene and Pliocene times, when the Indian Peninsula was an island, was considered. The remarkable affinities of some genera of plants rather with Borneo and Java, than with the E. Bengal flora, led to the expectation that the former means of transit was rather at a lower latitude, at or near the equator, but there is no evidence of this available.

The author called attention to the Indo-Ceylonese region of zoologists characterised by a few endemic genera in the fauna. He pointed out that apart from the Malayan type, the flora did not give very clear evidence of any other element peculiar to these districts, but mentioned some endemic genera in both which were not especially Malayan in character. As for the other parts of Ceylon, at least four-fifths of the Island, all N. E. and N. W., presents almost precisely the floral characteristics of the Carnatic, the few endemic species being closely allied to those of that district of S. India. Perhaps one or two of our endemic genera are also members of this flora. With regard to the flora of the mountains of Ceylon and the Nilgiris, it is simply a southward extension of the Himalayan; there are no endemic genera through such a vast number of endemic species, and every genus is also Himalayan; there appears to be no Malayan admixture.

The few Mascarene and tropical African affinities in the flora were then discussed, and their existence held to show the probability of the passage across the Indian Ocean in past times, by the aid of the former large islands marked by the banks and coral reefs of the Carcados, Chagos, and Maldives. The latter land must have approached very near to Ceylon, and played doubtless an important part in the history of the formation of our flora.

Mr. Wm. Ferguson proposed a cordial vote of thanks, which was seconded by Dr. Vanderstraaten, who took the opportunity to dwell on the great value of Dr. Trimen's work in reference to the botany of the Island, and to urge Mr. W. Ferguson to publish some more of the results of his study of the local vegetation and natural history. The Governor then put and conveyed the vote of thanks, and closed the Meeting.

COMMITTEE MEETING.

18th June, 1885, 4 p.m., at the United Service Library.

Present ;

The Hon. J. F. Dickson, C.M.G., President, in the Chair.

W. R. Kynsey, Esq., P.C.M.O., Vice-President.

T. Berwick, Esq.

J. Capper, Esq.

D. W. Ferguson, Esq.

W. P. Ranasinha, Esq.

J. L. Vanderstraaten, Esq., M.D.

W. E. Davidson, Hon. Sec.

Business.

1.—Read Minutes of last Meeting, and confirmed them.

2.—Read correspondence with the Government of India relative to casts or photographs of sculptures illustrative of Buddhist history.

3.—Read letter from Government announcing that L. C. Wijesinha, Mudaliyár, has been seconded for special duty in completing the translation of the “Mahavanso,” and in revising that portion translated by the Hon. M. Turnour.

4.—Read letter from Government forwarding copy of Ordinance No. 1 of 1885.

5.—Read letter from Clough’s Dictionary Revision Committee.

6.—Read papers regarding certain inscriptions discovered and copied by Mr. Evan Byrde, C.C.S., at Mannár.

7.—The Honorary Secretary reported progress made as regards the Society’s publications since last Committee Meeting :—

Journal, 1883, Vol. VIII., No. 26, out.

Do. 1885, Vol. IX., No. 30, now ready.

Proceedings, 1884, in the press.

Journal, 1884, Part I., Vol. VIII., No. 27, in the press.

Do. 1884, Part II., No. 25, in preparation.

Do. 1885, Part III., Játakas, No. 29, in preparation.

The prospects of the ensuing sessions being discussed, the Honorary Secretary stated that the following Papers had been received :—

(a) An Account of the Kabragal Viharé, by E. R. Gunaratna, Atapattu Mudaliyár of Galle.

(b) A Description of Moorish Jewellery, by A. T. Shamshuddeen.

(c) An Account of the Wild or Rock Veddás, by C. J. R. Le Mesurier, C.C.S.

(d) Tamil Customs and Ceremonies in connection with Paddy Cultivation, by J. P. Lewis, M.A., C.C.S.

Papers due:—

The Jinæ Caritæ, translation by D. W. Ferguson.

The Food Supply of Ceylon, by E. Elliott, C.C.S.

Some notes from a Jungle Diary, by S. M. Burrows, M.A., C.C.S.

The Fort of Colombo, by J. Capper.

Plumbago, by A. M. Ferguson, C.M.G.

Papers promised:—

Caste in Ceylon, by C. J. R. Le Mesurier, C.C.S.

Translation of Van Schowter's Account of Ceylon, by Philip Freudenberg.

Public Health of Ceylon, by W. R. Kynsey, P.C.M.O.

8. Read correspondence with the Government of India relative to an application from this Society for plaster casts or photographs of those Buddhist sculptures at Bharhut, Yusufzai, and elsewhere which specially illustrate the Jâtaka or Birth-stories of Buddha, together with two series of photographs received.

Resolved,—That the cost of the photographs be remitted, with thanks for the trouble taken by the Governments in Calcutta and Lahore. Resolved, further, that a list of the photographs be recorded in the Proceedings, together with copies of the following reports from Major-General Cunningham and Dr. Anderson:—

Major-General A. Cunningham to the Secretary, C.B.A.S.

Camp Jhansi, 19th January, 1885.

SIR,—I HAVE the honour to acknowledge the receipt of your letter No. 6, dated 6th January, 1885, regarding the loan of casts and photograph of ancient Buddhist sculptures to the Ceylon Branch of the Royal Asiatic Society.

In reply, I beg to state that the principal collections of ancient Buddhist sculptures have been found at Bharhut in the Nagode State, and in the Yusufzai District of Peshawur, to the west of the Indus.

The Bharhut sculptures have been published in my work on the "Stûpa of Bharhut," which contains photographs of all the Jâtakas (of former births of Buddha) that were discovered. Some copies of this work were supplied to the Ceylon Government. The negatives are now in England. No casts of these sculptures have yet been made, so far as I am aware; but as the sculptures themselves are in the Indian Museum in Calcutta, it would be very easy to have a few casts made from them.

The Yusufzai sculptures have not yet been published. There are two large collections of these remains—one in the Lahore Museum and the other in the Indian Museum in Calcutta. Several casts in plaster-of-Paris have been made of the Lahore collection, by Mr. Vupling, and copies of these could no doubt be obtained on application to the Punjab Government.

There are also numerous photographs of the Yusufzai sculptures in the Lahore Museum, which belong to the Punjab Government.

Of the Yusufzai sculptures in the Indian Museum, a few casts have, I believe, been taken, copies of which could of course be obtained from the Trustees of the Indian Museum.

But I am very much afraid that there are but few of the Yusufzai sculptures that belong to the particular class of Játakas which the Ceylon Branch of the Royal Asiatic Society is specially anxious to obtain, and there are certainly no casts of them. The only examples that I can remember were the Wessantara and Dasaratha Játakas on the risers of a flight of steps—and both of these are now in the British Museum.

I have, &c.,

A. CUNNINGHAM, Major-General,
Director-General Archæological Survey.

*The Under-Secretary to the Government of India to the
Superintendent of the Indian Museum.*

No. 17.

Calcutta, 7th February, 1885.

SIR,—I AM directed to forward a copy of the communications below noted* relative to an application made by the Royal Asiatic Society, Ceylon Branch, for the loan of any duplicate plaster casts or photographs illustrative of Buddhistic history.

2. The Governor-General in Council would be glad to know how far the authorities of the Indian Museum could make arrangements to comply with this request, or what help could be provided by them in the matter.

I am, &c.,

F. C. DANKER,
Under-Secretary to the Government of India.

*The Superintendent of the Indian Museum to the Under-
Secretary to the Government of India.*

No. 101.

Calcutta, 9th February, 1885.

SIR,—IN reply to your letter No. 17, dated the 7th instant, I have the honour to inform you that there are no duplicate plaster casts in this Museum illustrative of Buddhist history. Moreover, General Cunningham, in his letter to you, No. 253, dated the 19th January last, is in error in saying that any casts have been taken from the Yusufzai sculptures in the possession of this Museum.

* From the Colonial Secretary, Ceylon, No. 28, of the 11th December, 1884, and enclosures. From the Director-General of the Archæological Survey of India, No. 253, of the 19th January, 1885.

If casts are wished, there will be no difficulty in making them, with the assistance of the Calcutta School of Art, but the undertaking will be a costly one. I can, however, supply photographs illustrative of Buddhist history, subject to the sanction of the Director-General of the Archaeological Survey of India. The photographs to which I refer are those illustrative of the Buddhist sculptures from Bharhut and those from Yusufzai; and General Cunningham has fallen into a mistake in saying that the negatives of the Bharhut Stûpa are now in England, as they are under the custody of the Trustees, along with those of the Yusufzai sculptures. All these negatives, and a very large series of others from different parts of India, were made over to the Trustees by the Archaeological Survey of India, for safety, and on the understanding that no prints were to be taken from the negatives until the sanction of the Survey had been obtained beforehand. The Trustees of the Museum, however, addressed General Cunningham on the 24th of last month on this subject, asking whether he had any objection to prints from the Bharhut and Yusufzai negatives being supplied to the Ceylon Branch of the Royal Asiatic Society, and as I do not suppose there will be any objections, I would suggest that the Society be informed that there are 24 pictures of the Bharhut Stûpa containing Jâtakas, and that these could be printed for about eight annas each; and there are 27 of the Yusufzai or Gandhara sculptures, which might yield Jâtakas, and which could be printed at the same rate. If the Society sanctions the expenditure the printing could be gone on with at once.

I am, &c.,

JOHN ANDERSON,
Superintendent.

List of Photographs for the Royal Asiatic Society (Ceylon Branch).

GĀNDHĀRA.

Jamāl Gashi.

- | | |
|--|---|
| <p>A 5 Various religious scenes
6 Four-horse chariot, and religious scenes
7 Various religious scenes
80 Do. do.
9 Two chapels, with sculptures
10 Birth of Buddha
11 Buddha leaving his father's palace, &c.
12 Various religious scenes
13 Buddha waylaid by club-men
15 Domestic scenes—lady tubbing her child—lady at toilet, &c.
21 Nos. XIV., II., and IX., steps of Stūpa staircase
22 Nos. V., VIII., VI., and VII., ditto</p> | <p>23 Nos. XVI., IV., X., and XII., steps of Stūpa staircase
29 Rows of friezes, with figures in panels
30 Four-horse chariot, and religious scenes
31 Various religious scenes
32 Do. do.
33 Do. do.
34 Buddha waylaid by club-men, &c.
35 Various sculptures
36 Rows of winged figures
37 Birth of Buddha
38 Large chapel scenes
39 Two chapels
46 Risers of flight of steps
47 Do. do.</p> |
|--|---|

Bharhut.

- | | |
|---|--|
| <p>F 6 Ruined temple of Kannu Makhar
7 Outside views of E. gate of Stūpa
8 Inside of do. do.
9 Detail of pillar, E. gateway
11 Toran beam sculptures, and fragments
13 Sculptured pillar, monkey scene
14 Sculptured pillar, Jetavana scene
15 Sculptured pillar, deer scene
16 Fragment of end pillar, S. gateway
19 S.-W. quadrant, monkey and elephant
20 Part of S.-W. quadrant, with soldier</p> | <p>21 Corner pillar of W. gate
22 Ladder scene, corner pillar W. gate
23 Corner pillar W. gate, second face
24 Upper scene of corner pillar
25 Elephant scene of corner pillar W. gate
26 N.-E. quadrant pillar, Maya devi
27 Coping of S.-E. quadrant
28 Do. do.
29 Do. do.
30 Fragments of coping of S. gateway
31 Copings of S. gateway
32 Copings of S.-W. quadrant
33 Copings of N.-E. quadrant</p> |
|---|--|

H. B. MEDLICOTT,
Honorary Secretary.

GENERAL MEETING.

11th August, 1885, 9 p.m., Reading Room of the Museum.

Present :

The Hon. W. H. Ravenscroft, in the Chair.

Hon. R. A. Bosanquet.
A. M. Ferguson, Esq., C.M.G.
T. Berwick, Esq.
W. J. S. Boake, Esq., C.C.S.
J. Capper, Esq.
J. B. Cull, Esq., M.A.
A. R. Dawson, Esq., C.C.S.
J. G. Dean, Esq.
A. M. Ferguson, Esq., junior.
J. Ferguson, Esq.

D. A. Ferguson, Esq.
H. W. Green, Esq., C.C.S.
J. J. Grinlinton, Esq.
Hon. P. Ráma-Náthan.
R. W. Ievers, Esq., C.C.S.
L. O. Pyemont-Pyemont,
Esq., C.C.S.
W. P. Ranasingha, Esq.
J. G. Wardrop, Esq.
W. H. Wright, Esq.

W. E. Davidson, Esq., Hon. Secretary.

One visitor, and five ladies.

Business.

- 1.—Read and confirmed the Minutes of last General Meeting.
- 2.—The Secretary laid on the table List of Books received since last General Meeting.
- 3.—The following gentlemen were then proposed and seconded, and elected as Members of the Society :—

Mr. T. Alexander, Forester N.-C.P., Anurádhapura.
Mr. A. W. Cave, M.A., Colombo.
Mr. P. De Saram, Colombo.
Mr. W. Wrightson, F.W.D., Anurádhapura.

4.—The President, before introducing the Paper of the evening, made a feeling allusion to the loss the Society had sustained in the untimely death of Mr. Haliburton MacVicar, whose ornithological knowledge had often been of much value to the Society, and who was known to many of the Members as an intimate personal friend.

Mr. Elliott, after deprecating the pessimist views regarding paddy cultivation to which publicity had been recently given, stated that inquiries made by him gave such favourable results as to encourage the belief that paddy can be grown locally cheaper than it can be imported.

Reviewing the information regarding India, he finds that 30 to 40 bushels per acre is the general return.

As regards Ceylon, Mr. Elliott gave a detailed account of the modes of cultivation in the Má tara and Batticaloa Districts. The expenses of cultivation per acre he finds to be : in Má tara, 36 days'

labour of a man, and an outlay of 4 bushels of paddy; in Batticaloa, for munnari, 38 days' labour of a man and 8 bushels of paddy, for malamellama, 18 days' labour of a man and 10 bushels of paddy.

After giving some instances of exceptional crops in favourable localities, he stated that he considered 25 bushels as a fair average return from irrigated land.

With such a return, the average cost of raising a bushel of paddy ranges from $1\frac{1}{2}$ to $2\frac{1}{2}$ days' labour, while a return of 30 bushels reduces the cost from 1 to $1\frac{1}{2}$ days' labour. But as all these estimates are based on outside rates of expenditure, he considers it may be fairly assumed "a day's labour produces a bushel of paddy."

Cents 25 is an outside value of labour in the rice-producing districts. Mr. Elliott is of opinion the enemies of paddy are few, and can be easily combated. The Paper also gave particulars of cost of transport from the producing Districts—Batticaloa to the market at Jaffna. This amounts to 25 cents as cost of production, and transport 50 cents, and the paddy can generally be sold for Rs. 1.25.

The Hon. P. Ráma-Náthan opened the discussion by stating that the question Mr. Elliott had set himself to solve was whether Ceylon could grow rice so as to under-sell the Indian article in the local market, and he had not only answered that question in the affirmative, but had shown a profit of 75 per cent. for the cultivation. This was for the Málara and Batticaloa Districts, where Mr. Elliott had spoken of crops as high as 35 to 70 bushels per acre. Mr. Elliott had worked out the cost of cultivation, and put it at Rs. 13 per acre. Now, there was a very great diversity of opinion on these subjects, more particularly as to the yield of rice in crop, and this was shown by the report of the Irrigation and Paddy Commission of 1867,—on which were Sir R. Morgan, Col. Evers, Messrs. Parsons, Alwis, Wise, &c.,—who said, among other things:—

- The Committee have had under their consideration the returns of the quantity of paddy produced in the various Districts of the Island; these data show that the supposed average yield of ten-fold is rarely obtained, the produce usually ranging from three or four-fold to about eight-fold, whilst in other Eastern countries the return ranges between twenty and fifty-fold. The return in Ceylon during former periods was seventeen-and-a-half-fold, according to the inscription on the Polonnáruwa tablet, quoted in a preceding page, where the tenth is stated to be one amunam and three pélas. According to the information thus collected, it would appear that the yield per acre, instead of being as usually supposed thirty bushels, is not more than half that quantity.

The evidence on which this report was based was of the most varied and even contradictory character, and here Mr. Ráma-Náthan read several extracts showing how native cultivators gave such returns as 24, 36, and 9 bushels as the crop of paddy per acre. His own opinion on the subject was that the average yield for the Island was between 20 and 25 bushels. As regards

the cost of production, he thought Mr. Elliott had left out certain charges, such as the wear and tear of implements and tools, which he would put at Rs. 2 an acre, and interest Rs. 3, bringing the total up to Rs. 18 per acre, against a return of 20 to 25 bushels of paddy valued at Re. 1 each, leaving a margin of from Rs. 2 to Rs. 7 per acre. This he would compare with the return from cocoanuts, which was at least Rs. $37\frac{1}{2}$ per acre, or from cinnamon even—or perhaps tea. (Applause.)

Mr. J. Ferguson said that all who had studied this question were accustomed to take their start from the report of Sir Hercules Robinson's Commission already quoted, in which, after making inquiries and receiving evidence from all parts of the Island, it was stated that the average yield of paddy in Ceylon was nearer 15 than 20 bushels per acre, the range being four to eight-fold against twenty to fifty-fold for other favourite Eastern rice-growing regions. Mr. Elliott had undoubtedly brought together much valuable information respecting the yield and cost of rice in India, but he could not help thinking that, as regards the rich alluvial lands of the Gangetic valley, and of Burmah especially, the returns were under-rated. He had seen an official statement that the average for the rice-fields of Burmah was forty-fold, which would mean 40 bushels per acre according to their way of sowing, and Mr. Hallett, the co-traveller of Mr. Colquhoun, had stated in respect of the Shan country, north-east of Burmah, that the people told him in one large district that they got back 250 times what they put in of paddy. The latest Administration Report on British Burmah stated that there were four million acres under paddy, and that 100,000 acres were added to the cultivation yearly, the annual export of rice having risen to a value of £6,000,000 sterling. The estimate for all India was sixty million acres under rice. Looking at the matter broadly, therefore, he did not think any one could say that Ceylon could be put in comparison as a rice-growing country with Burmah or Bengal. But Mr. Elliott had confined his Paper to certain favoured Districts, and he (Mr. Ferguson) did not think any one had ever disputed the advantage of irrigation works and rice cultivation in Mátara and Batticaloa. At the Royal Colonial Institute he had carefully guarded himself by saying that where the land was suitable for rice-growing in Ceylon, and irrigation could be profitably applied for a resident population ready to take advantage of it, the unofficial public had uniformly supported the Government in such expenditure. He had then the Mátara and Batticaloa Districts specially in view. Further, he could add to Mr. Elliott's instances of very heavy crops in exceptional cases in Ceylon, from the authority of the intelligent Kachchéri Mudaliyár of the North-Western Province (Mr. S. Jayatileke), who had told him that on the banks of the Maha and Deduru-oyas, after floods with favourable weather, there are fields which give a return of 100 bushels per acre, and others 40 and 50 bushels. But such cases were entirely exceptional, and although he believed Mr. Elliott's Paper to be

a generally correct and most valuable account of grain cultivation in the Mátara and Batticaloa Districts, yet it was very difficult to reconcile it in some parts with other official statements. For instance, it was his (the speaker's) duty—a painful one rather—to study very closely year by year the Government Blue Books and Administration Reports. Now, while in the case of Mátara the grain statistics showed good progress, and the rate of yield was very steady at an average of 16 to 17 bushels per acre, in the favourite Batticaloa District the case was very different. The maximum of over a million bushels of crop was reached in 1870, with an average yield of 24 bushels per acre; that rate had gone down in 1877 to 17 bushels; in 1883 to 12; and last year the Blue Book figures positively only showed a return of 6 bushels per acre. (A laugh.) So again with the total production of the Island, our maximum seemed to have been reached in 1880; since then there had been a heavy falling off in the local crops. Now they all knew the disrepute attaching to Blue Book returns so far as agriculture was concerned, but if there was one District more than another from which they ought to have correct reports, it was surely Batticaloa, with its steady industry and supervised irrigation. However, passing over that and taking Mr. Elliott's own average of a return of 25 bushels per acre, produced at a cost of $37\frac{1}{2}$ cents per bushel, leaving a profit of 75 cents, or (leaving out carriage) let them say 50 cents per bushel, what was the net result? Only Rs. 12·50 per acre, while, as Mr. Ráma-Náthan had mentioned, cocoanut (or he might add areca-palm) cultivation gave the natives a net return not under Rs. $37\frac{1}{2}$ per acre. Again, Mr. Elliott had almost provoked a comparison with tea, which he (the speaker) thought the Government ought to encourage the Sinhalese villagers to cultivate around their huts and in their gardens after the fashion of the Chinese. A bushel of paddy, according to Mr. Elliott, and a pound of tea could be produced for nearly the same cost in Ceylon—the one being worth 75 to 100 cents, the other say 50 to 60 cents on the spot. But then, even with native cultivation and management, the cropping of the tea might safely be taken at 300 lb. an acre, and with a profit of 20 cents a pound that would be equal to Rs. 60 per acre, against the Rs. 12·50 for rice, so leaving a wide margin in favour of tea. Confining attention, however, to the old products, and looking at the country as a whole, in what direction did the people display most enterprise? In Burmah, without, he believed, any special stimulus from Government or irrigation works, there were about 100,000 acres added yearly to the rice-cultivated area. In Ceylon, 20 to 30 years ago, to take one instance, there was probably not a single cocoanut patch between Negombo along the Maha-oya towards Polgahawela; now it was almost a continuous expanse of that palm, and there were unbroken fields of as many as 5,000 acres. He was not aware that the Ceylon Government had done anything to stimulate this industry by even a single report on the subject, save that the land was surveyed and put up

for sale; but look at the result. Our exports now of cocoanut oil are between four and five times what they were 30 years ago; of coir stuffs we send three times as much away; copperah four times; nuts, poonac, &c., in proportion—and all this from what may be said to be a purely native industry. (Hear, hear.) Here then, at least for the Western and South-Western Districts, we have the most profitable investment for native enterprise. But he would not for a moment allege that there were not other Districts, and notably Mátara and Batticaloa, where rice is best fitted for native occupation, and where the Government might well do all they can to extend its culture, seeing the margin of profit is wide enough to satisfy the cultivator after paying for his rent and water-supply. One thing Mr. Elliott had made clear, that the so-called water-rate, considering the certainty brought by irrigation, was most moderate, and the Government levy in Ceylon was far less than in India, where, as Mr. Elphinstone told the speaker, only a few days ago he found the people at Trichinopoly gladly paying at the rate of Rs. 9 per acre for water privileges. In conclusion, he would only say that the wants and capabilities of each District and its people in the Island must be judged by Government on their own merits, and while he cordially agreed with much that Mr. Elliott had said about Mátara and Batticaloa, Government ought not, in other Districts at least, to forget that there were other industries worthy of direct encouragement besides rice-growing. (Applause.)

Mr. Berwick thought that the discussion had travelled a good deal beyond the limits observed by the writer of the valuable Paper to which they had listened with so much interest. That Paper had to do with rice cultivation solely in the Mátara and Batticaloa Districts, and he had not risen so much to discuss its merits as to gain information on certain points which puzzled him. He wished especially to know whether any account had been taken of the large original outlay of public money on the irrigation works in the Districts referred to. Had Mr. Elliott taken this heavy item into his reckoning? As regards the gentleman (Mr. Ráma-Náthan) who apparently would wish to stop the cultivation of paddy (No, no! from Mr. Ráma-Náthan), he would like to know if he had considered what the effect would be on the cost to us of imported rice if there were not a large local production to act as a check. (Hear, hear.)

Mr. A. M. Ferguson remarked that Mr. Elliott, by his very interesting and useful Paper, had proved himself doubly qualified, by national origin and acquired experience, to treat of the subject of *paddy*. (A laugh.) The facts he had stated with reference to the Districts of Mátara and Batticaloa showed that good results could be obtained from rice culture in Ceylon, where a steady supply of irrigation water had been provided. But still better results could be obtained, if only the natives under good and scientific advice sowed one bushel of seed to an acre instead of two, germinating the seeds in nurseries and putting out the plants

in the fields in drills, as was done in India and more especially in Java, where he had been delighted to see the careful and scientific mode of cultivation adopted by the peasantry. Another great improvement in the culture of rice in Ceylon would be the teaching of the natives to be less extravagant in the use of water. They flooded their fields instead of irrigating them, thus converting what was intended to be a semi-aquatic plant into one wholly aquatic, its produce being less in quantity and deficient in nutritious properties in proportion to the waste of water. We in Ceylon, with our poorer soil, could not compete with the fat alluvials of India and Burmah, but Mr. Elliott had shown that rice culture in the Island was susceptible of great improvement, and could be so conducted as to be remunerative to the natives. But Mr. John Ferguson's figures, showing apparent decadence instead of progress in production in the specially-favoured District of Batticaloa, were so bewildering, that, however sorry he might be to say such a thing in the presence of the honourable gentleman who occupied the chair (Mr. Ravenscroft), he was compelled to regard the question as one of utterly unreliable Blue Book statistics. (Laughter.)

Mr. J. Capper said it should not be forgotten that nearly all the rice locally produced was required by the cultivators for themselves and their families—very little was thrown into the markets for sale. The Commission of 1867 had to deal with the returns for the Island generally in giving their low estimate of production, but there had never been any doubt that under irrigation the cultivation of rice would pay and yield handsome returns. As regards the Blue Books, the figures were indeed a mystery, for in addition to what had been said about Batticaloa, he might mention that the Kurunégala District now showed the heaviest yield—some 26 bushels per acre—in the country, and Badulla 21 bushels, against $6\frac{1}{2}$ bushels for Batticaloa. (A laugh.)

Mr. A. R. Dawson, C.C.S., could not with so much confidence speak of Batticaloa, but as regards Mátara he could with certainty say—notwithstanding any contradiction in the Blue Book returns—that the production of rice had been steadily progressive, and he would recommend Mr. Ferguson, when in doubt as to the crops, to turn from the Blue Book agricultural tables to the Revenue returns, which were a sure index to the amount and value of the crops. In the case of Mátara, the revenue from grain had greatly increased since the irrigation works were completed. As regards Batticaloa, the system which had prevailed there of selling the rents was a very uncertain, unreliable one, and could not fail to lead to much uncertainty as regards the produce returns; but this would all be rectified by the work of the Grain Commission. In reply to Mr. Berwick's inquiry, he would state that in some cases the expenditure on irrigation works had been repaid by the cultivators benefited in a certain number of annual payments, in others by the addition of a rupee per acre to the rent, in perpetuity. He hoped that the Paper now read would be the

precursor of others equally instructive on the food supply of the country, and the various topics connected therewith. (Hear, hear.)

Mr. J. Ferguson explained that he had not criticised the Mátara crop returns, but only those of Batticaloa. He thought that with the Colonial Secretary in the chair, and so many rising Revenue Officers in the room, they ought to urge the necessity for greater attention in sending in Blue Book returns; the Government Agents ought to compare their revenue and crop statements year by year, and afford in notes needful explanations, or their own opinions on the produce figures where large discrepancies occurred. (Hear, hear.)

Mr. R. W. Ievers, C.C.S., rose to mention, with reference to Mr. Ferguson's statement about Burmah, that in a book he was reading the other day, written by a traveller in that country, it was distinctly stated that he had learned from the people their return of crops was from 10 to 25-fold. (Mr. J. Ferguson—I referred to British, not native, Burmah.) He could not see that the country could differ so much as to allow of a return in another direction of 250-fold, as had been stated.

Mr. H. W. Green, Director of Public Instruction: I worked out the returns from rice cultivation in Burmah not long ago in company with a friend, and we found as the result that the crops were equal to 70 and 150-fold. (Laughter.)

Mr. Elliott, in reply on the discussion, pointed out that it had gone over wider ground than he had covered in his Paper; indeed, had extended to the whole question of paddy-growing throughout the Island, whereas he had restricted his Paper to rice cultivation under irrigation, and to what was being done without entering on the question of what might be secured by improved cultivation. He had in his time advised a large expenditure in the Mátara District on irrigation, and now that he could adduce actual results, he was naturally anxious to vindicate the correctness of the views he had so long held. In reply to Mr. Ráma-Náthan's objections, he pointed out he had given the details of cultivation in his statement, and had provided for tools, allowing in grain one amunam of paddy, or at the rate of $7\frac{1}{2}$ bushels for 25 acres. Mr. Crowther had allowed 50 per cent. more, but his total expenses were under Mr. Elliott's. In Mátara he had allowed one bushel for $2\frac{1}{2}$ acres, which he believed was sufficient. As regards the quantity of paddy sown in an acre of land, $2\frac{1}{2}$ bushels to the acre had been long recognised and acted on as the proper equivalent in the Indian district. Mr. Ludovici also speaks of the usual paddy sowing basis as $2\frac{1}{2}$ acres to the amunam of six bushels. In the Batticaloa District the figures varied from two to four bushels, and he had taken three as a fair average. However, this difference but little affected the results. Again, as regards *wheat*, it was difficult to know what rate to fix and what value to place on the land. The lowest rate for money loans in Batticaloa was $16\frac{2}{3}$ per cent., and on loans of grain 50 per cent. in kind. In view of this, Mr. Elliott had only gone into the actual expenditure

on the land in raising the crop, such as a superintendent would have to disburse, leaving what might be called the "Colombo charges" to be added according to the circumstances of each case. Still, accepting Mr. Ráma-Náthan's figure of 20 bushels produce per acre, and an outlay including interest of Rs. 16, he pointed out that paddy would only cost 80 cents a bushel against 96, the Madras value, and Rs. 1.50 the usual selling price of India paddy in Ceylon. As regards water-rate, Mr. Elliott had allowed for this in the case of Mátara, where it was a charge (of Rs. 1.50) in perpetuity. In Batticaloa it was all paid off in ten years, and would be properly chargeable to the capital cost of the land. Against the low rates of yield quoted by Mr. Ráma-Náthan, Mr. Elliott gave some other instances of returns in excess of those on which he depended, which had been committed to him, one of 60-fold at Vavuniya-Viláṅkulam. He also quoted one from the same report as Mr. Ráma-Náthan had of a return of 150 amunams, or 1,125 bushels, from 40 acres, or 28 bushels the acre from land in Batticaloa. As regards the gentleman who had quoted Blue Book statistics,—which were admittedly untrustworthy, in spite of spasmodic attempts of individual officers,—to make them more correct, he reminded his hearers that, out of some 70,000 acres of paddy land in the Batticaloa District, only 36,000 were affected by the expenditure on irrigation, and some of this area was still imperfectly irrigated and requires further subsidiary works. He (Mr. Elliott) had always advocated irrigation where there was a nucleus of a population. In Batticaloa, where irrigation had been begun, it was about 70,000, and it was now over 109,000. He believed that there was room to make other Batticaloas and Mátaras in the Island, especially in that part stretching from the Giant's Tank to Elephant Pass, to which he believed the surplus population of the Jaffna Peninsula would flock if the water-supply could be made secure. In reply to Mr. Capper's query as to the development of rice cultivation in Batticaloa, Mr. Elliott gave the following figures:—

		Area actually Cultivated.			Land Revenue.
		Acres.			Rs.
1856	...	22,655	...		23,906
1866	...	41,380	...		37,157
1876	...	59,730	...		77,060
1883	...	58,916	...		60,757

The general revenue had increased from £6,071 in 1848 to only £7,315 in 1857, about which time irrigation had been commenced in Batticaloa. It then went up to £10,787 in 1858, and £16,855 in 1861 (but this included £6,872 from land sales). In 1865 it was £14,840, £21,000 in 1867, and £31,000 in 1883 (including only £1,382 from land sales). The revenue from the arrack farms had risen from £680 in 1867 to £2,038 in 1867, and £3,402 in 1883. Stamps gave £2,283 in 1883, against £1,020 in 1858.

Before separating Mr. Rāma-Nāthan wished to correct Mr. Berwick in the thought that he was opposed to paddy cultivation, or arguing against it—nothing could be further from his thoughts.

Mr. Berwick moved a vote of thanks to Mr. Elliott for his timely and valuable Paper, on one of the most important subjects which could occupy their attention ; and this was seconded by the Hon. R. A. Bosanquet, who said he had regularly attended their Meetings in the hope of gaining information, but that this was the first occasion he could remember on which he really felt he had been instructed and was going away wiser than he came. (Laughter.) He hoped similar discussions of practical value would frequently occur. The vote was carried by acclamation.

In replying to the vote of thanks, Mr. Elliott expressed his belief in the permanency of paddy cultivation. Rice had been grown on the same lands for over one hundred years, and the crops did not seem to be affected by those general adverse influences of nature which had so severely tried other branches of agriculture in Ceylon.

The Meeting separated about 11 P.M.

GENERAL MEETING.

28th August, 1885, 9 p.m., at the Colombo Museum.

Present :

T. Berwick, Esq., in the Chair.

P. D. Anthonisz, Esq., M.D.
W. J. S. Boake, Esq., C.C.S.
Hon. R. A. Bosanquet.
A. R. Dawson, Esq., C.C.S.
P. De Saram, Esq.
A. M. Ferguson, Esq., C.M.G.
A. M. Ferguson, Esq., junior.

J. Ferguson, Esq.
H. W. Green, Esq., C.C.S.
S. Green, Esq., F.L.S.
J. J. Grinlinton, Esq.
W. P. Ranasinha, Esq.
A. T. Shamsuddeen, Esq.

W. E. Davidson, Esq., C.C.S., Honorary Secretary.

Seven ladies present, and four visitors introduced.

Business.

- 1.—Read and confirmed Minutes of last General Meeting.
- 2.—Captain H. Morgan, R.E., was elected a Member.
- 3.—Mr. A. M. Ferguson then proceeded to read portions of his Paper, of which the following is a summary :—

Plumbago : With special reference to the position occupied by the mineral in the commerce of Ceylon ; and the question discussed of the alleged existence in the Island of the allied substance, Anthracite.

On the tables were various objects to illustrate the Paper, viz., a dāgoba formed of lumps of plumbago, samples of dust, chips, and lumps, pieces of rock showing iron pyrites, mica, &c., some fine crystals, a series of crucibles presented to the Museum by the Battersea Crucible Co., and two elephants cut out of plumbago.

Mr. Ferguson commenced by stating that the mineral of which his Paper treated was a form of carbon, the substance which constitutes so large a portion of organised nature, more especially of the vegetable world. Graphite was in truth vegetable matter mineralised by those various forces of moisture, heat, friction, pressure, and electricity or magnetism, which have so marvelously metamorphosed the primitive rocks in which the mineral is generally, if not exclusively, found. In Geikie's "Handbook of Geology," graphite is mentioned first in the list of rock-forming minerals, sulphur and iron following, before silica in its protean forms is specified. In a more or less definitely crystallised, foliated, columnar, needle-like, or massive shape, the mineral embodies the altered remains of some of the earliest plant-forms which appeared on the earth, when the fiat was uttered in the far back ages of creation, "Let the earth put forth grass, herb, yielding seed, and fruit-tree bearing fruit." Those of the audience who entertained a vivid recollection of the fascinating Paper by Dr. Trimen on the flora of Ceylon, recently read in that hall, could imagine the delight it would afford that eminent naturalist, and thousands of other scientists, could the brilliant steel-gray to jet-black ore they were considering reveal the secrets of its vegetable origin, and show the fibres, the leaves, the flowers, and fruit of the earliest herbage of the morning of the times, from which it has been transformed, in like manner as ordinary coal also generally speaks of the early days of the geologic ages. But graphite (so called from its earliest use in the formation of pencils for writing and sketching), which there can be little doubt is closely allied to coal, although generally older in origin, and the subject of more intense and long-continued metamorphic influence than the carbonaceous substance so valuable as fuel, is too highly mineralised (with the exception, perhaps, of the formations in Canada) to display a trace of the vegetable tissues from which it claims its descent.

To the seeker for fossil remains of ancient organic life, therefore, graphite, like our other primitive rocks, gneiss and crystalline limestone, is less interesting than are the coal measures, with their wonderfully preserved specimens of plants and animals and shells, on which human eye probably never looked until the operations of the toiling miner revealed their, in some cases, almost perfect lineament. Graphite seems, in truth, to be the most highly crystallised form of carbon next to the peerless diamond, which poetically, if not with perfect scientific accuracy, has been described as a drop of pure liquid carbon crystallised. Graphite (to which, when burnt, the diamond reverts) has a beauty of its own, and as small diamonds have actually been formed by artificial

means, the time may possibly arrive when the form of carbon which mineralogists rank only next below the diamond, may, by means of the appliances of progressive science, be advanced from the second to the first place. Let us only attempt to imagine a mass of pure graphite equal to a quarter of a ton, such as that sent to Melbourne in 1880, and the still larger mass which will probably figure in the Court of the Colonial and Indian Exhibition of 1886, metamorphosed into diamond "of purest ray serene," and try to conceive the thing of beauty it would be, even if shrinkage in the transformation process reduced its size to one-tenth or even one-hundredth of the original bulk. Meantime, it seems curious that Ceylon, so rich in "precious stones," which, with all their brilliancy are simply crystallised and coloured clays, should be utterly destitute of specimens of the king of all gems, seeing that diamonds are found close by us in Southern India, and in formations similar to those existing here: laterite, occasionally, and especially in association with corundum, which in Ceylon is so common and of which our most precious sapphires and rubies are but higher forms.

The Paper then stated that of more value to Ceylon economically, beyond all comparison, would be the real discovery amidst its rocks of that form of carbon which ranks next to the diamond and graphite, and which seems to be graphite and perhaps diamond in a less altered form. It need scarcely be said that coal is referred to.

The authority of the late Dr. Gardner, formerly of the Royal Botanic Gardens, Péradeniya, the late Rev. Dr. MacVicar, and Dr. William King, of the Indian Geological Survey, was quoted, to show the improbability of the existence of coal, where, as with us, primitive rock formed the surface strata, and the reader proceeded to discuss fully and to show the utter baselessness of statements made by Dr. Gyax, a Swiss mineralogist, and endorsed by Tennent, to the effect that, in addition to millions of tons of iron which could be laid down in Colombo at £6 a ton, anthracite, in association with plumbago and basaltic rock, was equally abundant, and could be laid down in Colombo at 18s. per ton, after cost of digging and conveyance from Sabaragamuwa. If Gyax and Tennent considered the alleged discovery of anthracite important with reference to steam navigation in 1848, how much more important would such a discovery be now, when the powerful but odourless and smokeless heat, which the form of coal called anthracite yields, would be just what is wanted by our expanding tea industry, while as regards the requirements of steamers, it need only be mentioned that between 1880—when Colombo Harbour first afforded moorings for steamers—and 1884, the imports of coal into Ceylon had gone up from 80,000 to nearly 200,000 tons, the average value being over Rs. 20 per ton. But while bituminous coal was found in India, anthracite did not exist there, the nearest approach to it being crushed coal near Darjiling, which had been converted into semi-graphite. But while

dogmatism was deprecated, entire scepticism was expressed as to the existence in Ceylon of anything more closely resembling coal than the peaty matter found, amongst other places, at Nuwara Eliya, and which, compressed and dried, might be useful as a fuel. What seemed beyond question certain, was that neither Dr. Gygax nor any other human being had ever seen anthracite in our gneiss rocks, and as to the alleged discovery of the mineral in enormous quantities, Mr. Ferguson said, in the history of scientific exploration and report, and of colonial history and progress, there seems to be no greater fiasco.

A curious circumstance in connection with the alleged existence of anthracite in Ceylon was mentioned. The late Mr. John Armitage, a well known and enterprising merchant, saw in the British Museum a specimen of fine iridescent anthracite, labelled as from Sabaragamuwa, Ceylon. It was said to be from the collection of a Colonel Greville, a name not prominent in the annals of Ceylon, and Mr. Ferguson added :—To show how confusion may arise, I need merely mention that through the dropping of a comma, plumbago is represented in successive works, including the "Encyclopædia Britannica," as found in "Travancore Ceylon," as if the localities were one. There is the case of *columba* root, too, which received that name because ships touching last at Colombo brought the bitter root to Europe from India. But the crowning absurdity was that the Emigration Commissioners, who had in 1846 the ordering of such matters, instead of saying to Messrs. Armitage and Tindall, "We will refer to the Governor of the colony for information," or, "You go and prospect, and let us know what you find and under what circumstances, make your offers, and we will consider them," jumped instantly to the conclusion that anthracite of such quality, in such plenty, and in such circumstances of cheap acquirement, existed in Ceylon that forty per cent. would be a fair royalty to charge! There the matter ended, until Gygax's alleged discovery was announced, two years subsequently. It seems just possible that in both cases the supposed anthracite was the rocky hard form of plumbago, which the natives call *yabora*, or iron dross. It was suggested that finally to set at rest the question of what minerals or metals might and might not be expected to occur in our Ceylon formations, the Asiatic Society should press on Government the propriety of asking for the loan of the services of a competent geologist, like Dr. William King of the Indian Geological Survey, who, with his experience acquired in India, could pronounce on all important points in a period of time probably not extending beyond a year.

Passing over much detail of a more or less interesting character, we quote as follows :—

、 But if the diamond, amber, coal, and petroleum are absent from our rock formations, happily there can be no question as to either the quality or the quantity of our mineral carbon in the shape of plumbago, of which indeed, in the form most valuable for the manufacture of metal-melting crucibles, Ceylon seems to have as

much a natural monopoly as she has of first-class cinnamon in the vegetable world. There are, no doubt, vast deposits of graphite in North America, especially in Canada, but the mineral seems to be generally diffused in rock from which it is difficult and expensive (labour being scarce and dear) to separate the small particles. Graphite, although rare in a form economically valuable, seems very widely distributed over the face of the earth. In India, plumbago has been found in a large number of places, and has been the subject of many experiments and much discussion, but the results have been hitherto disappointing. It generally appears sparingly in very quartzzy rock, and in heavy ferruginous gneiss. The mineral is deficient in lustre, contains much iron, and one specimen gave 35 per cent. of lime. Lime is, perhaps, even more fatal to the value of plumbago than iron, and although graphite may occur in the magnesian limestones of Ceylon (I never heard of but one instance), it is quite manifest that digging in the dolomite need never be resorted to, the mineral being so plentiful in our quartzzy gneiss, where the only enemy encountered, and that, happily, not very frequently, is iron. Like some other adversaries, this one sometimes appears in gneisses the most radiantly beautiful: in the present case as pyrites, varying from splendidly crystallised masses, with facets polished like finest silver, and again simulating auriferous treasures by putting on the most glorious colourings of gold, shading away to a lovely and delicate green, indicative, this tint, it is supposed, of the presence of sulphate of copper.

This auriferous coloured pyrite is appropriately named in Sinhalese, *diya rat-ran*, or "water gem-gold," the recognition of water as the agent to which the formation and its brilliant colours are largely due being, curiously enough, in perfect accord with the conclusions of the most advanced geological scientists.

To Mr. Williams, Acting Government Agent of the North-Western Province, I am indebted for a collection of interesting specimens from Polgolla, on the road to Dambulla, showing how plumbago is associated with and forms round a nucleus of crystalline or semi-opaque and sometimes garnetiferous quartz (the position of the minerals being, I am told, occasionally reversed), and quite a number of pieces of rock which the non-scientific might well be excused for regarding as coated and permeated with brilliant golden ore. These may be regarded as the flowers of the subterranean regions where plumbago is mined. I am bound to state, however, that the brilliancy of iron pyrites has no effect in modifying the inimical feelings with which those connected with the plumbago enterprise regard the mineral, while they talk with disapproval and disgust of the *yabora* = (*a*) *ya* iron, *bora* dross: iron dross, the hard iron-like form of plumbago; and any one desirous of procuring specimens will be made heartily welcome to what, in the eyes of the plumbago dealer, is associated with a rocky interior and unsaleable product. But truly the pure soft mineral itself, in its various forms of crystallisation, the most prevalent

being a radiating star-like arrangement, and its variation of sparkling colours, from steel-grey to plates of jet-black, may be regarded as a veritable "thing of beauty." A collection of first-class lumps, each highly polished and lustrous, intended for shipment to Germany, which could be seen at Mr. W. A. Fernando's store recently, was certainly a striking sight. In connection with this collection of silvery masses, Mr. Fernando showed us specimens of a dark-coloured variety, of needle-like formation, which he said he had been requested by his customers to make up separately, as the ordinary mills could not easily grind that particular quality. Graphite generally, like iodine, shows a bright metallic sheen, but it is at once distinguished from the true metals by its soft and unctuous mechanical condition. I am speaking of first-class mineral, for, showing us a specimen of plumbago formed, apparently, over an ironstone nucleus, Mr. Fernando declared such ore to be unsalable. In truth, the reasons why our Ceylon graphite is so much sought after, are the entire absence of lime from the mineral, and in most cases its equal freedom from ferruginous particles, the small proportion of foreign substances, if any, being volatile matter and minute fragments of silica and alumina. Besides grinding to extreme fineness, an acid bath is used to thoroughly purify graphite used for certain delicate purposes, such as electrotyping, when the finest and purest dust is required to coat surface of wood, plaster of Paris, gutta-percha, &c., to render them conductive. An authority, of all in the world, perhaps, best qualified to speak, describes Ceylon plumbago as combining the two qualities of being almost as refractory as asbestos, and at the same time the most perfect conductor of heat.

The various portions of the world in which graphite is found were then enumerated, from North America to Japan, and the first mentions of Ceylon plumbago were traced, evidence not being forthcoming to prove Bennett's assertion that Ptolemy, who wrote in the second century of our era, had referred to the mineral. The historical records of Ceylon are as silent regarding plumbago as they are with reference to cinnamon, but a medical treatise of the fourteenth century (about the date of a MS., extant in Europe, said to be ruled with black-lead) speaks of *kalu-miniran* (black mica) as a medicine when boiled and subject to the detergent influence of *Euphorbia* juice. The Cumberland black-lead was also sought after as a medicine about a century and a half ago.

To quote again : The officer of the late Ceylon Rifle Regiment, who wrote a book on Ceylon, stated that Thunberg, the Scandinavian naturalist, who wrote in 1777, was the first to notice plumbago as a product of Ceylon. This was an error. Robert Knox, who wrote in 1681, mentioned the existence of the mineral; and Valentyn gives a letter of a somewhat earlier period by the Dutch Governor Ryklof Van Goens, dated 24th September, 1675, addressed to his successor the Governor-General Jan Maatsuyker, in which he mentions veins of plumbago (*potloot*) in the hills and

mines in the low-country. He described it as a product of quicksilver, an error which, repeated, may explain the alleged discovery of a mine of quicksilver near Kótté, soon after the British took possession of Colombo. So important was the latter discovery deemed at the time that a military guard was placed over the mine; but subsequently the existence of quicksilver in Ceylon became as mythical as that of anthracite seems now to be, or the alleged discovery of coal by the Dutch, who are said to have disregarded it in view of the abundance of wood fuel. * * * A Mr. Ive, who wrote apparently in 1755, professed to have discovered "black-lead" and copper ores in Ceylon. Mr. W. P. Ranasinha has unearthed for me the tradition that the last king of Kandy, infamous for his cruelties as he is famous for his æsthetic taste, added to his many-sided character a development of the commercial instinct, supplying, it is said, plumbago to merchant ships, more than seventy years before such enterprising traders as the Fernandos and De Mels appeared on the scene. The tradition seems also to indicate that some of the plumbago in which the monarch traded was dug from a mine on the lands of Molligoda Disáwa.

Then followed references to notices of plumbago by Cordiner and Davy. Bertolacci, although he dealt with every export of any importance in detail up to the end of 1813, makes not the slightest mention of plumbago. The export of the article must have commenced between 1820 and 1830, however, for Mr. Joseph Dixon, the founder of the great American Crucible Company, obtained a shipment of Ceylon plumbago in 1829. In that very year Colonel Colebrooke, one of the Commissioners on Ceylon affairs, stated in his report that provision had been made for the delivery of cinnamon and black-lead in the Kandyan Provinces (then including the Seven Kóralés), at fixed rates. Reference to the Government Calendars shows that there is no mention of plumbago until 1831, when it was included in the list of articles liable to export duty, the rate being 10*d.* per cwt. The amount of revenue at this rate in 1832 was £22. 18*s.* 6*d.* The mineral did not, however, assume real importance in the commerce of Ceylon until 1834, and for the half century which has elapsed between that year and the end of 1884 I possess, thanks to the courtesy of the Assistant Auditor-General, Mr. C. Dickman, full details of the rise, progress, and fluctuations of the trade, until from small beginnings it has in the past five years attained truly important dimensions, whether regard be had to the quantity and value of the mineral exported, or the revenue derived by Government from a royalty finally fixed in 1877 at the very moderate rate of Rs. 5 per ton.

For the first three years of the period beginning with 1834 no export duty was levied on this article. From 1837 to 1846, and again from 1858 to 1869, a duty of 2½ per cent. was levied, which yielded in the earlier period sums so low as Rs. 12.25 in 1839, rising to Rs. 759 in 1846. In the second series of years, when export duties were levied expressly for railway purposes, the duty rose from Rs. 1,190 in 1853 to the appreciable sum of Rs. 22,240

in 1869. The latter sum was levied on 226,132 cwt., valued at Rs. 889,620. The rated duty seems, therefore, to have been as nearly as possible one-tenth of a rupee per cwt. The only Customs import to which plumbago is now liable is, apart from the royalty, seven cents per barrel, recently exacted for harbour purposes. As each barrel contains $5\frac{1}{4}$ cwt., net, of mineral, the burden is only a fraction over one cent per cwt., in addition to the royalty, which since 1877 has been levied at the rate of Rs. 5 per ton, or 25 cents per cwt., equivalent to $2\frac{1}{2}$ per cent. on the Customs valuation of Rs. 10 per cwt., but rising to 5 per cent. if the real value is only about Rs. 100 per ton. Previously to 1851 no royalty was levied, and the varying rates since then have been :—

In 1851, per ton	... 4s.	In 1864, per ton	... 16s.
„ 1852, „	... 5s.	„ 1869, „	... 30s.
„ 1859, „	... 7s. 6d.	„ 1873, „	... Rs. 10
„ 1862, „	... 14s.	„ 1877, „	... Rs. 5

There can be no possible question, it would seem, of the propriety of exacting a royalty, moderate in proportion to its market value, on this mineral, which is entirely an article of export, and which is as much the property of Government, or the people of Ceylon, as are the pearly treasures of the “oyster” banks off Arippe; providing, too, as the revenue from plumbago does, for the construction, amongst other public works, of means of communication which facilitate and cheapen the operations of the diggers. We could only wish that copper, tin, nickel, and other ores which have been so positively written about as occurring in Ceylon, with gold, which beyond question does exist, were found in quantities sufficient to add appreciably to the revenue in the shape of royalties. The one necessary qualification is, of course, that the amount of the tax should be such as not to bear heavily on an enterprise which is always toilsome and often precarious. Taking the average value of plumbago at Rs. 10 per cwt., the Customs figure, the present impost of 25 cents is, as noticed above, only equivalent to a rate of $2\frac{1}{2}$ per cent., which certainly cannot be complained of as unduly onerous, however justifiable complaints and remonstrances were when 14s., 16s., and even 30s. per ton were exacted, or Rs. 10 between 1874 and 1877. The present rate has the merit of being light, easily collected, and productive, for in the five years ended 1884 an average export of nearly 12,000 tons per annum, of an annual value of Rs. 2,400,000, yielded royalty equal to a yearly average in round numbers of Rs. 60,000. When the proceeds of digging licenses and leases of Crown lands, and stamps on those leases, are added, the average may be raised to Rs. 65,000. The maxima of quantities exported, total value, and total revenue were reached in 1883, when the figures were :—

Plumbago exported cwt.	262,774
Value @ Rs. 10 per cwt. Rs.	2,627,737
Total revenue {	Royalty	Rs. 65,694	} Rs. 70,421
	Leases and licenses	Rs. 4,727	

Wonderful contrasts these, even if we reduce the Customs valuation by one-half, to an export of only 423 cwt. in 1839, valued at only Rs. 490, or a little over Rs. 1 per cwt., and yielding to the revenue of the Colony only Rs. 12.25, a sum scarcely worthy of collection! The totals for the whole period of half-a-century of the export trade in Ceylon plumbago are striking, viz. :—

Quantity exported cwt. 3,526,000
Value of this quantity Rs. 25,742,000
Contributions to revenue Rs. 841,000

Crediting plumbago revenue with items brought to account under stamps and other headings, the amount might be raised to Rs. 900,000, and had Government always got its own in the shape of royalty, the round million of rupees would be considerably exceeded.

Taking averages of qualities and periods, it is probable that Rs. 200 per ton is too high a valuation for this mineral, and that twenty million of rupees would, more nearly than twenty-five million, represent the total value of the plumbago exported in fifty-one years, for which figures are given. At any average price of less than Rs. 100 per ton, it would probably not pay to dig plumbago, and, as a matter of fact, what was evidently over-production between 1880 and 1883, led to a reaction in 1884, when not only did exports fall off, but operations in the preparing yards in Colombo were stayed for a time by general consent, some not opening again even when the probability of a war with Russia gave a fresh fillip to the trade.

It is a melancholy fact that plumbago is one of the class of articles, like “villainous saltpetre” and some others, the trade in which prospers when war has broken out or when warfare is threatened. The reason in the case of our staple mineral is, that the chief use by far to which Ceylon plumbago is put is the manufacture of crucibles, nozzles, &c., employed in the preparation of Bessemer and other steel, now in such large requisition for ship-building, plates for ironclads, torpedoes, shot, shell, &c.; this, in addition to the melting of the precious metals, for which crucibles of refractory plumbago are eminently suited from their superior strength and perfect smoothness. There are many minor uses to which plumbago is put, as will hereafter be shown, but I believe I am right in stating that its extended consumption (if that word can be correctly applied to an article which is almost unconsumable) in recent years is due to the great and rapid advance of the steel industry on both sides of the Atlantic, not merely to provide materials for ships, durable and light, but for the dread weapons and appliances of modern warfare, such as Krupp and Armstrong guns, steel shot, &c. But the abundance of the ore in Ceylon, and the enterprise and activity with which the mining, preparing, and shipping of the mineral have been pursued, have in this case, as in so many others, recently led to production considerably in excess of demand, so that the profits of the pursuit, never very great and always precarious, have recently been low or *nil*.

When at its highest market value I do not suppose that Ceylon plumbago ever sold for more than £50 per ton ; indeed, the highest price of which I have evidence is £48, realised by Mr. W. A. Fernando, of Brownrigg-street, Colombo. What is this to the celebrated Borrowdale pencil "black-lead" mines, which, after having been worked since the reign of Queen Elizabeth, recently gave out, so that now pencils picked up at Keswick as curiosities cost sixpence each ! In the report of the Mátara District for 1870, the Assistant Government Agent stated :—To meet Ceylon plumbago in Cumberland was certainly a surprise, but when recently at the English lakes I learned that plumbago from this Island was mixed with the local graphite to make good pencils.

In the palmy days of the plumbago mines of the north of England, the black-lead obtained from them was valued at 30s. per pound, or over £3,000 per ton, or within about two-thirds of the price of ordinary gold. We cannot be surprised, therefore, to learn that a couple of centuries before the world heard of the gold escorts of California and Australia, the black-lead of the English lake region was guarded in its transit in carts, from mine to manufactory, by parties of military, the robbery of black-lead mines being, by an Act of George II., constituted a felony. The Act, curiously enough, recited that black-lead was employed for divers useful purposes, and more especially for the casting of bomb-shells, round shot, and cannon-balls. The connection, therefore, with the art of war of the mineral so long associated with the most intellectual and humanising of the arts of peace—writing and drawing, to wit—does not date from yesterday.

The quality of the Borrowdale ore, dark-coloured, pure, and soft, rendered it eminently suitable for pencils of the finest descriptions, and for about two and a-half centuries the world was practically supplied with pencils from this one source. From one pound of the ore, worth 30s., or at the rate of £168 per cwt., the number of pencils cut averaged from 18 to 20 dozen. The mineral was stated to be found in pipes, strings, and irregular masses called "sops," a description which, substituting modern terms for olden, applies equally to the Ceylon graphite formations. Since the exhaustion of the Cumberland mines, the best ore for pencils is *said* in some books to be obtained from Siberia, while no doubt the massive and soft stove-polish black-lead, occurring in various parts of Germany, —Bavaria, Bohemia, &c.,—is applied to the manufacture of pencils. It cannot be questioned also that some of the finest quality of Ceylon plumbago is thus used in Britain, and also in the United States.

Then followed notices of the various methods of manufacturing pencils, from the period when blocks of black-lead were sawn into pieces, until Conté, of Paris, in 1795, discovered the method now universally adopted of mixing finely-ground graphite and clay together and subjecting the mass to pressure and heat, plumbago crucibles being used to give a final firing to pencil-leads. In the one city of Nürnberg, 250,000,000 of pencils, worth £400,000,

are turned out annually, so that Mr. Ferguson felt justified in estimating the production of the whole world at 1,000 million, worth at least £1,500,000. Clay in varying quantities is used to give adhesion to crucibles, but those with the largest proportion of plumbago are of course the best.

To quote again :—The Canadian and United States plumbago is of as pure a quality as that of Ceylon, but good as the American ore is, when freed from the rock in which it is generally scattered, after the fashion of mica, I suspect the high cost of the labour necessary for first mining and then separating the mineral by the wet process—for the dry has proved a failure—will prevent continued and successful competition with Ceylon. We shall soon see, however, for the Joseph Dixon Crucible Company had produced in 1882 a quarter of a million pounds of native plumbago, against 16,000,000 pounds imported from Ceylon, and a determination to “go ahead” was expressed. Some as yet unthought of machinery, cheap chemicals, and appliances must, however, be brought into play before the pure, massive Ceylon product and our far cheaper labour are distanced in the race. And if, as Professor Dawson states, some of the Canadian ore is fibrous enough to indicate by its texture its vegetable origin, there is room to suspect that, however pure the mineral may be as carbon, its mechanical condition cannot be so good as that of the more highly crystallised Ceylon plumbago. One important element in the question is, that, according to our American friends themselves, enterprise and competition have had such influence, that Ceylon plumbago can now be obtained by them at 25 per cent. of what it cost some years ago.

The effect of competing demand for the substance, however, between 1850 and 1870, chiefly on the part of the Battersea Crucible Company, in England, and the Joseph Dixon Company, in the United States, was to enhance the value of the ore to such an extent in Ceylon as to produce temptations to cheating, which the native headman, whose business it was to weigh the output and collect the royalty at the pit's mouth, were unable to resist. These estimable servants of Government cheated the diggers out of bribes by threatening to report them as having surreptitiously removed plumbago on which royalty had not been paid, and they impartially cheated the Government by accepting bribes to largely under-report the quantities really dug and removed. The Customs figures enabled the Government authorities to appreciate the vast extent to which the demoralising system had gone, and so in 1873 legislation was initiated, the main object of which was the collection of the royalty at the Custom-house—a mode in itself far preferable to the direct system of collection previously in force, and securing every sixpence of royalty due, because, practically, every hundredweight dug is exported, the quantity as yet used in local foundries or for any local purpose being quite insignificant. I believe a few crucibles for gold and silversmiths' use are locally made, and the result of inquiries

made by Mr. W. P. Ranasinha, at my request, is that Ceylon potters occasionally employ the mineral for giving a glaze to pottery, as is the practice in India.

The mercantile community strove hard in 1873 to make out a case for the entire abandonment of the royalty, but the press supported Sir William Gregory's Government in resisting the pressure brought to bear in this direction, only that the *Observer* strongly urged a rate so low as Rs. 5 per ton, which, after four years' experience of Rs. 10 per ton, under which exports declined, was conceded in 1877. Under this rate, which is still in force, the exports more than trebled in the six years between 1878 and 1883.

Then follows a description of the largest plumbago mine in Ceylon :—

Mr. De Mel has been amongst the most prosperous of all who have engaged in the plumbago digging enterprise in Ceylon, his prosperity being mainly due to the rich yield of his Kurunégala District mine, which is by far the most important in Ceylon, having been sunk to a depth of 450 feet near the base of a hill, Polgola, which seems to be largely composed of fine quality plumbago. From this mine Mr. De Mel obtained an average of 800 tons annually for eleven years, his profits, he authorises me to say, being at the rate of £2,000 per annum. No wonder if, notwithstanding lessened production and profits in the past two years, connected with this mine, there is a steam crane for raising water and a considerable length of Decauville railway for the carriage of the ore from pit-mouth to cart, or that the enterprising owner has commenced a base-level tunnel at an estimated total cost of £2,000, to free and keep the mine clear of water, whether the result of springs in the rocks or of monsoon rains (the effect of the latter during the recent exceptionally heavy burst of the south-west monsoon in May was to fill up the pits and put a stop to digging everywhere), this, irrespective of a fall of £2 per ton from the price to which the mineral had been sent up by the war scare.

The tunnel in Mr. De Mel's mine, when completed, will not only carry away water, but facilitate the output of mineral from the lower, which are generally the richer strata, besides ventilating the mine so as to prevent injury from mephitic gases or inconvenience from the smoke of the explosive employed in blasting. The draft will also alleviate the heat in the interior of the mine, which the workmen now complain of as sometimes intolerable. For blasts under water, large quantities of dynamite cartridges are employed, in addition to gunpowder used in portions of the galleries comparatively free from moisture. The wages paid to diggers in this mine, chiefly low-country Singhalese, vary from 9d. per diem for coolies, to Re. 1 for those who perform the boring and blasting operations. In the Pasdun Kōralé there is a system of payment for labour by shares in the profits, after all preliminary expenses defrayed by the capitalist have been reimbursed.

The hill in which Mr. De Mel's mine has been opened—

Mr. W. A. Fernando having another at a higher elevation than De Mel's, with a depth of 330 feet—seems to be permeated in its whole extent by generally horizontal veins of the richest plumbago, associated with beautifully snow-white crystalline to semi-opaque quartz, the latter occasionally showing specks of garnet and bands of soapstone, and Mr. De Mel brings to the surface practically pure plumbago. As regards the generality of pits, he agrees with the estimate of Mr. W. W. Mitchell (who has probably purchased, prepared, and shipped to America as well as Europe more plumbago than any European merchant who ever resided in Ceylon) that the extraneous matter in the shape of earth and rock brought to the pit's mouth is equal to one-half of the whole, about 10 to 15 per cent. being the proportion carried to Colombo and separated from the ore in the preparing yards. Mr. Fernando's estimate, however, of foreign matter brought to Colombo is 5 per cent. for pieces of quartz round which plumbago adheres, and $2\frac{1}{2}$ per cent. for minute fragments of silica, iron, &c., mixed with the smaller pieces and dust. Any person who has witnessed and appreciated the difficulty and the expensiveness of the processes whereby small fragments of rock are separated from the lower classes of plumbago in Ceylon, can well imagine the obstacles to profitable separation of the mineral from rock in America, where there are no masses, but only scales of the mineral distributed throughout the rock.

Then followed a notice of a mass of plumbago only 14 lb. short of 6 cwt., which De Mel exhibited when the Prince of Wales visited Colombo, and the statement that large masses are sometimes, although pure carbon, of such hard consistency as to be commercially valueless. Mr. Ferguson suggested that this form of plumbago and not the softer kind should be used for sculpturing elephants and other objects. Then followed a description of the various systems in force in the three Provinces to which plumbago mining is practically confined. In the North-Western Province all the mines are on private property. In the Southern Province only licenses to dig are charged for, at the rate of Rs. 10 per annum, but no rent. In the Western Province, besides the charge for licenses, a rent-royalty of one-tenth of the plumbago dug, or its equivalent value, is levied, which adds considerably to the revenue. Sir Wm. Gregory, in 1873, announced that the policy of the Government would be to lease and not to sell plumbago lands, so as to prevent a monopoly in the hands of the rich. Mr. Saunders is, however, in favour of selling such lands outright, but only in small lots. He quotes in favour of his view the results of a sale in 1880, when a lot of 1 acre 1 rood and 13 perches realised Rs. 5,150. As a general rule, the rent-royalty exacted in the Western Province is somewhat below the sum of Rs. 5 per ton charged on export, so that the total impost on such plumbago is Rs. 10 per ton. Owners of private mines and diggers on Government lands in the Southern Province pay only Rs. 5. Mr. Ferguson said of the leasing system:—

The merit of the system, provided the rent-royalty is moderate, is that the lessee of the land pays only and just in proportion to the productiveness of the land he has leased, payment being accepted in money or in kind. At the end of each year the lease can be either renewed or otherwise, and plumbago lands which have been for a certain time abandoned, and which evidently do not contain appreciable quantities of the metal, are sold on the terms applied to ordinary Crown lands.

At present, as sources of plumbago, the North-Western Province seems entitled to first rank, the Western following as a good second, while the Southern is a distant third, the Galle Customs returns showing an export of one-tenth of the whole plumbago sent away, against nine-tenths from Colombo. Three-fourths of all the plumbago exported from Ceylon are dug in the Kurunégala and Kalutara Districts. It was then noticed that exaggerated figures have appeared in the Blue Books as to the number of plumbago mines in the Island, from the inclusion of abandoned pits and mere holes. While the pits opened from first to last must amount to thousands, those being worked at any one time may be taken at from 300 to 600. Water in the soil and from rainfall is the great difficulty. To quote :—

As a general rule, graphite seems to exist not far from the surface, on which its presence may be revealed through fissures, while, in regard to this mineral, as well as gold and other ores, indications in streams guide explorers up to the including rocks, generally quartzzy gneiss, in which the mineral is embedded or diffused. Mr. De Mel tells me that very good plumbago is often found near the surface, but that, as a general rule, the lower the digging operations go the better the quality and the larger the quantity of the mineral. Of course, the purer the finds are, and the larger the masses the better, but a visit to any of the preparing yards in Colombo will show, besides the cost of prospecting and mining and the uncertainty of ultimate success, a good deal of expense is involved in conveying a considerable proportion (already noticed) of extraneous matter to Colombo, there to be hammered, cut with small axes, picked, sifted, and washed out.

Still, with all its drawbacks, the plumbago enterprise is valuable to the country, not only for the revenue it yields, but for the generally remunerative employment it has given to many thousands of the population (from 15,000 to 20,000 men, women, and children, probably, including cartmen and carpenters), especially since the period when the collapse of the once great coffee interest led to so much distress in the country. The Kurunégala Administration Report of 1873 stated that in that District alone the plumbago industry had given employment to some 5,000 persons. The Galle Report for 1872 estimated that each mine required from two to eight or ten miners, and even up to fifty or sixty, at high wages. At a period when the plumbago industry was at the height of its prosperity, Mr. De Mel and other mine owners had almost concluded an arrangement with Messrs. John Walker

& Co. for a light railway line from the mine region to the Government Railway. Depression in prices caused this design to fall through, but the day cannot be far distant when Kurunégala, at least, will be connected with the Government Railway system at Polgahawela, forty-five miles from Colombo. The Western Province plumbago, found in the Pasdun Kóralé (a Kóralé which is famous for the quality, as well as the quantity of ore it produces), does not come on the railway at Kalutara. Once it is loaded in boats it comes by water all the way to Colombo.

A return furnished by Mr. Pearce shows that nearly one-half of all the plumbago exported from Ceylon comes on the railway at various points, mainly at Polgahawela, the quantity so carried in 1882 being no less than 5,642 tons.

To show the vicissitudes of the plumbago enterprise, I may quote from the Sabaragamuwa Report of 1873 to the effect that plumbago which formerly sold at Rs. 200 per ton, then realised only Rs. 90, while the working expenses had considerably increased in consequence of the enhanced prices of labour. It will be remembered that 1873 was the year in which the change was made to the collection of royalty at the Custom-house, in anticipation of which the great manufacturers in Britain and America had provided themselves with stocks of the mineral. Hence a fall in exports and prices. Eleven years subsequently, in 1883, Ceylon sent away her largest export of plumbago, but the depression had even then set in, which led to greatly reduced shipments in 1884. In the one matter of cask-making, however, the increase in the export of plumbago during the past five years must have largely filled up the void created by the decrease in coffee. Hora, one of our most inferior timbers, can be utilised for plumbago casks, and as the casks are uniformly made to hold a quantity somewhat over a quarter of a ton ($5\frac{1}{2}$ cwt. net), an average of 45,000 casks per annum for the past five years, or a total in the quinquennium of 225,000, must have given, in their manufacture, remunerative employment to a considerable number of carpenters who had previously been largely dependent on cask-making for coffee.

The industry now so wonderfully successful in the North-Western Province is apparently of quite recent origin. Gate Mudaliyár Jayatilleke states, in reply to my queries as to whether there were anything hereditary, or a system of payment by shares, amongst the mining class:—

“All the plumbago quarries that are now worked in the District are purchased from the Crown. No licenses have ever been applied for or granted to dig plumbago. The diggers are paid wages, and they are coolies from the Siyané and Hápitigam Kóralés in the Western Province. Very few Kandiyans are employed, as they are not handy in blasting and excavating any depth of more than 15 or 20 feet.”

I may add that but few Tamils are employed in the Ceylon plumbago mines, which are, I believe, exclusively owned by

Sinhalese, although, no doubt, the ubiquitous Chetty of Southern India is interested in the recovery of advances made, or supplies furnished, in some cases.

To Mr. G. S. Williams, the Acting Government Agent of the North-Western Province, I had previously been indebted for responses to my questions, thus :—

“The pits are about sixteen miles north-east of Kurunégala on the Dambulla-road. There is a good resthouse at about the twelfth mile, and the journey in decent weather is easy enough.

“The trade altogether failed last year—I mean no digging was done—on account of the fall in price, but this year operations have been resumed, and I am told that about 2,000 men are employed. The plumbago is found in rocky ground in which are very large crystals, transparent like Derbyshire spar.* De Mel is the owner of the principal pit. The resthouse is at Gokarella. It is not mentioned in Fyers’ Itinerary, but is between Polgolla (about a mile beyond it) and Ambanpola. On page 20 of the new edition (1881), Part I., you will find Wēṭakeiyāpota, which is 15·55 miles from Kurunégala, and 0·55 mile beyond that, or 16·10 from Kurunégala, ‘minor road to plumbago pit on right.’ There are other plumbago pits, some actually by the roadside.”

It thus appears that the best deposits of plumbago at present worked in Ceylon are situated at the base of the north-western portion of the mountain zone. The mineral exists at high elevations, up to Nuwara Eliya indeed, but apparently not in paying form or quantity. It would appear that while the veins of plumbago run generally from south to north in the Western Province, their direction in the Kurunégala District is from east to west.

It seems possible that if digging for gems and plumbago continues on a large scale, and becomes widespread, legislation may be needed such as exists regarding the protection of wells, and that measures to prevent accidents from subterraneous blasting and the collapse of tunnels, as also to secure free ventilation, may be necessary. Though not so much so as gem-digging, plumbago mining is, no doubt, largely a speculative pursuit, involving the loss and demoralisation which ever accompany gambling pursuits. The ultimate result is, however, beneficial to the people and the country.

From some of the Administration Reports consulted, it would seem that the plumbago industry is a recent one in the District of Sabaragamuwa, although the existence of the mineral must, surely, have been revealed to the gem-diggers who have for ages been engaged in searching for the sapphires and rubies for which the region around “the city of gems” (Ratnapura) is so famous.

A vivid idea will be formed of the extent to which Government

* Crystalline quartz, of course, as lime taking the form of spar seems to be non-existent in Ceylon ?

—that is, the public—were formerly cheated under the system of collecting the royalty at the pit's mouth, when it is mentioned that while 226,000 cwt. were exported in 1869, the royalty recovered was only Rs. 16,000, against Rs. 65,000 on 263,000 cwt. in 1883, the rate in the latter year being only one-third of that in the former.* The extreme rate of 30s. per ton in 1869 evidently proved an irresistible temptation to diggers and headmen, and the royalty recovered was only one-tenth of the sum which ought to have been collected.

As has been proposed in the case of chips in the cinnamon trade, it would almost seem desirable that low quality dust should be excluded from the exports. Buyers are strongly inclined to confine their attention to lump of best quality, and I have heard that some of the local dealers have injured their own reputation, and that of the article in which they deal, by mixing lower qualities with the higher. As matters stand, the proportions in which the mineral seems to be exported are :—lumps, 1st and 2nd quality, 50 per cent. ; chips and dust, each 25 per cent. ; so that dust is only one-fourth of the whole. In the home market, during the past five years of unprecedented out-turn, I am informed that prices have ranged from £20 per ton, the highest for lump, down to £10. In Colombo, apart from the exceptional case in the experience of Mr. W. A. Fernando, already mentioned, the highest prices ever known are stated to be Rs. 320 per ton for fine, Rs. 270 for ordinary, Rs. 95 for dust. In the old sailing ship days plumbago was taken at an exceptionally low rate of freight as “dead weight.” Since 1880 the average rates for a ton of 20 cwt. have been : steamer, 40s. ; sailer, 35s.

The United States are our best customers in the case of plumbago, the Ceylon form of which the late Mr. Joseph Dixon saw and appreciated in 1827, and of which he secured a first shipment in 1829. In 1882 the quantity received in the United States from Ceylon was stated at 16,000,000 lb., and of the *comparatively* small quantity of 22½ million of pounds sent from Ceylon in 1884, more than half went to the United States. But a memorandum showing the various countries for which the plumbago exported in the past five years was destined will clearly indicate how important a customer for our mineral we have in the United States, with its large steel manufacturing industry. The general result is, that of the whole export of 1,170,000 cwt. in the five years, 641,000 cwt. (or very considerably more than one-half of the whole) went to the United States, the United Kingdom taking the bulk of the remaining 529,000 cwt.

* How striking is the illustration here afforded of the value of indirect (and especially Customs) taxation, rather than a direct levy, in the case of Orientals. No greater fiscal boon could probably be conferred on the people of India and Ceylon than—if it were possible—the collection of all Government dues through the Customs Department, so saving an amount of oppression on the one hand and of bribery and corruption on the other, of which European administrators never get more than a faint idea.

Out of an export of 263,000 cwt. in 1883, Britain took 119,000 cwt. and the United States 142,000 cwt., leaving only 3,000 cwt. for other places. The memorandum referred to is appended as a note.* It seems probable that three-fourths of all the plumbago which Ceylon exports is used in the great crucible factories of Britain and the United States, that established by the Messrs. Morgan Brothers, at Battersea, and the crucible factories of Jersey City, New Jersey.

Notices then followed of the Battersea Crucible Works, and those of the Joseph Dixon Company, New Jersey, and it was stated that a vast fund of information regarding plumbago, and the very numerous and varied uses to which it is put, were quoted from descriptions of those extensive establishments.

The Battersea Works was founded by the Brothers Morgan, in 1855. The American establishment had been at work long before this period, but no doubt its productions did not go beyond local demand, for in a notice of the Battersea Works we find it stated that previously to 1855 crucibles were almost exclusively imported from Germany. Now that country, together with other centres of industry on the Continent, is principally supplied from Battersea, where crucibles are turned out at from 8*d.* per dozen, up to a gigantic melting pot costing £6.5*s.*, and capable of taking in 1,000 lb. of steel. Such a crucible can bear from 8 to 10 meltings, while in the case of gold, a crucible taking in 1,200 ounces can sometimes stand seventy meltings. So in the case of brass, while crucibles for assaying the precious metals are very carefully manufactured, being rendered porous by the use of charcoal. The absence of coal fuel from Ceylon is probably a fatal objection to local iron or steel manufacture on any extended scale, but for small quantities of superior steel for special local use, I would, with some diffidence, suggest that crucibles composed of our indigenous plumbago and kaolin clay, both abundant and cheap, might be profitably used. The existence of "millions

* Plumbago exported in each of the last five years, showing the countries to which the mineral was shipped :—

	1880. cwt.	1881. cwt.	1882. cwt.	1883. cwt.	1884. cwt.
United Kingdom	70,276	89,709	143,450	119,312	84,981
Holland ...	—	—	—	438	945
Trieste ...	107	4,217	1,828	—	210
France ...	507	699	300	294	884
Hamburg ...	—	4,031	—	—	816
U. S. of America	133,556	160,259	113,451	141,664	94,083
British India .	1,095	109	999	326	506
Australia ..	197	885	118	—	—
China ...	—	—	12	—	—
Hongkong ...	—	—	8	739	—
Totals ...	205,738	259,909	260,166	262,773	182,425

of tons" of iron ore in Ceylon is not so apocryphal as that of anthracite, and those who owe their origin to Britain are not likely to forget that her wealth in iron quite casts into the shade all the treasures of the diamond mines of Golconda, and the gold diggings of California and Australia.

Mr. Ferguson said, commenting on a very able Paper by Mr. Orestes Cleveland, of the Joseph Dixon Company:—In most of the works consulted in the preparation of this paper—and they have been many and various—the credit of having first made and used plumbago crucibles has been given to the Germans. Mr. Cleveland awards the credit to the Dutch, and it is certainly significant that the Dutch name for the mineral should be *potloot*, or pot lead, the lead of which crucibles are made (?).

Again:—And so our plumbago, like our coffee, suffers from the "ways," that are literally "dark," of the adulterators. Mr. Cleveland, in a kind of despair, exclaims:—Perhaps no article except mustard can be so successfully adulterated as plumbago. He means, of course, for stove polish, because adulteration in the case of plumbago used for crucibles would soon be betrayed in the trial by fire, one great value of the pure plumbago in crucibles being that it conserves carbon in steel when being melted.

As a lubricant for metal surfaces, journal boxes, carriage axles, and all metal bearings, we can easily understand why only the very finest plumbago should be used, the choicest lumps being pulverised till the particles will not glisten, but the mass becomes a dead black. It cannot, Mr. Cleveland states, be made fine enough by bolting (he means sifting through silk), but must be floated either in water or air.

I notice, however, from advertisements in the American papers, that "mica grease" as a lubricator is competing with plumbago, but how far successfully I cannot say. What I know is that the writer of a recent article on American minerals strongly supports Mr. Cleveland's view as to the great superiority of plumbago as a lubricator. I am not aware that it is so used to any extent in Ceylon, either in foundries or on the railways, although if all stated regarding its value be correct, Ceylon plumbago ought to be much more largely used in Ceylon than it is at present, as a lubricant and for other purposes. For all uses it would seem that grinding to extreme fineness is essential.

We now, said the reader, come to some miscellaneous and curious uses to which plumbago is put, the mineral being applied to articles so different as musical instruments, hats and boots, bottles, paint, boats, and yachts. Listen:—For pianos, plumbago is employed to coat the bridge over which the wires are drawn, because of its perfect lubrication; it prevents the wire from adhering to the wood, and should be as free from impurity as that used by the electrotyper, but need not be pulverised as finely. For organs, it is used to lubricate the sides, and should be the same as that used by piano-makers. The German black-lead imparts a peculiar tone to the colour, and a softness and

smoothness to the touch of felt hats. The very best lump only should be accepted. As it has once been washed and dried in lumps, they will readily separate again in water, and no pulverising is needed. For colouring dark glass for carboys, bottles, &c., the best German black-lead is used in lumps, but no inferior grade will answer. For paint, plumbago has long been known as possessing great value. The elements do not exhaust it, water sheds from it as from oil itself, and fire does not affect it. The grade need not be the highest. For the bottoms of boats and yachts it has long been used, especially for racing boats; but only the best Ceylon plumbago, very finely pulverised, is valuable.

A substance which, used as a paint, resists the action of the atmosphere, and is both water-proof and fire-proof, is surely of great economic value, and ought to be specially useful as paint for the numerous tea factories erected or in course of erection in Ceylon.

To quote again :—

Mr. Cleveland's very interesting and valuable notice of the American Crucible Company, and their varied manufactures of plumbago, is supplemented and brought down to so late a date as 1883, by the writer (Mr. John A. Walker) of an article on plumbago in a volume on the "Mineral Resources of the United States," prepared by the National Geological Survey Department, and supplied to our Library by the Smithsonian Institute, to which my attention was attracted by our Honorary Secretary, when he asked me to write this Paper. In the summary prefixed to this volume it is stated that the amount of graphite mined in the States in 1882 was 425,000 lb., worth crude at the point of production 34,000 dollars, equivalent to about Rs. 70,000. During the first six months of 1883 the production was estimated at 262,500 lb., worth 21,000 dollars. From Mr. Walker's detailed account we learn that graphite is, as a mineral, widely distributed in the United States; as an ore it is found in but few places in sufficient quantities and purity to be profitably worked.

The attention being paid to the mineral in America may be judged from the fact that samples had been received and reported on by the Joseph Dixon Crucible Company from no fewer than thirty-three localities, between October, 1877, and January, 1882.

The Joseph Dixon Company had laid themselves out to produce 500,000 lb.; altogether 525,000 lb., valued at 8 cents per lb. Let us say 18 cents of our rupee currency, and we get the high value (founded on cost as well as quality?) of Rs. 20 per cwt., or Rs. 400 per ton. The local production, however, was certainly not much to place against 16,000,000 lb. imported from Ceylon in 1882, with considerable quantities in the two following years.

Referring to analyses of Canadian and Ceylon graphites, quoted from the American authority, Mr. Ferguson said:—Both are almost absolutely pure, and did the Canadian and United States mineral occur in such a form in the enclosing rocks that it could be

cheaply mined and prepared, there would of course be an end of the export of Ceylon plumbago to America. But if, in America, plumbago, however pure, is only distributed in the proportion of 8 to 15 per cent. mineral to 92 to 85 rock, those connected with the Ceylon enterprise need not, it would seem, concern themselves greatly with the competition in America of indigenous ore with that from our Island.

Under the heading "Manufactures" there is interesting summarised information, which I quote :—

Proportionate amount of graphite used for different purposes :—

Manufactures.	Kinds of Graphite used.	Per cent.
Crucible and refractory articles, as stoppers and nozzles, crucibles, &c. ...	Ceylon, American ...	35
Stove polish ...	Ceylon, American, German ...	32
Lubricating graphite ...	American, Ceylon ...	10
Foundry facing, &c. ...	Ceylon, American, German ...	8
Graphite greases ...	American ...	6
Pencil leads ...	American, German ...	3
Graphite packing ...	Ceylon, American ...	3
Polishing shot and powder ...	Ceylon, American ...	2
Paint ...	American ...	$\frac{1}{2}$
Electrotyping ...	American, Ceylon ...	$\frac{1}{4}$
Miscellaneous — piano action, photographers', gilders', and hatters' use, electrical supplies, &c. ...	—	$\frac{1}{4}$
		<hr/> 100

A table like this will give many of the readers of this paper a new view of the multifarious uses of the mineral carbon called plumbago. It will be observed that, next to the manufacture of crucible articles, the great use of the mineral is for polishing and preserving from rust the ranges of stoves and other cooking appliances which contribute so much to the neatness, cleanliness, health, and comfort of modern abodes. The proportion used for this purpose in Europe—in Britain at least—cannot certainly be below that given for the United States. There are graphite greases as contradistinguished from lubricants, and the mineral seems to be used for the packing of engines. From the largest forges, where tons of steel are manufactured, in Pittsburg, down to the studio of the photographer and the shops of the gilder and hatter, plumbago is of valuable use. And not only is it called into requisition to produce the highest order of steel guns and steel armour for war-ships, but it is good for polishing the sportsman's powder and shot. Gunpowder used for blasting operations is also greatly improved by receiving a glaze or varnish of graphite, the philosophy of the operation being that thus the grains are prevented from absorbing the moisture which exist in mines and quarries.

Graphite enables the electrotyper to prepare and present to the world, cheaply and at will, casts of coins, wood-cuts, copper-plate, maps, &c., equal in the most minute and intricate detail to the most highly prized and costly originals. But next to the boon which the real discovery of anthracite or natural coke in Ceylon would be, is the certainty, of which we are assured, that in our teeming supplies of plumbago the tea planters of Ceylon can get a paint for their stores equal in its fire-resisting properties to asbestos paint. If this should prove to be correct, and we see no reason to doubt the statement, the prospect is that Ceylon will be speedily exporting, instead of importing, fireproof paint. Mr. Walker may well say in conclusion :—

“The growth of the graphite industry has kept pace with the age, each new development in metallurgy and engineering offering some new field of usefulness for graphite. For instance, it furnishes the pots for the manufacture of cast steel, and the nozzles and stoppers used in the Bessemer process. It is used in the manufacture of electrical supplies, &c. Fifty years ago graphite was little known and mis-named. Now it is of constantly increasing importance. From an insignificant beginning in the present century the industry has grown to its present proportions.”

A list is then given of twenty-five American firms engaged in the plumbago industry, of which the Joseph Dixon Company of Jersey City, New Jersey, takes the lead, employing 500 hands in the manufacture of everything for which graphite is used. The same number of hands find employment from the Eagle Pencil Company; while A. W. Faber, probably an immigrant or descendant of an immigrant from Nürnberg, employs 150 persons in his pencil factory. Others employ lesser numbers, six firms giving crucibles as their exclusive manufacture; three, lead-pencils; four, foundry facings and lubricants; seven, stove polish and lubricants. It will thus be seen that except in the branch of pencil-making, and perhaps electrotyping, the New World has gone, or is rapidly going, in advance of the old in the plumbago industry, which means corresponding advance in the steel industry. It is surely a striking incident in the romance of commerce that this ancient eastern isle of “Serendib,” the scene of the mythical adventures of Sindbad the Sailor, should be the main source of supply of an article so useful in the industries and elegancies of life, the appliances of peace and war, and the pursuits of the artist and literary man, not only to countries in the eastern hemisphere, but to the regions of the far Western World.

Having noticed the leading establishments in Europe and America where our Asiatic ore is so largely utilised, let us now turn to one of the compounds, or yards, with its brick and tar “barbecue” or platform, and surrounding sheds, in which Singhalese men, women, and boys prepare, assort, and pack the mineral when received in Colombo from pits, none of which are nearer than thirty miles, and some of which are so distant as the District of Hambantota, at the eastern extremity of the Southern Province.

The chief exhibitor of plumbago at the Melbourne Exhibition of 1880-81 was Mr. W. A. Fernando, of No. 1, Brownrigg-street, Cinnamon Gardens, Colombo, and a description of his establishment which the editors of the *Ceylon Observer* gave in their paper of August 12th, 1880, is, in all substantial details, corrected in August, 1885.

The description was then stated to be reproduced, and the closing remarks were to the following effect :—

We now feel confident that the number to which the pursuit gives employment was much under-estimated in 1880, and that, considering that 5,000 persons were said to be engaged in mining in one year in a single District of the North-Western Province, our higher estimate of an average of 20,000 men, women, and children at present engaged in the various operations of mining, carrying, preparing, packing, and shipping Ceylon plumbago, is not beyond the truth.

It is curious that the Sinhalese women should entertain a prejudice against plumbago as poison, seeing that it is included in the native pharmacopœia. We should have expected members of what Artemus Ward called "the female sect" to have been more troubled about the soiling of their persons and clothes by contact with the mineral; but in truth a coating of the shining ore, while easily got rid of by the use of water, produces no such hideous effect as that so familiar to us now in Colombo of the truly uncanny-looking coaling coolies, when proceeding to their houses after loading or unloading the bunkers of one of the multitude of magnificent steamers which now resort to our harbour. A polish of person, if not of deportment and manners, is the result of working amongst even the dust of plumbago, and it is curious to see the dark-skinned coolies of the plumbago stores walking about with their bodies shining as if they were electrotype statues vivified.

In its further metamorphic progress from vegetable to mineral, the form of carbon we call plumbago has certainly taken a great step in advance of the carbon we call coal, in getting rid of smoke entirely, and also of dirt. Coal, however, cannot be accused, as plumbago justly is, with causing a whole roof-covering of tiles suddenly to fall off, from the slipperiness created by wind-blown particles of the greasy mineral. We were greatly amused by Mr. Fernando's statement at the time, but others, Europeans included, who have to do with the preparation of plumbago, have fully confirmed his representation as to the incompatibility of plumbago dust and tiled roofs. In this connection we would advise visitors to plumbago compounds to be careful how they bear themselves in such slippery places. A sudden step on to the polished platform may end in an undignified tumble. And this reminds me of the sensation produced many years ago in Mincing-lane by the peculiar appearance of some Ceylon coffee which had been dried on a barbecue where plumbago had been previously spread. An attempt to impart a fictitious colouring to the beans was suspected until the requisite explanation was afforded.

As this Paper may be read beyond the limits of Ceylon, it may be as well to explain that *cadjan* is a word, curiously enough, of Malay origin, applied in Ceylon to plaited branches of cocoanut palms, used for roofing houses, sheds, carts, &c. *Compound* is a yard or enclosure, and *barbecue* is a platform.

I have already shown, what I may be allowed to repeat, that for the average shipments of 12,000 tons per annum of plumbago from Ceylon for the past five seasons, the yearly supply of casks must have been 45,000, and that the manufacture of these alone must have given welcome and remunerative employment to carpenters out of work by reason of the partial collapse of the staple Colonial industry; this, apart from the large number of persons (estimated above at 20,000) engaged in mining, carting, preparing, packing, and shipping the mineral.

Let us, therefore, hope that the plumbago industry of Ceylon may continue to prosper and extend, not as the result of wars or rumours of wars, but because of the steady and beneficial progress of the peaceful industries and arts which contribute to the elevation of humanity in all that constitutes comfort, happiness, and means to cultivate the loftier instincts and destinies of our race.

[It may be added that in appendices to the Paper much valuable information is contained, and that the collection of rocks and minerals associated with plumbago, made by Mr. Ferguson with the aid of Messrs. G. S. Williams, Jacob De Mel, and W. A. Fernando, including crystallisations of iron pyrites and quartz in various beautiful and interesting forms, is about the largest and most complete ever brought together. Mr. Williams has requested that the specimens sent by him, including a magnificent pyramidal crystal of translucent quartz, which was found embedded in kaolin with plumbago and pyrites at its base, should go to the London Exhibition, and there can be no doubt that Mr. De Mel will lend for this purpose his splendid, silver-like crystallisations of iron pyrites.]

The Chairman said that he had no doubt some of those present, merchants or scientific men, would have something to say on the subject of the Paper of which a sketch had been given to them. No one, however, rising to speak, Mr. Berwick continued that it therefore fell to him to propose a vote of thanks to Mr. Ferguson for the very interesting Paper, of which the harest summary evidently had been laid before them. The subject was one of great importance, relating as it did to the only mineral of marketable value which the Island possesses. The sight of those pieces of plumbago raised in his mind an almost overwhelming feeling, when he remembered that they contained the very oldest form of vegetation which this world had known, taking us back for not thousands of years, but for a space of time that only astronomers could calculate. We were reminded of the lapse of time as we gazed on the ruins of our own ancient cities, or read about those of

Egypt brought before us so vividly in the lines addressed to Belzoni's mummy :—

And thou hast walked about (how strange a story !)
In Thebes's-street three thousand years ago,
When the Memnonium was in all its glory,
And time had not begun to overthrow
Those temples, palaces, and piles stupendous,
Of which the very ruins are tremendous !

But these things were but as yesterday compared with what we had to realise as we looked on the pyramid before us, for the vegetation which went to its formation carried us back at one bound to the very first chapter in Genesis. He hoped that one effect of this Paper would be that new uses would be found for plumbago, and that the price would once more go up.

Mr. A. R. Dawson, C.C.S., in seconding the motion, said the clever Paper read by Mr. Ferguson appeared very opportunely at a time when they were all anxious to have attention attracted to the products and resources of Ceylon. He hoped that the Society would arrange to have copies of the Paper distributed from the Ceylon Court at the Indian and Colonial Exhibition next year, and still more that the interesting display of plumbago in its various states before them that evening would be secured to go forward among the Ceylon exhibits. (Hear, hear.)

Mr. A. M. Ferguson returned thanks, and said that Mr. W. A. Fernando had kindly placed at the disposal of the Exhibition Committee the pyramid of plumbago on the table, merely stipulating that the Secretary (Mr. Davidson) should take it home in his pocket. (A laugh.)

The Honorary Secretary stated that arrangements had already been made to have copies of Mr. Ferguson's Paper printed for distribution at the Ceylon Court in the Exhibition, and that the plumbago exhibits would be fully utilised, while he was glad to be able to say that they also hoped to send to London the largest mass of plumbago ever yet shown—beating even that displayed before the Prince of Wales, and also of far superior quality. This was a block weighing some 7 cwt., from the Pasdun Kóralé, whence some of the best plumbago came.

The Chairman then stated that the next Meeting of the Society would be held on September 21st, 1885, when Mr. Burrows, C.C.S., would read a Paper on the results of Archæological Investigations at Anurádhapura. The Hon. J. F. Dickson, the President of the Society, would occupy the Chair, and take farewell of the Members.

The Meeting then broke up.

COMMITTEE MEETING.

22nd September, 1885, 5 p.m., United Service Library.

Present :

The Hon. J. F. Dickson, M.A., C.M.G., President.
The Right Rev. the Lord Bishop of Colombo, D.D.,
Vice-President.

T. Berwick, Esq.
J. Capper, Esq.
D. W. Ferguson, Esq.

S. Green, Esq.
J. L. Vanderstraaten, Esq., M.D.
W. E. Davidson, Esq., Hon. Sec.

Business.

1.—Read and confirmed Minutes of the last Meeting.

2.—The President announced to the Committee that owing to his removal to Singapore he was obliged to place the resignation of his office as President in their hands, and requested the Committee to consider what arrangements should be necessary to fill up the post. He added that his Lordship the Bishop of Colombo had at his request signified his willingness to undertake the duties of President if that were the unanimous desire of the Committee.

After many expressions of regret at the loss to the Society, owing to the promotion of Mr. Dickson out of the Island, the Committee unanimously resolved that His Lordship the Right Rev. the Bishop of Colombo be solicited to allow the Committee to nominate him for the post of President in 1886, at the Annual Meeting of the Society in December, and that, meanwhile, he be requested, as Vice-President of the Society, to undertake the duties of the President until the Annual Meeting.

3.—The question having arisen as to the time and place most convenient for holding Meetings, no formal resolution was passed, but it was the sense of the Committee Members present that evening Meetings of the Society should be continued at the Museum, but that the Annual Meeting for the election of Officers, reading the Committee's Report, and the President's Address should be held as heretofore in the Council Chamber.

4.—Read letter from the Hon. the Colonial Secretary, dated the 4th August, 1885, forwarding a report by Mr. S. M. Burrows, C.C.S., on Archæological work at Anurádhapura, 1884–85.

Resolved,—That the Report be printed in the Proceedings.

Report on Archæological Work at Anurádhapura, 1884–85.

As the Archæological work on these ruins has been chiefly in my hands for the last eleven months, I am directed by the Government Agent to furnish a report, in reply to letter No. 221, of July 25th, from the Hon. the Colonial Secretary.

I annex a detailed account of the expenditure of the vote of Rs. 200, allotted to the Anurádhapura ruins, out of the vote of Rs. 500 mentioned in Colonial Secretary's letter No. 270, of March 27th. From this it will be seen that the money has been spent almost entirely on clearing jungle around newly-discovered ruins, and for exploration purposes, and upon the purchase of lime and cement for restoration purposes. The work of excavation has been carried on chiefly by convict labour. For the last three months I have been allowed a force of twelve men and a peon; previous to that the force was increased or diminished as occasion demanded.

The following details will give some idea of what has been done:—

1.—Of the work done at the Mirisvęti dágoba I say nothing, as this was carried out under the direction of the Royal Asiatic Society.

2.—The interesting ruins surrounding the dágoba called by hypothesis the Wijayaráma, were thoroughly cleared and a good road cut to them.

3.—The discovery of the centre piece of the stone canopy near the large canoe led to extensive excavations there. Mr. Ievers found three large stone sannasas, one of which is in perfect preservation, and has been copied. The heavy job of restoring the stone canopy to its original position has at last been satisfactorily accomplished.

4.—Mr. Ievers found an enormous "Bisokotuwa," lined with granite slabs, near the Queen's Palace, which has been cleared and excavated to the depth of about 35 feet. The large ruined pokuna near it has also been cleared.

5.—A very large vehera, measuring about 80 ft. by 60 ft., has been unearthed in the jungle opposite to the stone canoe. The stairway, door-guardians, &c., are the finest and most massive yet discovered. The whole of the surface has been cleared, exposing a "Yóga" stone in position; and the whole of the boundary wall with its perfect moulding has been laid bare.

6.—Beyond this "vihára" a large vihára with huge monolithic pillars and ornamented capitals has been cleared.

7.—Beyond this again a square vihára with more slender pillars (which, however, are also monolithic and ornamented) has been unearthed, and a quantity of interesting stones connected with it exposed to view. This vihára is particularly interesting, as it is the only specimen of a Mágoda-shaped vihára yet found.

8.—North of the vihára mentioned in paragraph 5, a very large sedent Buddha has been found, and restored to its original position.

9.—North-west of the Kuttam Pokuna, a square pokuna, of similar design and elaborate workmanship to the Kuttam Pokuna, has been cleared and a road cut to it. Near it, a curious inscription, apparently in the Canarese language, has been uncovered and copied.

10.—A path has been cleared to two collections of rock-dwellings north of the Tammettan Pokuna. Near one of these there is a long and clear inscription, in some language that is neither Singhalese, Tamil, nor Nágara, and which will be copied this week.

11.—A large expanse of jungle has been cleared and burned south of the Jétawanaráma, exposing to view a quantity of stone boundaries, pillars, water-courses, &c.

12.—A very fine vihára or pirawena has been discovered and cleared north-west of Lanḡaráma. Its moulding is unique in its massiveness; it has four annexes and a dágoba to the west.

13.—Two working parties of coolies are at present employed, (a) in excavating the eastern chapel of the Abhyagiri dágoba; (b) in clearing and partially restoring the two most perfect of the five pavilions on the outer circular road.

14.—A large number of enamelled tiles, iron and copper implements, interesting detached stones, &c., have been brought to light and carefully preserved.

The conclusion.—I would venture to express a hope that a surveyor will very shortly be detached for the special duty of laying down on the plan all the ruins, boundaries, &c., that have recently been unearthed. Only when this is done will it be possible to form any connected idea of the dimensions and general aspect of the old city. Such a plan would be of invaluable assistance to the future excavator, and I make no doubt that there are a vast quantity of ruins still lying hid in this dense thorn jungle.

The present force of convicts, if kept continuously at the work, will be amply sufficient to keep clear the paths to, and the jungle round the later discoveries.

The Disáwa of Tamankaḡuwa has been written to for a report on the work done by him at Polonnáruwa.

I am, &c.,

S. M. BURROWS.

27th July, 1885.

GENERAL MEETING.

22nd September, 1885, 9 p.m., at the Colombo Museum.

Present :

The Hon. J. F. Dickson, M.A., C.M.G., President, in the Chair.

The Right Rev. the Lord Bishop of Colombo, D.D.,

Vice-President.

P. D. Anthonisz, Esq., M.D.	J. P. Lewis, Esq., M.A., C.C.S.
H. P. Baumgartner, Esq., C.C.S.	Capt. Morgan, R.E
H. C. P. Bell, Esq., C.C.S.	E. T. Noyes, Esq., C.C.S.
T. Berwick, Esq.	E. T. Perera, Esq.
S. M. Burrows, Esq., M.A., C.C.S.	L. O. Pyemont-Pyemont, Esq., C.C.S.
J. Capper, Esq.	S. Rajapakse, Mudaliyár, G.G., J.P.
J. B. Cull, Esq., M.A.	G. S. Saxton, Esq., C.C.S.
J. E. Dean, Esq.	A. T. Shamsuddeen, Esq.
D. W. Ferguson, Esq.	H. Sumangala Terunnánse.
J. Ferguson, Esq.	H. Wace, Esq., C.C.S.
R. W. Ievers, Esq., M.A., C.C.S.	
C. J. R. Le Mesurier, Esq., C.C.S.	

W. E. Davidson, Esq., C.C.S., Honorary Secretary.

Sixteen visitors present, and nineteen ladies.

Business.

The Minutes of the last Meeting having been read and confirmed, the Secretary announced that the name of Mr. G. S. Williams, C.C.S., was submitted for election. He was proposed by the Chairman and seconded by the Secretary.

Mr. Williams was declared elected.

Mr. S. M. Burrows, C.C.S., then read an instructive and interesting Paper, entitled "Jottings from a Jungle Diary," of which the following is a brief summary :—

The scheme of this Paper is simple almost to crudeness. It is to give some account of the more recent archæological discoveries at Anurádhapura, and to describe one or two places and incidents which I have come across on circuit in the less beaten tracks of the North-Central Province. While carrying out some mild excavations on the outer circular road near the "stone canoe," in November last, we had the good fortune to dig up a magnificent stone, nearly square, and weighing some four or five tons, with sunk panelled mouldings to a depth of $1\frac{1}{4}$ feet. As the stone had fallen on its face, the delicate lines of moulding proved to be almost as perfect as on the day they were carved. A little further search was rewarded by the discovery of two smaller stones of similar design, which exactly fitted on to either side of the centre piece ; and it was then evident that the trio had formed an oblong canopy over some statue, or perhaps over a

throne. The pillars were discovered at some little distance from the canopy, at a depth of about four feet below the surface, and by degrees a series of oblong slabs were turned up, each bearing a bold fresco of peculiar design, which ran along, and were keyed into, the upper rim of the canopy. Finally, the site of the building was found about two feet down. The subsidence of the ground had displaced some of its pavement stones, but the general shape and the measurements left no doubt of its identity. Further excavations revealed no less than three large stone "sannasas," one quite perfect, the other two more or less mutilated; and also a very perfect specimen of a yōga stone, with twenty-five squares. The Paper then went on to describe "finds" in the adjoining jungle, the most important being a large sedant statue of Buddha, in excellent preservation. A little further on a magnificent staircase, unrivalled in the ruins for completeness and size, was unearthed. One of the door-guardian stones had fallen headlong, and was buried seven or eight feet deep; but when it was at length raised into position, it proved to be the most perfect specimen yet discovered. It measures 4 ft. 6 in. high by 2 ft. 3 in. wide inside the frame, the total length of the stone being 6 ft. The tip of the nose is broken; otherwise it is as perfect as on the day when it was carved. Still deeper in the jungle another large vihāra was discovered. When the trees and underwood that entombed it were at length cleared away, several pillars of great beauty were brought to light. They are monoliths, with highly-decorated capitals, 10 ft. 6 in. in height, while the width of each side of the pillar is $1\frac{1}{8}$ ft. Excavations are still going on here. About 200 yards to the east of this shrine I discovered still another vihāra, which differs in design from all those previously exposed to view. The slab form is as nearly as possible 38 ft. square; three rows of beautiful monolithic pillars, with delicately-carved capitals, run from east to west along the two sides of the platform, leaving a blank space in the middle, and I have little doubt that they supported a pagoda, or dome-shaped roof, and represent the only instance of this kind of roof at present discovered in Anurādhapura. To the north-west of the Kuttam Pokuna, a square pokuna of similarly elaborate workmanship has been found. The sides are lined with long smooth slabs of granite, arranged in tiers; and a long stone water-pipe projects into it, supported on a very grotesque and obese figure. Near it a very curious inscription was found, apparently in the Canarese language. A careful copy has been taken of it, and forwarded to the Colonial Secretary. In the jungle not far from the Thupārāma, I came across a curious stone, which has been identified as a "Pandu-oruwa," or dyeing-vessel. It is an oblong stone about 5 ft. in length, and $1\frac{1}{2}$ ft. thick. At one end there is a deep circular hollow, narrowing towards the bottom, the outer rim of the upper lip being decorated with the lotus leaf pattern. At the opposite end of the stone an oblong raised platform is cut, and its edges moulded. The stone was apparently for the dyeing

of priests' robes. In the channel recently cut I have found a large collection of ancient roof tiles, thickly coated with blue enamel, or glaze; none are absolutely perfect, though many are very nearly so. A great deal of old iron has been found, mostly in the form of rails, clamps, and bolts, proving, I think, clearly, that most of these stone pillars bore superstructures, and that the superstructures were of timber. The only articles of domestic use I have found are two old "katties," a pair of long scissors of a peculiar design, and one leg of an iron betel-nut cutter, ornamented with the head of a mythical beast. There is an old Italian saying that the safest time to turn heretic is when the Pope is dying: perhaps it may appear to be somewhat on the same principle that, in connection with the carvings and buildings we have been discussing this evening, I venture to suggest a theory to which I know that our President, of whom we are to take regretful leave to-night, will not agree. But I cannot help thinking it is just possible that the Tamil invader, who is generally looked upon as a mere iconoclast, was both the artist who designed and the workman who carried out the patterns and mouldings of the Great City. Of course one would like to believe that these delicate and chaste designs were the spontaneous outcome of the artistic Aryan mind, and spread from the cities of the Aryan invaders in Ceylon to the dark Dravidian continent, its neighbour on the north. Mr. Phœbus, the prophet of Aryan principles in Disraeli's "Lothair," "did not care for the political or commercial consequences of the Suez Canal, but was glad that a natural division should be established between the greater races and the Ethiopian. It might not lead to any considerable result, but it asserted a principle. He looked upon that trench as a protest." In the same way, there are many followers of Mr. Phœbus who looked upon the Palk Strait and the Gulf of Mannár as a protest: a watery intervention between the Tamil iconoclast and the Aryan artist. I confess that my own view of the matter is different, though an Aryan fellow-feeling makes me hope that the arguments which weigh with me will be successfully demolished. They are these:—1. Failing evidence to the contrary (and I submit that there is none trustworthy), the natural hypothesis to form concerning the architectural and artistic ideas which are realised in stone at Anurádhapura is that they gradually travelled down from north to south, and so were imported into the Island from the extremity of the continent, and not *vice versa*. 2. Unless we are to believe in the mystical flight through the air of the great missionary Mahindo, the assumption is that he travelled through the south of India to Ceylon, carrying with him reminiscences of the sacred edifices he had seen in his native land and on his journey, which he persuaded his insular converts to imitate and perhaps surpass, for the honour and glory of Buddha. 3. If we may trust the "Mahawamsa," we know as a fact that the early rajahs sought their wives from Southern India, that the Tamil Elala reigned peaceably for forty-four years, the great

Polonnáruwan monarch, Prákrama Báhu, imported Tamil artificers to carve his temples, and, as a pretty certain inference, that the early religion of the Island was Hinduism. 4. Nearly all religious emblems are plainly imported, and not original representations of local animals and ideas. The conventional rendering of the horse, the lion, the bull, and probably of the goose, *must* have travelled southward from the continent, while the "dvarpal," or door-guardians, the "makaratoranas," and the frescoes at the Isurumuniya temple are obviously of Hinduistic origin. The interesting ruins thirty-five miles south of Madras, known as the Seven Pagodas (so called, on the *lucus a non lucendo* principle, because they are nine in number), and which are of unknown antiquity, present so many strong points of resemblance to the sculptures of Anurádhapura, that I am surprised they have not been more dwelt upon. There are to be seen the same stairway, with highly mytbical animals forming the balustrades; the same door-guardians in the same saltatory attitude; there is the familiar flute-player of Surumuniya (an incarnation of the Hindu Mercury), and the squat, obese figures with a half-fractious expression, looking like Falstaff after he had swallowed his half-penny worth of bread. There is a roof precisely the same as that of the newly-discovered stone canopy; a stone bull which is own brother to the Anurádhapura bull with the prolific reputation; a wall with a bold frieze of elephants and lion closely resembling the elephant wall that surrounds the Ruwanwēlisēya; and many other minor likenesses, too numerous to detail. If my previous arguments are of any value they go to prove that Anurádhapura and Polonnáruwa are more or less replicas of the Seven Pagodas and similar Indian shrines. In conclusion, I would venture respectfully to urge upon the Society the advisability of encouraging in every possible way excavations similar to those I have detailed in so disjointed a fashion this evening. I only speak from a year's experience, but I am quite sure that an immense quantity of interesting discoveries remain to be made by a careful and intelligent use of the mamoty and pickaxe, and I can conceive no better archæological investment than the gradual acquisition of details concerning the two magnificent cities which have been so long and shamefully neglected. The first great want is an accurate and complete survey of all that has been discovered up to date; and with that foundation to work upon, with a regular supply of convict labour under intelligent overseers, and an annual monetary grant, I feel confident that these ruins would rank among the most interesting and instructive to be found in the world.

At the conclusion of the reading of the Paper, the President asked for discussion on it.

Mr. Cull demurred to the theory set forth by Mr. Burrows that the architects of Anurádhapura were the Tamil invaders and not the original Aryan inhabitants of the Island, and he would like to know if more light could be thrown upon that point.

The Bishop was very glad that Mr. Cull had challenged Mr. Burrows' idea on the subject, because he thought they would all be very much disappointed if the credit of that great work should be lost to the Aryan family, to which most of them had the honour to belong. He would not say that his confidence had been much shaken by the arguments of the reader of the Paper. He fancied the argument that in travelling from the north of India the invaders must have passed over from the south coast of India is a mistaken one. In early days people did not travel long distances by land, and in getting from the north of India to Ceylon they would come by sea, and if he remembered the "Mahawagga" correctly it states that they did come by ship. The parallel raised between the language and art of the Island and that of the north of India, he thought was a point which they would find came out more clearly the more they looked into it; but it was also true that the races of the north of India had great power in early days in the south, and brought their art into the south of India, and he had no doubt the interesting parallel Mr. Burrows had pointed out between the Seven Pagodas at Madras and the ruins of Anurádhapura had its foundation in that fact.

Mr. Berwick suggested that if the theory put forward by the Bishop was correct they would expect to find that the invaders, the builders of these great cities, would not have planted themselves in the interior of the Island, but that the colonies would have been placed more on the sea-border.

The Bishop said his remembrance of the history was that the colonists landed somewhere about Puttalam, and that they advanced gradually inland, and Anurádhapura was one of the first cities which they founded.

The President said the question Mr. Burrows had raised was a very interesting one, and he thought to most of them it would be novel. These were days in which many of their old preconceived notions, and he might say many of what they used to consider established beliefs, were rudely shaken, and amongst other things they might have to learn that the people of Ceylon not only had for seventy years to suffer under the subjugation of their Tamil neighbours of the south of India, but that they have nothing on which they can pride themselves, and that all the great irrigation works, architecture, and literature is due to the Dravidian element of Southern India. But he thought they would all of them want some stronger proof than his able friend had adduced before them, before they abandoned their belief that those works are Aryan, and that we owed almost all we have in Ceylon of the kind to the Aryan origin of the people. The President went on to speak of the endeavour of the Committee to secure for this Society photographs and casts of the more important sculptures connected with Buddhism, which have been discovered in various parts of India, and stated that they had obtained two very interesting albums of photographs from two different parts of India, showing

a totally different origin for these works of art, which in former days had led the people to illustrate the religion of their country. They would find there grounds for the carefully-considered suggestions which Mr. Burrows had thrown out. He was not prepared to say they would find those suggestions right, and he thought they would find that our architecture and all that is beautiful in the country is of Aryan origin; but it might be on further research they would find it was as Mr. Burrows suggested. To those who knew the interesting ruins which Mr. Burrows had described with so much enthusiasm, his descriptions would afford the greatest pleasure; those who did not know them he hoped it would induce such to go and see for themselves what treasures some, like Mr. Burrows and himself, had dug amongst the ruins and laid bare for their pleasure. He had now only to express the thanks of the Society to Mr. Burrows for coming there and reading his interesting Paper on the early works of architecture. He was sure they would vote the thanks of the Meeting by acclamation. (Applause.)

FAREWELL to Mr. DICKSON.

The Bishop:—It has been suggested that the honour should fall on me of proposing a vote of thanks to the chair. Proposing a vote of thanks to the chair is in many cases merely the duty of giving expression to an ordinary courtesy; but what is in our minds this evening is something more, it is to give expression to a real gratitude and a sincere regret. (Hear, hear.) The gratitude which we feel is not for anything which has taken place this evening only, but looks back a long way, and is due for a whole course of services. And it is accompanied by a sincere regret, a regret that when our President rises from the chair this evening he will be vacating altogether the position which he has adorned, and the importance of which he has enhanced by the zeal and ability which he has brought to bear upon it. It is not very long since, I believe, that Mr. Dickson has been able to take the part of an active Member of this Society, but in a comparatively short time he has done much. (Hear, hear.) His intimate acquaintance with this country, its people and the places in it, the conspicuous part he has had the opportunity of taking in developing its archæology, and his close interest in everything that concerns works of utility, ancient or modern, as well as the special attention he has paid to Eastern languages, have fitted him in a peculiar degree to occupy the President's chair of a Society which has so many objects within its scope as this one has. In that chair he has contributed, by Papers of his own, and by his able and instructive Presidential Address, valuable additions to the Proceedings of this Society. But that is not all, he has been able to kindle zeal in others, and to enlist for our Meetings the interest of the Members and of the intelligent public. I say it is not, I believe, a very long time since that Mr. Dickson has been able to take an active part as a Member of the Society, but it is many years since his name first began to be known as a worker in two, at least, of the

branches of study of this Society. To his work in developing the ruins of the ancient monuments which are found in this country I need hardly refer. Besides that, in the field of Páli literature, Mr. Dickson has made a name for himself as one of those first among European scholars to bring that study into popular interest. It was about the year 1875, I think, that his “*Kammavâcâ*” was published, and it at once superseded the ancient and necessarily imperfect edition of Spiegel, which had been in use since 1841. About the same time, or shortly afterwards, was issued his “*Pâtimokkha*,” which we fancy will supersede the Russian edition of Professor Mineyeff; but whether it be the *editio princeps* it certainly is the principal edition. It would be no slight thing now-a-days to show work like this, but things are very much changed since ten years ago, and the works which Mr. Dickson did are such as to entitle him to a prominent place, and his name will be remembered wherever Páli scholars exist. (Applause.) But we were hoping for yet more from our President, and under his inspiring leadership the Society was setting itself two ambitious tasks in this department of literature. We were thinking we might perhaps do something considerable in Páli literature, in contributing, at any rate, something towards the edition of the *Játakas*, and that in Singhalese literature we might lay the foundation of a dictionary. Whether we shall be able when our leader is gone, whose courage in putting his own shoulder to the wheel has been such as to embolden us to look upon such a task as not altogether impossible, whether we shall have courage to continue is a question we shall have to answer; but if these schemes ever come to anything they will be memorials of Mr. Dickson’s spirit, and will bear traces of his loss,—as lost to us, for the present at least, it seems he must be,—and therefore it behoves us to retain what we can of his spirit and take up his mantle. He leaves to us as students and scholars the same example which I believe he should to his colleagues and subordinates in the public service, an example of courage and conscientiousness. We hear it sometimes said of one man that he is nothing if not brilliant, and of another that he is nothing if not laborious; but even if it cannot be said of Mr. Dickson that he was painstaking, it can be said that he was brilliant, and if it cannot be said that he was brilliant, which it can, it can be said that he was painstaking. (Applause.) It is rarely given to one man to be both, but those who know Mr. Dickson, those who as his colleagues or subordinates in the public service have been closely connected with him, will bear me out in saying that with the temptation to be merely brilliant he is determined to be also painstaking. (Hear, hear.) He leaves us an inspiring example of one who is a lover of work, and a lover of good workmanship, and a workman who needeth not—and that is what we should all desire for ourselves whatever our work may be—to be ashamed of the work he turns out. That example we who remain in the Society should keep in mind, and since our President himself must leave us we will speed him on

his way with our most earnest good wishes and our sincere thanks. (Loud applause.)

Mr. Berwick :—Ladies and gentlemen, it is not usual in seconding a vote of thanks to say much, and I feel if I were to attempt to say much upon the subject which you have heard now, I should be repeating what has been so well said by his Lordship the Bishop of Ceylon. At the same time I cannot resist the opportunity of giving expression to the great pleasure which I feel in taking a secondary part in the proceedings of this evening, in joining in the expression of gratitude to a President who has distinguished himself so much already, and who has given promise to distinguish himself even more before his work is done, and joining in the expression of regret that we are to lose the valuable services which he has rendered to this Society. If I may to some extent modify a metaphor which I heard the President use in another place last evening, when he referred to the dark plumaged bird which hovers over every joy, I think there is another and a brighter plumaged bird : there is the dove of hope, and though we are to lose Mr. Dickson now there is this hope that he is not going very far away, he is going to a land which is very closely associated with that which he leaves, and we know he will find in the Straits many points of contact with Ceylon,—in ethnology, in archæology, and in many various ways ; and he will have opportunities of contrasting these points, and we may hope that Mr. Dickson, who, I believe, will continue a Member of this Society, and who will continue to take an active part in its operations, will favour us with communications upon those points from time to time.

The President :—Gentlemen,—You will not expect me to put to the vote the motion which my Lord has put before you, and which my friend Mr. Berwick has seconded, nor will I for the moment pay any attention to the too-flattering words which his Lordship has addressed to you respecting me, and which Mr. Berwick has been so good as to endorse. Those words I shall put aside as a kindly and friendly expression of feeling, and will not commit the fault of taking them to myself as deserved. I have now to resign you the honourable office you have been good enough to allow me to fill. I have humbly endeavoured to serve you to the best of my ability, and I shall be thankful if I can think I have been of any service to you. I am happy in resigning this office to tell you that the Committee of your Society met together to-day for the purpose of considering how this office should be filled, and I am sure it will give you all the greatest satisfaction to learn, and that you will all endorse with one accord and one voice the conclusion at which the Committee arrived unanimously and without one word of dissension, and that the Society will be an immense gainer if, on this opportunity, they are able to secure to themselves the advantage of obtaining my Lord's consent to become the President of your Society. (Applause.) It is the unanimous decision of the Committee that they will

propose to you at the next Annual General Meeting that the Bishop of Colombo shall be elected with one voice to be your President. I may say, and I say on account of the prospects of the Society for the future with very great regret, that he is the one man pointed out to be your President. I wish I could say that he had a second in the Society, but as that is not so, it is a good turn to the Society that they will be able to ask one so distinguished by learning and by scholarship, and by catholicity of character, to become President of a Society which is so essentially catholic in its nature. The important work of the Society of the past year has, indeed, not been mine, but has been his. It was to my Lord's suggestion that we undertook the great and interesting work of the study of the Játakas, as a Society, and it has been to his position as Chairman of the Committee appointed to undertake the great work of a scientific dictionary of the Singhalese language, that we have been able to give a satisfactory account of this year's work. I am able to read you an extract from a letter from Dr. Rost, the learned Librarian of the India Office, who, in addition to being one of the greatest amongst Oriental scholars, is, perhaps, of all Orientalists, the one with greatest sympathy with Orientalists all over the world. He writes :—"The Játaka work taken up by your Society is meeting with high approbation here." That, gentlemen, will show you what interest is taken in the important work which the Bishop has initiated, and which you have carried on with considerable success. That work is in the Bishop's hands, and that work is the Bishop's. If that stood alone, it would be sufficient to show you how great a gain you will have in obtaining the services of the Bishop of Colombo. But it is not that alone. He has undertaken a far greater and more important work. He has undertaken to be Chairman of the Committee for preparing a scientific dictionary of the Singhalese language. I need but tell you it may be fifty years before the fruits of his labour can be seen, to show you the task he has undertaken. I have great pleasure in congratulating the Society upon having the consent of the Bishop of Colombo to place his services at your disposal. Gentlemen, I thank you very much for the kindness with which you have responded to the cordial words my friends have addressed to you.

The President announced that the Bishop, as one of the Vice-Presidents of the Society, would preside at its Meetings till the Annual General Meeting, when it would be their duty to elect him President.

The proceedings then terminated.

COMMITTEE MEETING.

4th December, 1885, 4 p.m., United Service Library.

Present :

The Right Rev. the Lord Bishop of Colombo, D.D., Vice-President, in the Chair.

J. G. Dean, Esq., Hon. Treasurer.	D. W. Ferguson, Esq.
T. Berwick, Esq.	W. P. Ranasinha, Esq.
J. Capper, Esq.	J. L. Vanderstraaten, Esq.,
J. B. Cull, Esq., M.A.	M.D.

W. E. Davidson, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of last Committee Meeting.

2.—Laid on table the translation of Professor Virchow's Monograph on the Veddas of Ceylon, which had been received by the Society through the kind offices of Mr. Freudenberg.

Resolved,—That inasmuch as the translation is one authorised and supervised by Professor Virchow, the Paper should be printed *in extenso* in the Journal of the Society ; but that for the purpose of reading and discussion at Meetings of the Society, an abridgement of the Paper should be prepared by Mr. Berwick (who has kindly consented to do so), and this abridgement read at the next General Meeting.

3.—The Secretary having brought forward the question as to whether the Society, as a Society, could be represented at the forthcoming Indian and Colonial Exhibition of London (1886), and he having suggested the feasibility of representing a collection of the Pali classics and a set of the Society's publications, and the possibility of sending to the exhibition a Singhalese man to illustrate the manner in which old writing is done in Ceylon, it was resolved, after some discussion, that the Secretary do communicate with the Secretary of the Executive Committee with a view to carrying out these suggestions, if this can be done without any expense to the Society.

4.—*Resolved*,—That the Honorary Secretary be requested to insert advertisements in the local papers for the numbers of the Society's publications which are out of print, and of which copies are wanting in the Society's Library.

5.—*Resolved*,—That the next General Meeting of the Society be held on the 15th December, 1885 ; that the Annual General Meeting be fixed for Monday, the 21st December, 1885 ; and that a Committee Meeting be held on the 17th December, 1885.

COMMITTEE MEETING.

7th December, 1885, 9 p.m., at the Colombo Museum.

Present :

The Right Rev. the Lord Bishop of Colombo, D.D.,
President, in the Chair.

T. Berwick, Esq., Vice President.	J. Loos, Esq., M.D.
A. M. Ferguson, Esq., C.M.G.	J. H. Thwaites, Esq., M.A.
D. W. Ferguson, Esq.	J. L. Vanderstraaten, Esq., M.D.
F. C. Loos, Esq.	J. G. Wardrop, Esq.

W. E. Davidson, Esq., C.C.S., Hon. Secretary.

Business.

- 1.—Read and confirmed Minutes of last General Meeting.
- 2.—The following gentlemen were then elected Members :—

The Rev. S. Langdon.
The Hon. Cecil Clementi Smith, C.M.G.
R. Webster, Esq.

3.—Mr. Berwick then read an abridgement, very carefully prepared by himself, of a monograph on the Veddás of Ceylon, written by Professor Virchow, of Berlin, and since translated for this Society. The Paper, which was illustrated by a series of skulls lent for the occasion by Dr. J. L. Vanderstraaten, contained the Professor's conclusions, which were somewhat at variance with those arrived at by many persons who have studied this obscure race. It was decided, however, owing to the lateness of the hour when the Paper was concluded, to postpone any formal discussion of the subject until a future occasion, when Mr. Berwick's abridgement will be printed, and be in the hands of Members who were prevented from attending the Meeting. At an early gathering, it is hoped that the Society will be in possession of the views of several of its Members who have had exceptional opportunities of studying the Veddás, and that the views of Professor Virchow may be then discussed more fully.

The evening was unfortunately wet, which prevented the attendance of many Members.

THE VEDDAS OF CEYLON.

(An Abridgement, prepared by Mr. T. Berwick, of the
Monograph by Professor Virchow.)

[For the marginal headings the compiler of the Abridgement is responsible.]

Object of the Paper.—In the various mixtures of races inhabiting Ceylon, the Veddás have for a long time been objects of special prominence in the study of ethnography, because

there is much room for conjecture that in them is preserved a remnant of the aboriginal inhabitants of the Island. And now, when according to all accounts their number is so rapidly diminishing that, at no very distant date, their last members will have disappeared from among the living, a peculiar interest is added to the study, and it is desirable to transmit to posterity a trustworthy picture of their singular characteristics. For this purpose the material we now have is nowise sufficient; hence the object of the following disquisition is not merely to collect what has been already ascertained, but to point out the gaps which can be supplied only by further local researches. It is to be hoped that this may stimulate to the immediate application of all possible means to obtain the wanting material.

The Veddá Land.—The Veddás have dwelt, at least for some centuries, in the vast forests on the south-east side of the Island, between the mountains and the sea, and especially in the wild tracts of land called the *Veddá-rata* of Bintenna and the *Mahá Veddá-rata* of Uva. The more savage remnants of the tribe live in the beautiful District of Nilgala and in the forests of Bintenna. There is much evidence, however, that in times not very far distant the Veddás were scattered over a larger extent of country, which reached much further northward, and their earlier presence in the south and even south-west is also proved.* They are indeed spoken of as having formerly inhabited the districts between Adam's Peak and the Rayigam and Pasdun Kóralés on the west coast, south of Colombo, and are conjectured to have given its former name to Saffragam. (*Habaragamuwa* : *Habara* = "barbarian.")

The present Veddá land is very lovely, embracing a comparatively flat, wooded country, nowhere raised more than 200 feet above the level of the sea, and frequently having the appearance of a park. The character of the soil varies: damp and unwholesome marshes alternate with rock-ribbed hills, which stud the country between the central mountains and the sea coast. Here the Veddás live in perfect isolation even from their more civilised tribal brethren, without fixed abodes, but yet upon their own recognised lands, mostly in small groups or simply in families. Rarely do they venture beyond their own boundaries, and then only for the purposes of exchanging honey, wax, skin, or venison, for iron, axes, arrow-points, &c.

Their Numbers.—This secluded existence explains why the estimates of their numbers vary so greatly. No recent estimate leads us to conclude that the total exceeds 1,500, and the extinction of the tribe seems imminent, though wherefore we are unable to discover.

* *Knox*.—"Historical Relation of the Island of Ceylon," 1817, p. 91, 122. *Percival*.—"Description of the Island of Ceylon," translated by Bergk., p. 337. *Bailey*.—"Trans. Ethnol. Soc., Lon., 1863, new series, Vol. ii., p. 313, note.

Village and Forest Veddás.—From the time of Knox they have been classed in two groups, a “tamer sort,” or “village Veddás,” and a “wilder,” or “forest Veddás.” All observers, however, agree that both belong to the same race. Hence, for the study of their physical condition, the two groups may without hesitation be united; but for the observation of their social and physical conditions we must hold them strictly apart. In the latter respect only the forest, or jungle Veddás, are of any interest to us. These, therefore, will be mainly spoken of here; nevertheless, we may not venture quite to set aside the village Veddás, since their actual settlement and civilisation have succeeded only very imperfectly as yet.

Attempts at their Culture; Yakkho Worship.—All attempts to bring the Veddás into fixed abodes and to raise them to a higher culture have suffered shipwreck in far greater measure than the efforts to civilise the Australian. Whether they actually have any conceptions of God, or God-like beings, is, to say the least, very doubtful. The only thing that is proved is a lower kind of demon or *yakkho* worship amongst them, which here and there assumes the form of a worship of ancestors. Mr. Bailey tells us that those in Bintenua had mourned and buried their dead for a long time, but that the more barbarous inhabitants of Nilgala had only just begun to do so. Formerly they threw their dead into the jungle, or left them where they had died; after covering the body with leaves, they laid a heavy stone upon the breast, and sought out for themselves another cavern, giving up the one where death had entered to the spirit of the departed. These spirits—now become *yakkho*—watch over the welfare of those left behind, come to their relations when they are ill, visit them in dreams, and grant them flesh in the chase. They are invoked with dance and song around an upright arrow. Sometimes, while preparing for the chase, the spirit is promised a piece of the flesh of the slain animal; at other times they cook something and put it in the dry bed of a river or other obscure place, invoke the souls of the departed, dance round the food, and perform their incantations.* Mr. Hartshorne describes these sacrificial feasts. While invoking the departed spirit they roast the flesh of the *wandurá* monkey, or *talagoyá* (iguana), with honey and edible roots, and then distribute it among those present, who eat it on the spot.

* [In respect to these beliefs and customs—apparently put forward as illustrations of barbarism—do we, the most civilised, not also seem in our dreams to see those who have occupied our thoughts when alive, and still occupy our affections when gone? and who has not at least wished, or hoped, if not prayed for the countenance, the approval, even the aid in our needs, of venerated ones passed from hence? Do not the vastest number of Christians pray to and invoke the dead, not to speak of sacrifices and vows and offerings to them? Is the difference so great at bottom between the ideas of the Veddás on these heads and those of Augustan Rome or Modern Europe?—*T. B.*]

round the body by a string. The women wore round iron pegs stuck through their ears. Mr. Hartshorne, however, saw ornaments worn in the ears by both sexes, generally pearls or, what seemed peculiarly admired, empty cartridge cases. Evidently these are quite modern innovations.

Marriage relations.—It is a custom with them to marry with a younger sister—a practice in use among the royal families of the Singhalese from the time of Wijaya. The only marriage ceremony consists in the suitor bringing food for the parents.

Emotional expression.—There seems to be no particular depth of feeling among them. All the descriptions indicate rather a certain morose indolence. Whilst they can help it they not only do not laugh themselves, but they despise those who do. Mr. Hartshorne says of them that they are incapable of laughing. This, if it be true, is a peculiarity which, so far as the author knows, has not been told of any other race of people, and has only appeared among certain idiots.*

Intellectual capacity.—In point of intellect they seem indeed to stand very low. If they have any notion of numbers, or can count at all, it is to the most limited extent, probably not beyond five. It is said that they have no word for colour, nor any perception of differences of colour; that their memory is defective; and that they are incapable of forming any general ideas. Sir Emerson Tennent says they have no notion [perhaps it would be more correct to say only a very limited and vague notion] of time or space; no words for hours, days, or years; † no games, no amusements, ‡ no music. § These statements, however, apply in their full breadth only to the “wild sort,” for Davy says of the village Veddás that they have a rough kind of song performed as an accompaniment to a clumsily-executed dance. Granting some of the observations furnished to be too exclusive, still we are compelled to acknowledge the inferiority of the race.

* [It seems impossible to deny the existence of emotions, and of the outward physical expression of these, to any vertebrated animals at least. However low the sensibilities, pain and pleasure must equally be experienced, and be visibly manifested in the absence of some physical defect, and their deliberate suppression or control would seem to argue a degree of intellectual and moral strength which no one has given the Veddás the credit of possessing. Possibly, a low emotional excitability has been confounded with incapacity. Mr. Hartshorne's assertion has, however, been disproved, as appears in Russels' account of the Prince of Wales' visit to India.—*T. B.*]

† [But the ordinary Singhalese cultivator is singularly poor and vague in the observation and notation of time and space, though he does measure the day by the length of the shadow in feet, and the height of the sun by comparison with the height of a cocoanut tree. Is it quite certain the Veddás do not the same.—*T. B.*]

‡ [If their children do not gambol, if their men and women have no enjoyments, their life must be stagnant indeed and far below the level of the beasts in their forests. But who can believe this?—*T. B.*]

§ [Also incredible; and it has been already stated that they invoke the dead with dance and song.—*T. B.*]

Caste.—As they have no distinction of caste it is a very striking fact that they not only look upon themselves as superior to their neighbours, but are looked upon by them as members of a high and even of a royal caste. The Sighalese term for the agricultural caste is *Goyi-waṇsé*, the Malabar term *Wellála*; to this caste they are said by writers to belong, and those of Bintenna are said to call themselves “Vēddá-Wellálas.”

Dodda-Vēddás: Rodiyas.—In connection with this subject we must be careful not to confound the Vēddás with the “Dodda-Vēddás,” a name given to a division of one of the very lowest castes, or rather a tribe of outcasts, including the Rodiyas. Thousands of years had not sufficed to reduce the Rodiya outcasts to the degree of degradation to which the Vēddás had fallen when Knox first heard of them.

HISTORICAL AND LINGUISTIC.

Cultivated Races in the Island: Tamils.—This would be the place to bring forward the historical and linguistic observations which concern the relations of the Vēddás to the cultivated tribes of the Island, by far the most numerous of whom, after the Sighalese themselves, are the Tamils, who now exclusively occupy all those portions of the Island which lie nearest to the Indian continent, and whose connection with the Dravidians of India seems unquestionable. These are the *Damilos* of the “Mahá-waṇso,” a Páli term exactly equivalent to *Drávida* in the Sanskrit.* In local English speech they are frequently called Malabars, as if they came only from the Malabar coast, but in point of fact they belong to the ancient great Pándian kingdom, which stretched from the east to the west coast of India, and from the Deccan to Cape Comorin, but has ultimately dwindled to the little state of Madura. The first warlike invasion of the *Damilos*, of which there is historical record, took place 237 B.C., and during the whole of the next fourteen or fifteen hundred years their invasions were constantly renewed, and the dynasties of native princes repeatedly superseded by their Tamil conquerors. † In the beginning of the thirteenth century the whole country was overrun, subjected, and cruelly devastated, its inhabitants tortured, and many of its Buddhist monuments destroyed by a great expedition from Kálinga and the northern Circars of the Dekkan, under Mágha, who assumed the throne of the Island. In the result, the Sighalese people succeeded in recovering or retaining the Provinces of Ruhuna in the south, and Mayarāṭa in the mountainous centre of the Island; but the north of the country—the Province of Pihiti or Rájaraṭa, the land of the kings—remained,

* R. C. Childers. “Notes on the Sighalese Language.” Journal Royal Asiatic Society, 1875, London, Vol. viii., p. 133, note.

† *Mahāwaṇso*, chap. xxi., p. 127. *Ibid.*, Appendix, “Sovereigns of Ceylon,” p. lxi. Glossary, p. 5. *Mah.*, p. 128 lxiv. *Ekanayaka*, in Journal Royal Asiatic Society, 1876 Vol. 8, p. 297. Tennent, i. 412.

Yakkho and Nāga-worshipping Communities in early times.—

This word "*yakkho*" designates, according to Turnour, a kind of demon; though the demon-worshippers are also called *yakkho* and *yakkini*. He derives it from the root *yāga*, "to bring offerings." This word has, for a long time, justly excited the attention of scientists, since in the great historical work of Ceylon, the *Mahāvamsa*, the earliest inhabitants of the Island are called by that name. When Wijaya, the founder of the first-known Ceylon dynasty, in the year of Gautama Buddha's death, 543 B.C., landed in the Island, he found an already organised *yakkho* state; and indeed it is said of Gautama Buddha himself that he came to Laṅkā, "a settlement of the *Yakkho*." It is hardly allowable to conclude from this, with Sir Emerson Tennent and others, that these were identical with the *Veḍḍās*, and that up to the time of Wijaya an aboriginal homogeneous race inhabited the Island, though it may not be a mistake to assume that in the earliest period almost the entire population were devoted to this *yakkho*-worship as it now exists amongst the *Veḍḍās*. The identification of the *Veḍḍās* with those *Yakkho* would require us to assume such a deep physical and intellectual degeneration of the present *Veḍḍās* from old *Yakkho* times as would be without parallel in history, as well as in ethnology, and such as the author cannot bring himself to admit. Not a single fact sustains the conjecture that Wijaya, with his followers from the valley of the Ganges, was the first stranger who came to Ceylon. On the contrary, the legend of the advent of Gautama Buddha, and, no less, the old traditions of the *Rāmāyana*, clearly point to earlier arrivals and invasions, and if Wijaya found some kind of political organisation on the Island, the time in which the whole north of the Island was *Veḍḍā*-land must then be placed a good deal further back. The first visit of Gautama Buddha to the Island was, according to the *Mahāvamsa*, in Binteṇna. According to the *Yakkho*, in whose midst the Buddha here appeared, he visited on a second occasion, *Nāgadīpa*, the abode of the *Nāgas*, or snake-worshippers, which is generally assumed to be the name for the north and west of the Island; at any rate, mention is made of *Nāgas* living by the ocean, as well as mountain *Nāgas*, and a *Nāga* king of Kalniya, in the neighbourhood of Colombo, is spoken of. If any importance is to be attached to these traditions, a number of tribes, or at least a division of the original population, must be inferred. And it is not without value that the description of the *Nāga* states, in these most ancient myths, discloses to us a much more perfect organisation than we find any account of in the tales of the *Yakkho*. Nevertheless, we must renounce the idea of using these myths as the basis for ethnological contemplation, and for building up a highly developed *Veḍḍā* state in prehistoric times.

Veḍḍās nomadic hunters.—Up to a very recent date the *Veḍḍās* have been a nomadic, half cave-inhabiting race of hunters, each small family group having its special vaguely-defined

hunting ground, comprising a proportionately vast tract of woodland. Of any kind of culture, garden or farm, there was no trace. They had no domestic animal save the dog, of a species identical with that common in Ceylon, and apparently trained not for hunting but for watching. Their hunting implements are the simplest possible, consisting of a strong bow 6 feet long, and two or three arrows of $3\frac{1}{2}$ feet, having points of wrought iron, not made by themselves but obtained by barter for honey and wax. Besides these they have only an iron axe, or sometimes two (a larger and a smaller), obtained in the same way. Mr. Hartshorne rightly finds in their word for axe a reminiscence of an earlier period when stone weapons were in use among them, and for which it might be a not unprofitable task to explore the caverns where, according to Mr. Bailey, bones of the dead are still to be found. They subsist almost wholly on animal food, excluding the flesh of cattle, the elephant, bear, leopard, jackal, and fowls. Their food is cooked but very roughly, as they have no clay or earthen vessels. They have no special stimulants, and neither betel nor tobacco, but chew a kind of bark. Their only drink is water. Mr. Hartshorne says that even salt was unknown to them, but that when it was given to them they were much delighted with it. Only in occasional places where European influence is perceptible do we find a rude kind of agriculture, in the form of little strips of chena cultivation. With this exception, which really cannot be taken into account, their whole existence depends on the product of the chase; and there is nothing to speak of which indicates that anywhere or at any time they have risen above the condition of a savage tribe of hunters. Indeed, they have never arrived at even the very crudest form of permanent dwelling places; and although they sheltered themselves from the inclemency of the weather in natural caverns, or in simple huts made of branches of trees and bark, they seem never to have made these their settled abodes. On the contrary, perpetual change of place within their hunting grounds has been ever the rule.*

Influence of their mode of life on their Psychological Condition.—Hence their social intercourse is essentially limited to their next of kin, whose number is often very small, consisting of only four or five persons, and all stimulant to higher acquisitions and enjoyments, and need for sustained mental effort is, therefore, wanting.

Their Peaceable Character.—In character they are peaceable among themselves, and towards strangers so long as they are unmolested. They respect the rights of property, and are true and truth-loving.

Dress and Ornaments.—Both sexes go almost naked. In former times they wore pieces of bark from the *riri* tree (a species of *Anticaris*), which were later replaced by little bits of cloth held

* [And a necessity of their life, as hunters depending on game for their subsistence.—T. B.]

even as far as the Máhawila-ganga, in the possession of the Tamils, and was by them wholly and permanently Dravidised.

Moors.—More peaceable invasions of the country took place by Muhammadan Arabs, whose descendants are now called Moors, or Moormen. There seems to be no doubt that, at least since the first, and certainly since the sixth century A.D.,* very extensive mercantile relations existed between Persia, Arabia, and Ceylon, and that since that time many of these *Mauren* (as the Portuguese called them later) remained in the Island. The present Moors seem to be descended partly from these immigrants, who intermarried with native women, and partly from persons of similar origin in India, who in large numbers settled in the districts of Chilaw and Puttalam. † There is now little or no distinction between these two groups of Moors, who are scattered over the whole Island, and are the chief mediums of all mercantile intercourse—even with the Veddás.

Malays.—Malays, belonging throughout to the Muhammadan religion, are to be found in the Island only in comparatively small numbers, but scattered over many regions. According to the representations of Mr. Pridham‡ they are descended chiefly from the little Rájás and their followers, whom the Dutch brought hither from Java, Malacca, and Sumatra, and who were later taken by the English into their native regiments. More important it would be for us if the opinion were correct that the original population of the Island had been Malays. This is supported by the certainly very noticeable fact that the Singhalese use double canoes, or boats with booms, just such as are used in all the regions inhabited or colonised by Malays. This, however, is the only foothold for the hypothesis of an ethnic relationship.

Europeans, Negroes, Parsees.—Naturally, in the last centuries, the different nations of Europe, especially Dutch, Portuguese, and English, have added to the population; but for our researches they are of no importance. The same is to be said of the African Negroes and the Parsees, the former of whom have been only recently introduced, whilst the latter immigrated at different periods, but in small numbers.

Singhalese.—The southerly half of the Island, the old Province of Ruhuna and the central Maya-raṭa, are still peopled by the Singhalese; the former by comparatively pure-blooded Singhalese, the latter by the somewhat more mixed Kandyans, the immediate neighbours of the Veddás. The ethnological position of the Singhalese has been until now discussed chiefly on linguistic grounds, and on these it has been inferred by some that the Singhalese belong to the great D-akkan family, and by Max Müller that they are a mixture of Indians with Dravidian aborigines. But others entertain directly the opposite opinion, and particularly

* *Tennent*, I. 546, 555, 607.

† *Pridham*, i. 470.

‡ *Pridham*, p. 492.

Childers,* who derives the Sīhalese language from the ancient Eḷu, with, however, an immense admixture of Sanskrit words partly unchanged. According to him the word *Eḷu* is identical with the word “Sīhalese,” by which the Sīhalese call themselves. It stands for the old word *Heḷu* or *Heḷu*, and this again for the still older *Seḷa*, which leads us back to the Pāli *Sihala*. The Sīhalese language is very nearly related to Pāli, which, however, only represents the dialect of one of the districts of Māgadhā (the modern Behār), from a district of which (Lala) Wijaya, the founder of the Sīhala dynasty, is said to have come. Hence Sīhalese is one of the native Aryan (Sanskrit) languages of India, and very ancient, for it is absolutely identical with the Eḷu of the fifth and sixth centuries B.C., which is also found on the rock inscriptions of Mihintalé of the second or third century.

Veḍḍā Dialect.—What place the Veḍḍā language holds relatively to this is still in the highest degree dubious. In Ceylon itself the opinion has long prevailed† that it is a broken or corrupted Sīhalese; and all writers on the subject—Bailey,‡ Max Müller,§ E. Taylor,|| Hartshorne,¶ and Cust**—seem to consider it to be a dialect of, or to approach to the Sīhalese. But there is much difference of opinion as to the existence in it of Dravidian elements, the supposed mixture of which (Telugu) in a dialect of an Aryan tongue (which he considers Sīhalese to be) leads Mr. Taylor to say that “their language makes a mixture of Aryan blood along with Aryan language probable, whilst their bodily characteristics show that the race of Veḍḍās belongs chiefly to the native pre-Aryan type.” The disagreements in the views of linguists are so great that we unfortunately gain very little from them towards a just comprehension of the phylogenetic position of the Veḍḍās. On the contrary, the mystery that envelopes this people; so remarkable in themselves, is vastly increased, and the purely anthropological interest comes even more into the foreground.

The word ‘Veḍḍā.’—“Veḍḍā,” or some modification of it, is widely used in India—a whole series of little tribes dwelling far apart, and who probably have not the least connection with one another, bearing the very same name, or one very like it. Whether the word be derived from the Sanskrit *viyadha*, “hunter” or the Tamil *vedan*, “hunter,” “wood-dweller,” this much seems

* Childers, Royal Asiatic Societys’ Journal (new series), London, 1875, Vol. vii., p. 35; 1876, Vol. vii., p. 131. *Alwis*, in Journal Ceylon Branch R. A. S., 1876, p. 70.

† Knox, l. c., 122; Starkie, in Journal Ceylon Branch R. A. S., 1853, p. 80; Gillings, 84.

‡ Bailey, l. c., 297, 305, 309.

§ Max Müller, cited by Childers, l. c., Vol. viii., 131, note.

|| Journal Ethnol. Soc., London, 1870 (new series), Vol. ii., p. 96.

¶ Hartshorne, l. c., 417.

** Cust, “Sketch of Modern Languages of East India,” London, 1878, p. 63.

certain, that except when used in combination (as in the case of *Dodda-Veddá*) it always relates to aborigines, or savage races.

The Ethnological problem not to be solved by Linguistics, but by Anthropology.—Up to the present time two leading views stand opposed to one another, which are mainly supported by linguistic observations, and only in part by anthropological facts. According to one, the *Veddás* would be next of kin to the *Dravidians*; according to the other, members of the great *Aryan* family. In either case they must have immigrated from the Continent, only in the first very much earlier than in the second. If we assume that the *Veddás* originally belonged or were nearly related to the *Dravidians*, or even, if different from them, at any rate a savage aboriginal tribe, and that they only received their present language subsequently from *Aryan* conquerors, then it is difficult to conceive how the process of *Sinhalesing* the language could have been accomplished, whilst their whole way of living, their customs and habits, remained wholly unchanged. On the other hand, the hypothesis that the *Veddás* are *Sinhalese* who have become savage, would require us to fall back on some period after *Wijaya*, and, contrary to all experience, we should have to assume a descent from a high state of comparative civilisation to a degradation too great to be conceivable, unless we can prove at the same time a very deep physical demoralisation; and that, too, whilst in closest proximity,—even in direct contact,—with a people who had passed through a long and eventful history. From whatever side we consider the question, we must come to the conclusion that linguistics can only be used as aids in the investigation; and that if a real solution is to be found, it is only possible by means of anthropology.

ANTHROPOLOGICAL.

Veddás.—The earliest known description of the *Veddás* is contained in a work attributed to *Palladius*, Bishop of *Helenopolis* in *Bithynia*, who died 410 A.D. and in which he describes a journey made from *Thebes* to *Ceylon*. The *Veddás* are there described as feeble and small of stature, and as having heads black and apparently large, with long, smooth, unshorn hair. *Davy* has given the first description resting on autopsy. He says:—"Such of the village *Veddás* as I have seen were in general small men, between 5 ft. 3 in. and 5 ft. 9 in. high; muscular and well made; in colour, form, and features resembling the *Sinhalese*. Their appearance was wild in the extreme, and completely savage. Their hair seemed never to have been combed or cleaned; it was long, bushy, and matted, hanging about their shoulders and shading their faces in a very luxuriant and disgusting manner: nor were their beards less neglected." *Sir Emerson Tennent* describes their children as unsightly objects, entirely naked, with misshapen joints, huge heads and protuberant stomachs, and says of their women that they were the most repulsive specimens of humanity he had ever seen in any country. The men, he says, also presented

the same characteristics of wretchedness and dejection. He speaks of their projecting mouths, flattened noses, and stunted stature. Of several measured by Mr. Bailey, the tallest, who towered above his fellows, was only 5 ft. 3 in. in height, and the smallest 4 ft. 1 in.; and he concludes the average height of the men to range from 4 ft. 6 in. to 5 ft. 1 in., and of the women from 4 ft. 4 to 4 ft. 8 in. Observers present no facts which indicate disproportionate or imperfect development of the separate members of the body. Only Mr. Hartshorne asserts that they have short thumbs and sharp-pointed elbows. The descriptions we have of them are sufficient to show us that the Veddás are a dark, but not actually black race, and not woolly-haired like the Negro; and that they are a very small, not to say dwarfish race.

As to their features, Bailey says that these are, on the whole, tolerably regular. He, like Sir Emerson Tennent and Hartshorne, speaks of the flatness of the nose, and of the lips as somewhat thick. A woodcut, prepared from a drawing made from a photograph of a group of six Veddás, who were presented to the Prince of Wales, shows plainly the growth of the hair; the noses comparatively short, broad at the end and flattened; the eyes apparently deep-set; the lips of the younger persons full and bulging; and this gives a far more vivid idea of the people than any description could furnish. One only of the men has anything like a beard. We see the little spear worn by the men, the great bows they carry, the arrows with the leaf-like points, and, finally, the iron axe stuck in the girdle.

If we add to the foregoing description of their features, the short thumbs and sharp-pointed elbows referred to by Mr. Hartshorne, there are indications enough to distinguish the Veddás in a noticeable manner from the Oriental races living in their neighbourhood.*

In our comparisons with other races, the Singhalese and the Tamils come chiefly under consideration: the others only collaterally. Those two are so predominant, both through their numbers and the extent of territory they occupy, that, apart from their exclusively historical claims, they must be specially considered.

The Singhalese.—For purposes of comparison with the Veddás, the information with regard to the relative physical condition of their neighbours is very deficient, and osteological material scanty in the European collections; and what there is of that rather unsafe. The following remarks must, therefore, be taken with reserve, and are made principally to induce the sending of better material, and especially photographs, half lengths and not too

* [The detailed craniological observations which follow the descriptions of the external physical appearance of the different races are here omitted, as the material points are collected and compared or contrasted in the pages which discuss their comparative craniology and osteology.—*T. B.*]

small, showing the profile and front face in the right horizontal position.

The Singhalese occupy in the main the south and south-west of the country. According to Sir Emerson Tennent the inhabitants of the south coast, from Galle to Hambantota, are the purest Singhalese. This part formed an important division of the old Province of Ruhuna, which was very early colonised by the descendants of Wijaya, who neither mingled with the Malabars nor had any intercourse with them.

Physical appearance compared with the Veddás.—If we compare the descriptions given of the Singhalese with those of the Veddás, we find in reality few points of difference. The complexion of the latter may be on the average somewhat darker, but it varies, apparently, within the same limits. It is equally doubtful if the hair varies; allowance being made for its neglected, dishevelled condition in the one case, and its carefully combed and well-kept condition in the other, it may be considered that the difference here is owing rather to culture than to original peculiarity. The average height of the Singhalese seems to correspond with that of the tallest Veddá, but they are also somewhat shorter than Europeans. Among all the characteristics cited, there is in reality only one which seems to have made a great and decided impression on every observer, to wit, the form of the nose. Whilst with the Singhalese it is very prominent, resembling an eagle's beak, and therefore thin and round, with the Veddás it is always described as flat and with widely distended nostrils. Add to this, the thick and projecting lips and the large mouth, and perhaps also the comparative smallness of the Veddá face, and there remain few facial characteristics for diagnosis.* We may say that the Singhalese also belong to a dark, perhaps best described as a brown, smooth-haired, and a not (or only very moderately) prognathous race,—that is to say, the jaws do not project, or only slightly.

The Tamils or Malabars: their distribution in the Island, and physical appearance.—We understand by this term the Dravidian immigrants who, in historic times, came from many different parts of the peninsula of Hindústán, and in the course of two thousand years multiplied so greatly, that they almost exclusively peopled the north and a large portion of the east of the Island, more especially along the shore, and whom Pridham speaks of as inhabitants of the land from Batticaloa on the east to Jaffna on the north, and from there as far south as Puttalam on the west coast. When the Portuguese, the first pioneers of civilisation, obtained a firm foot-hold upon the Island, the Malabar rule was firmly established in the old Rájarata, or Pibiti. It is not to be supposed that they live even now

* [Another point—whether common to the Veddás also I do not know—which seems to me of perhaps ethnological importance, is the *yellow* tint or tone that seems to suffuse the brown Singhalese complexion, and which is noticed by Percival, Philoletes, and Davy.—T. B.]

wholly separated from the Singhalese. On the contrary, they are found in no small numbers mixed with other races. It is of special interest to us that they are immediate neighbours of the Veddás. Wolff describes the Malabars as black, long-haired, and without calves to their legs. Beyond this the author has found very few statements regarding their physical peculiarities; most of the writers limiting themselves to ascribing to them a stouter physique than the Singhalese, and greater activity.

The Moors, or Moormen.—Their number is small, and their effect upon the rest of the population even less highly to be estimated, because of their religion, which necessitates a sharply-defined separation, so that they rarely intermarry with the Singhalese or other natives. We have scarcely any description of their physical peculiarities. There seems to be only one skull of a "Moor" in Europe, and that is in the possession of Mr. Bernard Davis. This (317 of his collection) is a male skull of 1,495 cubic cm. capacity, therefore tolerably large; with a length to breadth index of 70; length to height index of 71; and a facial index of 85.7. It is accordingly ortho-dolichocephalic and chamaeprosop. From a single skull no judgment can be formed whether it is really typical of its race, and therefore further comparison is scarcely desirable.

Malays.—The existence of a scattered Malay element has been earlier discussed. A few statements as to their physical condition have come to us. Cordiner describes them as lighter, more inclining to copper colour than any other of the Indian races. Selkirk speaks of them as copper-coloured, below middle height, with flat brow, broad flat nose, and piercing eyes. In the Davis collection there is a Malay skull from Colombo, marked male. Its capacity amounts to 1,435 cubic cm.; the length to breadth index is 79; length to height, 76; face index, 108. It is therefore hypsimesocephalic and leptoprosop.

THE MUTUAL RELATIONS OF THE RACES.

We now proceed to consider the origin and relationship to each other of the different tribes existing close to one another in Ceylon: and it is noteworthy that the inhabitants of the Island are spoken of as belonging to distinct races both by Greek travellers in the sixth, and by Chinese travellers in the seventh centuries after Christ.

Question of a Chinese or Siamese origin of the Singhalese.—With respect to the question of a Chinese origin, which some have on insufficient grounds attributed to the Singhalese, we have reports of one warlike invasion by the Chinese; and Chinese soldiers are stated to have entered the military service of King Parákrama in 1266. The defeat of a King of Ceylon by a Chinese army so late as the year 1408 is also narrated. But nothing is known of any colonisation or settlement by the Chinese having ever taken place in Ceylon; and no elaborate proof is needed to

prove that neither Singhalese nor Veddás, at least in the form of their skulls, present the slightest indication of any relationship to the Mongols. According to an old tradition mentioned by Valentyn, the Sihala dynasty, from which Wijaya the conqueror was descended, had their residence in Tennasserim, so that a Siamese origin [or connection] is thus ascribed to the Singhalese; but it is unnecessary to follow up the tradition. Besides, it is not the search for the origin of the Singhalese which claims our first interest, but the derivation of the Veddás.

The Veddás not degenerated Singhalese.—Whether we consider the Veddás to be, as some say, “savage Singhalese,” or the Singhalese to be, as others say, “tame Veddás,”—thus deducing both from the same stock,—we must begin our investigations with the Veddás. A reverse order would be justified only if we assumed that the Veddás had sunk back from a condition of higher civilisation to that of absolute savagery, in which all travellers have found them for many centuries. The theoretical objection to such an assumption need not be again brought up, but I will only ask what signs of an earlier civilisation have actually been found? What remains of an earlier culture that, with any probability, might be attributed to the Veddás? A people who do not even possess clay vessels; who have no knowledge of domestic animals beyond the dog; who are unacquainted with the simplest form of gardening and agriculture; who lack almost every kind of social institution; who are not even counted as outcasts by their civilised neighbours,—cannot possibly ever have had the means which make a higher culture of any kind possible. The hypothesis of a relapse to barbarism must hence be definitely given up.

The ground for such an assumption could only be found in the language. But it has been already shown how great is the difference of opinion as to the place which should be given to that. That it is no Dravidian idiom, fundamentally, seems proved beyond a doubt. If we take it for a dialect of the Singhalese, and the latter for a primitive sister dialect of the Páli, it will still be truly very difficult for any one to argue from that, and still less from the Sanskrit words intermingled with it, the derivation of the Veddás from the valley of the Ganges. Surrounded for centuries by more highly cultivated peoples, a certain intercourse with their neighbours has been unavoidable, and consequently, where the Tamils have continually pressed on nearer to them,—as near Batticaloa,—a part of the Veddás have adopted the Tamil language. But for very much longer, and in the greater number of places, they have been in immediate contact with the Singhalese. What wonder, therefore, if they have adopted more and more Singhalese words and forms. The question is only whether besides these, as I suppose, borrowed words, their language has not preserved some individual elements? To this point so little attention has been given that we do not even know positively whether the Veddá language contains any words

designating numbers. It is no use being told that half the words noted down are corrupted Sanskrit. To what belongs the other half, which perhaps with greater attention might be enlarged? If we cannot class it among the Tamil languages it is very possible that it may prove specific. Nothing hitherto justifies us in any such one-sided statement as that of Mr. Tyler, who, without hesitation, calls the Vēddā language Aryan.

The matter would take a rather different aspect if we might assume that originally the Vēddās alone inhabited the Island, and that they were not only forced back into the forests by the immigrants, but had [partly] intermingled with them.* According to the native analysts the origin of the Singhalese is to be traced back to the followers of King Wijaya—a victorious host of immigrants from the valley of the Ganges, in a numerical proportion to the inhabitants which must have been somewhat like that of the Danes and Normans in England. A patriarchal system was introduced, which has lasted for thousands of years, and a series of facts testify that the aboriginal population was not wholly excluded from this system.† Upon such a foundation an intermingling of the Māgadha people with the aborigines would most naturally take place, and if we look upon the Singhalese race as the result of the commingling, the experience of so many other countries, where a similar commingling has taken place, would make it perfectly explicable that the Māgadha people made their language, the old Pāli or Eḷu, the ruling one, while in their physical conformation the aboriginal element won lasting influence. With such a view of the matter the Vēddās and Singhalese would neither be identical nor distinguished from one another merely by the degree of culture. The Vēddās would appear rather as representatives of the aboriginal race; the Singhalese, on the other hand, as hybrids produced by a union of immigrant Indians with Vēddās, and therefore varying according to the measure of these elements. This, indeed, strikes me as being the solution of the anthropological problem before us. The linguistic difficulty, that also the unmixed natives adopted to some extent—less or more—the Aryan language of their conquerors, appears no longer insurmountable, for the same thing is actually now happening with the Fins in the Baltic Provinces of Russia.

COMPARATIVE ANTHROPOLOGY.

The craniological materials available to the Author for purposes

* This has actually happened. Of the Tamils who did not immigrate till later, we may say that while in the north they have entirely supplanted the original population, in the east they have not merely mingled with the Vēddās, but have accomplished a veritable Tamilisation of them.

† [We have corroboration of this in the statement that "King Pandukhabayo (437 B.C.) placed the Vēddās in a *separate* settlement near the town (Anurādhapura)."—Burrows' "Buried Cities," p. 3. Unfortunately Mr. Burrows has not quoted his authority for this statement.—T. B.]

of comparisons have been the following. Of Veddá skulls, twenty-three well-authenticated specimens, including three lent to the Author himself from the Colombo Museum : but of this number two had to be excluded from some of the computations, owing to abnormalities, the probable consequence of artificial or accidental occipital pressure. Of Singhalese skulls, after setting aside those of which there are no detailed descriptions or measurements, or which are measured on a system different from that used by the Author, and also those of hybrids, there remained twelve available for comparison, which include two received by the Author himself, through the kindness of Consul Ph. Fréüdenberg ; a third, similarly received, proved to be probably that of a Tamil child. These would form a good broad basis for future decision, if important measurements were not wanting in those belonging to Mr. Davis' collection,—for instance, of the orbits, nose, and palate. With respect to Tamil or Malabar skulls, only a single specimen was known in Europe until lately. This was in the collection of Mr. Davis, in which was also the skull of a hybrid of Malabar and Singhalese. This has been supplemented, through the kindness of Mr. Fréüdenberg, by three Tamil skulls, unfortunately all without the lower jaw, and a child's marked Singhalese, but which rather appears to be Tamil. There are therefore, strictly, only four specimens for comparison, and in giving the averages of measurements only these undoubted ones are taken into computation.

[There is only a single skull of a Moor known in Europe, and in the Davis collection one Malay skull from Colombo, but these are not brought into the comparisons.]

ANTHROPOLOGICAL COMPARISON OF THE VEDDÁS WITH THE SINGHALESE.

Considered simply on anthropological grounds, the differences between the Veddás and the Singhalese are not so great as to oblige us to assume an absolute contrast in the two tribes. The skulls which have been personally examined by the Author are too few to lead to a definite conclusion, but they seem sufficient to enable us to ascertain whether any reason exists for distrusting results obtained in other ways. Such reason the Author does not find.

Comparing briefly what has been arrived at, the result is that the Veddás, as well as the Singhalese, are dark tribes, whose complexion varies—apparently within the same limits—between yellow-brown and black. The character of the hair also is plainly similar : only that here the effect of culture is conspicuous to a much greater extent. Both tribes, however, wear the hair long ; it is black, luxuriant, and a little wavy ; but with the Veddás, owing to neglect, it hangs down in tangled, but properly speaking, not curly nor woolly tresses. There is special testimony which conclusively proves that the Singhalese hair, when not cared for, strongly resembles that of the Veddás. Information

with respect to the colour of the *iris* is less complete, but it may be gathered that, as a rule, it is black or dark-brown in both cases. As regards size, plainly both races are of moderate stature, rather short than tall. The significance of the shorter measure of the Veddás cannot be doubted, but the fact that they are not all dwarfs, and that comparatively large Veddás are met with, may be adduced in favor of the hypothesis that their often dwarfish size is a result of long continued unfavourable conditions for development. Nevertheless, the fact in the main is well established that the Veddás belong to a small, indeed to one of the smallest known races. Concerning the development of muscle and strength of body, the witnesses testify loudly in favour of the Veddás. With respect to the shortness of the thumbs and pointed elbows, emphasised by Mr. Hartshorne, only the first would be of any importance if it should be proved by measurement to be altogether disproportionate. It may, perhaps, be a deception, such as that of Mr. Burnet in regard to the length of the foot, which direct measure shows to be of perfectly fair proportions.

Similar observations, only still less distinctive, we find in regard to the size of the head, and especially the capacity of the skull. The result proves that Veddá skulls are on the average much smaller than Singhalese; their capacity only averaging 1,261 cubic cm. against 1,406 cubic cm. for the latter. [The average capacity of the English male skull is 1,511 cubic cm., taking the average of those in the Royal College of Surgeons—*T.B.*] Some of the Veddá skulls are positively nano-cephalic, descending in one specimen to a capacity of 1,025, and in another, that of an adult man, to a capacity of only 960 cubic cm. This term nano-cephalic [pigmy-headed] is chosen to distinguish the case from micro-cephalic in the pathological sense [*i. e.*, smallness of the head the result of disease or malformation]. But notwithstanding this difference in average, the numbers slide over from both sides; the higher average of the Singhalese does not prevent the occurrence of very small specimens; for the extremes range from 1,694 to 1,110 cubic cm.; and *vice versâ*, the certainly very low average of the Veddás includes some pretty large specimens (one 1,420, and one 1,614). The length measures and the relations deduced from them have brought to light certain differences between the two tribes, but we shall represent these parallel to each other in their indices. One of the proportions is, however, now mentioned as being of considerable importance, viz., that with the Singhalese the front and middle of the head have the larger share in forming the roof of the skull, while with the Veddás it is the occipital region that does so. Of special interest is the comparison of the skull indices. The average ratio between length and breadth, ascertained by the Author, is for both tribes almost identical: 71·8 for the Singhalese; 71·6 for the Veddás. This is a highly dolicho-cephalic [long-headed] measure [and its value will be better appreciated if we remember that for the narrow, long-headed Negro the ratio is nearly the

same, while for the European it is 80, and for the broad and short head of a Tartar tribe 85, and in some Mongolian tribes even 88.—*T. B.*]. For our present purposes of comparison we can only say that these important relative measures do not point to any radical difference in race between Sighalese and Veddás. With both, the skull is long and narrow, yet among the Veddás there is a greater number in which the narrowness is extreme than among the Sighalese. The Veddá skulls are narrower than those of the African Negroes, and sometimes as narrow as those of the new Caledonians. [The narrowest appear to be the Fijian mountaineers, with whom the average ratio is only 66.—*T. B.*] It is the same with the ratio between length and height, which is ortho-cephalic [straight-headed] with both tribes; [the average for the Sighalese (74·2) being only a little below that for the Veddás (74·9)]. With reference to the height measures the ratio is somewhat different, in so far as the larger figures are on the side of the Sighalese. In both the vertical height exceeds the breadth. These coincidences of the main indices are so great that they could not be greater within the limits of a single race. The configuration of the capsule of the skull may—apart from the share of the separate bones in it—be considered as identical. The total result as regards the formation of the skull is that a great correspondence exists between the proportions of the skulls of the Sighalese and the Veddás, while the absolute figures show those of the Sighalese to exceed the Veddás, as a rule, in height.

In fact, according to the testimony of travellers, the difference of race is more conspicuous in the face than in the skull. It is chiefly to the form of the nose, particularly the flatness of its ridge and the breadth of the nostrils, but likewise to the form of the lips and jaws, which are throughout described as prognathous [projecting], that the various writers call attention as being characteristic features of the Veddá face. Contrasted with the Sighalese nose,—which the old Chinese reporters call a bird's beak, and in the description of a Kandy beauty is compared to a hawk's bill,—and also contrasted with the delicate lips and orthognathous [straight] jaw, which we perceive in Davy's drawings, there are certainly very striking differences. Unfortunately no other observer has recorded orbital measurement for the Sighalese, and there is a difference in the system of the published measurements which prevents our turning the skulls in England to much account in this direction; but, on the whole, osteological investigation has, in regard to the main facts, confirmed the observations made among the living. The skeleton face of the Sighalese differs far more from that of the Veddás than their respective skulls do. The index for the face shows very considerable contrast to that of the Veddás, averaging for the latter only 83, against 89 for the former, calculated on five female and one male skulls, one of which is that of a weak-minded person. In general the skeleton face of the Sighalese is much

narrower and longer than that of the Veddás. Corresponding with this the palate with the Singhalese is more long and narrow; with the Veddás rather short and broad, with a prognathous jaw. In the last particular, however, the contrast is not so clear. With the Veddás occur mesoconchy (orbital index 84.6) and mesorrhiny (52), with many individual aberrations it is true, so that with the women more platyrrhine [flat nose], with the men more leptorrhine [narrow-nose], forms occur. On this point the Singhalese material is very unsatisfactory and quite inadequate.

ANTHROPOLOGICAL COMPARISON OF THE TAMILS WITH THE VEDDÁS AND SINGHALESE.

It is necessary to take the Tamils next into comparison, chiefly because the historical accounts, going backwards as far as the time of Wijaya, inform us of numerous marriages, not merely of the kings, but of their retainers, with the Malabar women, not to mention the very early invasions and settlements made on the Island by Tamil hordes.

In spite of the meagre reports with regard to the physical characteristics of the Tamils, we cannot doubt that they, likewise, are very dark, more or less black, and have long black hair. For the rest, observers lay stress on their greater strength and activity, nothing more. Hence there remains only the scant craniological material found in Mr. Davis' and the Author's own collections. As these are all insufficient for a final authoritative answer to the question of the ethnological relation of the Tamils to the two other (Singhalese) tribes, the author wishes his conclusions only to be accepted with great reserve.

All the Tamil skulls are comparatively small; the average capacity being only 1,247 cubic cm., which is even less than the average of the Veddás (1,261 cubic cm.) and of the Singhalese (1,406 cubic cm.). It is scarcely possible to look upon this number as the typical one for the race, and it is only interesting as showing that small skulls may be found among all the races in the Island. Still, none of them reach the minimum figure for the Veddás. More important, however, is the difference in the form of the head. The Tamil skull, judging from these specimens, is hypsi-meso-cephalic [*i. e.*, the height index exceeds the breadth index; while the relation of the breadth to the length approaches the medium]—in fact wholly different from the Singhalese and the Veddá skull. Corresponding to this its transverse vertical length is greater than its sagittal circumference length. In the shape of the separate bones of the skull in forming the roof of the skull we also find a great difference and radical contrast; the squama occipitalis [the flat portion of the occipital bone] is much smaller, and the frontal bone considerably larger than with the Singhalese, and still more emphatically so than with the Veddás. While with the Tamils the skull-roof

culminates with the frontal division, with the Sinhalese, and still more with the Veddás, the occipital is strongly developed. The basilar view shows plainly the extraordinary shortness of the occipital region in the Tamil skulls. After this we must say that the skull of the Tamils, so far as can be ascertained from those under consideration, exhibits no relationship either with the Veddás or with the Sinhalese.

In size the Tamil face occupies a middle position between the Sinhalese and the Veddá face. The Sinhalese is the largest, then the Tamil, and the Veddá the smallest. The proportions of the Tamil face may briefly be stated in the following formula: mesokonchy, mesorrhiny, prognathy, and hrachystaphy [medium orbital index, medium nasal index, projecting jaw, and short palate.—*T.B.*] This positively distinguishes the Tamil face from the Sinhalese, and brings it nearer to the Veddá face. But the almost complete identity of the nasal indicés (Tamils 51, Veddás 50-52) does not prevent the greatest variety in the formation of the nasal bridge. Owing to the greater narrowness of the nasal bone, as well as the form of the bridge, we would not be at all justified in representing the flat, and, towards the lower part, broad nose of the Veddás as a Tamil inheritance. The form of the orbits is different in all the three races; and to this dissimilarity is to be added the very different formation of the naso-frontal region, in which, however, the proportions in the Sinhalese more nearly resemble those of the Veddá. The form of the aperture of the nose is with the Tamil more like that of the Sinhalese than that of the Veddá, both being platyrrhine, and that of the Veddá mesorrhine; but at its epiphysis, nevertheless, the Veddá nose is flatter and more depressed; the Sinhalese and Tamil protuberant—the Tamil, in fact, more than the Sinhalese. The chief distinctive feature of the Veddá palate is that the “tooth-curve” has very nearly the outline of a horse-shoe. Wholly different from the Tamils, and also somewhat different from the Veddás, is the “tooth-curve” of the Sinhalese. With them the palatal plate is unusually large, and at the same time of considerable breadth, so that it is very large; but the sides are more parallel, and the region of the incisors forms a broader, flatter curve, jutting out in front. The *os palatinum* has a relatively large share with the Sinhalese in the formation of the palatal plate. The Tamil palatal index is in very striking contrast to the Sinhalese.

The facts given in respect to three of the most important regions of the skeleton face show that great difficulties are encountered in attempting to ascertain the degree of affinity existing between these three tribes. If we take, as usual, the indices as guides, we gain for each region another combination. Most nearly related are:—

- According to the orbital index—the Veddá and the Tamil.
Do. nasal index —the Tamil and the Sinhalese.
Do. palatal index—the Sinhalese and the Veddá.

We must not forget, however, that here only one individual is taken from each tribe, and that he by no means corresponds in every particular to the average of his tribe, the Author having had to select for his illustrations from the few skulls available those which gave the best indications of regular development, but which perhaps do not, in all respects, represent typical forms. The Author's work will have fulfilled its aim if it hastens the bringing up of better material. For the present he can only assert that, so far as we have a distinct view of the physical relations, as few evidences appear of a real affinity between the Tamils and the Vēddās as between the Tamils and the Sīghalese.

Question of Dravidian element in Vēddās and Sīghalese.—This, however, does not decide the question as to whether there is a Dravidian element in either the Vēddās or the Sīghalese. We know now that the Tamils who made invasions and settlements in Ceylon came not only from the nearer points on the coast of India, but also from quite northern districts; and before expressing a decided judgment, all the tribes of Hindustan which are usually embraced in the term “Dráviḍas” must be compared in turn. A comparison of this kind would here be out of place, and the material is not sufficient. For the present, it will only be stated that the physical condition of the Tamils, including those of the Coromandel coast, is not sufficient to represent perfectly the Dravidian type.* Close beside them in the mountains we come upon other “Dráviḍas,” such as the Kurumbars and other wild tribes of the Nilgiris, of stunted stature and debased type, who, to all appearance, are essentially different from the Tamils, and whose skull measurements show great similarity to those of the Vēddās of Ceylon, while the form of their face, though differing from that in both Tamils and Vēddās, is not so different from the latter as to justify an ethnological separation. Therefore, if one would search out the connection of the Vēddās, and perhaps of the Sīghalese themselves, with Dravidian India, it would be advisable to go beyond the inhabitants of the coast, and bring the mountain tribes into comparison.

But even here the researches will not end; for, according to all probability, the present mountain tribes are not the real aborigines of Hindústán. We have the tradition that, together with the Kurumbars, the Vēddās were the oldest inhabitants of Tōṇḍamaṇḍalam (Madras); and of them it seems was said “there were then no forts, only huts; no kings; no religion; no civilisation; no books; men were naked savages: no marriage institutions.” And we have the tales of the fight of Viṣṇu with fabulous Assurs; and of the war of Ráma upon Ráwaṇa, the Ceylon

* Of two skulls from Tanjore,—the Chola of the Sīghalese annals,—one is dolicho-cephalic, the other mesocephalic. Which is here typical? One is hypsiconch, the other mesoconch; one leptostaphyline, the other brachystaphyline. According to which shall we decide?

champion of the Yakkho and Ráksha worship ; and also the traditions preserved among the Hayas in Nepál, and the Wouralis of the Konkán, that their tribes emigrated from Ceylon to their present mountain homes when Ráwana was slain. Such traditions are, of course, of no positive value for the diagnosis of the different tribes, but they at least warn us not to decide as to the aboriginal races of India and Ceylon simply on the ground of some crude linguistic indications, or the physical characteristics of a few better known tribes. All the same, we cannot avoid the conviction that the earliest inhabitants of Ceylon stand in a close affinity to the aborigines of India.

Proto-Dravidians and Pre-Dravidians.—Whether these aborigines were Proto-Dravidian, or even Pre-Dravidian tribes, we cannot with certainty decide at present. When the light-skinned Aryans from the Punjáb invaded the land later called Hindústán, they found it already in the possession of numerous tribes of “dark-skinned” people, who in the Vedas are designated by the generic name of “Dasa.” The greater part of them, as the conquerors penetrated further into the valley of the Ganges, were forced back on both sides, to the mountains northward into the Himálaya, and southward into the Vindhya ; those who remained behind were adopted as Sudras, thus becoming a part of the Aryan organisation. Hence nothing stands in the way of the assumption that the mountaineers in general belong to the aboriginal tribes. But neither does anything compel us to consider all these tribes of the *Dasyu* as homophylic [one race]. M. Rousselet speaks most positively of an immigration of Tibetan tribes of the yellow race from the east, and another of Turanians from the west, before the Aryan invasion ; but he assumes, as anterior to both, a population of Negritoes. To the admixture of the latter with yellow tribes he first of all ascribes the origin of the Proto-Dravidians (counting among these the Malars, the Konds, and perhaps the Gonds) ; and only when fresh troops of invaders had again mixed with the Proto-Dravidians, arose, in his opinion, the “Dráviḍas” or “Tamiḷs.” They brought the snake (Nága) worship with them. On the other hand, from the immigration of the Turanians arose in the plains the Yats ; in the mountains the Bhils, Minas, and Mhairs. He regards as the last remains of the primitive black population scattered remnants of a small black people upon the high plateaus of the Amarkantak, who became known under the name of Djangals, Puttnas, and Yuangas (Dschuangs).* If I have many doubts about admitting the distinctions of M. Rousselet, especially with regard to the assumption of a veritable Negrito race as the aboriginal race of India, I yet in nowise oppose the idea that the tribes of black-skins which the Aryans found established in the

* Col. Dalton states that these belong to the Kolars ; and his description of these contains quite as many Mongolian as Negretian characteristics.

valley of the Ganges were mixed. How much Mongolian, Turanian, or Negrito blood flowed in their veins, must remain for the present undecided. But it is certainly not impossible that a part only of the "Dasa" were Dravidians, and that even before the Proto-Dravidians of M. Rousset, Pre-Dravidian tribes inhabited the land. Neither the Mongols nor the Turanians satisfactorily explain the stunted growth of the tribes of "black-skins" to whom even Pliny alludes as "pigmies." All the information we have of them is so imperfect as to admit of being turned to account for any sort of opinion. M. de Quatrefages has collected accounts of the Negritos in India, from which he concludes definitely that Negritos are still living in various parts of the country. I cannot esteem the evidence sufficient, but will not deny that the question is open to discussion.

As affording grounds for misgivings, reference may be made to the so-called Negrito race inhabiting several clusters of islands and parts of Malacca, and also to their neighbours, the "little-blacks," who dwell in the Andaman Islands. In various respects, as by their dark complexion, the smallness of their frames, and particularly of the head, they unquestionably show a striking approach to the Veddás and Kurumbas. But the one circumstance of the difference in the form of the skull, which, with the Andamanese as well as the Negritos generally, is in reality brachy-cephalic, distinguishes them definitely from all the Ceylon races. When to this is added that their hair grows in spiral coils, and is to be classed with the woolly hair of the genuine Negro, every possibility disappears of a connection with the Veddás, unless we assume that climatic influences have especially affected the hair. Even less analogy is found between Veddás and Australians, although M. Topinard has recently emphasised the supposed relationship of the Australians to the Veddás, as well as to the Bhils, Gonds, Khandas, Kurumbars, &c.

Malay element.—Very much more complicated is the question whether Malay elements were not infused into the aboriginal population of Ceylon. The Malays have extended their settlements much further, and even as far as Madagascar. There are, however, no obvious physical indications of such a relationship. Only Mr. Williams, an American missionary in China, observed in the Sinhalese "a Malay expression of countenance."

CONCLUSION.

From the foregoing discussion we assume as proved :—

1st —That manifold resemblances exist between Veddás and Sinhalese, and that the origin of the Sinhalese race from a mixture of Veddás and immigrants from India possesses great probability, as well upon historical as upon anthropological grounds.

2nd —That the Veddás, as well as the Sinhalese, are, in the main features, distinguished from the Ceylon Tamils, and equally from those of Tanjore (Chola).

3rd.—That on the other hand, among the remnants of the old Dravidian, or perhaps Pre-Dravidian tribes of Hindustan, we find even to-day evidence of analogies with the Vēddās.

The low development of the Vēddās a race distinction and not an hereditary morbid condition.—Have the Vēddās remained in the condition of the Proto-Dravidians, or possibly Pre-Dravidians? or have they, in their isolation, sunk to a lower state? In other words, are they ethnologically to be turned to account in order to paint anew the picture of this primitive period? If, in spite of reasons which seems to the Author conclusive, one would assume that they have by degrees retrograded physically and intellectually, we should be forced to represent them as a pathological tribe; and the question suggests itself whether the tiny size of their skulls and small capacity for mental development do not stamp them as microcephalic in the pathological sense? We can distinctly deny this suggestion. The individuality of the Vēddās is psychically fully developed. So far as their needs demand they have matured their capacities, and are able to take care of themselves and their children; and they even associate, so far as is unavoidable, with neighbours and strangers in a free way and as self-determined men. They are distinguished in all the main features from micro-cephalic tribes in the technical sense; and it may therefore be admitted, without hesitation, that the inferior bodily and mental development of the Vēddās is not owing to a really morbid condition, which, as such, might be hereditary, but is rather to be regarded as a race peculiarity.

This, however, by no means excludes the possibility that favourable outward circumstances, especially better food, might produce a more complete development, the body become larger and stronger, and the skull and brain formation more perfect. In fact, such cases appear among the Vēddās, as is proved by examples of men far exceeding the average height, and by skulls having a capacity of 1,614 and 1,420 cubic cm. It might follow from this that the Sinhalese are civilised Vēddās who simply owe the superiority of their physical development to their better life. But the Vēddā race is still, as it was in ancient days, among the smallest of the living human tribes. Similar dwarfish tribes are scattered all over India, which possibly was in ancient times inhabited by tribes which had a close relationship to these. And with just as little propriety as the present Hindūs can be said to have sprung, and progressively developed from these more or less dwarfish aborigines, does such a kind of explanation suit the connection of the Vēddās with the Sinhalese. As they have not descended from the Sinhalese by regressive degeneration, neither surely have they been transformed by progressive evolution into Sinhalese. That no such affinity exists is proved chiefly by the form of the face, to which all observers testify. All descriptions, and history confirmed by the Rāmāyana, as well as the Wijayan legend, show there can be no doubt that the Sinhalese face is an importation from the Aryan province of the Indian

continent; while, directly to the contrary, all observers ascribe to the Veddá face a foreign, and very frequently, Dravidian type. It becomes clear, then, that genealogical investigation must make the face a main object of study.

If the view be correct that the Veddás are a pure and the Singhalese a mixed race, we may then leave the question out of consideration as to how far soil, food, a climate, and the like may have operated to determine the formation of the body or the size of the head, or to transform the character of the hair from that of woolly-haired blacks, like Negritoes, &c., to what we now find it. Although facts bearing more or less plausibly on this question may not be wanting, we should hesitate before applying arguments gathered from the history of domesticated animals to the savage inhabitants of Ceylon, at any rate until it is proved that the latter actually possessed in earlier times different physical characteristics. The present state of the hair plainly corresponds to the description given by Palladius, and must, therefore, have been just as it now is for at least fifteen hundred years.

Direction of further inquiry: the Veddás a member of the pre-historic Dasa group—It is very certain that if we would pursue the search for the origin of the Veddás genealogically, we must first turn our investigations to the savage or half-savage tribes of India. Every possible effort must be made to enlarge the facts bearing on Indian ethnology in order to be able to investigate radically the tribes of "Black-skins." Since a part of the Dasa were transferred to the Sudras, and consequently included in the caste system of the Hindús,—as the Veddás in that of the Singhalese,—it is not possible to bring to a conclusion the physical anthropology of the Hindús and the Singhalese, until we have resolved the evidently very composite group of the Dasa into its separate members. One such member is plainly the tribe of the Veddás: their natural isolation upon an island has perhaps tended to preserve in them, more than in similar places upon the Continent, their peculiar character, and made them an object by which to test the admissibility of the theories concerning the origin of the "Black Indians." May the zeal of the observer know no flagging, that, before the utter extinction of this already much-depleted race, the language and customs, the physical and mental constitution of the Veddás may, in all particulars, be firmly established.

COMMITTEE MEETING.

17th December, 1885, 4 p.m., at the United Service Library.

Present :

P. Freüdenberg, Esq., in the Chair.

T. Berwick, Esq.
J. B. Cull, Esq., M.A.
J. G. Dean, Esq.
D. W. Ferguson, Esq.

J. L. Vanderstraaten, Esq.,
M.D.
W. E. Davidson, Esq., C.C.S.,
Honorary Secretary.

Business.

1.—Read and confirmed Minutes of last Committee Meeting.

Resolved,—That the following list of gentlemen be recommended by the Committee to the Society at the Annual General Meeting as Office-bearers during 1886 :—

President.—The Right Rev. the Lord Bishop of Colombo, D.D.

Vice-Presidents.—W. R. Kynsey, Esq., P.C.M.O., and T. Berwick, Esq.

Hon. Treasurer.—J. G. Dean, Esq.

Hon. Secretary.—W. E. Davidson, Esq., C.C.S.

Committee.

The Hon. Lieut.-Col. F. C. H. Clarke, R.A., C.M.G.

J. Capper, Esq.
J. B. Cull, Esq., M.A.
D. W. Ferguson, Esq.
P. Freüdenberg, Esq.

Staniforth Green, Esq., F.L.S.
W. P. Ranasipha, Esq.
H. Trimen, Esq., M.B., F.L.S.
J. L. Vanderstraaten, Esq., M.D.

2.—The Secretary submitted a draft Report of the Society's labours during 1885 for approval. After being read and discussed, the report as amended was approved and passed, and the Secretary desired to read it at the Annual General Meeting.

ANNUAL GENERAL MEETING.

21st December, 1885, 9 p.m., at the Colombo Museum.

Present :

The Right Rev. the Lord Bishop of Colombo, D.D.,
Vice-President, in the Chair.

H. P. Baumgartner, Esq., C.C.S.	J. J. Grinlinton, Esq.
T. Berwick, Esq.	W. R. Kynsey, Esq., F.C.M.O., (Vice President).
Hon. Lieut.-Col. F. C. H. Clarke, R.A., C.M.G.	L. O. Pyemont-Pyemont, Esq., C.C.S.
J. B. Cull, Esq., M.A.	Hon. C. Clementi Smith, C.M.G.
J. G. Dean, Esq.	W. Subhúti Terunnánsé.
A. M. Ferguson, Esq., C.M.G.	H. S. Sumanggala Terunnánsé.
D. W. Ferguson, Esq.	H. Trimen, Esq., M.B., F.L.S.
W. W. Fisher, Esq.	J. Wardrop, Esq.
Ph. Freüdenberg, Esq.	W. E. Davidson, Esq., C.C.S., Honorary Secretary.
A. P. Green, Esq.	

Two visitors.

Business.

1.—The Minutes of the last Meeting having been read and confirmed, Mr. J. G. Dean proposed, and the Secretary seconded :—

2.—That Mr. W. W. Fisher be elected a Member.—*Carried.*

3.—Proposed by Mr. J. F. De Saram, and seconded by the Secretary :—That Mr. Pestonjee Dinshajee Khán be elected a Member.—*Carried.*

4.—The Chairman announced that a letter had been received from the Governor's Aide-de-Camp expressing His Excellency's regret at not being able to be present ; and then called on the Secretary to read the Committee's Annual Report.

The Secretary read the Report of the Committee for 1885, as follows :—

ANNUAL REPORT.

"YOUR Committee beg to lay before the Society a brief Report showing the work done by the Society during 1885, and the position it is now in, at the end of the fortieth year of its existence.

Meetings.

"There have been during the year six General Meetings, besides this Annual General Meeting, at which the following Papers have been read and discussed :—

1. A translation, from the Dutch, by Mr. Ph. Freüdenberg, of the account of Ceylon by Johann Jacob Saar, a soldier in the

congratulate ourselves on the fact that the material for printing is forthcoming in such abundant quantities.

Dutch service in the East from 1647-1667. He served in all the leading operations which resulted in the conquest of the Maritime Provinces by the Dutch from the Portuguese.

2. Remarks on the Composition, Geographical Affinities, and Origin of the Ceylon Flora, by H. Trimen, M.B., F.L.S., Director of the Royal Botanic Gardens, Pêrádeniya.

3. Rice cultivated under Irrigation in Ceylon, by E. Elliott, C.C.S.

4. Plumbago: with special reference to the position occupied the Mineral in the Commerce of Ceylon, by A. M. Ferguson, C.M.G.

5. Jottings from a Jungle Diary: being an account of certain recent Archaeological Discoveries in Anurádhapura, with a theory as to their origin and construction, by S. M. Burrows, M.A., C.C.S.

6. An Abridgment, by Mr. T. Berwick, of a Monograph on the Veddás of Ceylon, contributed to this Society by Professor Vüchow, of Berlin.

These General Meetings have all been held in the evening at the Colombo Museum, and from the large attendance—the average being over thirty-three persons at each Meeting—it is evident that the custom suits Members better than the afternoon Meetings in the Fort.

Journals.

The Society has published during the year the following numbers of its Journal:—

No. 26, Vol. VIII., 1853, containing the Papers read in 1853.

No. 27, Vol. VIII., 1884 (Pt. I.), Report by Mr. H. Parker, M.I.C.E., on the Archæology of Tissamáharama.

No. 28, Vol. VIII., 1884 (Pt. II.), the Játaka Studies of the Society during 1884, edited by the Bishop of Colombo.

No. 30, Vol. IX., 1885 (Pt. I.), Catalogue of the Flowering Plants and Ferns of Ceylon, by H. Trimen, M.B., F.L.S., Director of the Royal Botanic Gardens, Pêrádeniya.

No. 31, Vol. IX., 1885 (Pt. II.), containing three popular lectures delivered during the year by H. Trimen, M.B., F.L.S., E. Elliott, C.C.S., and A. M. Ferguson, C.M.G.

“ Besides these, there are now in the press: (1) Proceedings of 1884; (2) Proceedings of 1885; (3) No. 29, Vol. VIII., 1884 (Pt. III.), containing a large number of Papers contributed during 1884, and closing the Society's Publications for 1884.

“ The Society must acknowledge a debt of gratitude not only to the Government for permitting to the Society, under certain restrictions, the use of the Government Printing Press, but also to Mr. G. J. A. Skeen, the Government Printer, without whose ready co-operation and assistance so much editing work could not have been accomplished. As it is, five Parts of the Journal have been issued during the year, and although there is much leeway to be made up before the Society succeeds in publishing all its work for a year within the year, yet we have cause to

Programme for 1886.

“The intention at present is to print the following Publications during 1886, before all arrears are blotted out :—

- (a) No. 29, Vol. VIII., 1884 (Part III.).
- (b) Proceedings of 1884.
- (c) Proceedings of 1885.
- (d) No. 32, Vol. X., 1885 (Part III.) ; which will consist of a series of translations from French and Dutch writers on Ceylon, contributed by the late Colonel A. B. Fyers, R.E., once President of this Society, and by Mr. Ph. Freüdenberg.
- (e) No. 33, Vol. IX., 1885 (Part IV.), in which will be printed Professor Virchow's Monograph on the Veddas of Ceylon, as well as the correspondence and supplementary Papers which are likely to result from a full discussion of the Professor's views.

“There are fortunately good prospects for future Meetings as far as Papers are concerned, and your Committee would recommend for adoption the following distribution of the Society's Meetings :— During January and February to have two Meetings. It has been usual for some years to devote these Meetings to translations of writers on Ceylon, or to subjects of historical or antiquarian interest. Mr. Freüdenberg's translation of the Ceylon portions of Wouter Schouten will find a place at one of these Meetings. For the other Meetings Papers are promised by Dr. Kynsey, and by Dr. Vanderstraaten. A series of the so-called popular lectures should be read (as in this year) during July, August, and September. Towards this series, contributions have already been promised by the Vice-President Dr. Kynsey, Mr. J. Ferguson, Mr. Le Mesurier, and others. In October and November a series of Meetings should be devoted to the continuation of the Society's Játaka studies, one of the important works which the Society must steadily push on. Work has already been in progress some time on this subject among the best Páli scholars of the Society.

Members.

“The number of Members at the beginning of the year was 143. It is now 136. Twelve new Members have joined. Death has taken Sir John Douglas, our genial patron and our good friend ; Mr. Haliburton MacVicar, F.Z.S., whose ornithological knowledge and love of natural history have often been of use to the Society ; Mr. G. D. Browne, C.C.S.; and the Rev. S. Ondaatje. Eight Members have resigned, and the names of seven others have been struck off, under the rules, for neglect to pay subscription.

Finances.

“A statement of the Society's finances is subjoined. The position of the Society is sound, thanks in a large degree to the

industry of Mr. J. G. Dean, the Treasurer. The assets of the Society divide themselves into three sections: (1) The ordinary balance of annual subscriptions over the expenditure. This balance is now Rs. 70-90, the income of the year being approximately spent in the year. (2) The amount realised by a certain number of Members having compounded and having become, by a payment down in lieu of the annual subscription, Members for life. The balance stands at Rs. 417-50. (3) The total balance under the exploration account of Rs. 354-59. As regards the current balance nothing need be said: the main payments are in printing, the binding of a large number of books in the Library, and in the payment of £20 for the translation of Professor Virchow's contribution. As regards the second balance, the sum obtained by capitalising part of the Society's yearly income should, the Committee think, be diverted to some permanent work, unconnected with the annual expenses. The Committee would suggest the advisability of using it for the purpose of reprinting some of the back Numbers of the Journal which are out of print, and are now very difficult to procure. The Secretary has at the moment with him six applications for the purchase or exchange of a complete set of the Society's publications, and these cannot be complied with for the lack of seven Numbers, of which no copies are left. The sale of Numbers of the Journal might in future be funded on this account.

Reprints.

"The Committee further venture to hope that, when once the process of reprinting is taken in hand, overtures may be made to the Asiatic Society of Bengal to allow the reprint by this Society among its own records of the contributions (especially concerning Ceylon History) made by the Hon. G. Turnour in 1836-38. These contributions form a series in the Papers of the Asiatic Society of Bengal, having been written some years before the birth of this Society. This series of Papers, which form perhaps the most important contribution within the last century to the elucidation of the ancient history of India and Ceylon, have a peculiar claim on our attention, as they were the work of the first great Páli scholar of Ceylon, and as the discoveries made by him were gleaned from the ancient record of Ceylon History. The Asiatic Society of Bengal has lately permitted the same privilege of reprinting Papers on Malayan subjects to the Straits Settlements' Branch of the Royal Asiatic Society.

Exploration.

"Turning to the third fund to the Society's credit, namely, the balance from the special fund raised towards assisting in the exploration of the remains of Anurádhapura, there is still a sum of Rs. 354-59 to the credit of this fund. Your Committee consider that this balance should be applied to the purposes for which it was originally raised. Opportunities may arise at any time for

the useful application of the sum in hand. A special Sub-Committee, consisting of His Excellency the Governor, the late President Mr. Dickson, and Dr. Kynsey, associated with the Revenue and Engineer Officers at Anurádhapura, were nominated at a General Meeting to direct the expenditure of this fund, and this Sub-Committee will be able, with the assistance on the spot of Mr. Burrows, one of our most industrious Members, to turn the balance to good account.

Secretaryship.

“The Honorary Secretary Mr. Davidson, proceeds to Europe on six months’ leave of absence from March next, but the Committee have been fortunate enough to obtain the promise of Mr. R. W. Ievers’s services during Mr. Davidson’s absence : possibly Mr. Ievers may be induced to take up the Secretary’s duties permanently.”

On the conclusion of the reading of the Report—

The Chairman rose and said : “I perform a little more than a formal duty in moving the adoption of the Report. I think we shall all agree that it is a record of useful and satisfactory work. It exhibits a sound financial position, and lays before us sensible suggestions for the arrangement of our Proceedings in the coming year. In moving the adoption of the report, I feel that I am to some extent asking the Members present to put their seal upon the valuable services of the reader. A Society of this kind owes its efficiency and prosperity in a very large proportion indeed to the activity of its Secretary, and we have been very happy in having such a Secretary as Mr. Davidson, and we shall regret for a time that he is going away. There is one part of the Report with regard to which I should like to make a suggestion, if it were in order now, and that is with respect to the closing words, in which he threw out some hint that on his return the duties will still remain in other hands. We shall enjoy the able services of Mr. Ievers, and the time I hope will come when he will be permanently connected with us ; but until we have had a great deal more out of Mr. Davidson, we shall not, I hope, see the work entrusted to other hands. (Laughter and applause.) I beg to move the adoption of the Report.”

Mr. A. M. Ferguson, C.M.G. :—I have much pleasure in seconding the motion.

The motion was put and carried unanimously.

ELECTION OF COMMITTEE.

Mr. Ph. Freüdenberg :—“My Lord Bishop, Ladies, and Gentlemen,—I have been requested to lay before you for your approval the list of the Members of Committee for the ensuing year, as suggested at our last Committee Meeting. It is usual on such occasions to express the wish that a task like this had been entrusted to abler hands to do justice to it ; but, as such a remark

would be conspicuous by want of freshness, I will refrain from making it, however intense my feelings on the point may be. (A laugh.) The list which we have to submit to you contains very few new names. His Excellency the Governor is the Patron of this Society, and, as a matter of course, is not subject to re-election; but we trust that His Excellency will not withdraw his patronage from this Society as long as he rules over this Island. (Hear, hear.) The direct intervention on behalf of the Society by His Excellency has immensely benefited it, and the gatherings we have been used to of late—and I do not think I am exaggerating when I say so—are greatly due to the interest which His Excellency takes in the Society; and it is quite refreshing to contrast the gatherings now with, for instance, one which I remember in this very room not many years ago, when the only persons present were the late Honorary Secretary, one Member to read his Paper, another to listen, and your obedient servant in the chair! (Laughter.) The office of President has been vacated by the Hon. J. F. Dickson on his departure from Ceylon. His Lordship the Bishop has very kindly consented to temporarily act for him; and to-day we are going to ask him to fill that office permanently. You are all aware what a vast amount of work His Lordship has done for this Society, and his name will always in our annals be associated with those delightful tales of domestic occurrences in Buddha's life—the Játakas. As first Vice-President, we propose to you to re-elect Dr. Kynsey, who has so worthily filled the post hitherto; and as second Vice-President, my learned friend Mr. Berwick has the unanimous recommendation of the Committee. The worthy Treasurer has enabled the Secretary to lay before you to-night such a glowing account of the financial position of this Society that I think we are all anxious to saddle him once more with the arduous duty of looking after the pounds, shillings, and pence, and we only hope he will be as fortunate in the future as he has been in the past in handling the gigantic accounts entrusted to his safe keeping. Of Honorary Secretaries we have had two—Mr. H. C. P. Bell, and Mr. W. E. Davidson. Mr. Bell has, in the interests of the Service, been removed from Colombo, and I think we shall have to forego his assistance as Secretary, while we trust he will be able to give us his valuable aid by helping to edit the Journal of this Society. Mr. Davidson is proposed as Honorary Secretary. On this occasion I should have liked to say something about him, but unfortunately for me His Lordship has anticipated me. When filling in the names of the gentlemen to serve on the Committee, I inquired who were the ladies who had first arrived at the bright idea of adding charm and lustre to our Meetings by their presence, because I am of opinion that the very least we could do to show our gratitude was to elect one of them to serve on the Committee. (Laughter.) I was stopped in my researches by the Honorary Secretary, who pointed out that ladies were permitted to attend, not as Members, but as guests. This is an instance of the selfishness of men who frame laws for the exclusion of the fair

sex from power, and afterwards claim the merit of politeness in doing a small part of their duty. The names of the Committee Members are those of John Capper, Esq., the oldest Member of this Society; Hon. Lieut.-Colonel Clarke, C.M.G., one of the youngest Members, but whom we trust to see following in the footsteps of his predecessor in office, the late Col. Fyers, who at one time was President of this Society; J. B. Cull, Esq., M.A., indispensable for discussions at our Meetings; D. W. Ferguson, Esq., who will be very useful to this Society in his absence, inasmuch as he has promised to write a Paper or two for us when he takes his leave to Europe, having at present no time to attend to us; Staniforth Green, Esq.,—we trust that Mr. Green, who continues so immersed in his researches, will give us a most interesting account of the marriage customs of the Hymenoptera (laughter); W. P. Ranasinha, Dr. H. Trimen, and Dr. J. L. Vanderstraaten, are the three other Members of Committee propose. Gentlemen, I leave the list of names in your hands, and I trust to find that we have only anticipated your decision.” (Applause.)

Mr. J. J. Grinlinton seconded.

The motion was unanimously carried.

The Bishop of Colombo then rose to deliver the Presidential Address, which ran as follows:—

PRESIDENT'S ADDRESS.

“THE custom of an Annual Address by the President is in itself an excellent custom, but it imposes a task which is very difficult to perform. Those who have preceded me in this chair have been men remarkably well qualified to undertake it, either by general culture or by special acquaintance with one of the subjects of the Society's study, or by both. Yet such men as these, I find, have very frequently omitted the Presidential Address, and those who have discharged the duty have had the great advantage of doing so after the custom had been some years in abeyance. They have thus had the events and proceedings of three or more years to describe; or, in some cases, after a much longer interval, they have had occasion to revive decayed interest, and when the retrospect was unsatisfactory they have found room for exhortation in looking forward.

“My immediate predecessor possessed in a high degree the qualifications, both general and special, for this task, and had he been still with us would no doubt have discharged it well to-day. He would have been able to review a year's work over which he had himself presided.

“I, on the other hand, have, I think, good reason to ask your kind indulgence, if on first entering on office I am unprepared either to review or to direct the Society's exertions. A few weeks ago I had no notion that I should become in any degree responsible for them. During the time I hold the office to which you have been so good as to appoint me, I will try to keep at

least *au courant* with your proceedings, and what concerns them; but I speak to-day as one who has been till quite recently little more than an outsider.

"A President's Address ought, I think, to do one of two things. It ought either to pass in review the different branches of learning which come within the purview of the Society, and to describe and estimate the progress made in each, both within the Society and without it; or, if the speaker be characteristically a specialist, his address should be either a popular sketch of, or a substantial contribution to, the subject of which he is a master. Both these methods are unhappily impossible to me. I am neither Jack of all trades, nor master of any one.

"What a President's Address ought not to be, that I fear is all that I can offer, namely, the occupation of a certain amount of the Society's time, with no definite result either for edification or amusement.

Botany.

"Of the Papers which the Society has lately printed, several had been already some time in its possession, and were therefore referred to by my predecessor among the events of last year. This is the case even with Dr. Trimen's very valuable catalogue of Ceylon plants;* which is important enough, however, to signalise the year of its actual publication as well as that in which it was presented to the Society. I consider it a high honour to the Society to be the *medium* of presenting to the scientific world a work which, I am sure, will be of abiding value.

"Taking stock afresh, after the interval of twenty years which had elapsed since Dr. Thwaites' "Enumeratio" came out, of the stores of knowledge which had been collected by many observers (several distinguished Members of this Society among them), Dr. Trimen has added 200 species, he tells us, to the list of 1864, and has revised and re-arranged the whole. This catalogue must be of inestimable value to professed botanists; but to the general readers the Remarks on the Ceylon Flora, which the author read to us in February last, will be still more acceptable. It surprises us to find how many of those plants which we had regarded as most characteristic of Ceylon have really been introduced from other lands. Without the mango, the jak, the areca, the castor-oil plant, the datura, or the temple trees, one thinks Ceylon would hardly be Ceylon. Yet these, Dr. Trimen tells us, are as much foreigners and colonists here as any Member of this Society. It is gratifying to learn that our flora is decidedly a rich one, and that we beat our Indian neighbours—area for area—in this particular. To an inhabitant of Ceylon it is still more gratifying to learn that a large portion, some 30 per cent. of the kinds, are endemic or peculiar to the Island, and that in spite of our close proximity to the Indian Continent. Of the rest nearly all are

identical with species found in the adjoining Peninsula; so that the north of Ceylon is with reason believed to have been joined to the mainland in recent geological times. But more than half of our mountain species are not found even in the Nilgheris, though they belong to genera found there.

"But there is a strong non-peninsular element, found chiefly in the south of the Island, and this is Malayan in affinity (similar, *i. e.*, to the flora of Assam, Burmah, the Andamans, Singapore, and Sumatra). And this Malayan element is present here more conspicuously than on the Indian coast. Whether these came through India or not, is doubted. Wallace thinks they did. Dr. Trimén is inclined to think they came direct from the islands. It cannot but strike one as curious that the same affinities are conspicuous between the floras as between the peoples and religions of Nepál, Burma, and Siam on the one hand, and Ceylon on the other. Still more that the question should be under dispute, whether the course of immigration of these gentle and gradual visitors, as well as of the ruder steps of human civilisation, was from the north and east direct, or by the way of Southern India.

"Dr. Trimén's lighter touch, in this more popular Paper, shows how well he could do, what we so much want some one to do, a popular Hand-book of Botany for Ceylon. I asked one of the leading English botanists for such a book, and his reply was: 'There is none, get Dr. Trimén to write one: he is the very man.'

Natural History.

"In a cognate field of Natural History the Society may congratulate itself on having received and published Mr. A. M. Ferguson's excellent Paper on Plumbago.* He not only told us about the mineralogical and chemical qualities of this mysterious substance, and gave much information as to its geological relations, but he gave a very practical turn to the subject by tracing the fluctuations of the trade, and describing the application of plumbago in the arts. The intimate connection of this industry with the native enterprise, and native labour, the primitive mining operations, the employment of large numbers of operatives of both sexes in the mills, combine to render this a subject of peculiar interest to us, and the Paper I refer to must be of great value to very many.

"This is in the first place a learned Society, but if it can so pursue science as to promote useful industry, or so follow the steps of industry as to collect observations of scientific value, it is doing—I venture to think—what is essentially its proper work.

"I could wish that in this direction another track might be explored, or rather the result of its exploration recorded in a scientific form. I refer to the search lately made for gold. I suppose a great deal of information must have been acquired, in different places by

* C. A. S. Journal, Vol. IX., No. 31 of 1885.

different people, valuable geological and mineralogical observations made, in the course of explorations conducted with a more commercial aim, but I am not aware that these results have ever been collected. The same gentleman who gave us the admirable Paper on Plumbago has been the means of giving so much information to the public, that I confess I am quite unable to keep pace with it, and what I am desiderating may have already been done; but, if not, I would venture to commend this suggestion to him and to other Members of the Society.

Geology.

"The study of the geology of Ceylon is not very attractive superficially, because it would consist almost entirely, I imagine, of the history of the earth itself, and not of the lighter amusement of fossil hunting. And yet I have heard scientific men say that there is a vast deal to be learnt here, nor can anyone travel much about this Island without wishing to know why the hills lie like gigantic wind-driven waves across the country, abruptly broken down on one side and sloping on the other; why through large areas of the Island we meet with low ridge after ridge, as if vast furrows had been washed by the ocean into soft undulations; why the quartz veins crop up here and there, or run in one long rib across the country; what coast is rising, and what sinking; and of what other land, now, perhaps out of sight, our "Lañká Dwípa" was once a part. I am venturing out of my depth, but, before I turn back towards the shore, I will venture to express a hope, in regard to the Meteorological Observations over which the Surveyor-General so ably presides—observations which his recently provided directions must have much facilitated—a hope that to this branch of knowledge, too long absent now from our Proceedings, we may some day have a contribution from his hand. One stroke more, before I turn landward—there is something exhilarating in being out of one's depth—in these days of excitement about everything electrical, it has often occurred to me how great a field is afforded in Ceylon, where electric energies are so powerful, and display themselves often in so grand and terrible a scale, for systematic recording of the force and direction of earth-currents, as well as of the motions of storms, and of the phenomena of terrestrial magnetism.

Archæology and History.

"I should like to have spoken at some length of Mr. Parker's deeply interesting Paper on Tissamaharáma,* but, though only just printed, it was fully reviewed by Mr. Dickson a year ago. I would express the greatest admiration for Mr. Parker's industry, judgment, and learning; but at the same time I hope his facts will be distinguished from some of his inferences; the former are very precious; many of the latter are, no doubt sound; all are

ingenious ; but I should like to see a good battle over some of them before they go down to future readers under the shelter of the reputation for learning and accuracy which this Paper will assuredly secure to their author.

“ Exiled in that remote, and, but for his exertions,—possibly in spite of them, still, to some,—that unattractive spot, Mr. Parker has not only discovered amid its dulness a store of antiquarian wealth, not only extracted thence treasures of information, not only repeopled—what he would not allow us to call a desert—with the scenes of life and prosperity, but he has gilded it—this home of his toil—with, may I venture to say, just a touch of that gleam that never was on sea or land ; it must be no less than the great capital and even source of Aryan civilisation for the Island ; there Wijayo himself must have landed, and thence the Princess Kachchānā have been escorted to Anurādhapura. Now, we can see Adam’s Peak from off Chilaw (and probably farther north), as well as from off the southern coast ; and before Tambapanni is to be fixed on the banks of the Kirinda, we must look a little closer into some of the arguments, lest we be caught by the enthusiasm of an explorer, who is too jealously bent *ut exordia urbium angustiora faciat*.

“ It is very possible that the result of debate may be to place Mr. Parker’s conclusions on an unassailable basis. In the meantime, I should like to express my conviction—it is one at which most Members of this Society have arrived—that he does absolutely right in taking as a guide, to be trusted even further than at first sight seems possible, the old historical works of the Sinhalese,—the ‘Dīpavaṇṣa’ and the ‘Mahāwaṇṣa.’ What can be more instructive than the successive confirmations of that history which successive discoveries bring to light ? How clear is the warning which these give to students of history, that excessive scepticism—contemptuous setting aside of local chronicles—may be far more unphilosophical than a humble following of them, wherever they can reasonably be followed.

“ The fashion of historical scepticism, under the teaching of Niebuhr and his followers such as Grote, Mommsen, and others, had led to an excessive distrust. I suppose no more signal refutation of their position could be found than the ‘Mahāwaṇṣa’ affords.

“ Here are the records of a people imperfectly civilised ; a people of the so-called imaginative Indian race ; records preserved in poetry ; records about countries which the nation by whom those records are preserved had left centuries ago ; records overladen with ridiculous monstrosities, nāgas, yakkhās, oceans of ghee, and mountains of flowers, and 84,000 monks coming though the air on every possible occasion. Every sign by which an untrustworthy record was supposed to be marked was present ; yet when was record more triumphantly confirmed ?

“ The ‘Mahāwaṇṣa’ states that Aśoka lived at such a date. The identity of Aśoka and Piyadassi is stated by the ‘Dīpawaṇṣa,’ and

proved by his own edict ; the very writings of Piyadassi, on the rocks in many parts of India, name the contemporary Greek kings : the date of those kings, ascertained from undoubted Greek history, confirm with practical accuracy the date assigned to Aśoka.

"The 'Mahāvaṃsa' goes into detail about Aśoka's doings, and asserts that he sent preachers of Buddhism into various countries, amongst whom one Kassapa was sent with others, it says, to the Himavanta. This statement remains unverified in the pages of the 'Mahāvaṃsa' till the nineteenth century. Then the dāgoba of Sanchi is explored ; relic-boxes are found ; they are inscribed with names in the unmistakable characters of Aśoka's time, the characters of his inscriptions (I speak within the limits of practical accuracy), and on one of these are found the words *Kasapa gotasa Sava hemavat acāriyasa* ' (Relics) of Kassapa, teacher of the whole Hemavanta country.'

"In view of such evidence as this, to question the mission of Mahinda would be absurd, and he would be a rash man who would draw the line there. And if Mr. Parker lays emphasis on the 'Dīpavaṃsa,' saying that it was by stress of wind that Wijayo was driven to Laṅkā, and that he saw Adam's Peak before he landed, he is at any rate on safer ground than I should be, if I said it was extravagant to attach weight to such details.

"From Anurādhapura new discoveries have been reported to the Society in a Paper, rich in facts as well as gay with humour and daring in speculation, by Mr. Burrows.* I hope the challenge which he has thrown down will be taken up during the coming year by some advocate of the prevailing opinions. In presenting the solid results of his labours in exploration, he diverged into ingenious speculations as to the origin of all that art and civilisation, and shocked the Aryan sensibilities of some of us by suggesting that it was in reality Dravidian. There is much to be said no doubt on both sides. Some scholars of name, Lassen in particular, laid it down years ago, before they had much means of ascertaining, that the origin of the Sinhalese language was Dravidian ; and hence, in spite of Max Müller and most modern authorities, there are still those who dispute the fundamentally Aryan character of the language.

Veddās.

"The same question is touched upon in the elaborate Paper of Professor Virchow on the Veddās. In discussing whether the affinities of that race be Aryan or Dravidian, he considers the question of the Sinhalese language itself as too uncertain to be made the ground of argument. The Professor's Paper will no doubt be criticised. Mr. Le Mesurier and others will soon present us with views which differ, I understand, in some degree from the Professor's ; and indeed, when we see how lamentably hampered Professor Virchow was by having to take almost all his

* "Jottings from a Jungle Diary."

facts at second-hand, we may think—without arrogance—that on many points he may be yet corrected by observers on the spot. But in the meantime his general conclusion is based on too careful consideration of all the available testimonies to be easily overthrown. He thinks that the Vedḍās are a pure and strictly native race, who inhabited the Island before the Wijayan settlers came; that they are probably akin to some of the mountain tribes of Southern India rather than to the Tamils; and that the Sīghalese are a mixed race, the offspring of these aboriginal inhabitants on the one side, and of the Wijayan immigrants on the other.

Jātakas.

“On the same questions, of the immigration and affinities of nations, the permanence of customs, the veracity of traditions, as well as on the great subjects of religion and ancient art, light will be thrown, I hope, by the study, which we hope to carry on during the coming year, of the Pāli Jātakas. An instalment, very sketchy and superficial, and from the nature of the case irregular in form, is so far through the Press that our Secretary has reckoned it as printed. We have promises of contributions for the translation of a considerable proportion of the next hundred stories, and we shall be glad to receive more; but what we want especially is that Members should undertake some of the collateral work of illustration. We require for instance, at the very outset, a good list of the books which have been written about the Jātakas, with a brief intimation of the contents of each; we require a comparison of the tales in this collection, with those which occur in Burmese, or Chinese, or Thibetan collections; we want the Gāthās traced to their sources, in the ‘Dhammapada,’ in other Piṭaka books, or in outside literature; we want the Jātakas which occur, in various stages of development, in the various Piṭaka books, compared with the same as they stand in the Jātaka Commentary itself. As the Committee do not propose to bring on those Papers till towards the end of the year, it is to be hoped that Members will be found to undertake each a share in these several departments of the work.

Sīghalese Dictionary.

“A word must be said about the scheme for a Sīghalese Dictionary. We have taken the first step, but only that; but we have not abandoned the idea. My own absence and Mr. Dickson’s departure have delayed the Committee; but I hope it will soon meet and finally agree upon a ‘sample glossary’; which will be circulated among those who are likely to help us, as an indication of the kind of help we seek. The idea is, not to begin to compile a dictionary, but to begin to form glossaries of particular books, each co-operator taking a book or a portion of a book, and undertaking to make an alphabetical list of the words contained in it, giving for each the exact place or places where it occurs, and the meaning which it bears there. It is thought that out of many

such glossaries, showing in what books of different ages and styles each word occurs, and what varieties of meaning it has gone through, a systematic and scientific dictionary may some day be made. That we do not hope to see: we are content to make bricks at present for the building that is to come.

Conclusion.

"And now, ladies and gentlemen, I must detain you no longer. I have touched on only part of the topics which belong to the scope of our Society. Modern history, such as Mr. Freüdenberg is translating for us, modern language, present customs, religion, art, many things not less important than those I have mentioned, I have left untouched. How vast is the field of study that opens out before us, when we direct our thought upon even so small a world as that of this little Island! And what is all this in comparison with the expanse that lies before the restless intellect of man to be explored and sounded! *Ars longa vita brevis!* Yet in such leisure hours as we have, few enough with many of us, it is something if we have let in the light on one spot, however small, that was dark before; or have laid some stone, however insignificant, in the vast fabric of knowledge."

His Honour the Lieutenant-Governor:—"As your youngest Member, I feel that it is somewhat venturesome on my part to act on a suggestion which has been made to me, namely, that of acting as your mouth-piece in giving our thanks to his Lordship for the very excellent address which he has delivered. I was rather under the impression when he opened his remarks that he would sit down after giving us but very little information, but as his Paper developed itself, I felt that we were listening to a master, and that the Royal Asiatic Society of this Colony had at its head a President worthy of itself, and worthy of its past history. He touched in so many ways exactly upon those points which we should expect a President of a learned Society to touch upon, that he fulfilled his duty far more to our satisfaction, I am sure, than to his own. The Address which he has read will be perused, I am quite sure, by the other Members present who have not had the advantage of attending here to-night, with that gratification which we have all derived from it. On your behalf I beg to tender to his Lordship our thanks for his very excellent Address, and our thanks for having accepted the post which the Society wished that His Lordship should fill permanently." (Applause.)

The Hon. Lieutenant-Colonel Clarke seconded the motion for a vote of thanks.

His Honour the Lieutenant-Governor:—"As it is impossible for his Lordship to put this to the vote, I beg to do so. The motion is that a vote of thanks be tendered to his Lordship for his very admirable Address."—Carried by acclamation.

The Chairman:—"I have to thank you for the confidence you have been kind enough to put in me and to say that the business of the Meeting is concluded."

LIST OF MEMBERS.

(Corrected up to December 31st, 1885.)

1.—LIFE MEMBERS.

The Right Rev. the Lord Bishop of Colombo, D.D.	Ferguson, D. W.
Dauids, T. W. Rhys	Ferguson, J.
Davidson, W. E., C.C.S.	Freüdenberg, Ph.
Dickson, J. F., C.M.G.	Grant, J. N.
Ferguson, A. M., C.M.G.	Gunn, J.
Ferguson, A. M., jun.	Lewis, J. P., M.A., C.C.S.
	Nicholson, Rev. J.

2.—HONORARY MEMBERS.

Gray, A.	Künste, M. M.
Holdsworth, E.	Military Medical Officers in Ceylon

3.—ORDINARY MEMBERS.

Alexander, J.	Daendliker, P.
Alwis, Hon. A. L. D.	Dean, J. G.
Anthonisz, P. D., M.D.	Dias, C. P., Mahá Mudaliyár
Arnell, J. A.	Dias, W., M.D., M.R.C.S., L.S.A.
Bailey J. B. A., C.C.S.	Dickman, C., C.C.S.
Baumgartner, G. A., C.C.S.	Duncan, W. H. G.
Baumgartner, H. P., C.C.S.	Dunlop, C. E., C.C.S.
Bell, H. C. P., C.C.S.	Dawson, A. R., C.C.S.
Berwick, T.	Elliott, E., C.C.S.
Blair, W.	Ferguson, W., F.L.S.
Boake, W. J. S., L.M.S.C.D., C.C.S.	Fisher, W. W.
Bois, H.	Fleming, Hon. F.
Bois, F. W.	Fowler, G. M., C.C.S.
Bosanquet, Hon. R. A.	Garvin, T. F., M.B., C.M.
Burrows, S. M., M.A., C.C.S.	Green, A. P.
Capper, J.	Green, H. W., C.C.S.
Carbery, J., M.B.	Green, S., F.L.S.
Cave, A. W., M.A.	Grenier, Hon. S.
Christie, T. N.	Grenier, J.
Churchill, J. F., M.I.C.E.	Grinlinton, J. J., C.E., F.R.G.S.
Clarke, A.	Gupatilaka, W.
Clarke, Lt.-Col. F. C. H., B.A., F.R.G.S., F.C.S., C.M.G.	Guparatna, E. R., Mudaliyár
Coghill, J. D. M., M.D., C.M.	Haines, W. G., C.C.S.
Conolly, P. W., C.C.S.	Hill, C. G.
Comára Swámy, P.	Ievers, R. W., M.A., C.C.S.
Crawford, M. S., C.C.S.	Jayatílaka, S., Mudaliyár
Cull, J. B., M.A.	Jayawardana, A., Mudaliyár
	Kásipillai, M., F.H.S.

- Karunaratna, F. C. J., Mudaliyár
 Kynsey, W. R., M.K.Q.C.P.I.,
 L.R.C.S.I.
 Langdon, Rev. S.
 Lawrie, A. C.
 Lee, L. F., C.C.S.
 Le Mesurier, C. J. R., F.R.G.S.,
 F.R.A.S., F.R.C.I., C.C.S.
 Loos, F. C.
 Loos, J., M.D., M.R.C.P., L.R.C.S.
 Mackwood, Hon. F. M.
 Mason, J. D., C.C.S.
 Morgan, Capt. D., R.E.
 Morgan, J. T., M.R.C.S., M.B., C.M.
 Moysey, H. L., C.C.S.
 Nell, L.
 Nevill, H., C.C.S.
 Noyes, E. T., C.C.S.
 Pánabokke, T. B., R.M., P.M.
 Perera, E. F.
 Perera, J. F., Mudaliyár
 Perera, J. M.
 Perera, W. R. H., Mudaliyár
 Pestonjee Dinshanjee Khau
 Pieris, J. M. P., Mudaliyár
 Plaxton, J. W., M.R.C.S., L.S.A.
 Price, F. H., C.C.S.
 Pyemont-Pyemont, L. O., C.C.S.
 Rajapakse, S. De A. W., Mudaliyár
 Ráma-Náthan, Hon. P.
 Rapasingha, W. P.
 Ravenscroft, Hon. W. H.
 Rockwood, W. G., M.D.
 Sagarajasingham, M.
 Santiago, A., Mudaliyár
 Saram, F. J. De
 Saram, J. H. De, C.C.S.
 Saram, P. De, Mudaliyár
 Saunders, Hon. F. R., C.C.S.
 Saxton, G. S., C.C.S.
 Seneviratna, J. D. A.
 Senaviratna, K. D. C.
 Shamshuddeen, A. T.
 Short, E. M. De C., C.C.S.
 Skeen, G. J. A.
 Smith, Hon. C. Clementi, K.C.M.G.
 Soyza, C. H. De, J.P.
 Subhúti, W., Terunnánsé
 Sumaggala, H. S., Terunnánsé,
 High Priest of Adam's Peak
 Symons, C. E. H.
 Templer, G. W., C.C.S.
 Templer, Hon. P. A., C.C.S.
 Thomas, A. H.
 Tothill, J. F. H.
 Trimen, H., M.B., F.L.S.
 Thwaites, J. H., B.A., F.R.C.I.
 Vanderstraaten, J. L., M.D.,
 M.R.C.P., L.S.A., L.R.C.S.
 Vanderspar, G. H.
 Vandort, W. G., M.D., C.M.
 Wace, H., C.C.S.
 Wardrop, J. G.
 Webster, R.
 White, H., C.C.S.
 Williams, G. S., C.C.S.
 Wilmot, C. E., C.C.S.
 Worthington, G. E., C.C.S.
 Wright, W. H.
 Wrightson, W.

ROYAL ASIATIC SOCIETY.

(CEYLON BRANCH.)

The Asiatic Society of Ceylon was instituted 7th February, 1845, and by the unanimous vote of a Special General Meeting of the Royal Asiatic Society, held on the 7th February, 1846, it was declared a branch of that Society, under the designation of "The Ceylon Branch of the Royal Asiatic Society."

RULES AND REGULATIONS.

Preamble.

1. The design of the Society is to institute and promote inquiries into the History, Religions, Languages, Literature, Arts, and Social Condition of the present and former inhabitants of this Island, with its Geology and Mineralogy, its Climate and Meteorology, its Botany and Zoology.

Members.

2. The Society shall consist of Resident or Ordinary, Honorary, and Corresponding Members; all elected by ballot at a General Meeting of the Society.

- (a) Members residing in Ceylon are considered Resident.
- (b) Persons who contribute to the objects of the Society in an eminent and distinguished manner are, on the recommendation of the Committee, eligible as Honorary Members.
- (c) All Military Medical Officers in Ceylon are Honorary Members of the Society.
- (d) Persons residing at a distance from Colombo may, upon special grounds, and on the recommendation of the Committee, be elected Corresponding Members.

Entrance Fee and Subscriptions.

3. Every Ordinary Member of the Society shall pay on admission an entrance fee of Rs. 5.25, and an annual subscription of Rs. 10.50. Annual subscriptions shall be considered due on

the 1st of January of each year. Members who fail to pay their subscriptions by the end of the year (provided they have been called for) shall be considered, *ipso facto*, to have relinquished their connection with the Society. Members who have been absent from Ceylon have the privilege of rejoining the Society within twelve months of their return to the Island, on payment of the subscription for the current year.

- (a) The privilege of *Life membership* may be ensured by the payment of :—(i) Rs. 105, with entrance fee on admission to the Society ; (ii) Rs. 84, after two years' subscription ; (iii) Rs. 73.50, after four or more years' subscription.
- (b) *Honorary* and *Corresponding* Members shall not be subject to any entrance fee or subscription, and are to be admitted to the Meetings of the Society and to the privilege of its Library, but are not competent to vote at Meetings, to be elected to any of its offices, or take any part in its private business.
- (c) Persons desirous of rejoining the Society may be readmitted Members without entrance fee, subject to the discretion of the Managing Committee.

Office-bearers.

4. The office-bearers of the Society shall be : a President, two Vice-Presidents, a Treasurer, and a Secretary, all appointed by open vote at the Annual Meeting of the Society ; and their functions shall be as follows :—

- (a) The President, or in his absence one of the Vice-Presidents, shall take the Chair at all Meetings of the Society and of the Committee, maintain order, collect the votes, and cause the laws of the Society to be observed and enforced.
- (b) The Treasurer shall receive, collect, and pay out all moneys on behalf of the Society, keep an account thereof, including the vouchers, and submit a statement of the pecuniary affairs of the Society to the Annual Meeting, and at all other times as may be required.
- (c) The Secretary shall arrange, give notice of, and attend all Meetings of the Society and of the Committee, and record their proceedings. He shall also edit the Journal, and exercise a general superintendence under the authority of the Committee.

In the event of any office-bearer leaving the Colony for three (3) months, it shall be competent for the Committee to fill up the office at the next General Meeting.

Committee.

5. The affairs of the Society shall be managed by a Committee of nine Members (with power to add to their number), in addition to office-bearers, and elected in like manner; but subject always to the rules and regulations passed at General Meetings. Three to form a quorum.

Mode of Admission.

6. Members desirous of proposing candidates for admission to the Society shall give notice to the Secretary, in writing, at least a fortnight before the assembly of any General Meeting. Admission to Membership of the Society shall be by ballot at any General Meeting. No candidate to be considered as elected unless he has two-thirds of the votes taken in his favour.

Meetings.

7. An Annual Meeting of the Society shall be held in December, and General Meetings at such other times as may be determined by the Committee; due notice of the Meetings, of any intended motions which do not come through the Committee, and the nomination of new Members, being always first given by the Secretary.

8. The course of business at General Meetings shall be as follows:—

- (a) The Minutes of the last Meeting shall be read by the Secretary, and signed by the Chairman.
- (b) Candidates for Membership shall then be proposed, ballotted for, admitted or otherwise.
- (c) Reports of Committees shall be read, and communications made of all articles received, and donations to the Society.
- (d) Any specific business submitted by the Committee, or appointed for consideration, shall be proceeded with.
- (e) Papers and communications for the Society shall then be read.

9. Every Member of the Society has the privilege of introducing, either personally or by card, one or two visitors to the General Meetings.

10. Special Committees may be formed for the prosecution of any specific object or matter of research. These must be named at a General Meeting, and will act as much as possible in co-operation with the Secretary of the Society, who will be a constituent Member of all such Committees.

Papers and Communications.

11. All Papers and communications shall be forwarded to the Secretary at least a fortnight before the assembling of the General

Meeting at which they are intended to be read. Such Papers shall be read by the author, or the Secretary, or by some Member of the Society.

12. All Papers and other communications to the Society read or submitted at any General Meeting shall be open to free discussion ; and such Papers and discussions may be printed in the Transactions of the Society, if approved by the Committee.

13. The writer of any Paper which is published in the Society's Journal shall be entitled to receive twenty-five printed copies of his Paper.

Journals.

14. One copy of each Journal shall be sent by the Secretary to every Member who has paid his subscription, for the current year, and to every Honorary Member ; and every such Member may procure a second copy on application to the Secretary. Members requiring more than two copies of the Journal can be supplied with them at half the price charged the public.

Suspension and Alteration of Rules.

15. It shall be competent for any General Meeting to suspend any of the above rules.

16. No alteration of rules shall be made except at the Annual Meeting, and unless carried by a majority of not less than two-thirds of the Members present ; due notice of any proposed alteration having been given in writing to the Secretary at least a fortnight before the Meeting.

ROYAL ASIATIC SOCIETY.

(CEYLON BRANCH.)

The Asiatic Society of Ceylon was instituted 7th February, 1845, and by the unanimous vote of a Special General Meeting of the Royal Asiatic Society, held on the 7th February, 1846, it was declared a branch of that Society, under the designation of "The Ceylon Branch of the Royal Asiatic Society."

RULES AND REGULATIONS.

Preamble.

1. The design of the Society is to institute and promote inquiries into the History, Religions, Languages, Literature, Arts, and Social Condition of the present and former inhabitants of this Island, with its Geology and Mineralogy, its Climate and Meteorology, its Botany and Zoology.

Members.

2. The Society shall consist of Resident or Ordinary, Honorary, and Corresponding Members; all elected by ballot at a General Meeting of the Society.

- (a) Members residing in Ceylon are considered Resident.
- (b) Persons who contribute to the objects of the Society in an eminent and distinguished manner are, on the recommendation of the Committee, eligible as Honorary Members.
- (c) All Military Medical Officers in Ceylon are Honorary Members of the Society.
- (d) Persons residing at a distance from Colombo may, upon special grounds, and on the recommendation of the Committee, be elected Corresponding Members.

Entrance Fee and Subscriptions.

3. Every Ordinary Member of the Society shall pay on admission an entrance fee of Rs. 5.25, and an annual subscription of Rs. 10.50. Annual subscriptions shall be considered due on

the 1st of January of each year. Members who fail to pay their subscriptions by the end of the year (provided they have been called for) shall be considered, *ipso facto*, to have relinquished their connection with the Society. Members who have been absent from Ceylon have the privilege of rejoining the Society within twelve months of their return to the Island, on payment of the subscription for the current year.

- (a) The privilege of *Life membership* may be ensured by the payment of:—(i) Rs. 105, with entrance fee on admission to the Society; (ii) Rs. 84, after two years' subscription; (iii) Rs. 73.50, after four or more years' subscription.
- (b) *Honorary* and *Corresponding* Members shall not be subject to any entrance fee or subscription, and are to be admitted to the Meetings of the Society and to the privilege of its Library, but are not competent to vote at Meetings, to be elected to any of its offices, or take any part in its private business.
- (c) Persons desirous of rejoining the Society may be re-admitted Members without entrance fee, subject to the discretion of the Managing Committee.

Office-bearers.

4. The office-bearers of the Society shall be: a President, two Vice-Presidents, a Treasurer, and a Secretary, all appointed by open vote at the Annual Meeting of the Society; and their functions shall be as follows:—

- (a) The President, or in his absence one of the Vice-Presidents, shall take the Chair at all Meetings of the Society and of the Committee, maintain order, collect the votes, and cause the laws of the Society to be observed and enforced.
- (b) The Treasurer shall receive, collect, and pay out all moneys on behalf of the Society, keep an account thereof, including the vouchers, and submit a statement of the pecuniary affairs of the Society to the Annual Meeting, and at all other times as may be required.
- (c) The Secretary shall arrange, give notice of, and attend all Meetings of the Society and of the Committee, and record their proceedings. He shall also edit the Journal, and exercise a general superintendence under the authority of the Committee.

In the event of any office-bearer leaving the Colony for three (3) months, it shall be competent for the Committee to fill up the office at the next General Meeting.

Committee.

5. The affairs of the Society shall be managed by a Committee of nine Members (with power to add to their number), in addition to office-bearers, and elected in like manner ; but subject always to the rules and regulations passed at General Meetings. Three to form a quorum.

Mode of Admission.

6. Members desirous of proposing candidates for admission to the Society shall give notice to the Secretary, in writing, at least a fortnight before the assembly of any General Meeting. Admission to Membership of the Society shall be by ballot at any General Meeting. No candidate to be considered as elected unless he has two-thirds of the votes taken in his favour.

Meetings.

7. An Annual Meeting of the Society shall be held in December, and General Meetings at such other times as may be determined by the Committee ; due notice of the Meetings, of any intended motions which do not come through the Committee, and the nomination of new Members, being always first given by the Secretary.

8. The course of business at General Meetings shall be as follows :—

- (a) The Minutes of the last Meeting shall be read by the Secretary, and signed by the Chairman.
- (b) Candidates for Membership shall then be proposed, ballotted for, admitted or otherwise.
- (c) Reports of Committees shall be read, and communications made of all articles received, and donations to the Society.
- (d) Any specific business submitted by the Committee, or appointed for consideration, shall be proceeded with.
- (e) Papers and communications for the Society shall then be read.

9. Every Member of the Society has the privilege of introducing, either personally or by card, one or two visitors to the General Meetings.

10. Special Committees may be formed for the prosecution of any specific object or matter of research. These must be named at a General Meeting, and will act as much as possible in co-operation with the Secretary of the Society, who will be a constituent Member of all such Committees.

Papers and Communications.

11. All Papers and communications shall be forwarded to the Secretary at least a fortnight before the assembling of the General

Meeting at which they are intended to be read. Such Papers shall be read by the author, or the Secretary, or by some Member of the Society.

12. All Papers and other communications to the Society read or submitted at any General Meeting shall be open to free discussion ; and such Papers and discussions may be printed in the Transactions of the Society, if approved by the Committee.

13. The writer of any Paper which is published in the Society's Journal shall be entitled to receive twenty-five printed copies of his Paper.

Journals.

14. One copy of each Journal shall be sent by the Secretary to every Member who has paid his subscription, for the current year, and to every Honorary Member ; and every such Member may procure a second copy on application to the Secretary. Members requiring more than two copies of the Journal can be supplied with them at half the price charged the public.

Suspension and Alteration of Rules.

15. It shall be competent for any General Meeting to suspend any of the above rules.

16. No alteration of rules shall be made except at the Annual Meeting, and unless carried by a majority of not less than two-thirds of the Members present ; due notice of any proposed alteration having been given in writing to the Secretary at least a fortnight before the Meeting.

RULES FOR THE LIBRARY.

1. The library is open on week days (except Fridays) from 7 A.M. to 6 P.M., and on Sundays from 3 P.M. to 6 P.M.

2. The Librarian shall keep a register of books belonging to the library, showing their title, name of author, date of receipt, whence obtained, edition, number of volumes, number of plates, place and date of publication.

3. All books, pamphlets, and periodicals received for the library shall, immediately on receipt, be entered in the library register, and stamped with the library stamp. The Librarian shall see that each plate and map in books received for the library is carefully stamped on the reverse side with the library stamp. New books received shall be stamped on the cover with the words "Royal Asiatic Society, Ceylon Branch."

4. A book shall be kept in which shall be entered the title of every work lent out, the number of plates (if any) it contains at the time of its being lent, the name of the Member borrowing the same, and the date on which it is lent. A Member applying in person for a work shall sign a receipt for the book and plates it may contain at the time of borrowing. A Member not applying in person shall send a written request for the books he requires, and this request shall be filed in the library as a voucher, the Librarian duly noting on it the books actually lent out. The Librarian shall send with each packet of books a form of receipt, to be signed and returned by the borrower. Should any Member prefer to keep a private register of books borrowed from the library, it shall be the duty of the Librarian to enter in such register the names of all books issued, and to initial receipt when returned.

5. On return of any books to the library, the Librarian, after satisfying himself that the book is in the same condition as it was when lent out, shall insert opposite to the entry, in the loan register, the date on which the book has been returned, and return to the borrower the receipt or other voucher given by him, duly cancelled. And if on the return of any book the Librarian shall perceive that it has sustained any damage since it was taken from the library, he shall make a note of the particulars, and report the same to the Honorary Secretary.

6. No Member shall remove any book, pamphlet, periodical, or any other article the property of the Society from the library without giving the Librarian a receipt for the same.

7. No book, pamphlet, journal, or periodical, &c., shall be lent out before the expiration of one week after its receipt in the library.

8. Periodicals and unbound Journals in numbers shall be returned after the expiration of one week.

9. Works of reference and certain rare and valuable books, &c., must not be taken out of the library without special permission of the Committee.

10. Non-resident members are entitled to take out books, plates, &c., from the library on making special application to the Honorary Secretary, and signing an obligation to defray the expenses of carriage, and to make compensation for any book, plate, manuscript, &c., which may be lost or damaged.

11. No member shall be permitted to have more than three sets* of books from the library in his possession at any one time without the special permission of the Honorary Secretary.

12. Except with the special sanction of the Committee, resident members shall not be permitted to keep books, &c., borrowed from the library for more than fourteen days, and non-resident members for more than one month.

13. All books, except in the case stated below shall be returned to the library before the 1st January in each year. Early in December the Librarian, having previously ascertained that the books are actually absent from the library, shall forward to all members who have books belonging to the Society in their possession a letter requesting that such books be returned before the end of the month. Non-resident members who on the 1st January have had books, &c., for less than one month may send a detailed list of such books instead of returning them.

14. The Librarian shall report to the Honorary Secretary, for the information of the Committee, each year in January, the names of all books not returned, and of the members by whom they were borrowed.

15. If application be made to the Librarian for a book already taken out from the library, he shall issue a notice to the borrower requiring him to return it free of expense, within one week from the receipt of such notice if a resident member, and within one month if a non-resident member.

16. If any book borrowed from the library be lost, damaged, defaced by writing or otherwise, the borrower shall be held responsible for such loss or damage; and if the book belong to a set, he shall be liable to make good the set to the satisfaction of the Committee, or pay its value.

17. No books, &c., shall be issued from the library to any member while he retains any property of the Society in contravention of the above rules.

* Each volume of the Transactions of any learned Society or similar publication shall be counted as one work.

18. A book shall be kept in the library in which members may write the names of any books, &c., they may recommend to be purchased for the library.

19. No person who is not a member of the Society shall be permitted to take away any book from the library without special authority from the Committee, or to have access to the library without permission of a member of the Committee.

20. In no case shall any member be allowed to take out of Ceylon any book, manuscript, pamphlet, periodical, &c., belonging to the Society.

21. The Librarian shall be held personally responsible for the safety of the books, &c., belonging to the Society's library under his charge, and that these rules are properly carried out, as far as lies in his power.

22. The Committee may at any time call in all books, &c., and may cease to issue them for such periods as the interests of the Society may require.

PROCEEDINGS.—1886.

GENERAL MEETING.

February 13, 1886, 9 p.m., at the Colombo Museum.

Present :

T. Berwick, Esq., Vice-President, in the Chair.

A. M. Ferguson, Esq., C.M.G.	W. R. Kynsey, Esq., Vice-
D. W. Ferguson, Esq.	President.
Ph. Freudenberg, Esq.	J. Loos, Esq., M.D.
A. P. Green, Esq.	J. D. MacDonald, Esq., M.D.
J. J. Grinlinton, Esq.	W. G. Rockwood, Esq., M.D.
R. W. Ievers, Esq.	J. L. Vanderstraaten, Esq., M.D.

W. E. Davidson, Esq., Honorary Secretary.

One visitor.

Business.

1.—Read and confirmed Minutes of the Annual General Meeting held on December 21, 1885.

2.—Dr. J. D. MacDonald was duly elected a Member of the Society.

3.—Dr. Kynsey then proceeded to read his Paper, first explaining that the original had been presented to him by Professor Virchow in return for some human skin and hair which he had sent to the learned Professor. In translating the Paper he had been greatly assisted by Dr. MacDonald, who had a thorough knowledge of German, and he had thought it right to associate Dr. MacDonald's name with his own, though against that gentleman's wish. The title of the Paper was "Ethnological Studies on the Siphalese Race, by Professor R. Virchow. (Read before the Anthropological Society of Berlin, January 17, 1885.) Translated by W. R. Kynsey, M.K.Q.C.P., and J. D. MacDonald, M.D."

The Paper commences as follows :—

"At the time when I wrote my treatise concerning 'The Veddás of Ceylon, and their relation to the Neighbouring Races,' it was not possible for me to obtain a single satisfactory scientific description of the principal race of the Island, viz., the Siphalese. What I was then able to ascertain concerning them is there stated on page 60 and the following pages.

"My disappointment was, on that account, great, at not seeing the large caravan which Herr Hagenbeck brought to Europe in 1883.

"At the sitting of the Paris Anthropological Society, on October 18, 1883 (Bulletin p. 713), M. Manouvrier made an official report concerning that company, the meagreness of which is even acknowledged by the author himself, who explains it as due to want of courtesy on the part of the leader.

"Last year another caravan visited the country, and I consider myself fortunate in finding it still here on my return to Berlin. Herr Hagenbeck himself had the kindness to give the necessary instructions so as to facilitate my examination. After his departure Herr Von Schirp had the kindness to bring the people before me one by one. Notwithstanding this, I was only able to examine a small number of the forty persons of which the company consisted. There was all the preparation of their approaching departure going on, and I must say, like the Paris Commission, that the time spent in obtaining my results was too short. Besides, the determination of personal relations was surrounded with much difficulty."

The difficulties referred to were due to the impossibility of ascertaining the previous history and descent of the persons examined. Professor Virchow had hoped to meet Ceylon-born Tamils, but was obliged to abandon this hope. The Sinhalese he divided into two groups, and he gives minute details regarding colour of hair and skin, measurements of height, &c., shape of head, hands, and feet.

On the conclusion of the reading of this Paper a discussion took place, in which Messrs. R. W. Ievers, Ph. Freüdenberg, A. M. Ferguson, T. Berwick, and Dr. Kynsey took part.

Mr. Ievers referred to the difficulty of finding pure specimens of Sinhalese in many parts of Ceylon, owing to the alliances which had taken place between Portuguese and Dutch soldiers and native women. He also said that as the agent of Herr Hagenbeck was again in Ceylon engaging another troupe to take to Europe they might communicate with him and learn something of the antecedents of the persons who were to go.

Mr. Freüdenberg said that as German consul he should be happy to give any assistance.

To this Mr. Ievers replied that they would have to be careful how they mixed themselves up in the matter, as the Ceylon Government had recently paid a heavy sum for the expenses of sending back from France a party of Sinhalese who had been abandoned by their employer.

Mr. A. M. Ferguson expressed his surprise at the statement in the Paper as to the Sinhalese being a very mixed race.

To this Dr. Kynsey replied that anyone visiting the Southern Province for the first time could not fail to be struck with the

Malay or Chinese look of the people, and it was known that there had long been an intercourse between the south of Ceylon and the Malay Peninsula.

Mr. Ferguson suggested that the local Executive Committee for the Colonial and Indian Exhibition should take steps to send to the Exhibition specimens of Sighalese types, which might be examined by Professors Flower, Virchow, &c.

Mr. Davidson thereupon read a list of the persons (Sighalese and Tamil) whom the Committee were sending.

4.—The Chairman, after expressing his belief in the mixed character of the Sighalese, expressed his pleasure at the lively discussion which had taken place, and asked if there could not be some practical outcome of it. He hoped a Sub-Committee would be nominated to take steps towards collecting information for the elucidation of the questions discussed in the Paper read.

After some further conversation, Dr. Kynsey proposed and Mr. A. M. Ferguson seconded, that the following gentlemen be appointed an Anthropological Committee with the special object of contributing materials towards the ascertainment of the genesis of the Sighalese :—Dr. W. R. Kynsey, P.C.M.O. (Chairman), Mr. Ph. Freüdenberg, Dr. J. D. MacDonald, Dr. Rockwood, Dr. J. L. Vanderstraaten, and Mr. R. W. Ievers, C.C.S., Secretary. Carried unanimously.

5.—The Meeting broke up, after a vote of thanks had been passed to Dr. Kynsey, Dr. MacDonald, and the Chairman.

COMMITTEE MEETING.

February 16, 1886, evening, at Darley House.

Present :

The Right Rev. the Lord Bishop of Colombo, President, in the Chair.

W. R. Kynsey, Esq., Vice-President.

T. Berwick, Esq., Vice-President.

J. B. Cull, Esq.

D. W. Ferguson, Esq.

Ph. Freüdenberg, Esq.

S. Green, Esq.

W. P. Ranasingha, Esq.

H. Trimen, Esq., M.B., F.L.S.

J. L. Vanderstraaten, Esq.,

M.D.

W. E. Davidson, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of last Committee Meeting.

2.—Elected Mr. R. W. Ievers, C.C.S., a Member of Committee in the room of Mr. J. Capper, resigned.

3.—Nominated Mr. R. W. Ievers to act as Secretary during the absence of Mr. W. E. Davidson, c.c.s., from the Island.

4.—Elected the Hon. W. H. Ravenscroft a Member of Committee by virtue of the power to add to their number vested in the Committee, under Rule 5.

5.—Considered the proposal of Mr. J. J. Grinlinton, submitted through the Secretary, that Mr. J. Capper now leaving the Island should be elected an Honorary Member for life, in recognition of the eminent and distinguished manner in which he has, during forty years connection with the Society, from its original foundation, contributed to the objects of the Society (*vide* Rule 2, (b)). Considered also the Secretary's proposal, that Professor Virchow should receive the same recognition.

Resolved,—after considerable discussion, that further consideration be postponed to another Meeting.

GENERAL MEETING.

February 16, 1886, 9 p.m., at the Colombo Museum.

Present :

The Right Rev. the Lord Bishop of Colombo, President, in the Chair.

T. Berwick, Esq., Vice-President.	W. R. Kynsey, Esq., Vice-President.
Hon. R. A. Bosanquet.	Pestonjee Dinshajee Khan.
J. B. Cull, Esq.	L. O. Pyemont-Pyemont, Esq.
A. M. Ferguson, Esq., c.m.g.	W. P. Ranasingha, Esq.
D. W. Ferguson, Esq.	H. Sumangala Terunnánsé.
W. Ferguson, Esq., F.L.S.	H. Trimen, Esq., M.B., F.L.S.
R. W. Ievers, Esq.	J. L. Vanderstraaten, Esq.,
S. Green, Esq., F.L.S.	M.D.
A. Jayawardana, Mudaliyár.	J. G. Wardrop, Esq.

W. E. Davidson, Esq., Honorary Secretary.

Visitors, five ladies and two gentlemen.

Business.

1.—The Hon. Secretary read the Minutes of the last General Meeting, and on the Chairman asking if it was the wish of the Meeting that they should be confirmed,—

Mr. Berwick rose to point out a slight inaccuracy in the wording of the resolution regarding the appointment of an Anthropological Committee.

The Hon. Secretary explained that the original copy of the resolution had been handed to the *Times* reporter, who had not returned it, so that he was unable to give the exact wording.

Mr. A. M. Ferguson said that, as Mr. Berwick had drawn out the resolution, his recollection of the wording might be taken as correct. He might mention that the resolution was already published in that evening's paper, but he feared that a copy was not in the room to refer to.

The Minutes were then confirmed, subject to possible verbal alteration in the resolution referred to.

2.—The President announced with regret the resignation of Mr. J. Capper, who on leaving the Island has severed his connection with the Society, which he has assisted in various capacities for forty years.

3.—The President announced the early departure of Mr. Davidson on leave of absence, and that Mr. Ievers had consented to undertake the duties of Hon. Secretary in his absence.

4.—The Hon. Secretary then made a statement regarding the probable work of the Society for this year. It was hoped to have a Meeting in March for the reading of Mr. Ph. Freüdenberg's translation of Wouter Schouten's account of Ceylon. It was the custom to devote the first three months of the year to Papers of this nature. This Paper, with Mr. Freüdenberg's translation of Saar and the late Col. Fyers' translation of M. Tombe, would form one Number of the Journal. In April, May, and June it was usual to have no Meetings. In July, August, and September they hoped to have another "popular series," Papers having been promised by Dr. Kynsey, Mr. J. Ferguson, Dr. Vanderstraaten, and Mr. Burrows. Messrs. Le Mesurier, Bell, and Parker had material for Papers, and would, he hoped, contribute. November would be devoted to the Játaka studies, Játakas 51-150 being translated and discussed. To this work the Bishop and Mr. P. A. Templer were to contribute, and Messrs. E. R. Gooneratna and Ranasinha, A. Jayawardana and P. Coomara Swámy, the Rev. S. Coles, Sumaggala Unnánse and Subhuti Unnánse, would also take part, as well as several others. The publications of the Society which would be issued were as follows:—Journals, No. 29 of 1884 (in the press); Nos. 32 and 33 (a Veddá Number), 1886; Proceedings, 1884 and 1885 (in the press). There would also be hoped be two reprints, the Committee having last year resolved to devote to this purpose the amount funded by composition of subscriptions.

5.—The President then rose, and stated that he laid on the table translation of Játakas 91-95. These it had been thought advisable to send to the editor of the *Orientalist*, for publication in that journal. Mr. Berwick's abridgment of Professor Virchow's Monograph on the Veddás was also laid on the table.

6.—Mr. Frøidenberg then read the Paper for the evening, viz., “Outlines of Two Years’ Scientific Researches in Ceylon, by Drs. C. F. and P. B. Sarasin.”

The Paper begins by thanking the Society for the gift of a set of its publications, and individual Members for help. It proceeds to describe the distribution of the Sighalese and Tamils, and gives their numbers according to the last census.

The Paper then goes on to relate the researches made by the Drs. Sarasin among the Vēddās. Details are given regarding height, size of head, and face, diameter of back part of skull, width of lower jaw, size of eyes, shape of nose, measurement of limbs, and colour of skin. The first portion of the Paper concludes as follows :—

“Summing up, we learn by the measurements that the Sighalese, Tamils, and Vēddās are three well distinguishable races; and further, the measurements give much reason to suggest that the Tamils are more closely allied to the Vēddās than the Sighalese, which latter no doubt represent the highest race, whilst the Tamils in many respects range between the two others.

“One result in any case is certain, viz., that the Vēddās are by far the lowest in the scale of the three races, not only in their habits, but also in their anatomy; and this fact confirms the opinion of those who claim the Vēddās as the remnants of an old tribe of aborigines. We can pass over the customs and the religion of the Vēddās, because former writers have dealt with them, and the principal facts are generally known. We will call attention to one point only, because it illustrates clearly the primitive customs of this race, and that is the wearing of leaves as a cloth. A string is tied round the loins and small branches are put underneath, till a thick belt of leaves is formed. This custom is now almost extinct owing to increasing civilisation, but nearly every Vēddā, if requested to do so, appears in a few minutes in his dress of leaves.

“It is our intention at a later period to deal more exhaustively with the anthropology of Ceylon, and to illustrate our writings by maps and photographs. We therefore confine ourselves in the meantime to these preliminary notes.”

The second portion of the Paper is entirely zoological, dealing first with the investigations carried on by the Drs. Sarasin into the development of *Epicrion glutinosum*, a kind of ground snake inhabiting the tropics, which has hitherto been classed with the *Amphibia*, but which, according to the learned writers, belongs to the *Reptilia*. The details given are of the highest interest to zoologists, but too technical for the general public. The results arrived at regarding this animal are given as follows :—

“1.—*Epicrion* (like *Coecilia*), on the basis of its anatomy, cannot be placed in any known group of Amphibians.

"2.—Its embryonic evolution passes the same stages as the salamander as a larva.

"3.—In consequence, *Epicrium*, notwithstanding its very different appearance, has to be classed as the nearest neighbour of the salamander."

The Paper then describes researches carried on regarding the gigantic *rainworm* of the hills of Ceylon, which attains a length of about four feet and a thickness of a large thumb.

After giving details regarding investigations into the vascular system of *Epicrium*, the writers proceed :—

"The next five months were devoted to travelling in the south-east of the Island, partly in search of information about Veddás, partly with the object of obtaining an embryo of an elephant. His Excellency the Governor had the kindness to give us free permission to shoot elephants, with the special right also to kill females for the aforesaid purpose. But unfortunately our exertions in this latter direction were not successful. Three female elephants were killed, but none had an embryo. Part of the intestines of the animals has been preserved for future histological examination."

Two parasitic *sea-snails* discovered by the Drs. Sarasin are next described, as well as gigantic *sea-urchins*, among whose spines small fish find refuge, these fish having the colour of their hosts, but losing it, chameleon-like, when removed. The Paper concludes with the description of a beautiful gigantic sea-urchin, apparently new to science, which the Messrs. Sarasin propose to call *Diadema imperator*.

On the conclusion of the reading of the Paper, Dr. Kynsey rose to propose a vote of thanks to the authors, and to Mr. Freudentberg for so kindly putting it into a readable form, and reading it. He expressed his regret at the shortness of the Paper and the fact that the anthropological investigations had not been pursued further. The latter part of the Paper was of too special a nature for a general discussion. He heartily proposed the vote of thanks.

Dr. Trimen rose to second the vote, and regretted the absence of the authors of the Paper. Owing to the amount of detail, the Paper was difficult to criticise. The presence in the Island of the Drs. Sarasin would tend to elucidate many obscure points in our natural history. The British colonies were becoming quite international as regards the investigation of natural history, and this was only the beginning of Papers which would before long be written of the zoology of Ceylon. From his own personal experience he could only speak regarding the work of the authors at Périadeniya. The story of *Epicrium* was very interesting, the whole history being traced. The speaker also referred to the remarks on the vascular system of this animal, the discoveries made by the writers being original and very interesting. The

identification of the blue patches on the sea-hedgehog with eyes was new, but he did not know if it would be sustained. He concluded by cordially seconding the vote of thanks.

Mr. A. M. Ferguson rose and said that it had been a great comfort to him to listen to the Paper read that evening. At the last Meeting, the Paper by Professor Virchow had referred to the Siphalese as a mixed race; and, while Mr. Ievers had said that to find a pure type of the Siphalese one must go to the Southern Province, Dr. Kynsey had stated as soon as one left Galle one was struck by the marked Malayan type. The learned gentleman who occupied the chair on that occasion, moreover, had asserted the mixed character of the Siphalese, and the fact of even minor subdivisions into classes; stating also that the successive waves of immigration themselves had brought elements of mixture. Mr. Ferguson then referred to the resemblance of the Bengális to the Siphalese, which had struck him when he first saw them.

With reference to this last remark, Mr. Berwick asked if Mr. Ferguson would inform them to what extent the Bengális themselves were pure Aryans.

To this Mr. Ferguson replied that surely the fact of the Aryan invaders speaking of the aborigines as "black devils," who were to be torn and cut to pieces, showed the hatred they had towards them, and this would tend to keep the races from mixing.

Mr. W. P. Ranasinha then spoke at some length, affirming, from a linguistic point of view, the Aryan origin of the Siphalese, and showing how few Tamil words had been incorporated into their language.

7.—The vote of thanks was carried by acclamation, and the Meeting broke up.

COMMITTEE MEETING.

May 31, 1886.

Present:

The Right Rev. the Lord Bishop of Colombo, in the Chair.

P. Freüdenberg, Esq.

W. P. Ranasinha, Esq.

J. G. Wardrop, Esq.

[Mr. Freüdenberg consented to act as Secretary to this Meeting.]

Business.

1.—Proposed by Mr. Ranasinha, seconded by Mr. J. G. Wardrop, "That the Minutes of last Meeting be considered read."—*Carried.*

2.—Proposed by Mr. Ranasinha, seconded by Mr. Freüdenberg, "That Mr. H. C. P. Bell, C.C.S., be re-appointed Honorary Secretary, *vice* Mr. Ievers, now at Anurádhapura."—*Carried.*

3.—Proposed by the Chairman, “That Mr. Wardrop be re-appointed Honorary Treasurer.”—*Carried.*

4.—Proposed by the Chairman, “That a General Meeting of the Society be fixed for Saturday, June 12, at 9 p.m., at the Museum.”—*Carried.*

5.—Mr. Wardrop stated that he had taken over from the late Hon. Treasurer (Mr. J. G. Dean) various accounts, and gave an outline of the Society’s liabilities.

Resolved,—“That the Secretary be requested to apply to Government for the annual grant of Rs. 500 for the current year.”

GENERAL MEETING.

June 26, 1886, 9 p.m., at the Colombo Museum.

Present :

The Right Rev. the Lord Bishop of Colombo, in the Chair.

T. Berwick, Esq.

H. Bois, Esq.

Ph. Freudenberg, Esq.

A. P. Green, Esq.

S. Green, Esq.

P. D. Khan, Esq.

W. P. Ranasinha, Esq.

J. G. Wardrop, Esq.

R. Webster, Esq.

H. C. P. Bell, Esq. Hon. Secretary.

And the following visitors :—F. H. M. Corbet, Esq. ; Rev. S. Coles ; Major Clutterbuck ; Captain Robinson.

Business.

1.—Read and confirmed Minutes of last Meeting.

2.—D. A. Tilakaratna, Esq., Mudaliyár of Talpé Pattu, Galle District, was elected a Member of the Society.

3.—The Hon. Secretary laid on the table a list of books received since last Meeting.

4.—Mr. T. Berwick said, before they commenced the regular business of the evening there was a matter which, he was sure, engaged the interest of every intelligent person in Ceylon, especially Members of this Society, on which many of them would be very glad to have a satisfactory account,—he referred to the translation of the “Mahāvamsa.”

The Hon. Secretary, Mr. Bell, said he was able to tell the Society that Mr. Wijasinha had been called upon for a Report of his year’s work, and he hoped that it would be received early next month. The Report would enter fully into the work of the year, giving the nature of the chapters which have been dealt

with and also a synopsis of the remaining chapters, with some intimation of how long the remaining chapters, which are rather more difficult to translate, would take; by next Meeting he hoped that the Report might be laid on the table with Government sanction.

Mr. Berwick :—And a large portion of the translation itself?

Mr. Bell :—If obtainable; but I hardly think Mr. Wijasingha will be ready with it.

5.—The Hon. Secretary then read the first Paper on the order of the evening, a *précis* of Wouter Schouten's Account of Ceylon in the seventeenth century. Only portions of the Paper were read, as there was a very full programme to get through.

Mr. Bell said :—"Mr. Freüdenherg is unfortunately unable to read his translation of Wouter Schouten's Account of Ceylon this evening; nor has there been time to make a *précis* of the entire paper, if indeed it be possible to satisfactorily *précis* a narrative of this kind. I propose, therefore, to read a few extracts, from which the nature of the account may be gathered, premising that it contains, with much that is clearly second-hand, a fair amount of information of historical value, especially as regards dates and details of the capture from the Portuguese of the several fortresses held by them on the sea-borde of Ceylon.

"Wouter Schonten entered the service of the Dutch East India Company as clerk at the age of nineteen in 1658, and left for Batavia on April 16. He had a contract to work in a mercantile office of the Company at Batavia for the first three years, but obtained permission to travel to other stations. He was subsequently employed at different places. He returned to Holland in October, 1665, and seems to have settled in his native town, Haarlem, for his name is mentioned amongst the members of one of the Guilds there. His book was published ten years later, the drawings of which were originally sketched by himself.

"He appears to have first landed on this Island in September, 1661 (five years after the capture of Colombo by the Dutch), on the south coast at the harbour of 'Galyettis.'

"A description of the villages and their inhabitants is given, in which they are represented as living peacefully and happily under the rule of the Dutch. Schouten and some companions visited 'Dondery' (Dondra-head), and mention is made of the famous temple which had been destroyed by the Portuguese, and was even then lying in ruins. The country is said to have been 'infested with tigers, jackals, wolves, snakes, and many other monsters.' Whilst enjoying a picnic, consisting of cocoanuts and fruit, they were interrupted by the visit of a snake, which Schouten remarks in no wise seemed to disturb the natives, who only laughed at the fears of the visitors. On this circumstance, he moralises as follows :—"This impressed us very much with

the reprehensible idolatry of the beguiled Siphalese, who, as we were informed, actually worship snakes, tigers, crocodiles, monkeys, and such like monsters; they humour them and even furnish them with eatables, so that snakes and other animals generally dangerous to man should not hurt them. One really hears very seldom of the Siphalese being injured by them. Some Dutchmen wish to conclude from suggestive symptoms (but who can speak with certainty on the point?) that the Evil One sometimes appears to the idolatrous Siphalese in the shape of snakes, tigers, crocodiles, and monkeys. This much is proven:—that the Siphalese sorcerers, as well as those of other East Indian nations, in catching and conjuring them, know how to bring about supernatural effects, just as has often been reported to us as likely. But on this I shall enlarge when an opportunity offers.'

"Mention is made by Schouten more than once of the value of arecanuts as an export to the Coromandel Coast; in fact, he mentions vessels laden with that commodity, and that by the trade some places were made populous and wealthy.

"The writer was at Colombo when the Dutch were making preparations for attacking the Portuguese settlements on the Malabar coast, and describes what he saw of the town:—

"'Whilst thus riding at anchor off Colombo, we found an opportunity to go and see this old and famous town. Many fine buildings, even whole streets, were lying in ruins, partly from age, partly from sieges and wars, and many of the ruins were covered with grass and brushwood. Nevertheless, we found in the town fine buildings, lofty churches, wide streets and walks, and large houses in great number: they are spaciouly built, are airy and high, with stone walls, as if meant to stand for ever, according to the Portuguese way of building. The town of Colombo, famous since olden times, is situated barely seven degrees to the north of the equator, on the west coast of Ceylon. The gallant Portuguese constructed it well nigh one hundred and fifty years, ago; they peopled it and have since dwelt in it in wealth and pomp. But in May, 1656, after a close siege of seven months duration, after many desperate assaults and furious fighting, the daring Dutch compelled the Portuguese to surrender the afore-named fortified town of Colombo by capitulation to the East India Company. The principal kings in India were surprised at this, and not less the Portuguese, who considered Colombo impregnable. Since then our countrymen have reduced the town, which was spacious and wide, and too large to garrison, to a smaller size and a more compact fortress. Still Colombo remained provided with many strong bastions, bulwarks, walls, and a fresh-water canal, and supplied with ammunition, war-material, and men, in such wise that it would not easily have yielded to any person in or out of the country. Behind, to the east and the north, is pleasant country

plains, fields, and woods rich in cinnamon, likewise lakes, swamps, tanks and big rivers. To the west the great Ocean washes the cliffs, and rocks of Colombo.'

"Further on, in describing the country, he says Ceylon in shape nearly resembles a ham:—'Before the time of the Portuguese, who were the first Christians who came to the East Indies, the Saracens, the Turks, and the Ethiopians often visited the Island, and made no small gains by their trade in pearls, precious stones, and above all in cinnamon.' In regard to the story of Chinese occupation, he says:—'Some would have it that this wealthy Island was first discovered by the Chinese, who, having been driven out of their course in a junk by a storm, and having landed here, gave out that their ruler was the son of the sun, which so pleased the Singhalese (who likewise worshipped the sun) that they set up the captain of the junk as King of the Island, from whom it is said the kings and queens of the Island have descended.'

"A brief description is given of the forts, towns, and trading places on the coast taken from the Portuguese, including Kalutara, Colombo, Negombo, Chilaw, Mannár, Kalpiṭiya (Calpentyne), Jaffna, &c., and incidents of the several assaults and sieges are related. Trincomalie and Batticaloa are also mentioned, and the remark is made that there is no cinnamon in that part of the country.

"Galle (always mentioned as 'Punto Gale') seems to have sustained a heavy siege and bombardment before it was surrendered to the Dutch:—'Beyond the town of Punto Gale, as also around the bay and further inland, there are beautiful fields, high mountains, pleasant plains, and delightful walks, which are neatly laid out here and there between high hills, crags, and rocks, by digging and cutting through them, and are called *gravettes*. The countries and villages attached to Punto Gale produce to the Company not a little profit, having frequently realised in the farming out alone more than 15,000 rix-dollars a year.'

"The treatment of the natives by the Portuguese, Wouter Schouten characterises as proud and tyrannical, harsh and unjust. 'This excited the wrath of God, and the hatred of the people has been since made sufficiently clear to that nation.'

"We have a history of the reigning dynasty in Kandy about this time, which is extremely interesting to all students of Ceylon history. The successes and defeats of the Portuguese, and how they were supplanted by the Dutch, is related in pleasant, readable form.

"In describing the Singhalese, Wouter Schouten does not seem particularly impressed with their domestic virtues,—rather the contrary,—nor does he give them any very great credit for bravery:—'In war they are quick and skilful in going against

the enemy ; great heroes when the enemy is worsted ; but they cannot be trusted even in the smallest difficulty.' Caste and religion find a place in this relation, and the Bnddhist priests, whom he terms Brahmins or 'Bragmannen,' get anything but a good character given them. The temples and dagobas, with the sacred tooth—'the tooth of a white monkey'—and monasteries for the monks, are not omitted ; and for so short an account it is remarkable to find how almost everything relating to Ceylon and its inhabitants at that day finds a place.

"One passage may interest those who have lately been discussing the question of the Siphalese being a mixed race : 'There are also many Siphalese who, by the exertions of 'Moormen,' have been induced to adopt the Muhammadan religion. Many Moors and descendents of Turks, and other foreign people, are likewise found in Ceylon.' Elephants are described, and the mode of catching them in kraals, with a notice of their habits both in the wild state and in captivity."

Mr. Berwick said the Paper which had just been read possessed a considerable amount of interest, arising from the fact that the author had the advantage of being a contemporaneous historian. The exact precision with which the author gave the dates of the attacks on the various fortresses of Ceylon was of value. The Paper also dealt at some length with the embassy of the first Dutch General to Kandy, and following upon that was a very interesting notice of the relationship which existed between the Kandyan power and the settlers. It seemed to him (Mr. Berwick) that it would be desirable, as this Paper was to be printed along with the other Papers more or less connected with the same subject, to print also another Paper of exactly the same category which he had had the advantage of reading that day. So far as he knew it had only been published in the columns of the *Observer*, and it was the only detailed account of the capture of Colombo they had,—he referred to Mr. A. Clark's Account of the Capture of Colombo. Connected as it was with the account given by Schouten, he thought it might be very desirable that they should reprint in the same Number of the Journal that exceedingly valuable and more than interesting Paper of Mr. Clark's. He should like to know where Mr. Clark got his materials from. Wherever he got them they were evidently authentic.

Mr. Bell said he would at once answer the question whence Mr. Clark got his materials ; it was from Baldaeus chiefly. He did not think they were quite justified in printing Mr. Clark's Paper, as a translation of Baldaeus had already been in print for one hundred and fifty years. They had the book in their Library (Churchill's Voyages, vol. III.). If it was the wish of the Society that they should print it, he did not know of any rule against it.

Mr. Berwick suggested that the Paper should be sent round to those Members of the Society who took an interest in the matter: Baldaeus was not accessible to many of them.

The President said his own impression was that their object was rather to give new matter to the world than to put in the hands of Members existing literature. Mr. Clark's Paper had appeared in the *Observer*, and they had had an opportunity of becoming acquainted with it. Any copies they had in hand might be sent round to those interested in it.

Mr. Freüdenberg remarked that a description of the siege of Colombo was also given in Saar's Account of Ceylon, read before the Society last year, so that in the Number of their Journal in which Schouten's account would appear there would be a full description of the capture of Colombo.

6.—The Honorary Secretary next read a Paper on "Vehera-goda Dévāle," by Arthur Jayawardana, Esq., Mudaliyār of the Wellaboda Pattu, Galle District.

At its conclusion, Mr. Bell said in connection with this Paper he should like to move that a sum of Rs. 20 or Rs. 30 be voted to the Mudaliyār to enable him to continue the excavation. Mr. Berwick seconded.

The President said he was very sorry to be in opposition to a suggestion of this kind, but on hearing the Paper he could not say that he had gathered that there was any considerable importance attaching to the place, except traditionally. He thought it would be a pity that this Society should pay into the hands of a local "Kapurāla," who was evidently desirous of being a successor to the original Déviyó. He thought they would be doing something perhaps a little below the dignity of the Society, without further knowledge of the probabilities of antiquities being found, if they were to take a step of that kind. He thought it was within the means of a gentleman like the writer of this Paper himself to make the excavation, and that he would be amply rewarded by the *éclat* which would accrue to him.

Mr. Berwick did not take the same view. He did not expect much advantage to result from further excavation, but he thought it was a very good thing indeed to know they had amongst them a Singhalese gentleman taking an interest in this work, and he felt bound to support Mr. Bell's suggestion. It was a very small sum asked, and if any good could be accomplished by that trifling sum, and he thought some good might be accomplished—it should be granted.

After some further remarks from the President on the need of caution in granting money for excavations, Mr. Bell withdrew his motion for the present.

7.—The Honorary Secretary, Mr. Bell, read a Paper by Mr. S. M. Burrows, c.c.s., "A Year's Work at Polonnāruwa."

As to Mr. Burrows' explanation of "*Gaṅgawaṇsa*," as equal to "*Goyiwaṇsa*," Mr. Ranasinha remarked that the ancient kings frequently got their wives from the Northern Circars, and the word "*Gaṅga*" he did not take to mean as referring to the caste, but as referring to the river Ganges, which was the only river the people of the Northern Circars knew. He thought that the Queen mentioned came from the Circars, and was called "*Gaṅga*" because she came from there.

The Rev. S. Coles threw some doubt on the corrections of Mr. Ranasinha's contention, as the word "*Gaṅga*" was not unfrequently met with in Pāli and Sinhalese, used in a generic sense of Indian rivers.

The President said he should like to know how a Sinhalese scholar was struck by the way in which Mr. Burrows had vindicated (successfully as it seemed to him) the reading "*Segiri*" as opposed to "*Sigiri*." He seemed to have made good his ground, and it was just what this Society should do—show that the reckless generalisations of scholars in Europe could be corrected by careful observers on the spot. At the same time it was perhaps worth while, if they were going to print this Paper, that they should take care the transcriptions should be revised by competent scholars. Perhaps the Secretary could tell them what assistance Mr. Burrows had had at his command?

Mr. Bell said he could not say who Mr. Burrows' local paṇḍit was, but every inscription received by Government was revised by the Interpreter Mudaliyār of the Colonial Office, Mr. B. Gunasékera, than whom there was, he thought, no more competent scholar.

8.—A vote of thanks to the writers of the three Papers, moved by H. Bois, Esq., seconded by Mr. T. Berwick, concluded the Meeting.

COMMITTEE MEETING.

August 11, 1886.

Present :

W. R. Kynsey, Esq., P.C.M.O., Vice-President, in the Chair.

P. Freudenberg, Esq.

S. Green, Esq.

W. P. Ranasinha, Esq.

J. L. Vanderstraaten, M.D.

H. C. P. Bell, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of Committee Meeting held on May 31, 1886.

2.—With reference to Mr. S. M. Burrows' Paper read at the last General Meeting, and the ensuing discussion as to the true

meaning of "*Gangawaṇsa*," applied to Niṣṣaṅka Malla's queen, the Honorary Secretary stated that "Notes" thereon had since been received by him from Mr. T. Berwick and Mr. W. P. Ranasiṅha ; that Mr. Burrows had abandoned his own explanation of "*Gangawaṇsa*" as equivalent to "*Gahawaṇsa*"—i.e., "*Goyiwaṇsa*," or the "Vellala caste," for that of Mr. Berwick. The latter understands the expression to mean "of the Ganga (or Kongu) race," an important dynasty during many ages in Southern India. Mr. Ranasiṅha had come independently to much the same conclusion.

Resolved,—that both these "Notes" be printed as Appendices to Mr. Burrows' paper.

3.—Read letter from Government (A) annexing extract from the diary of the Acting Government Agent, Anurādhapura (Mr. R. W. Ievers), relative to the discovery in his district of some ruins, the original purpose of which so far baffled conjecture. Mr. Bell said that from the description the ruins would seem to be ancient burial vaults, but that further particulars should be obtained, and that he had written to Mr. Ievers on the subject.

4.—Read extract (B) from the diary of the Acting Government Agent, Hambantota (Mr. C. A. Murray), regarding the ruins of an old palace at Tisamaharāma. The Honorary Secretary stated that he had been in communication with Mr. Murray with the object of eliciting his aid in continuing, if possible through his headmen, the important excavations made at Tisamaharāma by Mr. H. Parker, and read portions of a letter from Mr. Murray showing that further interesting discoveries might be expected.

5.—Read letter from Government (C) forwarding a marble *karaṇḍuwa* (casket), together with copies of letters from Mr. S. M. Burrows regarding its discovery by him when excavating the northern chapel of the Jétawanārāma Dāgoba at Anurādhapura. The *karaṇḍuwa* bears an inscription in the modified Aśoka character, which Mr. S. M. Burrows reads tentatively: "*Siddham Gamini Tisa Maha Rajaha Rajini mi tabi hadu teni dini*." Mr. Bell stated that the *karaṇḍuwa* had been left at the Museum with a view to its complete decipherment, adding that Mr. Burrows' reading of some words appeared to be undoubtedly correct.

6.—Read letter (D) from the Office Assistant (Mr. S. M. Burrows) to the Government Agent, North-Central Province, forwarding some metal plaques similar to those found by Mr. H. Parker at Tisamaharāma, and believed by him to be coins of very great antiquity (C. A. S. Journal, No. 27, pp. 47–60). Mr. Bell said, that the majority of the plaques sent by Mr. Burrows agreed with those unearthed by Mr. Parker in the south of the Island, but that the six largest were exactly of the size and type

of the four found by Mr. R. W. Massie, c.c.s., in the Mullaitivu district; that a "Note" on these plaques (or "coins"?) would, he hoped, be shortly drawn up by Mr. Parker, to whom he proposed to send all together, for the purpose of comparison.

7.—Read correspondence between Government and D. A. De Silva Baṭuwantudāwé Paṇḍit and H. Sumaṅgala Terunnānsé, sent to the Society for its information, touching the *Ṭikā*, or commentary to the "Mahāwaṇsa," entrusted to these learned Singhalese scholars, and recently completed. The printing of the translation of the *Ṭikā* is to be taken up as soon as the Government Printing Office is less heavily weighted with work.

8.—Read letter from Government (E) forwarding copy of Mudaliyār L. C. Wijasiṅha's Report on his year's work upon the English translation of the portion of the "Mahāwaṇsa" left uncompleted by Mr. Turnour. As this Report is eagerly awaited by Oriental scholars in Europe as well as in the East, and a General Meeting of the Society might not be held for some weeks, it was decided to send the Report to the public press. The Honorary Secretary was further authorised to similarly publish any of the other communications received from Government.

9.—The Honorary Secretary stated (a) that owing to an unfortunate oversight in 1885, Nos. 27 and 28 of the Journal and Proceedings 1885 had been wrongly paged, and that he had by circular called in all copies issued, to be repaged; (b) that Proceedings 1884 had lately been issued, those of 1885 would be out next week, and Journal No. 29 (completing Vol. VIII., 1883-84) within a month; (c) that No. 32 (Vol. IX., 1886) was in the press, and that copy for No. 33 was ready for the printer.

10.—Read letter dated July 28, 1886, from H. H. Risley, Bengal Civil Service, forwarding copies of printed papers regarding certain ethnographical inquiries now in progress in Bengal, and desiring the criticism or suggestions of Members of this Society. Decided to circulate the paper among the Committee in first instance.

11.—The Honorary Secretary pointed out that he had found it necessary to employ a clerk to assist him in properly carrying on the correspondence entailed upon him, and that he had engaged the services of one at Rs. 5 per mensem from June 1. Sanctioned.

A.—The Hon. the COLONIAL SECRETARY to the HONORARY
SECRETARY of the Royal Asiatic Society.

Colonial Secretary's Office,
Colombo, July 24, 1886.

SIR,—I AM directed to transmit for the information of the
Royal Asiatic Society, Ceylon Branch, the enclosed copy of an
extract from the Diary of the Government Agent, Anurádhapura.

I am, &c.,

H. C. P. BELL,
for Colonial Secretary.

Diary Extract referred to.

June 16, 1886.—In the afternoon I went about six miles with
Mr. A. Murray to see some ruins, which I hear were discovered on
the Anurádhapura-Trincomalee road near Kalpé. I was told the
coolies, in cutting an ant-hill in the side drain, broke up a small
bronze chatty, and that Mr. F. W. Johnson, the District Engineer,
had the fragments. Met the Kórála, whom I had asked to have
the “ruins” cleared. Found that they consisted of a large
number of squares formed by four large uncut stones, the tops of
which were almost level with the present surface of the ground,
and having no slab or stone inside them. There were about
twenty or more of these squares scattered about in the jungle, but
no remains of pillars or structures. We were much puzzled to
conjecture what the squares could be, as the Singhalese never buried,
but either exposed the dead bodies in ravines, &c., or cremated
them, in ancient times. The Kórála was as puzzled as we were.
He lives about a mile away, and says the place has neither name
nor tradition connected with it. One square lay just where the
side drain of the road will run, and one of its large side stones had
been removed. Upon an ant-hill inside the square a tree was
growing. We put on a number of coolies, and cut the tree and dug
down and came upon a heap of round stones, from which we cleared
away the earth. The stones were nearly all of the size of two fists
joined, and naturally round: none were cut or squared. When
these were removed, at a depth of about three feet, we dug into the
earth, and found fragments of pottery in different places. Each
little collection of pottery had with it about a handful of ashes;
and we came to the conclusion that this was a sort of “family-vault,”
where chatties of cremated ashes were deposited, and that the
roots of the trees above had broken all the small chatties, which
were of red burnt clay, open mouthed, and about four inches high.
Mr. Murray sketched in pencil the position and size of the square,
which explains its appearance better than I can describe it.

B.—Extract from Diary of C. A. MURRAY, Esq., Assistant Government Agent, Hambantota.

May 30, 1886.—Went in search of the ruins of an old palace said to exist north of the Tisa tank, but could find no trace of it. Left two men to continue the search. * * *
 Resumed search of palace, and found the ruins this morning (31st) in dense jungle two miles from and at the back of Tisa tank to the north. There were five pillars still standing, and some were lying down half buried. Taking the measurement from the outermost pillars, the building must have been 85 feet long by 35 broad, running from east to west, and standing on rising ground. The ground round about was covered with old bricks and pieces of broken pottery. The pillars were almost round, having been dressed to that shape, and having a more finished appearance than others I have seen, which were generally of an irregular oblong or square shape. Two pillars were lying on the ground in sections three feet in length, and had at one time been placed one on top of the other and joined by mortar. The ends have been chiselled to a smooth surface so as to fit. About 300 yards in front of the ruins are two artificial ponds which must have been on either side of the main approach. They are round, and each covers an area of from two to three acres. They are about 50 feet deep and must have been excavated, the sides having an even slope from top to bottom.

C.—The Hon. the COLONIAL SECRETARY to the HONORARY SECRETARY, Royal Asiatic Society.

Colonial Secretary's Office,
 Colombo, August 5, 1886.

SIR,—I AM directed to transmit to you the enclosed copy of letter from Mr. S. M. Burrows relative to the discovery by him of a *karaṇḍuwa*, (casket) while excavating the northern chapel of the Jétawanārāma Dágoba, Anurádhapura, and I am to request you to be good enough to have the inscription on the *karaṇḍuwa* (herewith forwarded) examined with a view to its decipherment.

I am, &c.,

H. C. P. BELL,
 for Colonial Secretary.

Letter referred to.

To the Hon. the COLONIAL SECRETARY.

Anurádhapura, July 3, 1886.

SIR,—I HAVE the honour to inform you that a fortnight ago, when carrying out some excavations at the northern chapel of

the Jétawanárâma Dâgoba, I turned up the lower half of a marble *karanduwa* with an inscription running below the rim. I have reason to think (hut I may be quite wrong) that this inscription has a right to rank among the oldest inscriptions in Ceylon. It is in the Sîphalese form of the Aṣôka character ; but there is no one here who knows anything of that character, and my own acquaintance with it is of very recent date. As the *karanduwa* is portable, I am taking it in with me to Mátalé (on my way to Badulla), and will venture to send it to you from there by train "On Her Majesty's Service," and I would suggest that it be submitted either to Mr. Guṇasékara or to the Royal Asiatic Society for an opinion. I think that when deciphered, it might be as well to return it again to Anurâdhapura, as all the inscriptions found there are gradually being collected in the Kachchéri compound, and will ultimately be arranged in chronological order.

I enclose a note upon the inscription, and I should be glad to know whether the *karanduwa* reaches you unbroken.

I have obtained the consent of the Government Agent before sending it.

I am, &c.,

S. M. BURROWS.

Note on inscribed marble karanduwa.

July 16, 1886.—I found this *karanduwa* while I was excavating the northern chapel of the Jétawanárâma Dâgoba, Anurâdhapura. This chapel was entirely concealed by a vast mass of *débris*, and the casket was unearthed, at the bottom of a trench I drove into the heart of the chapel, about 12 feet deep. I am inclined to think that the inscription has some claim to rank among the oldest inscriptions yet discovered in Ceylon ; but I wish to suggest rather than assert this, as my acquaintance with the language in which it is written (a Sîphalese form of the Aṣôka dialect) is very slight. My reading of it is as follows :—*Siddham Gamani Tisa Maha Rajaha Rajini mi tabi hada tēni dini*. I am pretty certain as to the first six and the last words, and extremely uncertain as to the seventh, eighth, and ninth words. The first five words, however, are the important part of the inscription, and are those which must determine its date. The genitival form "*Maharajaha*" fixes the date, according to Dr. Müller, as anterior to the fourth century A.D., and I think the words "*Gamani Tisa*" (if my reading is correct) thrust it back still further. A reference to Dr. Müller's notes on the first eight inscriptions in his valuable collection will show how very rare and obscure are the allusions to this king ; while an additional interest is put to this inscription by the fact that all inscriptions of this age, and up to a considerably

later period, have hitherto been found only on slabs or on the living rock. I take the sixth word, “*mi*,” to be equivalent to “*nimi*,” “herself,” and would refer for confirmation to Dr. Goldschmidt’s third Report, dated Akuressa, September 11, 1876, pages 6 and 7.

I am inclined to think, however, that the forms of the letters of this inscription do not belong to quite the earliest times, but most closely resemble the lettering of the inscription at the Situlpa Vihāra (No. 16 in Dr. Müller’s book); while if the date usually assigned to the erection of the Jétawanārāma is correct, the inscription cannot be older than the fourth century A.D. I will defer what further remarks I have to make on it until the opinion of more expert archæologists has been taken.

S. M. BURROWS.

I annex the passage from Dr. Müller’s “Ancient Inscriptions in Ceylon” (p. 26) which refers to the words “*Gāmini Tisa*.” The italics are mine :—

3.—Dambulla Vihāra. This inscription was published by T. W. Rhys Davids in the *Indian Antiquary*, 1873, p. 248, but he ascribed it to a son or brother of the great Dewānampiya Tisa, which for two reasons I think impossible : (i) no inscriptions are known in Ceylon as old as Dewānampiya Tisa : (ii) the temple at Dambulla is not known to have existed before the time of Duṭṭhagāmini or Waṭṭagāmini. *The combination “Gāmini Tisa” does not occur in any other inscription*, and therefore I believe that we have to correct “Gāmini putasa Tisasa,” and that it refers to the same Tisa as No. 2 [Mahāchūla Tisa, the son of Khallātānāga, who was adopted by Waṭṭagāmini].

The Gāmini Tisa tank was bestowed on the Abhayagiri Vihāra by Gaja Báhu, according to “Mahāwaṇsa,” p. 223.

S. M. B.

D.—THE GOVERNMENT AGENT, Anurādhapura, to the Hon. the COLONIAL SECRETARY.

Badulla, July 29, 1886.

SIR,—I HAVE the honour to forward eighteen metal plaques similar to those referred to and described by Mr. Henry Parker in his archæological report on Tisamahārāma, pp. 47–60, and said by him to be coins of very great antiquity. As I understand that a paper is shortly to be written on the subject by a more competent authority than myself, I will not trouble you with further remarks on them at present; but will simply state that I do not believe them to be coins, that they were found during some

excavations I carried out at the northern chapel of the Jétawanáráma Dágoba, and that the credit of first detecting the figures and symbols upon them belongs to Mr. R. W. Ievers, Government Agent.

I am, &c.,

S. M. BURROWS,
for Government Agent.

E.—The Hon. the COLONIAL SECRETARY to the HONORARY
SECRETARY, Royal Asiatic Society.

Colonial Secretary's Office,
Colombo, August 27, 1886.

SIR,—I AM directed to transmit herewith for the information of the Society, a copy of a Report on the progress made during the past year in the translation of the “Maháwaṃsa.”

I am, &c.,

H. C. P. BELL,
for Colonial Secretary.

Special Report on the Translation of the “Maháwaṃsa.”

THE portion of the “Maháwaṃsa” that I am engaged in translating consists of 61 chapters ; that is, from the 39th to the 101st chapter. It contains 5,970 verses, and embraces a period of 1,336 years, from 479 to 1815 A.D. During the year I have finished translating 32 chapters containing 2,992 verses, or a little over half of the whole work. There now remain 29 chapters containing 2,978 verses to complete the task.

The elaborate and provokingly intricate style adopted in that portion of the work comprising chapters 62–79 require more than ordinary care to secure a correct rendering of the original. These chapters contain the narrative of the life and reign of Parákrama the Great, and form nearly one-third of the whole book.

Maháwaṃsa, “The Great History,” or “The History of the Great” is, as is well known, a metrical composition of the history of Ceylon from its earliest period down to the time of the British occupation of the Kandyan kingdom.

The first portion containing 36 chapters is known as the work of Mahánáma, an elderly monk, the uncle of King Dhátuséna. To it there is a *Tiká* or Gloss, supposed to have been prepared by the same author. This portion and chapters 37 and 38 were transliterated and translated by Mr. Turnour in 1836, which,

together with his learned and valuable dissertation, threw a good deal of light on some obscure points in the history of India, and consequently attracted the attention of the great Oriental scholars of that time. The work is out of print and is extremely scarce, and I would therefore respectfully recommend to Government the desirability of printing a new and revised edition of this work, which, though it contains many defects and errors, is, nevertheless, a production of rare value. The importance of the portion of the “Maháwansa” translated by Mr. Turnour is admitted by a great many. But the larger portion of it treats of a period so early that legend and myth are intermixed with historical facts.

It is not so, however, with the later and subsequent portion of this “Great History”: except in two or three instances there is nothing of the marvellous or incredible related in its pages, and the most scrutinising reader is struck with the air of soberness and truth which pervades the narrative as a whole. Exception must be taken, however, to that portion of the history which treats of the wonderful career of Parákrama the Great, wherein the author betrays a cringing flattery, and blind adulation of perhaps one of the greatest monarchs who wielded the sceptre of “Lañká,” but the lustre of whose great fame has been tarnished by some deeds of needless cruelty and foul treachery. The murder of his foster-father’s faithful General, and the spoliation of his wealth recorded in the 65th chapter; the dissimulation and treachery exhibited at Polonnáruwa while remaining as an honoured guest in the palace of his cousin, King Gaja Báhu, recorded in the 65th chapter, without one word of indignation or blame,—show that the hand of an unscrupulous minion was at work in the composition of the narrative.

Another salient feature observable throughout the whole of the “Maháwansa” is the abhorrence shown to the too frequent Tamil invader, who was held in detestation, not only because he was a heartless ravaging foreigner, but also because he desecrated the holy places, and demolished the shrines of the land. Nowhere in the pages of this history does it appear that the Dravidian adventurers built up altars or shrines or monuments or works of public utility to improve the land over which they held temporary dominion from time to time. On the contrary, their vandalism and spoliation of the country are recorded in words eloquent with the indignation of patriotism. These are facts which militate against the view held by Mr. S. M. Burrows c.c.s., in his “Buried Cities,” attributing a Dravidian origin to the superb architecture in which the ruins of those cities still abound.*

It might be said, however, that national prejudice made the Singhalese historians suppress the good that might have been

* “The Buried Cities of Ceylon.” Colombo, 1885, pp. 14, 15.

effected by foreign usurpers ; but this is not the case, as will be seen by a reference to the 21st chapter, in which the reign of the Chólian usurper Elála (204 B.C.) is described in most laudatory language. This king reigned over the north of the Island for 44 years, and although he left no public work as a monument to preserve the memory of his extraordinary reign, the historian records the fact that, although he continued to cling to his heresy throughout his reign, yet he was free from bias and enjoyed much glory.

Besides these considerations, there is another significant fact recorded in the "Maháwaṇṣa," which likewise goes to show the improbability of Mr. Burrows' theory. The 78th chapter contains an account of the erection of sacred buildings by Parākrama Báhu, and among them is a great *Chétiya* or *Dágaba* towering above all others, and called the "*Damiḷa Chétiya*," because it was built by the combined labour of Sinhalese and of the "Damiḷas" (Tamils), who had been brought as captives after the invasion and conquest of the Páṇḍiyan country. The passage occurs in "Maháwaṇṣa," chapter 78, vv. 79-81. It runs thus : "He caused the great *stúpa* to be built by his own royal might, without the intervention of supernatural aid from gods or saints. A *stúpa* one thousand and three hundred cubits in compass ; it was larger than all other *stúpas*, and was like a second Kailása, and was named the "*Damiḷa stúpa*" because it was caused to be built by the Damiḷas, *also* who were brought hither from the Páṇḍiyan country after it had been conquered." It seems to me that what the author means here is, that Tamil labour was employed *jointly* with Sinhalese labour in the construction of this stupendous edifice, and that the reason why the circumstance is specially mentioned is, because that was an uncommon instance in which the services of Tamils were utilised. It proves the exception rather than the rule.

Another important fact that would strike the attention of any ordinary reader of the "Maháwaṇṣa" is the prominent, if not the leading, part played by the lords and princes of Róhāṇa, or the south of Ceylon, in the past history of the country. When the kingdom was divided against itself and became dismembered, when internal disorder brought on revolution after revolution, or when the foreigner took forcible possession of the Crown and ruled with a rod of iron the "King's country" (as the north was then called), deliverance came from the south. A Dutthagámini (Dutugemunu), a Vikrama Báhu, or a Parākrama Báhu, arose from among the princes of the south, drove the invader or usurper away, reduced the country under "one canopy of dominion," and restored order and prosperity throughout the land.

"The Hillmen," or the Malaya inhabitants, now known as the Kandyans, were, it would seem, of no consequence then. Enclosed by the hills and mountain fastnesses which nature had set up for them, they lived in the obscurity of their vales and gleus a

life of ease and inactivity, without bestowing so much as a patriotic thought on their down-trodden countrymen. Their roads were impassable, their forests impenetrable, their rivers and streams dangerous, and their country unfrequented by their more civilised brethren of the north and south.

Here is a casual but terse and graphic description of the great wilderness, which as a contrast to its highly favoured appearance at the present day may perhaps be interesting. The passage occurs at the opening of the 70th chapter, wherein the successful campaign of the great Parákrama Báhu against the north is narrated:—"By cunning he (Parákrama Báhu) induced Rakkha Dandánátha, who was a General of King Gaja Báhu placed in charge of Yatthikandaka and Dumbara, in the great Malaya country, to come to him, and, after gratifying him by a display of great attention and hospitality, the King arranged with him for the surrender of the Malaya, a country passable only by a footpath, and which, on account of its many mountain fastnesses and wild beasts, was difficult of access and unfrequented by men of other districts, being moreover rendered horribly frightful by its being overspread with deep waters infested with crocodiles that eat human flesh." I need only say that the General proved a traitor, and subdued the country for Parákrama in spite of the resistance of the people whose wishes he was bound to consult and whose rights he should have protected.

It is to be regretted that the perusal of the "*Maháwaṇsa*" may tend to damp the ardour of many an enthusiastic explorer. Its records will show conclusively that the Tamil invader, who from time to time held uninterrupted sway over the land for long periods of years, had ransacked its high places and plundered their treasures, so that it would be almost useless to make expensive excavations into the half-buried ruins scattered about the Island, with a view to finding anything valuable, ancient or great. Even the Ruwanweli Dágaba, in which were embowelled the richest offerings of a devout monarch, did not escape the savage rapacity of the ruthless invader, and the pages of the "*Maháwaṇsa*" abound in notices of the spoliation which had been thus committed from time to time. As an instance a striking passage occurring in the 80th chapter may be quoted. It relates to Mágha, a powerful chieftain of Kálingga, who invaded and conquered the Island 1222 A.D., and held sway over the land for 21 years, devastating the country, and spreading dismay among its inhabitants:—

"In consequence of some great sins committed by the people of Lañká, its tutelary deities abandoned her to her fate, and a certain cruel and ignorant king, by name Mágha, who was born of the Kálingga race, and was a ruler over 24,000 strong-men, invaded and conquered the Island. Like a wild fire raging in the wilderness during a drought his strong men spread themselves throughout

the land, and boasting that they were 'the Giants of Kérala, plundered the country everywhere. They robbed the people of their raiment and jewels, violated the purity of families that had been long preserved, cut off their hands and feet, broke down houses, seized and took cattle, tied up and tormented rich people, and took possession of all their wealth and reduced them to poverty. They broke down image houses and destroyed many shrines, took up their abode in Viháras, flogged devotees and children, persecuted monks, novitiates, and candidates for orders, and made the people carry heavy burdens, and put a heavy yoke on them. They, moreover, loosened valuable books from their covers and bindings, and cast them about everywhere. Even the high and noble structures, such as the Ruwanweli Dágaba and others, which stood like the embodied glory of former Kings, they spared not, but broke into and destroyed a multitude of relics which were to them like their lives. Alas! alas!" ("Maháwaṇsa," ch. 80, vv. 54-79, A.D. 1223.)

The number of tanks and other reservoirs of water for purposes of irrigation said to have been constructed by former kings would strike one as really wonderful. I fancy, however, that the inexactitude of the writers in using the same word "*kara*," "make," to convey the idea of both "construct" and "repair" has swelled the number to incredible extent. Nevertheless there can be no doubt that the country was everywhere studded with tanks and ponds in the days of former kings, and that there was neither lack of water nor population to till and cultivate the land. Among these great works of agriculture, Kalavápi or Kaláveva appears to have been the scene of struggles for power between rival princes arriving at supreme ascendancy over the whole kingdom. It seems that either from a strategic point of view or on account of the flourishing district that surrounded it at that time, it was regarded as the key to the opening up of the whole upper country. In 624 A.D. it was the scene of a pitched battle between two aspirants to the throne, Jetthatisa and Agrabódhi III.; and about 1160 A.D. one of the famous Generals of Parákrama the Great fought hard there to force a passage across the Kaláveva river. He raised fortifications on its bank, and spanned the river with a solid bridge which is thus described:—"This General (Deva Senápati), who was gifted with great prudence, equipped all his host, and advancing to the banks of the Kalavápi river, built a fortress and occupied it. Then, by order of the King, he constructed over the Kalavápi a bridge made of timber, two hundred cubits long and twenty broad, fastened and made exceedingly strong with iron plates and bolts—a most beautiful bridge, passable by elephants and horses and chariots and infantry. And the General, having left some of the officers, proceeded thence fighting heavy battles in various places." ("Maháwaṇsa," ch. 70, vv. 126-29.)

It is to be regretted that such an important historical work as

the “Mahāwaṅsa” should have been composed in verse, wherein for the sake of metre or euphony a writer is often tempted to make superfluous additions or important omissions that tend to obscure the narrative. The “Mahāwaṅsa” therefore is not free from such flaws, and it requires great tact and discretion to make out where they occur. To enter at this stage of the translation into a critical examination of the style of each separate chapter of the text would, I think, be unnecessary, and would besides entail an expenditure of time that could be more advantageously devoted to the work of the translation itself. Moreover, the composition and style of several chapters taken together are so similar that groups of them appear to point to the hand of one writer or of one school of writers.

For the present, therefore, I shall only briefly point out these groups which, in my humble opinion, deserve a critical examination by Pāli scholars. Chapter 39, as well as the one preceding it, appears to be the work of one writer. The 40th chapter is missing, but the 41st chapter continues the narrative unbroken, although the reign of Kumāradāsa, a celebrated king whose name is associated by tradition with a tragic occurrence, is but cursorily mentioned. The 42nd chapter is very elegantly written, and appears to be the work of a master of the language. The 43rd does not appear separately numbered, but has evidently run into the 44th chapter, which, together with the following chapters as far as the 50th, is remarkably well written, the language being chaste and elegant. From the 51st to the 61st the style and phraseology are very rich and abound with the beauties of poetry. From the 62nd to 78th chapter the construction of sentences is intricate and complex, and the language elaborate, ornate, and verbose. They relate several incidents in the early life of Parākrama the Great, and give a minute and tedious account of his prolonged contest with Gaja Báhu and Mánabharaṇa for supreme power. It also gives an interesting account of the great irrigation works and other public and sacred buildings constructed by him. The chapters abound in fulsome flattery of the king in whose lifetime it appears to have been composed. This portion is evidently the work of one writer who was proficient in Sanskrit literature, but who was sadly deficient in good taste and judgment for writing the history of a remarkably great man. From the 79th to 87th chapters there is a striking likeness in style and phraseology; the chapters are moderately well written. The five chapters following them are very elegant and abound with the graces of style and diction.

Chapters 92 to 101 contain many errors of grammar and prosody, and some of them are composed unsystematically. They appear to have been written at a period when literature was in a state of decay. Between 1542–1592 A.D. Rājasiṅha of Sítāwaka, who embraced Saivism, used all his efforts to destroy Buddhism

and its literature by putting to death its priests and destroying its temples and books. In consequence of this fierce persecution a large number of monks cast off their robes, a few remained in concealment, and some left the country, so that the religion of the land lost its vitality, literature perished, and the order disappeared. This state of things continued until Kīrtiśrī Rājasīṅha, who ascended the throne about 1744 A.D., endeavoured to restore Buddhism and its order. It must have been at various intervals during this lamentable period that the chapters in question were composed.

As requested I have appended to this Report a rough synopsis of the remaining chapters of the “Mahāwaṇsa,” including therein those chapters also that have been already dealt with.

L. C. WIJASINHA.

Mátalé, July 18, 1886.

COMMITTEE MEETING.

October 19, 1886.

Present :

W. R. Kynsey, Esq., F.C.M.O., Vice President, in the Chair.

J. B. Cull, Esq., M.A.

W. P. Ranasīṅha, Esq.

S. Green, Esq.

J. L. Vanderstraaten, Esq., M.D.

H. C. P. Bell, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of last Meeting.

2.—The Honorary Secretary read a further letter (A) from Mr. R. W. Ievers, Government Agent, North-Central Province, regarding the “stone squares” referred to in his Diary (June 16th). Mr. Ievers is convinced that these squares are ancient burial places.

3.—The Honorary Secretary stated that Mr. H. Parker and B. Gunasékara Mudaliyār had examined the inscription on the *karaṇḍuwa* excavated at the Jétawanārāma Dágaba, Anurādhapura, by Mr. Burrows, and that their readings would be printed in the Proceedings (*vide* B). Mr. Parker had further promised a note on the “plaques” (or “coins”?) also found by Mr. Burrows (*vide* C).

4.—The Honorary Secretary laid before the Meeting several additional Diary entries of archæological interest, extracted from the Diaries of Mr. Ievers, Mr. C. A. Murray, and Mr. H. L. Moysey.

Resolved,—That they be printed with similar communications in the Society's Journal or Proceedings.

5.—The Honorary Secretary moved that the Society do subscribe to the Hakluyt Society, stating the object of that Society in printing rare or unpublished voyages and travels not otherwise easily accessible to English readers, and adding that Mr. A. Gray, an Honorary Member, had strongly commended the Hakluyt Society to the notice of the Ceylon Asiatic Society. Mr. Bell tabled a prospectus of the Hakluyt Society for the information of the Committee.

Resolved,—That the Honorary Secretary do communicate with Mr. Gray with the object of arranging with the Hakluyt Society.

6.—The Honorary Secretary stated that he had received a Paper from Dr. Vanderstraaten, entitled "A Brief Sketch of the Medical History of Ceylon," which he had duly circulated among the Reading Committee, and moved that a General Meeting for reading the Paper be convened before the close of the month.

Resolved,—That the Honorary Secretary do ascertain whether His Excellency the Governor will be willing to preside at a General Meeting to be held at the Museum at 9 P.M., some evening next week, the exact day being left to His Excellency's convenience.

A.—THE GOVERNMENT AGENT, Anurádhapura, to the HONORARY SECRETARY, Royal Asiatic Society.

Anurádhapura, (on circuit) September 22, 1886.


SIR,—AT your request I have made a further examination of the "stone squares" referred to in my Diary, of which an extract was sent by His Excellency the Governor to the Society. This examination confirms me in the belief that these "squares" are ancient burial places.

There are twenty-seven of them visible, all close together in about an acre of ground. They are situated at the foot of a rocky ridge called a "*hinna*" in this district, and are on level ground. This ridge has large boulder-stones and slab rocks, and must have easily afforded the necessary stones for the retaining walls of the squares. These stones are uncut, and appear to be just as they were taken from the "*hinna*."

Having looked at all of them, I found there was not one which was not more or less displaced by vegetation or pressure of the earth. I selected one which appeared to be in the least disturbed position, and the sides of which were some height above ground level. But even here two side stones were out of the perpendicular: No. (2) was leaning outwards, and the base seems to have been pushed in by some tree that no longer exists; while No. (1) was slightly inclined inwards at the portion above ground.

I carefully removed the earth inside, and at a depth of a few inches were found stones all over the area. Two were of considerable size; (A) was oblong and set up on end, being about 14 inches long by 6 inches across; (B) was a rough round stone. Underneath these were fragments of pottery and whitish earth, which may have been ashes. The stones were not symmetrically placed as those in the other "square" first opened, but laid without order. The earth was intensely hard round and beneath these stones, and though I removed it most carefully and slowly, the pottery was all in small fragments. No bronze or metal pieces were found. The pottery found in the "square" first opened, although broken, showed the shape of the chatty, but these pieces were broken too small to make out their shape.

I excavated to the base of the side stones inside, and for about half a foot above the base level the earth was free of pottery. In the centre I dug a deeper hole with the same result. The side stones are in this position—not drawn to scale, but I give the actual measurements:—



		Above ground. ft. in.		Length. ft. in.		Depth. ft. in.		Width. ft. in.
(1)	...	1 3	...	3 8	...	4 1	...	0 8
(2)	...	1 2	...	4 4	...	4 0	...	0 9
(3)	...	1 11	...	4 1	...	5 2	...	0 6
(4)	...	1 4	...	3 4	..	4 2	...	0 6

In giving the measurements I have taken them from the stone at its widest or highest point : they are only rough slabs, and the largest (No. 3) was somewhat of this shape seen from the inside.



(3)

Nearly all the “squares” are now level with the present ground level. But as we find in the excavations at Anurádhapura that the buildings are covered by an accretion of soil several feet in height, and this place being so old that there is neither name nor tradition connected with it, we may fairly assume that, when originally placed, these side stones stood about $3\frac{1}{2}$ feet over the then ground level.

Conical heaps of stone are common all over this province (North-Central Province), where a person of consideration has been cremated, but I have not seen or heard of any use of retaining walls formed of stone monoliths.

I may mention that in cutting the side drains of the new road which passes this place the fragments of pottery are so numerous that the overseer assured me it must have been “a potter’s field.” This may be a true explanation of the matter ; but the side-stones are not taken into consideration.

I regret that my examination was so fruitless, but I doubt that any chatties would so long sustain the pressure of earth and the crushing of roots of trees, as to reward the trouble of opening other enclosures here.

I am, &c.,
R. W. LEVERS.

B.—The HONORARY SECRETARY, Royal Asiatic Society, to the Hon. the COLONIAL SECRETARY.

Colombo, October 15, 1886.

SIR,—In reply to your letter of the 14th instant, I have the honour to inform you that the inscription has been examined by Mr. H. Parker and B. Gunasékara Mudaliyár, and that their opinions will be printed in the Society’s Proceedings for the current year.

I am, &c.,
H. C. P. BELL,
Hon. Sec.

(i)—HENRY PARKER, Esq., to the HONORARY SECRETARY,
Royal Asiatic Society.

Vilāṅkūlam, September 10, 1886.

DEAR SIR,—I RETURN your “squeeze” of the inscription with many thanks. It is interesting, but unfortunately there is no way of at present identifying the king who is mentioned in it. It runs as follows :—

Siddham! Maḷu Tisa Maha Rajaha Raji nimi tabi hada tani jaṇi.

“Hail! Fashioned, established, (and) put in the prepared place in the reign of king Maḷutisa.”

Maḷu Tisa has not been identified as yet. There is an inscription by him in the north-western part of the North-Central Province, which I intend to include in my general report on the archæology of Northern Ceylon (if it ever see the light). In it he calls himself the son of “Naka Maharaja”; but there are so many kings of that name that this does not help us much. The shape of the letters on the *kaṇḍuwa* agrees with those of the inscription in the North-Central Province at Ussayippukallu; but in the latter we have the palatal *ḍ* of the modern form. This and the shapes of some other letters show that the date of this king is probably not earlier than the fourth or fifth century. This inscription contains nothing of importance; but among other things it says that he enlarged the city, and the priests’ grove (*tapawaṇa*). “The city” is, of course, Anurādhapura.

With regard to the *kaṇḍuwa* inscription I may throw out the following suggestions :—

Raje = *rajiyahi*; I have found *rajahi* in another inscription of the first century A.D.

Nimi = *nimmita*.

Tabi—of common occurrence.

Hada—derived from *sādheti*; cf., the inscription on the Mal-pōruwa at Tisamahārāma, given in my report on that place.

Tani = either *tanhi*, or (possibly) *tane*, the vowel being intermediate between *i* and *e*.

Jaṇi—apparently derived from *dadhāti*.

Whatever translation may be arrived at, I have no doubt regarding the transliteration, except in the case of the *m* of *Siddham*. The horizontal mark above this letter usually denotes *o*; but in this case it is separated by a considerable distance from the consonant, and I think that it cannot be transliterated as *o* in this instance.

See also Dr. Müller’s notes on his inscription No. 98 (p. 55). This is also by a son of Naka. However, I intend to discuss these inscriptions by Naka’s son or sons, when giving a translation of the Ussayippukallu inscription. The date of the king can probably


ॐ नमो भगवते वासुदेवाय ॥

INSCRIPTION

ON A MARBLE KARANDUWA
excavated at

ANURADHAPURA

(Size $\frac{1}{3}$ of original)



never be ascertained with certainty. There is perhaps just a possibility that Maḷu Tisa is the younger son of Mahallaka Naga.

Yours, &c.,

HENRY PARKER.

(ii).—HENRY PARKER, Esq., to the HONORARY SECRETARY,
Royal Asiatic Society.

Mullaittivu, Northern Province, October 21, 1886.

DEAR SIR,—THANKS for your note regarding the *karandūwa* inscription. I am glad to find that Mr. Guṇasékara partly agrees with me regarding the reading. The hurried notes I added regarding it are merely tentative. With the exception, however, of the horizontal stroke over the “m” of “*Siddham*,” and the rather doubtful vowel in the “ni” of “*tani*,” the transliteration, at any rate, may safely be trusted. I have dozens of inscriptions in which these letters occur, where there can be no doubt regarding them, including several published by Dr. Müller.

I have had no chance of working at the “plaques” yet. At present I am on a long trip through this Province. On my return to Vilápkulam I hope to send you some notes on them. I have taken advantage of the opportunity that my stay here has afforded to visit the garden where the Mullaittivu “plaques” were found, and to examine the well out of which they came. I will give some particulars of the site in my notes. I also recovered five more of these “plaques” from the man, the last that he possesses, he said.

I believe that I have made a discovery of some importance during the last few days, regarding the site of another early station; but I must reserve particulars until I can refer to the “Maháwaṇsa,” on my return to Vilápkulam. There is a very long inscription at the spot, one of the longest in the Island. Some 75 lines of about 70 consonants each,—but the greater part of it is illegible. I have copied what I could decipher. I have now nearly exhausted the Northern Province inscriptions; I know of only two more that I have not copied, or perhaps three.

Yours, &c.,

HENRY PARKER.

Strange that there is not a single Tamil inscription in the Province.

(iii).—B. GUṆASÉKARA, Mudaliyár, Chief Translator to Government, to the HONORARY SECRETARY, Royal Asiatic Society.

Colombo, October 30, 1886.

SIR,—IN returning the “squeeze” of the inscription on the *karandūwa* found among the ruins of the Jétavanárāma,

Anurádhapura, I have the honour to state that it admits of different readings and as many renderings.

In the absence of reliable historical data to go upon, I would venture to read it "*Siddham Maḷu Tisa Maha Rajaha Rajini Mitabiya data nidane*," and submit the following interpretation:—

"Success! The treasure given by Mitabiya, Queen of the great King Maḷu Tisa."

One would at first sight feel inclined to indentify "Maḷu Tisa" with Chūla Tisa or Kaniṭṭha Tisa, but as this king reigned about the middle of the second century of the Christian era, neither he nor his queen could have endowed the *Arāma* which was founded by Mahá Séna, who, according to the "*Mahāwaṃsa*" and "*Rājataruākara*," reigned between 275–303 A.D.

I think this "Maḷu Tisa" is identical with "Makalan Datu Tisa," brother of Mahá Séna. Unfortunately, we read nothing of the above-mentioned queen either in the "*Mahāwaṃsa*" or any other native chronicle.

The *karaṇḍuwa*, which is a casket, must have contained some valuable article, and the inscription is evidently a record of the grant to Jétavanārāma either during or subsequent to its foundation. The characters resemble those of an inscription at Ruwanweli Dágoba, in the reign of Kírti Śrī Méghavarṇa, son of Mahá Séna.

Whatever may be said of the reading and rendering arrived at, I think we cannot be far wrong in ascribing this inscription to the close of the third or early part of the fourth century.

I have, &c.,

B. GUÑASÉKARA,
Mudaliyár.

(iv).—S. M. BURROWS, Esq., to the HONORARY SECRETARY,
Royal Asiatic Society.

Badulla, December 20, 1886.

DEAR SIR,—I OUGHT to have returned these to you long ago. Many thanks for sending them. I quite agree with the Mudaliyár about the latter part of the inscription; i. e., I at once accept his emendation of "*tabiya data nidane*" for my reading. But I doggedly hold out for "*Gamini*" or "*Gamani Tisa*," as opposed to "*Maḷu Tisa*," until either the Mudaliyár or Mr. Parker have carefully examined the inscription itself and pronounced upon it.* For I would point out that the reading "*Maḷu*" leaves out of sight altogether the horizontal stroke over the *m* of "*Siddham*," which stroke certainly means something, and certainly does not

* Guṇasékara Mudaliyár examined the *karaṇḍuwa* at the Museum, before writing his report.—*Hon. Sec.*

mean the “stopping” of the *m* in “*Siddham*.” There are several early examples of similar strokes representing a *g*; and the squeeze does not do justice to it. And I think too that the letter forming the last syllable of “*Gamini*” or “*Malu*” (whichever is read) is as likely to be “*ni*” as “*lu*,” but on this I do not insist so strongly. Nor do I for a moment set my opinion, as to the horizontal stroke, against that of such experienced Orientalists as Messrs. Parker and Guṇasékera: I only appeal unto Cæsar instead of to an impression of Cæsar.

I shall eagerly expect Mr. Parker’s disquisition upon the “plaques.”

Yours, &c.,
S. M. BURROWS.

C.—H. PARKER, Esq., to the HONORARY SECRETARY, Royal Asiatic Society.

Panikkankulam Resthouse, N. P., August 27, 1886.

DEAR SIR,—THIS morning I duly received your letter and the packet of “plaques.”

Besides these there are about a dozen more in Anurádhapura, but these last are mostly in a very defective state. I will write to Mr. Ievers about them, so as to be able to compare the whole series.

There are three distinct classes of the “plaques”:—(1) those from Tisa, (2) those from Mullaitivu, and (3) those from Anurádhapura. The Mullaitivu ones are distinguished by the bull, while the Tisa ones differ in workmanship.

These Anurádhapura “plaques” decidedly strengthen my case. One of them has a very clear “Aum” monogram on it,—nearly the same as the symbol on the large circular coin found at Tisa, and like the “Aum” which accompanies Indian inscriptions.

There is a clear “E” on another bearing a bull’s head. What can this be but the initial of Elára? The sitting king of this coin is almost in the position of the king on my Yatṭhala geu and on the more modern coins. I am able to trace the prototype to Chaldea, where it occurs on early cylinders. I hope very shortly to send you a note on the “plaques,” but at present all my time is occupied with my plans, &c., for the irrigation of the Karachchi delta.

The sitting figures are very interesting, especially the king on the throne.

The two female figures are puzzling, but if these are really coins, they may represent Anula.

I do not see why the Singhalese should not have oblong coins. The early Indian coins were square, Chinese (I believe) and Japanese oblong, and I have an elliptical coin of Parákrama Báhu I., which Mr. Nevill is going to figure in the “Taprobanian,” together with some other new coins.

shall certainly have pleasure, if it is so, in giving the Society the benefit of anything that I may have discovered.

"The debt of gratitude which I owe to the Veddás certainly emboldens me to speak on their behalf as a much maligned race. They have been by previous writers described as semi-idiotic, or, at any rate, so by inference. That, I am sure, is perfectly incorrect : a much higher standard must, by those who carefully and thoroughly examine the Veddá character, be allotted to them. At the point of death from jungle fever, far away—32 miles—from any European or Singhalese settlement, the Veddás, without being directed to do so, spontaneously, of their own inclination, carried me, tied to a pole with jungle ropes, to where I could obtain medical advice—to the resthouse at Bibile. It is on that account I feel that if I can in any way tend to remove the erroneous impression of their mental and social capabilities, which I see from works which Members of this Society and others have kindly lent me prevail very generally, I shall have, in some part at least, repaid the obligation which I feel towards the Veddás.

"In the second place, I feel a great surprise that, while other communities, some very far distant from your shores, have thought the subject of the Veddás of sufficient interest to send agents at great expense to inquire into their condition, manners, and customs, so little appears to be really known here, where they are at your very doors, so to speak. The surprise is not lessened by the fact, which I have since ascertained, that the information required can easily be obtained by any one enthusiastic enough to take up the work *con amore*. I found not the slightest difficulty in getting, not only among the Veddás, but at their social life. It was only my inexperience that prevented my obtaining a much more varied stock of information than I have obtained.

"I may first remark that, being in the Civil Service of Queensland, and a member of various societies in Australia, on the occasion of my taking a twelve months' furlough, I was requested by the Royal Philosophical Society, on my intimation that I intended to visit Ceylon, to make such inquiries as were possible into the question of the origin of the Veddás. That, I find, will require a much longer stay than at present I can devote ; but the social habits, manners, and customs of the people from whom I have lately come are certainly worthy of the time that I have been enabled to spend among them.

"I started, as His Lordship remarked just now, from Batticaloa. My first introduction to the Veddás was under the Bishop's auspices at Válaichchéñai. From thence, returning to Batticaloa, I found from inquiry, and also in some degree from previous information in Colombo, that a very rigid line would have to be drawn between the 'Village' Veddá and the 'Rock' or 'Wild' Veddá. There is no doubt that the date for the observation of the

Veddá, as he originally existed, say some four or five hundred years ago, has gone by. The Veddá of the present day is not even in his wild state the Veddá of an earlier period, but sufficient interest still attaches to him to render it absolutely necessary for science, if she would obtain any record of a rapidly perishing race, to obtain by whatever means, a more authentic record of them than is possessed at the present time. There is no difficulty whatever in obtaining it. It is simply a question of £. s. d. ; and anybody enthusiastic enough, and with time at his disposal to go among them, may obtain it. I speak with more confidence on this point because, in the course of twenty years, spent more or less among various races, I have never found a more pacific and humbler set of so-called savages than the Veddás. I do not speak of the 'Village' Veddá, but of the genuine wild animal. I think that, as far as the latter is concerned, I have come upon him. I found him in the Nilgala country, and only there at present. I have not yet visited the hill districts in which the Veddás reside, but hope to do so on my return from India.

"Starting once more from Batticaloa I went south. You will kindly excuse me from giving the names of the villages, as they are rather trying to an inexperienced tongue, and I have no acquaintance with Siphalese or Tamil. I think that the non-acquaintance with those tongues was rather a benefit than otherwise to me in making myself acquainted with the Veddás. I should probably have talked more and seen less (*laughter*). The Veddá is a quiet man himself, and strongly objects to enthusiastic chatter. As long as I did not take a Siphalese or Tamil with me into their camp they raised no objection whatever to a European. They have unquestionably an intense aversion—contempt I might almost say—both of the Siphalese and the Tamil. The difference between the 'Wild' Veddá, when confronted by the European, with his ordinary retinue of Tamil or Siphalese servants, and by the solitary European, is simply marvellous. He does not appear the same person.

"I had been warned, when entering the wild country, that if I came suddenly upon the Veddás I should very likely be greeted with an arrow shot, or that they would run away. Neither occurred. I was watched with some caution at first. But I took the precaution to send back the guide or native servant when within a mile of the Veddá encampment, to doff the ordinary European clothing and to simply assume that worn by the Veddás (which I need not remind you is scanty), and go among them simply with a present of tobacco, salt fish, cloth, salt, areka or betel-nut, just thrown over my shoulder. In no case was any hostility manifested to my sudden entrance among them; but, after sitting some two or three hours in silence among them, and being scanned with great surprise, they would gradually become friendly, would bring me water, and would accept what I

had brought them. There was no difficulty in my not being able to converse with them. They readily understand signs and pictorial representations. My notebook was always at hand, together with pencil and paper. In no circumstances, I think, did they fail, after a few minutes, to understand what I wished them to do. They allowed me to sleep either in the rocky caverns in some cases, or in the little huts in the *chena* that they build. They would go out with me hunting during the day, and consider me as simply one of themselves.

"The rocky dwellings of course interested me far more than did the *chena* huts; but they are very few. I think there were only some ten or a dozen *Veddás* in all the country I traversed, who were living in the rocks: and I think I may fairly claim to have been all over the *Veddá* country of the Eastern Province and the greater part of *Uva*. Some *Veddás* were endeavouring to cultivate *chena* in a very imperfect manner.

"The skill of the *Veddá* as a hunter is unquestionably on the decline. The old men use the bow with great skill and great force; the younger ones are but very poor *toxophilites*. Their food still consists, in the wild districts, of roast meat, jungle yams, and some berries and leaves.

"When I had become familiar with the *Veddás*, and gained their confidence, after a week or two I would take two or three back to the place where I had left my stores and native servants, and, carrying with me as I did a *Sinhalese* and *Tamil* interpreter, I would keep the *Veddás* for an evening and ask from them explanations of all that I had seen. They never withheld the information, but there is a peculiarity in them which I have not observed in any other race before, and that is that they never gave the information voluntarily. I had to draw it out of them, in consequence of which I had to verify at each camp that which I had gained in the others.

"I have come to the conclusion, from what I have seen, that the reputation of the *Veddás* among the *Sinhalese*, their neighbours, is correct. The *Veddá* is eminently truthful. He scarcely knows how, or does not care, to tell a falsehood. Neither is he addicted to the vice of petty theft. This may be readily explained by the fact that he has nothing to steal. Beyond his bow and two or three arrows, his axe, bark bag, and it may be a few gourds, and a little *kurakkan*, he has no possessions at all. So the absence of any regulations, or any punishments, among them, relating to stealing, can easily be accounted for.

"I paid particular attention to their form of government amongst themselves, for they do not trouble the Government Agent or the powers-that-be in any respect. I found only one rule among them; and, as far as I can gather, the enforcement of that rule has for many years been a very rare incident.

Should a Veddá make improper overtures to, or have improper relations with, his neighbour's wife, the injured husband, with the consent of the community, has a perfect right, at any time that he pleases, to send an arrow into the offender. No other law exists whatever, so far as I was able to gather. Should a Veddá be found lying dead from an arrow shot—a mark most unmistakable—the elder men meet, and immediately come to the conclusion that the defunct Veddá has been in fault in the above said respect, and he is at once interred without any further comment.

“Living as the Veddá does in some cases in villages near Siphalese settlements—when I say ‘near,’ the Veddá has a different conception of distance: he thinks ten or fifteen miles near, because he is essentially a creature of motion—it may be supposed that, when he runs short of provisions, his neighbours’ food might suffer. I made particular inquiry amongst the Siphalese inhabitants, and in no case did I find that any charge of petty theft, or suspicion even of it, had been brought against the Veddás. In that respect they certainly are an improvement upon their neighbours.

“The language spoken by the ‘Wild’ Veddá is a most extraordinary one. When walking quietly together, as, for instance, hunting in the thick depths of the Bintenna forest, five or six preceding me, also carrying a Veddá bow and arrow, about twenty yards ahead, on the look out for elk or pig or anything that might occur, it was some weeks before I found out that the Veddá was talking. It is done so quietly; with the long hair thrown over the face—an intentional arrangement I am quite sure—the Veddá speaks to his neighbour Veddá in such a peculiar undertone, such a strange muttering, that, unless close behind, it is impossible to hear him. Their language, though I carried with me a very competent interpreter, is not intelligible to the ordinary Siphalese on the whole. Probably in a long sentence the interpreter will understand about a third of it; they have an original language with which the Siphalese is not familiar. I have obtained a vocabulary of 180 purely ‘Veddáic’ words,—if I may use the expression,—but that vocabulary will, of course, have to undergo revision at the hands of Oriental scholars before I can publish it.

“The life of the Veddá may be simply described as that of perpetual motion. With the exception of sleeping, he is not still a moment. I rarely saw a Veddá sit for five minutes in any given position. He will walk all day long without feeling the slightest fatigue, and walk in a most peculiar manner. I have often put on four or five pairs of heavy merino socks to deaden the rustling sound, and started out on an expedition. Despite my precautions and every effort I could make I have frequently scared animals before coming up to them. The Veddá moves like a

shadow : that is the only term that can be applied to it. You cannot hear him in the slightest. It is simply marvellous : they tread on sticks and twigs and not one will rustle under their feet.

“The bows and arrows which they use appear to be the same in all the villages with one exception, that at Unapau, in the Bintenna country, where I saw some arrows fourteen inches long in blade. Usually they are four or five inches : this is a fair medium sample [*taking up an arrow*]. The force with which the arrow is projected can be understood when I say this arrow was fired at my request through a large wild pig. It was shot on a moonlight night, near a waterpool. The Veddā wished me to shoot first : I declined the honour, and indicated that the Veddā was to fire. Sitting down he held the bow in a peculiar manner, and drawing the string with both hands he shot the arrow off ; at the same moment two other Veddās on each side of him fired. A pig squealed most dolefully, and I ran round the edge of the waterpool to find the arrow. I looked round for a moment or two. Some six feet from there the arrow was very nearly up to the feather in the bank. I have tried the experiment with a rifle. I was unable to send a bullet through the animal. The force with which the arrow was sent can therefore be imagined. When I say that, from what I have seen of them, I would far sooner at fifty yards face the fire of an ordinary rifle in the hands of an experienced person than I would allow a Veddā to fire an arrow at me at the same distance, you may be sure I feel pretty convinced as to the efficacy of the weapon. Up to the feather is a not unfrequent occurrence when firing at a buffalo.

“It is said that the Veddās do not eat the flesh of cattle at all. Certainly, I never saw them attempt to eat it. It is said also they will not eat fowls. I think that is an error. At any rate the ‘Village’ Veddās and those intermediate between the ‘Village’ and the ‘Wild’ Veddās have all of them, in their camps, a number of poultry. Eggs I know they eat, and sometimes, when the Veddās were in my camp, I gave them a part of a roast or boiled fowl, which they have eaten. It may be that they did not know what they were eating, but I am inclined to think they did know, and relished it too. They, however, will not eat the bear or the leopard ; the jackal especially they will not touch. I asked them why, and they gave me a reply which was equivalent to saying it was not clean. From what that notion arose I was unable to gather. In connection with the poultry another incident occurs to me. I remember seeing two Veddās trying to knock over with sticks a jungle cock. It is not likely that they wanted it for feathers for their arrows, because they usually employ peacock feathers. They did not succeed in getting the bird, and when I asked them what they wanted

it for, they pointed towards the camp, but my interpreter not being there, I could not ascertain for what purpose they wanted to catch the bird.

“They have no idea of hoiling anything. The nearest approach to it is the case of the ‘Village’ Veddás, who, to make a candle out of beeswax, put a little water into a gourd which they have hollowed out. When the wax is on the point of solidifying they take it up in the hand and squeeze it round either a piece of cloth, if they happen to possess any, or twisted thread, and use it for giving light. Here are two of these primitive candles [*showing those on the table*].

“Light they obtain from wood, though some of them also have a rough kind of flint and steel which is composed of a piece of iron bar, about three eighths of an inch thick, made to go round the little finger. But they place much more reliance upon the wood. It appears to be the wood of a particular kind of tree. The old men carry the stick to assist them in walking. When fire is required, this stick is often simply snapped into two pieces. The Veddá sits on one piece laid on the ground, and, making a small hole in it, places the other piece, slightly pointed, therein perpendicularly; then putting a stone or cocoanut-shell on the top, he presses it down with his forehead, working it about in the hole with a cord of bark twisted round and held by the hands. [*Mr. Stevens here showed the manner in which the sticks and cord are arranged.*] The exertion required to produce fire is very great, but the Veddá will do it, apparently without any effort, and in five or six minutes smoke appears. As soon as he perceives the slightest spark, he places a bundle of fibre close by and begins blowing, and in five cases out of six succeeds in obtaining fire.

“The only other weapon the Veddá carries besides his bow and arrows is an axe. He uses the axe-blade for all the purposes of a knife: for skinning animals, for cutting up his meat—in short, for anything where a little edge is required the axe-blade is used. One blade that I have with me—this one [*holding it up*]
—was forged by a Veddá himself. It was forged with the back of an axe on a stone. From some traces and indications among them, I am inclined to think they once universally possessed the knowledge of working in iron, at any rate so far as was required for their weapons. They seem to have lost it now owing to the greater ease with which they can obtain their weapons from Singhalese or Portuguese blacksmiths at a distance of fifteen or twenty miles—what they term close at hand.

“Their proceeding is exactly that described in other accounts, only that the punishment for non-compliance with their wishes is not carried out now owing to the fear of the Government Agent and his orders. Taking a number of leaves, or a piece of wood—they seem to use them indifferently—of the pattern

desired to the smith's house late at night, they hang it up at the doorway.

"I accompanied a Veddá on one of these expeditions, and some of these arrows were made in that way. He hung it at the doorway, hanging at the same time a present of meat, wax, honey—the honey being placed in one of these bark bags. Three evenings afterwards he went again, and the arrows were ready for him. In former days had that smith not complied with the request—I do not take this merely from books, but I ascertained that it was true—the Veddá would simply have lain in wait for the unfortunate man and sent an arrow through him, as an intimation that he was offended at the want of compliance; and, therefore, the smith very rarely objects to put aside other work and go on with the work the Veddá wants done. If the work is done, for two or three nights subsequently presents will be laid at the smith's door. The smith is exceedingly over-paid for his work, according to the ruling rate of exchange, but the Veddá does not seem to care what he gives so long as he obtains his arrow, arrow-blade, or axe.

"I found great difficulty in getting them to part with some of these articles. Money is not of the slightest value to them; of trade they have no idea, and presents they look upon with wondering interest.

"The bag which I was speaking of is formed from a tree which grows principally round the Mahá-oya (in some districts it does not grow at all), and the Veddás have to travel into that district when they want to obtain any, either for use as bags or—as they did at one time, according to their own statement—for the purpose of garments for 'the ladies.'

"I wondered much that I did not see any skins used. In no case did I see any skin utilised for any purpose whatever. The Veddás sometimes wear the broad leaves of a tree, the name of which I have yet to verify. [*Mr. Stevens here drew the shape of the leaf on a sheet of paper.*] At other times simply a spray or twig of small leaf like the English hazel, is worn allround as a girdle, with a strip of bark or twigs tied in this manner. [*Shows.*]

"With his long hair and girdled with leaves the Veddá looks, it may be supposed, a very peculiar individual, but when he is performing one of his dances by the firelight, he looks an individual a great deal more 'uncanny.' It was during one of these dances when 'in the leaf' that he gave me a very convincing proof of the great—I may say one of the principal—peculiarities of the 'Wild' Veddá. He will not stand ridicule. If you attempt to laugh at him the probabilities are that he will take a very speedy revenge.

"During a dance on one occasion at night such peculiarly comic antics were suddenly indulged in that I involuntarily commenced laughing. The dance was round an arrow stuck into the sand,

the bows being placed round in a circle. I had scarcely begun my ill-timed merriment before the Veddá pulled the arrow from the ground, in a moment his bow was in his hand, and before I could move—I was only three yards from him—au arrow whizzed past me ! I attribute my escape solely to my proximity to the enraged Veddá, and his extreme haste in shooting. I thought he was going to fire another arrow (for they are marvellously quick), but he did not happen to have one at hand, and perhaps he did not care about coming to close quarters with his axe. However, he took all the merriment out of my face, and taught me a very sufficient lesson not to laugh again.

“On another occasion, in the presence of Mr. Ælian King, the Provincial Agent of Uva, and Mr. Moss, of the Forest Department, after the Veddás had carried me into Bibile, a similar incident occurred. Some Tamil and Singhalese idlers gathered round began laughing at the dance, which by special request was being performed. Instantly every Veddá—there were seven—had his hand to his bow and the arrow drawn to the head, pointing at the Singhalese and Tamils ! I jumped out of bed, though very ill at the time, as I saw there was mischief brewing, and, seizing the chief Veddá's bow, I called on Mr. King to send the laughers away. There was no necessity for the latter injunction, they had promptly disappeared—and it was well they had, for I verily believe the Veddás would have sent the arrows among them.

“You cannot possibly annoy a Veddá more than by laughing at him, and that I think has been one of the great stumbling-blocks to observation among them before. Instead of going solitarily, the European has invariably taken a retinue of ignorant or careless Tamil or Singhalese attendants. In the first place, the Veddá has a great aversion to them, and they are sure to begin laughing at him. They treat the Veddá simply as a subject for ridicule, and the Veddá thereupon assumes a mask of complete impenetrability ; he just looks what he has been described as—a perfect idiot. Drawing the hair over his face, so that his eyes are rarely visible, he stands a perfect picture of stolid unimpressionability.

“On one occasion only did I see him assume that attitude towards me. I wanted to know what became of the dead Veddá babies. I could see no burial-place. I knew such a thing must occur. I could not find it out from the Singhalese, and, having a good interpreter, I asked the first camp I came to what they did with their dead children. The only reply was—if you can call it such—to throw the hair over the face and remain stolid and impassive. I repeated the question to make sure that they understood it. They understood it well enough. They were too truthful to tell me a falsehood in the matter, and they did not intend to tell me, so they remained quiet, and not even threats on

the part of the interpreter (which I afterwards found out he had been using) could get me an answer.

"I am perfectly at a loss to know what they do with their children when they die. My own impression—it is only an impression—is that they place them in hollow trees and cover them in with clay; but I am very doubtful about it. I was unable to find that out, but I hope to do so on my next visit. I do not know whether any Member of the Society has any information on the point; if he has I shall be very glad to get it.

"The number of the Veddás has, I think, been over-estimated. Taking the district over which I went, and comparing it with those in which Veddás are known to exist, I question very strongly whether there are 500 Veddás in the Island. I think that within the next hundred years it will be almost impossible to get a real Veddá. Therefore it behoves the Asiatic Society, the Museum, the powers-that-be, and all others who may be interested in them, to obtain, before it is too late, the information which in a few years will be unobtainable.

"In stature, the Veddá, as far as I have been enabled to judge yet, varies from 5 ft. 7 in. (which is considered to be unusually tall amongst them) to 4 ft. 3 in. Their build is exceedingly slight. They appear not to have a pound of superfluous flesh upon them; but, notwithstanding their slight dimensions, they are exceedingly strong and wiry. They will carry a load upon their shoulders that would fairly tire me, for I tried it; and the ease with which they will draw these heavy bows and shoot, although a great deal may be due to practice, is simply astonishing. Any one present trying to pull this bow [*handling one*] will find it tax his muscles very considerably, and that is only one selected out of a number which I obtained; some are far longer and stronger.

"Peaceable, mild, and quiet, the Veddás only ask to be let alone. Unfortunately the latter request is not complied with. The most shameless extortion and plunder are practised by the A'rachchies, Kórálas, and Ratémahatmayás in their districts. On some occasions where I have been able to do so, I caused restitution to be made. Supposing an A'rachchi, having nothing particular to do, feels disposed to have some elk meat, bees-wax, honey, &c., as the case may be: he simply walks to the nearest Veddá village and intimates that the Government Agent requires these things as a tax, and invariably succeeds in getting it. The Veddá never thinks of resisting, and this little fraud is repeated in many cases three or four times in the year. I believe to some extent this is known to the Government Agents, but the question is how to put a stop to it. It is so difficult to obtain any evidence, for the Veddás simply refuse to speak if confronted with the Agent. It speaks volumes for their peaceable nature and also ready obedience to the law.

"Much has been said of the readiness of the Vēddā to greet a stranger with an arrow. In some cases he does so. If a Sinhalese or Tamil, I firmly believe, were to go among some of the camps which received me with simple, questioning wonder, I am very much of opinion that he would be promptly greeted with an arrow. The intense aversion which the Vēddā feels to the Sinhalese is rather difficult of explanation. He certainly considers himself his superior. The Sinhalese rather allow that superiority, while at the same time they use the word '*Vēddā*' as a term of reproach.

"The nearest and most correct estimate of the Vēddā character is probably that found over the initial 'J. B.' in the Appendix to an account in the Journal of the Ceylon Asiatic Society, No. 24, 1881.* There is nothing there but what I have actually observed, and though not quite complete, still it is devoid of any of the absurdities which have been written elsewhere.

"That number also contains an article by Louis De Zoysa, Mahā Mudaliyār. He specially states that the information embodied in the article was given him by a low-country Sinhalese of Badulla. Mr. De Zoysa unfortunately did not verify his information, and has therefore placed on record some matter which appears to me to be so totally incorrect—I refer to the Vēddā charms and songs—that I intend to make a special trip to Horaborawēwa in particular to ascertain whether it is so or not. No Sinhalese or Tamil, however educated, was able, in the first place, to make out more than two-thirds of any statement by the Vēddās, more particularly their songs; but these are given by Mr. De Zoysa in detail. The remarks supposed to be made by the Vēddās are such as I feel confident from my short acquaintance with them never entered into any actual Vēddā head. Nor is the style of the literature at all like the Vēddā songs.

"This I did not know until I entered the park country. When lying asleep in a Vēddā encampment I was aroused by something tapping me on the head, from outside the little hut in which I was. Opening my eyes and peeping out, I found a party of Vēddās squatted round listening to a song sung by another just outside. I kept my eyes shut and my ears open, and for more than an hour he continued this song—very different to the song that the Vēddā sings when making an invocation or propitiation. It was a rather low musical rhythm. Occasionally he would converse in a low voice with the other Vēddās, and very frequently a laugh passed round.

"The old absurd statement that the Vēddā never laughs has

* Extracts from the late Mr. John Bailey's account of the Vēddās, in Trans. Ethnol. Soc., vol. II., n.s., art. xxvi., 1863.

been effectually disproved. He can laugh just as freely as any Sinhalese or Tamil, and a great deal more musically; but anything more discordant than the Veddá's speech when suddenly confronted by strangers it will be difficult to conceive. It is positively as if under the influence of great fear, although the Veddá in the presence of wild animals exhibits considerable nerve and very little fear. But the whole manner of the man seems to have completely changed under the two circumstances of solitary insecurity, and in the presence of strangers, that you would scarcely believe the man to be the same.

"In one of this Society's Journals [No. 13, 1865-66, pp. 1-117], which were kindly given me by your Secretary, Mr. H. C. P. Bell, C.C.S., after my return—for I visited the Veddás unbiased by previous perusal of the literature on the subject—appears a very interesting article by Mr. Dandris De Silva, Mudaliyár, on the Demonology of the Sinhalese. I am sorry I did not see this article before I started on my trip. I made particular inquiry into the Veddá religion. From all I can gather, demonology is an incorrect expression to apply to it. It is rather '*Kapuisim*,' but with the indifference that they have no special '*Kapuisim*' among them. They do not believe in the existence of any injurious or malevolent spirits, differing very greatly from their neighbours the Sinhalese in this respect. The sight of myself, with my white epidermis burnt by the sun, groping among the habitations of their dead, must have given them a very strong notion of one or two Sinhalese demons which are very much dreaded! To further test the idea of the Veddá as regards superstition, I buried a skull under the entrance to one of their little chena huts in their full view. Not a single Veddá made the slightest hesitation in walking over it. From what I have read, I think an ordinary Sinhalese villager would absolutely have dropped down dead with fright if he thought any charm were placed under his feet in that way.

"Once a year the whole of the Veddá encampment make a propitiation. It is not worship: I am firmly convinced that that term is inapplicable to it. They simply make a propitiation to the collective gods,—the Veddás have some eight or nine gods,—and they consider the gods will ward off any injury to them if they make this propitiation. If injury happen to a survivor it is considered that the man has not performed his propitiation properly. But there is one remarkable exception. In gathering the honey of the large *Rambara* bee from the face of the cliffs a jungle rope is used with a cross-stick, which is lowered down to the place where the bees have formed their nest on the side of the cliff. The Veddá slides down, and gathering the honey into one of these bark bags [*shown*] put round his neck, ascends—that is, if the rope does not break, as sometimes it does. In that case no reference whatever is made to the man not having

properly performed his propitiatory rites. It is taken for granted that the next of kin, on whom always devolves the task of selecting and fixing the rope, has failed in judgment: he has to support the deceased Vēddā's family in consequence, and the blame is not laid upon the spirits or gods.

"They have one or two dances when they are going out on any expedition: these seem to be directed solely to the spirits of their dead relatives. While I have repeatedly heard the Vēddās invoke their dead fathers, mothers, and other relatives, I have never heard them invoke their children. The invocation is a repetition of two or three lines, of which I have a translation. I cannot give it now, but hope to do so shortly. That performed, the Vēddā starts with a light heart on the performance of whatever he is doing. Superstitious he certainly is not. He knew, I think, a great deal more about rites and ceremonies at one time than at present. Having no written characters whatever the whole of the traditions have been handed down from father to son orally, and a great deal has evidently been forgotten.

"The life of the Vēddā under his rocky cavern is simple in the extreme. Rising at the earliest dawn, the women — 'the softer sex,' if I may call them so, but I really do not think the term applies to them — attend to their domestic duties. The Vēddā wife is not quite a pleasing person. She is very unlike her husband; she is very noisy. She is rough in her manners and demeanour, and certainly reverses the ordinary condition of things, and is not half as good looking as her spouse. Only on one occasion did I see a good looking Vēddā woman, with her two little children as good looking as herself; the generality are very plain. In one account I have come across an expression seems to hint that originally the Vēddās were remarkable for their good looks, and it is not improbable that the observation may be correct, for I think that, physically and mentally, the Vēddā, within the last four or five hundred years, has degraded very much indeed. — To resume: the husband, or men of the encampment, start out to look after game. They are out all day, and taste no food until they come back, when they take a little roasted flesh, and it may be some *kurakkān*, or yams, or berries, — the Vēddā never eats more than once a day when by himself, — and then retire to rest.

"The Vēddā is a good father: very kind. He seems to be an equally affectionate husband, and quarrels between husband and wife are exceedingly rare.

"As regards the children, I did not know until after my return that doubt existed in various writings that they had any play-things. They have: I have seen the Vēddā children play. I am now speaking of the more remote Vēddās. The children play with little balls, large berries, and three little sticks which they toss up in a peculiar manner, and different mud images. The fact of their making mud balls and images would seem to imply that

at no distant date the Veddâ understood how to make pottery. There is certainly a tradition among the Sighalese that they did, but they have no idea at present about it. The play of the children is of a very subdued character; not noisy, romping, and high-spirited, like other children, but rather as if they were under the impression that they were going to be scolded if they made a noise. When they have done playing, the playthings are carefully put away in the roof, or in a hole in the rock, or under a bush. Doubtless that is how the toys have hitherto escaped observation. They do not apparently attempt to play during the day—only in the evenings, when their parents have returned.

“Rice, the ‘Rock’ Veddâs will not touch. On two occasions I gave ‘Wild’ Veddâs some rice when they came to the camp of the interpreter. They ate it,—certainly with no great gusto,—but immediately afterwards asked for different food, ‘because if they ate that it would make them sick.’

“The Veddâs divide themselves into eight clans. I am not aware that this information has been made public before. I have taken great pains to verify it, and I find that one of the subjects on which a Veddâ most prides himself is in belonging to one of the higher clans, or ‘*Virga*,’ as they call it. Originally the whole of the *Virgas* appear to have been concentrated—at least so far as the Veddâs have any tradition—in two clans, the *Unapâni* and the *Lochcho*. I am obliged at present to give these names phonetically; but they will be submitted to competent scholars, and the result will appear before the Asiatic Society shortly.

“The traditions in connection with these clans are rather interesting, and have to a great extent been verified. It would seem that the Veddâs of Bintenna—whether they derived the idea from the Sighalese or not I cannot say—believe one clan, *Bandâra*, the greatest and first, to derive its origin from Wijayo. Whether that came from Sighalese notions implanted in them I cannot say at present; but it certainly agrees with the theory that has been started, and with the assertion of the Sighalese of the Bintenna district, who hold the same view. The second clan, *Nebadâni*, claim to be descended from the union of another Sighalese prince with one of their own people. The third, *Unapâni*, was one of the original clans; and the fourth settled in a village of their name after they were driven back by the Sighalese from some other part of the Island. It would appear as if that portion of the country is the Adam’s Peak district, Sabaragamuwa, or Saffragam. History records that they were driven back in that way, and the traditions of the Veddâs go no further than the settlement in two particular villages, not very many miles apart, of the *Unapâni* and *Rukam* tribes. Between these two there was considerable rivalry and jealousy, but from them spread out, as they increased in numbers, the other clans. The localities to which each clan went

are rather important, and are under revision in order to ascertain what places can be found in those districts, to test the correctness of the tradition. *U'rava* is the fifth clan, *Rukam* the sixth, *Tala* the seventh, and *Embula* the eighth. The last-mentioned seems to have disappeared altogether. It was swamped in the parent stock, and in the district where it originally settled no trace whatever can be found.

“As regards *Unapáni* there is some doubt as to the meaning of that word—viz., as to whether it means ‘bear village’ or ‘hot water village.’ Another clan, after leaving the parent stock, settled at the time of very heavy flood at a pool, near the sea coast, in which, on the water subsiding, a large skate fish was found imprisoned. They killed the skate, an unusual thing for them to see, ate it, and took their name from it. *U'rava* is another clan. This outgoing colony settled by a large tank where many pigs were seen, and the settlers were called *U'ravas* or ‘pig-pond’ *Veddás*. The derivation of *Rukam* is yet in a state of uncertainty; the *Veddás* themselves could not explain it. *Tala* were ‘the open country’ *Veddás*, who settled away from the jungle. *Embula* has the most peculiar tradition of all. It is that a new colony, on starting away, proceeded, immediately on reaching their new grounds, to fell *chena*. One of the mothers of the colony left her little child under shelter while she went to work. Coming back she found the child apparently killed by an attack of red ants. The interpreter gave the translation to me at first as ‘red worms,’ but I found out afterwards he was wrong; the word means ‘red ants.’ Considerably shocked at the conduct of the mother the parent stock gave this colony the name of *Embula*, ‘red ant’ *Veddás*; and this tribe it is that has disappeared. *Nebudáni* is the tribe derived from a Singhalese prince. The word means ‘wise’ or ‘witty.’ The Singhalese prince referred to, on the occasion of his army arriving at a very dry region, had to go without any water to drink or cook rice. Two *Veddá* women thereupon set themselves to think how they could supply the king with water. Taking off their clothes, they laid them on a rock, and a heavy dew falling saturated the clothes, so that they were able to give the king sufficient water to drink and cook rice in the morning before proceeding. In recognition of their cleverness the king termed them *Nebudáni*, or ‘wise’; hence the name of the clan. This tradition appears to have some foundation in fact, and is not merely fanciful; but on my second trip I hope to bring back such information as will place it beyond all doubt.

“In the next room are seven representative skulls, one of each of the first seven clans. They vary considerably in many respects, but are fairly representative. The *Embula* is missing. There is also a skeleton showing the average size of the *Veddá*. The account of my trip, which appeared in the *Ceylon Observer* of the 1st

instant, is accurate in all respects with the exception of the statement regarding the use of skins : these I have never seen used.*

"Before concluding, there is one point which I should be glad of the assistance of the Members of the Asiatic Society in unravelling. While taking up a Veddá skeleton I came upon a very ancient Sighalese skull—indeed, so much so that the jungle roots were simply holding it together, and it fell to pieces in my hand. Driven into this skull were three iron nails, a piece of a carpenter's bit, and a brass nail. Now there is a *hūniyam* charm which doubtless many will recollect, of five nails being driven into a wax image. The skull was found so far away from the Sighalese villages that no inquiries I could make could elicit any information upon the point. I shall be glad if those who have any knowledge of Indian charms could throw some light upon the subject.

"I fear I have taken up, in the few disjointed remarks I have made, more time than I should have done ; but my only regret is that I have not been able to give you more information. I thank you most heartily for the attention with which you have listened to me, and I trust that the fuller information to which I referred will be obtained as soon as possible, in view of the rapid extinction of the Veddás. I may remark that I have made a proposition to Mr. Bell as to obtaining that information which may lead to some solid result, and be of assistance in bringing it about. I have, in other words, offered, if it can be arranged, to go and settle for one or two years among the Veddás, and transmit the information gained from time to time to this Society for revision and dissection. There exists in the Bintēnnadistricts sufficient material for four or five Papers in the possession of an intelligent Sighalese gentleman who has made the subject a special study. Some four or five hundred words I know exist, because I have been carefully taking notes of some ; and an educated Sighalese has on many occasions been among the Veddás and picked out all the words which were neither Sighalese nor Tamil. That information should be forthcoming, and a great deal more too, if only any one chooses to go and collect it. My own duties at present compel me to leave for India, but I hope, on my return, to spend six months more among the Veddás, and by that time I have no doubt some really more authentic information than what I have at present obtained will be at the service of the Asiatic Society,—to which Society I have to tender my best thanks for the assistance which they have given me in obtaining such information as I now possess. I regret it cannot all be laid at once before you, especially the scientific part, because so much

* "In one encampment of the 'Rock' Veddás ten men were found in absolute nudity, whilst the women of the party apparently wore a small portion of the skin of some animal."

has to be verified. So much rubbish has been written about the Vēddās that I cannot but emphatically decline to have my name mixed up with any information unless it has the approval of those who are well qualified to decide upon such matters, in Ceylon. I have to thank you again most heartily for the patience with which you have listened to me." [*Mr. Stevens then resumed his seat amid hearty applause, after speaking nearly one and a half hours with scarcely any notes to aid him.*]

6.—On Mr. Stevens concluding, Mr. A. M. Ferguson proposed a very cordial vote of thanks from the Meeting, remarking that he had probably been chosen for the task from some supposed affinity to the Vēddā as "the oldest inhabitant" (*laughter*). He alluded to several notable points in Mr. Stevens' most interesting and instructive address, more particularly to the "perpetual motion" of the Vēddās, in striking contrast to the characteristic indolence of other Oriental races, and also to their absolute truthfulness, a virtue qualifying them to send a Missionary to other classes in Ceylon. Dr. Kynsey seconded.

7.—The Bishop proposed Mr. Stevens' election as an Honorary Member of the Society.—*Carried by acclamation.*

8.—His Excellency the Governor: "There is one question which I wish to ask Mr. Stevens. Speaking of the process of making fire by the fire sticks. Are the two sticks of the same or different wood?"

Mr. Stevens: "The same wood, one piece being cut off from the other."

His Excellency the Governor: "I have seen a good deal of fire-making, but there were always two kinds of wood used."

Mr. Stevens showed from the pieces that, in the case of the Vēddās, the sticks were pieces of the same wood.

His Excellency the Governor: "There is one other question I wish to ask, with regard to the arrow. You said they are taken to the smith to be made. Does the Vēddā take the iron or does the smith supply the iron?"

Mr. Stevens: "The smith supplies the iron: in one case, however, a piece of iron was obtained by the Vēddā from some of the Singhalese in the village, and then hammered into a blade."

9.—Mr. T. Berwick: "There is a further point, which perhaps Your Excellency will allow me to elicit. Mr. Stevens said the Vēddās had eight or nine gods. I should like to know whether their idea—such as it is—of the unseen world has any reference to belief in gods or merely to the spirits of their departed ancestors?"

Mr. Stevens: "A distinction is certainly drawn by the Vēddās between the gods and the *manes*. The god is a being of power: the departed spirits are simply present to watch over them, and can neither do them good nor evil."

Mr. T. Berwick : " They have a belief in gods distinct from the spirits of their departed relatives ? "

Mr. Stevens : " Certainly : therefore I say it is not demouology, but rather '*Kapuism*.' "

GENERAL MEETING.

November 18, 1886, 9 p.m., at the Colombo Museum.

Present :

The Right Rev. the Lord Bishop of Colombo, President,
in the Chair.

Hon. P. D. Anthonisz, M.D.	J. Ferguson, Esq.
T. Berwick, Esq.	W. Ferguson, Esq.
Hon. H. Bois.	W. R. Kynsey, Esq.
F. H. M. Corbet, Esq.	W. P. Ranasinha, Esq.
W. H. G. Duncan, Esq.	H. Sumagala Terunnánsé.
A. M. Ferguson, Esq., C.M.G.	J. L. Vanderstraateu, Esq., M.D.

H. C. P. Bell, Esq., Honorary Secretary.

And several visitors, including some ladies.

Business.

1.—Read and confirmed Minutes of last Meeting.

2.—The following gentlemen were elected Members of the Society :—P. Brito, Esq., M. Cochran, Esq., F. Dornhorst, Esq., C. A. Murray, Esq., C.C.S.; and the Rev. S. Coles was re-admitted a Member.

3.—Dr. Vanderstraaten then read his Paper : " A Brief Sketch of the Medical History of Ceylon."

4.—Mr. A. M. Ferguson thought some one else should have been asked to move the vote of thanks, though he would yield to none in his sense of obligation to the lecturer. He referred to the vast benefits conferred by medical science under the British Government—so great, through improved sanitation and continous peace, that in some parts like Bengal, scientists feared evil rather than good results owing to over-population, the checks of periodical famine and devastating wars having been removed from a people who would not migrate to take up waste land. So it was at Jaffna in Ceylon: he was there in 1845, when a cholera epidemic swept away large numbers, simply because the people outraged every law of sanitation. The improvement was great in the health of their soldiers now occupying palatial barracks after the squat huts he could remember : the mortality was then equal to 50 per 1,000 ; it was now probably less than half.

The Hon. H. Bois seconded the vote of thanks, which was very heartily accorded.

5.—The usual vote to the chair was given on the motion of the Hon. Dr. Anthonisz.

6.—It was announced that there would be no more General Meetings this year, but that the Annual Meeting would be held in December as usual.

COMMITTEE MEETING.

December 14, 1886.

Present :

The Right Rev. the Lord Bishop of Colombo, President,
in the Chair.

W. R. Kynsey, Esq., Vice-President.

Hon. Lt.-Col. F. C. H. Clarke,	J. B. Cull, Esq., M.A.
R.A., C.M.G.	S. Green, Esq.

W. H. G. Duncan, Esq., Honorary Treasurer.

H. C. P. Bell, Esq., Honorary Secretary.

Business.

1.—Read and confirmed Minutes of last Meeting.

2.—Considered certain proposed amendments in the Rules and Regulations, clauses 4 and 5.—*Carried.*

3.—Nominated the following gentlemen as Office-bearers for 1887 :—

President.—The Right Rev. the Lord Bishop of Colombo, D.D.

Vice-Presidents.—W. R. Kynsey, Esq., P.C.M.O., and
T. Berwick, Esq.

Honorary Treasurer.—W. H. G. Duncan, Esq.

Honorary Secretaries.—H. C. P. Bell, Esq., C.C.S., and
W. E. Davidson, Esq., C.C.S.

Committee.

The Hon. H. Bois.	W. Ferguson, Esq., F.L.S.
The Hon. Lieut.-Col. F. C. H. Clarke, R.A., C.M.G.	P. Freüdenberg, Esq.
Rev. S. Coles.	S. Green, Esq.
J. B. Cull, Esq., M.A.	The Hon. P. Ráma-Náthan.
A. M. Ferguson, Esq., C.M.G.	W. P. Ranasinha, Esq.
	H. Trimen, Esq., M.B., F.L.S.
J. L. Vanderstraaten, Esq., M.D.	

4.—The Hon. Treasurer submitted the Annual Balance Sheet of the Society, showing Rs. 541-96 to its credit.

5.—The Hon. Secretary submitted the draft Annual Report.—*Approved.*

6.—*Resolved*,—To hold the Annual General Meeting on the 16th instant, at the Museum, and to invite His Excellency the Governor to preside.

ANNUAL MEETING.

December 16, 1886, at the Colombo Museum.

Present :

His Excellency the Governor, in the Chair.

The Right Rev. the Lord Bishop of Colombo, President.

W. R. Kynsey Esq., Vice-President.

J. Alexander, Esq.

Hon. P. D. Anthonisz, M.D.

Hon. H. Bois.

Hon. H. H. Cameron.

M. Cochran, Esq.

J. Ferguson, Esq.

W. Ferguson, Esq.

P. D. Khan, Esq.

W. P. Ranasingha, Esq.

A. H. Thomas, Esq.

H. Sumangala Terunnánsé.

Hon. G. S. Williams.

W. H. G. Duncan, Esq., Honorary Treasurer.

H. C. P. Bell, Esq., Honorary Secretary.

Some visitors, including two Buddhist priests.

Business.

1.—Read and confirmed Minutes of last General Meeting.

2.—*Excavations at Anurádhapura.*

His Excellency said, that before proceeding to the business of the evening for which they were summoned together, he wished to put upon the table for the inspection of Members some plans of the recent excavations at Anurádhapura. He also wished to refer to two coins of some interest. Those of them who had read Mr. Burrows' interesting Report upon the archæology of Anurádhapura would remember that he found in one of the ruins a copper coin of the Emperor Antonius. The coin was of interest as showing what communication there was between Constantinople and Ceylon in those days. At Galle a very beautiful gold coin of the Emperor Theodosius had also been found some time ago. It had been for a considerable time in the possession of the Mahá Mudaliyár, who had kindly lent it. It was a very beautiful specimen. The inscription on the obverse was plain, but the reverse could not be made out.

3.—*Alteration of Rules.*

(i) The Bishop of Colombo: "There are certain small changes which the Committee propose in the Rules and Regulations, of which I will briefly explain the purport. In clause 3, at the end of section *a*, it is proposed to omit the words 'or more' after 'four,' and add at the end 'Rs. 62 after seven years' subscription, Rs. 50 after ten years' subscription.' This rule has reference to Life Membership. The object of the amendment is to make it possible for those who have subscribed for a large number of years to a certain extent to commute and become Life Members on payment of a sum proportionate to that which they have yet to contribute to put themselves on a footing with those who qualified by paying originally Rs. 105. It is proposed therefore that it should be possible, after seven years, to pay Rs. 62 and become a Life Member, and after ten years or more to become a Life Member on payment of Rs. 50."—The amendment was agreed to *nem con.*

(ii) The Bishop of Colombo: "The Committee propose also an amendment in clause 4, which regulates the Office-bearers of the Society. It is proposed to add certain words which will cause all who have held the office of President to be *ex-officio* Vice-Presidents so long as they are Members of the Society. That is a rule which obtains in the greater number of societies like ours elsewhere, and has the obvious advantage that it retains upon the managing body of the Society those who have necessarily acquired experience of its affairs, and who may be fairly reckoned upon as having a real interest in it. That general principle would have induced the Committee I think to propose the amendment; but we had in view also its application to a particular case which will commend it, I am sure, all the more to the Members of the Society. We have only one ex-President actually amongst us, Mr. Ravenscroft, and I am certain it will be the wish of all that we should have the benefit of his assistance and counsel. It is therefore proposed to insert after the words 'appointed by open vote at the Annual Meeting of the Society' the words 'besides all ex-Presidents, who shall be *ex-officio* Vice-Presidents so long as they are Members of the Society.'—Amendment agreed to.

(iii) The Bishop of Colombo: "The Committee further propose in clause 5 to substitute the word 'twelve' for the word 'nine.' Since that clause was framed I believe the number of the Members of the Society has doubled. It seems, therefore, not unreasonable that the number of the Committee should be increased. There is a very largely increased number of Members whose interest and service may be counted upon. The Secretary informs us that there has often been great difficulty in obtaining a quorum: but if the number of those votes on the Committee were greater it would be more certainly obtained.

But though we propose to increase the Members of the Committee we do not propose to increase the number required for a quorum."—Amendment agreed to.

4.—The Hon. Secretary laid on the table the list of books received since last Meeting.

5.—The President then called upon the Hon. Secretary to read the Annual Report of the Committee for 1886.

ANNUAL REPORT.

"The past year may be characterised as normal. If there has been no falling-off either in numerical strength or in the quality of the work done by the Society, on the other hand there has been no marked advance. This condition of things can fairly be assigned to two causes: first, 1885 was an exceptionally active year, and a certain reaction has resulted; secondly, the Society has this year suffered by unusually frequent changes in the two officers upon whom devolves the greater part of its routine work: three Secretaries and Treasurers have held office during 1886. Under such circumstances your Committee is confident that it will not be expected that the Society should have made any great progress.

"*Members.*—The list of Members up to the close of 1885 gives the total number at 137. Since then 11 Members have severed their connection with the Society upon leaving the Island or through persistent default of subscription, chiefly the latter. In this connection it may be parenthetically noted as hardly creditable to a Society of our standing that so large a proportion of its Members (nearly one-fourth) should allow their small annual subscription to run into arrears in spite of repeated reminding. Your Committee trusts that it has only to earnestly commend this shortcoming to the notice of Members to bring about more regularity in this respect. Against the above loss of 11 Members is, however, to be set an increase of 23 (including those gentlemen just elected this evening), raising the full strength of the Society to 149, or more than double that of a few years back. The amendment of the rule relating to Life Membership, carried this evening, should induce more Members to compound their annual subscription by a single payment.

"*Meetings.*—During the year four General Meetings have been held. At those of February 16, August 26, and November 18, the following Papers were read:—(1) 'An Outline of our Studies in Ceylon,' by Drs. C. H. and P. Sarasin; (2) 'Wouter Schouten's Account of Ceylon in the Seventeenth Century,' by P. Freudenberg, Esq.; (3) 'A Brief Sketch of the Medical History of Ceylon,' by Dr. J. L. Vanderstraaten. In addition, the Society had the benefit of listening, on November 3, to a very interesting address delivered by Mr. C. S. V. Stevens, of the

Queensland Civil Service, detailing his experiences amongst the Veddás. The change inaugurated in 1884 of convening these Meetings in the evening at the Museum has continued to prove successful in drawing together a larger attendance of Members. Whether it may not be advantageous to hold one or two *conversazioni* every year under the Society's auspices is a question worthy of consideration.

“Journal.”—No less than five Numbers of the Society's Journal were issued in 1885, but the Government Printer, though ever willing to aid, has not found it possible to spare compositors and type so readily this year. What has been printed amounts to about four Numbers, i.e., Proceedings, 1884; Proceedings, 1885; Journal No. 29, 1884 (too long delayed), completing Volume VIII.; and portion of No. 4, 1848-49, reprint. It was suggested in last year's Report that the Bengal Asiatic Society should be applied to for permission to reprint as part of our Transactions the valuable articles contributed to that Society's Journal by the late George Turnour. But until several Numbers of our own Journal (which have been out of print for years) are reprinted, it would be undesirable to seriously consider the proposal. Experience has proved that the Government Printing Office is too heavily weighted to undertake, in addition to our current demands on it, the reprinting of back Journals, with any prospect of completing them within a reasonable time. Since 1880 the only reprints issued have been No. 6, 1853, and No. 9, 1856-58, and of these the last was turned out by a local press. As there are at least half a dozen Numbers still to be reprinted, it would seem advisable to arrange, without further delay, with one or two outside presses to contract for their early issue.

“Library.”—Although our funds have not admitted of a large investment in new works this year, by exchanges and presentations the Society has acquired a substantial addition to its Library. The last catalogue was issued in 1882, and subsequently a Sub-Committee was appointed to thoroughly overhaul the Society's Library and draw up a Report for its general improvement. The great defect hitherto has been the want of a regular system of checking the issue and return of books. It is hoped that the coming year will see this defect finally remedied. Your Committee has consented to hand over, under proper safeguards, the entire Library to the Museum authorities, for the purpose of being amalgamated into one joint catalogue. The Society will retain an exclusive right to its own books, which will be clearly distinguished in the Museum catalogue by an asterisk. The catalogue is to be commenced at once, and Members will be requested by circular to return temporarily every book now in their hands, very many of which have been lost sight of for years, and are not to be found in the catalogue of 1882. The sum of Rs. 69.50 was

spent in book-binding in the course of the year, but a great deal more has yet to be done to ensure the Society against the frequent expense of replacing unbound Volumes and Numbers of periodicals, now lying loose upon the shelves.

Archæology.—Some interesting discoveries of ruins have been reported during the year by the Government Agent, Anurádhapura, and the Assistant Government Agents of Hambantota, Vavuniya-Viláṅkuḷam, Mañṇár, and Mátalé, and it is proposed, under Government sanction, to print so much of these Reports as appears desirable, with other Papers of a similar character forwarded to the Society, as a separate Number of the Journal. Special attention has been drawn by Mr. W. J. S. Boake to the ruins of the ancient city of Tirukésvaram (Mántota); and in forwarding a box of antiquarian relics, Mr. Boake asked for a small grant to enable him to carry out some excavations at the site. The project seemed to your Committee sufficiently promising to justify it in voting a sum of Rs. 50 for the purpose, on the understanding that Mr. Boake would personally supervise the work. The balance remaining on the Excavation Fund raised by special subscriptions in 1884 amounts to Rs. 440·05, besides a small balance of Rs. 40 remaining in Mr. Levers' hands from the advance of Rs. 200 issued to the Government Agent, Anurádhapura, at different times. As the work at the Mirisweti Dágoba (for which the fund was originally subscribed) is completed the Committee is of opinion that the fund may be usefully transferred to the general funds of the Society, to be applied to such other excavation schemes as may commend themselves to the Committee at its discretion. To this proposal the consent of the Special Committee appointed to deal with this fund (of which His Excellency the Governor is Chairman) has been solicited.

Translation of the 'Maháwaṇso,' and the Vocabularies Committee.—Brief reference may be made to two other subjects in which the Society is interested. First, the continuation of the English translation of 'Maháwaṇso' from the point reached by Turnour. L. C. Wijasipha, Mudaliyár, has now been nearly eighteen months engaged on the work, the completion of which Oriental scholars everywhere are eagerly awaiting. A long and interesting Report of Mr. Wijasipha's progress up to June 30 was transmitted to us by the Government, was published in the *Ceylon Observer* of August 18, and will appear also in our Proceedings for the year. It is highly satisfactory to feel assured that, before our next Annual Meeting, this great work ought to be in the printer's hands. This portion once out, the revision of the first 37 chapters will, it is hoped, be sanctioned and entrusted to the same able scholar.

"Acting on a suggestion thrown out by Mr. Bruce, in his Presidential Address of 1881 to supply 'perhaps the greatest

literary need felt in Ceylon, the want of a good Sinhalese and English dictionary,' a Select Committee was formed in 1884 to take such steps as it deemed advisable towards this end. This Committee has met once or twice, but has as yet not advanced beyond preliminaries. A small 'Specimen Vocabulary' in the shape the work might ultimately best assume has been prepared, and is shortly to be circulated among the Select Committee, the Members of which will be invited to select each some one Sinhalese word, prose or poetical, with the object of making during 1887 as complete a glossary as possible on the lines of the 'Specimen Vocabulary.' These are small beginnings, and years must elapse before any real results ensue; but, if steadily pursued, they cannot but aid the future dictionary-maker, a Sinhalese 'Murray' perhaps yet unborn.

"*Finances.*—The balance sheet of the Society herewith submitted shows that its financial position continues sound. It has been found undesirable to follow out a proposal made in last year's report to fund the subscriptions of Life Members separately, and the amount has accordingly in the present statement been incorporated with the other receipts. The balance to date on this general account is Rs. 541.96. The items differ but little from those of past years, though it should be remarked that the Society has undoubtedly profited by handing over the agency for the sale of its Transactions to a local firm, Messrs. A. M. and J. Ferguson. A sum of Rs. 126 appears credited under this head. The Excavation Fund has been dealt with already.

"In conclusion, your Committee congratulates the Society on its present healthy condition. For 1887 the outlook is certainly encouraging. Papers have been promised, yielding in no way in value and interest to the many read before the Society from time to time; and it rests with Members themselves whether the Society is to continue to develop the sphere of useful work in the several branches of knowledge which it is its design to investigate and record."

6. The Report having been duly adopted, Mr. J. Ferguson rose and said:—"Your Excellency, I have been asked to propose the election of the Office-bearers of the Society for the coming year, as nominated by the retiring Committee. The list which I have the honour to move is as follows:—*President*, the Right Reverend the Lord Bishop of Colombo; *Vice-Presidents*, W. R. Kynsey, Esq., and T. Berwick, Esq.; *Honorary Treasurer*, W. H. G. Duncan, Esq.; *Honorary Secretaries*, Messrs. H. C. P. Bell and W. E. Davidson, c.c.s.; *Committee*, Hon. H. Bois, Hon. Lieut.-Col. F. C. H. Clarke, R.A., C.M.G., Rev. S. Coles, and Messrs. J. B. Cull, M.A., A. M. Ferguson, C.M.G., W. Ferguson, F.L.S., P. Freidenberg, S. Green, Hon. P. Ramá-Nathan, W. P. Rauasipha, H. Trimen, M.B., F.L.S., and J. L. Vanderstraeten, M.D.

I think, Sir, it will generally be admitted that the usefulness and prosperity of a Society such as our own in a colony like Ceylon, depend in a very great degree on the Committee, and especially on the executive officers, and I think I may congratulate the Members on this occasion on the exceptionally strong and representative character of the Committee proposed. Nearly all classes and races seem to be represented, and each Member, if I judge correctly, should be able to bring to the board peculiar and useful experience and knowledge differing from that possessed by his neighbours. I would particularly refer to the advent of one so well known as Mr. Duncan as Treasurer in the room of a gentleman who for many years faithfully served the Society, until he left the Island, and also to the nomination of our former Secretary Mr. Davidson as joint Secretary with Mr. Bell. Under this happy conjunction, Your Excellency, I think we may fairly look forward to a double degree of usefulness for the Ceylon Asiatic Society in 1887. I have much pleasure in moving the list as read."

The Hon. P. D. Anthonisz seconded.—*Carried.*

6.—The President then rose and delivered a short address, summarising the work done by the Society during the year :—

PRESIDENT'S ADDRESS.

The Bishop of Colombo: "Your Excellency, Ladies, and Gentlemen.—If there are no other reasons for my rising, it will certainly be my duty, in my own name at least, whether or not I may take upon myself to speak for the other Office-bearers of the Society, to thank you for the honour which you do me in re-electing me to the office of President. I am very conscious that, during the past year, I have done very little for the Society. I suppose that I have fallen even more short of fulfilling the expectations of those who elected me than I have in fulfilling my own hopes; and I can hardly promise that I shall be more successful in the year which is coming than I have been in that which has passed. I can only promise that I shall do my best, and that the recollection that one of the two years for which I have held office has not seen much fruit from my exertions will stimulate me to try and make the most of the one that remains.

"Not that the year during which I have had the honour of presiding over the Society has been altogether a barren one. I think we may say very much the contrary. It has seen a large increase in the Members of the Society, and an increase in the interest which is taken in it both within and without. We cannot expect in every year to have Papers read of such marked importance as some of those which were given us in the year before—Dr. Trimen's Paper upon the Botany of Ceylon, or such reports as Mr. Parker's upon *Tisamahārāma*. But we have not been without very much during the past year of interest, and we have

touched upon and received some information in most branches which the Society aims at cultivating.

“In the field of Science we had from the brothers Messrs. Sarasin a very interesting and learned account of their work in Ceylon; and many of us will no doubt look forward with interest to the publication of the results. They gave us in so many instances only a description of the processes, and had not yet been able to tabulate and estimate the results obtained. In the same field we are making a little effort now, which, perhaps, it would be well to commend to the attention of the Members of the Society. The Committee has attempted to obtain information upon one definite and simple point. Upon the motion of Mr. R. L. M. Brown, a circular has been issued asking for information with regard to those flights of butterflies which so curiously are to be observed in different periods of the year. I venture to think that this is an instance of the way in which, without any high pretensions, Members of a Society like this by their own united action may contribute to the obtainment of really valuable knowledge; and I hope that those who happen to have it within their power to notice any of these phenomena will not think their observations unworthy of being contributed to the common store.

“In the field of history, we had the interesting account of Ceylon of Wouter Schouten translated for us by Mr. Freidenberg. It has left a good deal that should be further inquired into, and I hope that it may be printed some day, accompanied with notes showing what are the places to which Schouten referred,—mere names not known to us at present,—and elucidating some other points which were just touched upon in the evening when the Paper was read. In this field too one of our most assiduous Members has been at work, though not exactly within the region of the Society itself. Our Secretary Mr. H. C. P. Bell, in conjunction with Mr. A. Gray, has nearly seen through the press for the Hakluyt Society Volume I. of their joint work, the translation of François Pyrard's Voyage to the Máldives and other parts of the East Indies,—a work which is of very considerable interest, and which I believe Mr. Bell is qualified to further illustrate by notes and researches of his own, which I hope he will ere long have time to give us the benefit of. We know that he has already done for us considerable work in that field, and he has by him still materials which only need time and leisure to be brought into order and applied in elucidation and illustration of such a work as that which, under the auspices of the Hakluyt Society, he is at present aiding in editing.

“In the field of Antiquarian Research we have not had any Paper read to us, but we have had many contributions, and none perhaps more replete with interesting information than those which Your Excellency has been kind enough to lay

upon the table this evening. The Diaries also of the officers in different parts of the country which Your Excellency has been kind enough to place at the disposal of the Society contain a great many interesting facts. We cannot expect that that should always be so within the limits of the Society, but it is kindred work which we are very glad to be privileged to record and count ourselves to have a share in. Mr. W. J. S. Boake is undertaking, as you have heard, a report on a work which may possibly lead to interesting discoveries at quite a new site (Tirukésvaram). The quantity of objects of interest which he has discovered is really remarkable, considering that he has at present only looked upon the surface. At the same time I suppose there is considerable wisdom in the warning of Mr. L. Wijasingha, Mudaliyár, in his Report upon the ‘Mahāvamsa,’ that the accounts which are given there of the elaborate thoroughness with which the Tamil possessors of the Island ransacked all the treasures of its ancient sites and ruins leave very little hope that much of any great value—at any rate of any great intrinsic value—will be discovered in ruins not yet opened.

“Nothing I think contributed more to spread the popular interest in the work of the Society than that pleasant evening which we spent in listening to Mr. C. S. V. Stevens’ account of his visit to the Veddás. It was astonishing, if only as a record of individual enterprise. The courage and resource which Mr. Stevens had himself displayed, the way in which he had gone unprotected either by arms or even by clothing, or by knowledge of the people, to bring himself into the closest possible contact with their modes of life, and the still more astonishing readiness which he displayed to go back and live there for a period of something like two years—these are (to my mind at least) revelations of a degree of enthusiasm and energy which were very startling. Mr. Stevens would not like us to consider that he had brought his researches to an end, or that his results were final; but at any rate we may note this much,—and I for my own part note it with very great satisfaction,—that he disposes, I think, finally of the notion that the Veddás cannot laugh; and I mention that, not as a matter of so much importance in itself, but as typical of the exaggerated notion which has prevailed about the Veddás and their savage character. He told us at the outset that they were very far from being the degraded semi-animal creatures which they were represented to be. We know how often an article in the *Daily Telegraph* will sum up mankind, through all his various races, from the writer himself down to the Veddá. I hope that it will be impossible any longer, whatever may be thought of the writer on the *Daily Telegraph*, to put the Veddá at the bottom, and that persons must look elsewhere than Ceylon to connect the missing link between ourselves and the lower forms of animal beings. This is an explosion

of an error which has been founded, like so many other errors, upon the exaggerated credence given to the reports of individuals and irresponsible observers. The tendency is, I think, always to place too little credence in records and monuments and too much in the statements of any one who rushes into print; and I confess I am very glad to see a systematic inquiry on foot which may have the tendency of letting in the light upon a region which has been darkened by what I may call these hasty and irresponsible statements.

“While I am speaking of the Veddás, I think it may be, perhaps, not impertinent if I note what does not seem to have struck the attention of so many of those who have discussed the subject—that, supposing the Veddás to be an independent and original race, they are among the very few who have preserved no name. Obviously, ‘Veddá’ is not a name; it is the description of their occupation; and not here only and in this language only, but in the languages of many parts of India, it is a generic term, descriptive sometimes of the huntsman and sometimes of the wild tribe, but in neither cases does it do duty as the name of any particular race or family of men. When Mr. Stevens began to tell us what names they have,—the clan names, for instance,—those were so far from being special or peculiar that they appear to have close affinity to the languages of the principal races of the Island. I cannot help remarking at the same time that, while I admit the wisdom and the necessity of prosecuting those cranio-logical inquiries upon which the Papers which we have listened to here, with considerable interest, have been founded, we may hope that, Mr. Stevens, by his large opportunities has carried them as far as they can be carried at present. We have had the skulls of our neighbours in this very building, and I hope the time has been reached when we shall not only feel that we may safely recognise in our Veddá neighbours our brother-men, but that we shall also feel that no race is merely a subject for scientific inspection, but is to be treated with the respect which one man owes to another, and in particular that there shall never be forgotten the reverence which man owes to his brother-man.

“In Dr. Vanderstraaten’s interesting account of the progress of Medical Science and Medical Instruction in the Colony, the Society diverged into a more general field where science strictly so called mingles with social and economic science. We were all, I think, very much interested in listening to the Paper, and I am in hopes that we shall not be too strict in drawing the line of the limits of our subjects: that subject must be very alien to our objects indeed before we refuse to listen to it. I think if we are ready to open our doors, and come and listen to any one who is ready to give us information on matters that really concern the life and history and interest of the people, we shall do wisely to do it.

"I would go further and add my word of persuasion to the suggestion which has been made in the Report which the Secretary has read, that *conversazioni* of a more informal character, and where subjects of whatever kind may be discussed among ourselves in a more or less informal way, should be held under the auspices of the Society.

"One branch, and that I must say a not unimportant one, of the subjects with which the Society generally deals, has had either no, or very little, place in our transactions this year. I mean the whole branch of Literature and Philology. It may partly account for my own feeling of having done very little for the Society ; as that is the only branch in which I should have hoped to have done anything for it. At the same time, I think, I shall, perhaps, be right in informing the Members that we have not been altogether idle, and that besides myself having laid upon the table certain translations from Páli at an earlier Meeting, several of the Members of the Society have been upon a concerted plan at work upon a similar translation. That takes time and those people who thought they would get through a certain amount of work at the end of twelve months, find themselves at the end of the year only at the beginning ; but there are several who have begun, and I hope we are not altogether forgetting at any rate that purpose.

"The same kind of description will apply to what has been done in respect of that Singhalese Dictionary work, to which we are inclined rather to give the title of ' Singhalese Glossary Committee.' I will just explain very briefly what are the objects we have in view. We are not attempting to produce a Dictionary, and therefore, perhaps, it is better not to mislead any one by the title of the Singhalese Dictionary Committee ; but we do hope to set on foot what will be a permanent institution in connection with the Society, the collection of material on which hereafter a Dictionary might be founded ; that we should make it possible for any student in Ceylon with the aid of the Society to undertake such a work. I confess I regard it as one of the great advantages which a Society like ours confers, that it enables people to make use of small capacities and limited means of time and special knowledge by putting together what they are able to do. I hope that we shall make such a glossary that even a beginner studying for his own instruction should be able to contribute his mite towards the material which will be constantly accumulating in the hands of the Society until some one arises with genius and knowledge enough to take up the work. There are two kinds of work : that work of higher type which requires great knowledge and ability, where one man projects and another man carries through some large work ; and the other which depends upon the co-operation of many whose individual skill need not be great. We may compare them to two kinds of buildings.

There is such a structure as this great Museum or as that beautiful Cathedral which has risen at Kotahena, the finest work of architecture which Ceylon has I suppose as yet produced : these require the planning mind of a capable architect and large resources. On the other hand, when we go up the railway to Kandy, we see a building, of entirely different character. We see a whole hillside manipulated by the hand of man and accommodated to his purposes and laid out in small and regular terraces, everywhere fenced, sluiced with the greatest accuracy and minuteness—a work which I suppose is the accumulation of the separate industry of a multitude of individuals in a multitude of ways, gradually extending the range of their work and gradually seeing more and more what rule might govern and how it might be legislated for as a complete whole, and yet producing a work which we cannot but regard as stupendous and which may well be compared with those larger works of splendid genius, but which, if no less vast, is no less serviceable and may perhaps be even more durable than any of them. I hope it may be the privilege of this Society in the field of literature and science and kindred inquiry at least to enable its members during the coming year to bear their part in this humbler and perhaps not less remunerative kind of work.” (*Applause.*)

At the conclusion of the Address,

7.—His Excellency the Governor said: “Your lordship was good enough to thank the Society for electing you again as President ; but I am sure I only express the feelings of the Society when I say far more thanks are due on our part to Your Lordship for your kindness in consenting to retain that post. I am quite sure there is no Member of the Society, either present or absent, who would not most willingly pardon, I will not say Your Lordship’s indifference, to the work of the Society during the present year, in consideration of the valuable contributions which at great cost of your own time and labour you have laid before the Society from time to time. Might I ask, in a mere conversational manner, what progress has been made with that work to which Your Lordship has been devoting so much time ?”

The Bishop of Colombo : “We hope to get fifty Játakas done during the year. Mr. Pánabokké has, I believe, done his ten, I have done about seven, and Mr. Templer has done about three or four ; I am not aware what one or two other gentlemen who gave indefinite promises have done.”

The Governor then invited the Members present to examine the two coins, and the plans of the buildings the foundations of which have been cleared by the excavations recently executed at Anurádhapura. These have been prepared by Mr. A. Murray, Public Works Department, and are very elaborate and interesting ; a few of them are to appear in Mr. Burrows’ Archæological Report.

CLXXVIII ROYAL ASIATIC SOCIETY (CEYLON BRANCH).

Dr. The Honorary Treasurer in account with the Royal Asiatic Society (Ceylon Branch). *Cr.*

1886.	Rs.	¢.	1886.	Rs.	¢.
To Balance on December 31	...	488	40	...	249
" Members' subscriptions	...	989	50	...	68
" Entrance fees	...	68	25	...	34
" Government grant to the Society	...	500	0	...	68
" Sale of Journals, &c.	...	126	0	Cost of lithographing plates for Journal	35
" Interest from Bank of Madras...	...	12	12	No. 29	51
				Advertising Meetings, &c.	59
				Binding	116
				Stationery	80
				Gas Company for gas	69
				Charges, on account of clerk's salary, &c....	55
				Balance	21
					7
					20
					1
					138
					92
					541
					96
Total ...	2,184	27		Total ...	2,184
					27

Excavation Account.

	Rs.	¢.
To balance on December 31, 1885	...	354
" dividend recovered from O.B.C.	...	59
		85
		46
	Rs.	440
		5

Colombo, December 14, 1886.

W. H. G. DUNCAN,
Honorary Treasurer.

OFFICE BEARERS, 1887.

Patron:

His Excellency the Honourable ARTHUR HAMILTON GORDON,
G.C.M.G., Governor.

Vice-Patron:

Sir CECIL C. SMITH, K.C.M.G., Lieutenant-Governor.

President:

The Right Rev. R. S. COPLESTON, D.D., Lord Bishop of Colombo.

Vice-Presidents:

W. R. KYNSEY, Esq., F.K.Q.C.P.; T. BERWICK, Esq.

Honorary Treasurer:

W. H. G. DUNCAN, Esq.

Honorary Secretaries:

H. C. P. BELL, Esq., C.C.S.; W. E. DAVIDSON, Esq., C.C.S.

Committee:

The Hon. H. BOIS.	W. FERGUSON, Esq., F.L.S.
The Hon. Lieut.-Col. F. C. H. CLARKE, R.A., C.M.G.	P. FREUDENBERG, Esq.
Rev. S. COLES.	S. GREEN, Esq.
J. B. CULL, Esq., M.A.	The Hon. P. RAMA-NATHAN.
A. M. FERGUSON, Esq., C.M.G.	W. P. RANASINGHA, Esq.
	H. TRIMEN, Esq., M.B., F.L.S.

J. L. VANDERSTRAATEN, Esq., M.D.

LIST OF MEMBERS.

(Corrected up to December 31, 1886.)

1.—LIFE MEMBERS.

Copleston, the Right Reverend R. S., D.D., Lord Bishop of Colombo.	Ferguson, A. M. (junior), M.R.A.S.
Cull, J. B., M.A.OXON.	Ferguson, D. W., M.R.A.S.
Davida, Professor T. W. Rhys., M.A.	Ferguson, J. Hon. Cor. Sec., R.C.I.
Davidson, W. E., C.C.S., F.R.C.I.	Freüdenberg, P. Consul for the German Empire.
Dickson, The Hon. J. F., M.A. OXON, C.M.G.	Grant, J. N.
Ferguson, A. M., C.M.G.	Gunn, J.
	Lewis, J. P., M.A., C.C.S.
	Nicholson, The Rev. J., M.A.

2.—HONORARY MEMBERS.

Gray, Albert., B.A.	Stevens, C. S. V., Queensland
Holdsworth, E.	Civil Service.
Künste, Professor M. M., PH.D.	Military Medical Officers in Ceylon.

3.—ORDINARY MEMBERS.

Alexander, James.	Bosanquet, The Hon. R. A., M.L.C.
Antonisz, The Hon. P. D., M.D.ST.AND., F.R.C.S.EDIN., M.L.C.	Brito, P. S., M.B.C.M.ABER., M.R.C.S. ENG.
Bailey, J. B. A., C.C.S.	Brown, R. L. M.
Barber, J. H., Proctor, M.R.A.S.	Burrows, S. M., M.A.OXON, C.C.S., M.R.A.S.
Bawa, B. W., Advocate.	Byrde, E. M. D., C.C.S.
Baumgartner, G. A., C.C.S.	Cameron, H. H., C.C.S.
Baumgartner, H. P., C.C.S.	Carbery, J., M.D.C.M.ABER.
Bell, H. C. P., C.C.S.	Christie, T. N., J.P.
Berwick, Thomas, Barrister-at- Law, D.J., Colombo.	Clark, A.
Blair, W.	Clarke, Lieut.-Colonel, The Hon. F. C. H., B.A., C.M.G., F.R.G.S., F.R.C.I.
Boake, W.J.S., L.B.C.S.I., L.F.P.S.G., C.C.S.	Cochran, M., M.A.F.C.S.
Bois, H., F.R.C.I.	Goles, The Rev. S., M.A.C.M.S.
Bois, F. W., F.R.C.I.	

Conolly, P. W., C.C.S.
 Coomára-Swámy, P. Proctor,
 M.M.C.
 Corbet, F. H. M.
 Crawford, M. S., B.A., C.C.S.
 Daendliker, P., Consul for the
 Netherlands
 De Alwis, The Hon. A. L., Proc-
 tor, M.L.C.
 Dean, J. G.
 De Saram, F. J., Proctor, J.P.
 De Saram, J. H., C.C.S., F.R.C.I.
 De Saram, Peter, Mudaliyár
 De Soysa, C. H., J. P.
 De Vos, F. H., Barrister-at-Law.
 Dias, Wijayawardana Bandáraná-
 yaka, C. P., Mahá Mudaliyár.
 Dias, Wijayawardana Bandáraná-
 yaka, Wm., M.D.ST.AND., M.R.C.S.
 ENG., L.S.A.LOND.
 Dornhorst, F., Advocate, M.C.L.E.
 Duncan, W. H. G.
 Dunlop, C. E., C.C.S., F.R.C.I.
 Elliott, E., C.C.S.
 Ferguson, W., F.L.S.
 Fisher, W. W., Barrister-at-Law,
 Crown Counsel.
 Fowler, G. M., C.C.S.
 Garvin, T. F., M.B., C.M.ABER.
 Green, A. F.
 Green, H. W., C.C.S.
 Green, Staniforth.
 Grenier, The Hon. J. C. S.,
 Attorney-General, F.R.C.I.
 Grinlinton, J. J., A.INST., C.E.,
 F.R.G.S., F.R.C.I.
 Gunatilaka, W. Proctor.
 Gunaratna, E. R. Jayatilaka,
 Mudaliyár of the Gate, Hon.
 Secretary, P.T.S.
 Guzdar, D. J.
 Haines, W. G., C.C.S.
 Ievers, R. W., M.A., C.C.S.
 Jackson, W. H., C.C.S.
 Jayawardana, A., Mudaliyár.
 Karunaratna, F. C. Jayatilaka,
 Mudaliyár.
 Keith, W. G., M.B. & C.M.EDIN.,
 L.R.C.P. & S.EDIN.
 Khan, P. D.
 Kynsey, W. R., F.K.Q.C.P., L.R.C.S.I.
 Langdon, The Rev. S., M.A.
 Lawrie, A. C., Advocate, D.J.,
 Kandy.

Lee, L. F., C.C.S.
 Le Mesurier, C. J. R., C.C.S.,
 F.R.G.S., F.R.A.S., F.R.C.I.
 Lewis, F.
 Loos, F. C., Proctor, F.R.C.I.
 Loos, J., M.D.ST.AND., M.R.C.P.
 EDIN., L.R.C.S. ENG.
 Macdonald, J. D., M.D.GLAS.
 Mackwood, F. M.
 Mason, J. D., C.C.S.
 Moir, R. W. D., C.C.S.
 Morgan, J. T., M.R.C.S.ENG.
 M.B.C.M.ABER.
 Moysey, H. L., C.C.S.
 Murray, C. A., C.C.S.
 Nell, Louis, Advocate, Crown
 Counsel.
 Nevill, H. C.C.S., F.Z.S., Cor. Mem.
 A. N. Sc. Philad, M.B.O.U.
 Noyes, E. T., C.C.S.
 Pánabokké, T. B., Raṭémahat-
 mayá, P. M.
 Perera, E. F., Proctor.
 Perera, J. F., Mudaliyár.
 Perera, J. M., Proctor.
 Perera Wijayawickrama Senaratna,
 W. R. H., Mudaliyár.
 Pieries Wickramasipha Siriwar-
 dana, J. M. P., Mudaliyár of the
 Gate.
 Price, F. H., C.C.S.
 Pyemont Pyemont, L. O. B.A.
 OXON., C.C.S.
 Rájapaksa, N. de A. Wijayaguna-
 ratna, Mudaliyár of the Gate,
 J.P.
 Rájapaksa, W. N. de A. Wijaya-
 gunaratna, Proctor.
 Ráma-Náthan, The Hon. P.,
 Advocate, M.L.C., M.C.L.E.,
 F.R.C.I.
 Ranasipha, W. P., Proctor
 Ravenscroft, The Hon. W. H.,
 C.C.S.
 Renton, J. H.
 Rockwood, W. G., M.D.MADRAS,
 M.R.C.S.ENG., M.R.C.P.LOND.,
 F.R.C.I.
 Sanders, W. R. B., C.C.S.
 Santiago Chandrawarnam, A.,
 Mudaliyár.
 Saunders, The Hon. F. R., C.M.G.,
 C.C.S.
 Saxton, G. S., C.C.S.

- | | |
|---|---|
| <p>Seneviratna, A. de Alwis, Advocate, M.C.L.E., M.M.C.
 Seneviratna, K. L. Don Charles
 Shams-ud-din, M.
 Short, E. M. De Coucy, C.C.S.
 Skeen, G. J. A.
 Subhúti, Waskaduwa, Terunnánsé.
 Sumangala, Hikkaduwa Sri, Terunnánsé, High Priest of Adam's Peak
 Symons, C. E. H.
 Tarrant, H.
 Templer, G. W., C.C.S.
 Templer, P. A., C.C.S.
 Thomas, A. H.
 Thomson, A.
 Thwaites, J. Hawtrey, B.A.CANTAB., Barrister-at-Law, Registrar Supreme Court, F.R.C.I.
 Tilakaratna Disánayaika, D. A., Mudaliyár.</p> | <p>Tothill, T. F. H., M.D. PARIS, M.R.C.P. EDIN., L.S.A. LOND.
 Trimen, H., M.B. LOND., F.L.S.
 Twigg, T. McC., C.C.S.
 Vanderstraaten, J. L., M.D. ST. AND., M.R.C.P. LOND., L.S.A. LOND., L.R.C.S. & L.M. EDIN.
 Vanderspar, G. H.
 Vandort, W. G., M.D., C.M. ABER.
 Vigors, C. T. D., C.C.S.
 Wace, H., C.C.S., F.R.C.I.
 Wall, George, F.L.S., F.R.A.S.
 Wardrop, J. G.
 Webster, R.
 White, H., C.C.S.
 Williams, G. S., M.A.C.C.S.
 Wilmot, C. Eardley, C.C.S.
 Worthington, G. E., C.C.S.
 Wright, W. H.
 Wrightson, W.</p> |
|---|---|

APPENDIX.

JOURNALS AND PROCEEDINGS.

VOLUMES I. to IX.,

1845-1886.

VOLUME I.

No.	Year.	Pages.	
*1 ...	1845 ...	1-100 ...	With Proceedings. (i-viii)
†2 ...	1846-47 ...	1-176 (?)	With Appendix, Proceedings, February 26, 1847.
‡3 ...	1847-48 ...	1-214 ...	With Appendix, Proceedings, April 22, 1848.

VOLUME II.

Part I.

§4 ...	1848-49 ...	1-96 ...	With Appendix, Proceedings, March 31, 1849. (i-xxvi)
5 ...	1849-50 ...	1-218 ...	With Appendix, Proceedings, December 1, 1849, to August 13, 1850. (i-xxxiv)

Part II.

¶6	1853	{ 1-56	—
7 }		{ 57-96 ...	With Appendix, Proceedings, February 7, 1852, to April 4, 1853. (i-lxii)
8 ...	1855 ...	97-184 ...	With Appendix, Proceedings, April 30, 1853, to August 17, 1854. (lxiii-cxx)

VOLUME III.

¶9 }	1856-58	{ 1-180	—
10 }		{ 181-276...	With Appendix, Proceedings, Oc- tober 2, 1856, to January 21, 1858. (i-xx)

* Reprint (1849), pp. 1-120, with Proceedings, i-x.


† Reprint (1861), pp. 1-176.

§ Reprint (1870), pp. 1-222.

‡ Reprint (1887), pp. 1-126.

¶ Reprint (1882), pp. 1-68.

¶ Reprint (1883), pp. 1-161.

 THE following Numbers of the Journal of the Royal Asiatic Society, Ceylon Branch, are out of print :—

<i>No.</i>		<i>Year.</i>	<i>No.</i>		<i>Year.</i>
5	1849-50	16	1870-71
10	1856-58	21	1880
11	1858-59	22	1880
12	1860-61	23	1881

March, 1888.



- 11 ... 1858-59 ... 1-110... With Appendix, Proceedings, May 8, 1858, to September 12, 1859. (i-xxii)
 12 ... 1860-61 ... 1-82 ... With Appendix, Proceedings, December 17, 1859, to July 6, 1861. (i-xx)

VOLUME IV.

- 13 ... 1865-66 ... 1-184... With Proceedings, June 21, 1862, to July 6, 1866. (i-xii)
 14 } 1867-70 { 1-150 —
 15 } 151-196... With Proceedings, November 6, 1866, to March 12, 1870. (i-x1)

VOLUME V.

- 16 ... 1870-71 ... 1-168 —
 Proceedings, March 24, 1870, to January 16, 1871. (i-lx)
 17 ... 1871-72 ... 1-66 ... With Proceedings, June 15, 1871, to November 7, 1872. (i-xxxiv)
 18 ... 1873 ... 1-79 —
 19 ... 1874 ... 1-94 —
 Proceedings, January 29, 1873, to November 2, 1874. (1-24)

VOLUME VI.

- 20 ... 1879 ... 1-60 —
 21 } 1880 { 1-90 —
 22 } 1-48 —
 Proceedings, February 1, 1875, to December 16, 1880. (i-xxxii)

VOLUME VII.

- 23 } 1881 { 1-56 —
 24 } 57-162 —
 Proceedings, February 2, 1881, to December 16, 1881. (i-lx)
 25 } 1882 { 163-254 —
 Extra } 1-60 —
 Proceedings, January 25, 1882, to December 22, 1882. (lxi-xcvi)

VOLUME VIII.

26 1883 1-94 —

Proceedings, January 25, 1883, to December 20, 1883. (i—xxviii)

27	}	1884	{	95-192	—
28				193-296	—
29				297-483	—

Proceedings, February 1, 1884, to December 22, 1884.
(xxix—lxxx)

VOLUME IX.

30	}	1885	{	1-138	—
31				139-266	—

Proceedings, January 29, 1885, to December 21, 1885. (i—cx)

32	}	1886	{	267-348	—
33				349-	—

Proceedings, February 13, 1886, to December 16, 1886.
(cxi—cxvii)

C O N T E N T S.

VOLUME I.

No. 1.—1845.

Proceedings.—Opening Address of the Hon. Justice Stark.—Buddhism: No. 1. By the Rev. D. J. Gogerly.—General Observations on the Translated Ceylonese Literature. By W. Knighton.—The Elements of the Voice in reference to the Roman and Singhalese Alphabets. By the Rev. J. C. Macvicar.—The Ravages of the *Kuruminiyá*, or Cocoanut Beetle. By J. Capper.—The State of Crime in Ceylon. By the Hon. Justice Stark.—Account of some Ancient Coins. By S. Casie Chitty.—Remarks on the Collection of Statistical Information in Ceylon. By J. Capper.—Buddhism: No. 2. By the Rev. D. J. Gogerly.

No. 2.—1846.

Address of the Hon. Justice Stark.—Buddhism. By the Rev. D. J. Gogerly.—The Sixth Chapter of the *Tiruvátavúr Puránam*, translated, with Notes. By S. Casie Chitty.—The Discourse on

the Minor Results² of Conduct, or the Discourse addressed to Subha. By the Rev. D. J. Gogerly.—The State of Crime in Ceylon : No. 2. By the Hon. Justice Stark.—The Language and Literature of the Singhalese. By the Rev. R. Spence Hardy.—Education Establishments of the Dutch in Ceylon. By the Rev. J. D. Palm.—Account of the Dutch Church in Ceylon. By the Rev. J. D. Palm.—Notes on some Experiments in Electro-Agriculture. By J. Capper.—*Singálowáda*. Translated by the Rev. D. J. Gogerly.—Colouring Matter discovered in the Husk of the Cocoonut. By Dr. R. Gyax.—Proceedings of Second Anniversary Meeting, February 26, 1847.

No. 3.—1847-48.

The Mineralogy of Ceylon. By Dr. R. Gyax.—Account of the Dutch Church in Ceylon (*continued*). By the Rev. J. D. Palm.—The History of Jaffna, from the earliest Period to the Dutch Conquest. By S. Casie Chitty.—The Rise and Fall of the Kelani-ganga from 1843 to 1846. By J. Capper.—The Discourse respecting Ratapála. Translated by the Rev. D. J. Gogerly.—The Manufacture of Salt by Solar Evaporation : Methods adopted in the Chilaw and Puttalam Districts. By A. O. Brodie.—A Royal Grant engraved on a Copper-plate, translated, with Notes. Communicated by S. Casie Chitty.—Buddhism. By Rev. D. J. Gogerly.—Some Coins, Ancient and Modern, of Ceylon. By the Hon. Justice Stark.—Notes on the Climate and Salubrity of Puttalam. By A. O. Brodie.—Revenue and Expenditure of the Dutch Government, in Ceylon, during the last years of their Administration. By J. Capper.—List of Books in the Páli and Singhalese Languages. By the Rev. R. Spence Hardy.—Proceedings of Third Anniversary Meeting, April 22, 1848.

VOLUME II.

Part I.

No. 4.—1848-49.

On the formation of a Collection of Lepidoptera in Ceylon. By E. L. Layard.—Buddhism : *Patta Kamma*, or the Present Results of Virtuous Conduct. By Rev. D. J. Gogerly.—Rural Economy of the Singhalese, more particularly with reference to the District of Sabaragamuwa, with some Account of their Superstitions. By R. E. Lewis.—Sketches in the Natural History of Ceylon : Entomology (Genus *Papilio*). By E. L. Layard.—Catalogue of Books in the Tamil Language, with the names of Authors, Subjects, and Dates, as far as can be ascertained. (Sections I., II.) By S. Casie Chitty.—Sketches in the Natural

History of Ceylon : Ornithology (Genera, *Bucco*, *Hirundo*). By E. L. Layard.—On Ceylonite found near Trincomalee. By Lieut. Henderson.—Appendix : Hints to Amateur Conchologists, by H. Cuming ; Proceedings of Anniversary Meeting, March 31, 1849 ; Register of Temperature at Puttalam for Twelve Months, by A. O. Brodie ; Abstract of Meteorological Register kept at Batticotta in 1847 and 1848.

No. 5.—1849-50.

Remarks on an Analysis of Ceylon Coffee, with suggestions for the application of Manures. By Dr. R. Gygax.—Descriptive Catalogue of the Woods of Ceylon. By J. Capper.—Catalogue of Ceylon Woods. By J. Capper.—Sketches in the Natural History of Ceylon : Description of Two Minute New Freshwater Molluscs of the Genus *Planorbis* and *Bithinia*. By E. L. Layard.—Outline of the Tamil System of Natural History. By S. Casie Chitty.—Prison Discipline in Ceylon. By A. G. Green.—Catalogue of Books in the Tamil Language, with the names of the Authors, their Subjects, and the Dates, as far as can be ascertained. (Section III.) By S. Casie Chitty.—Sketches in the Natural History of Ceylon : *Mammalia*. By E. L. Layard.—Sketches in the Natural History of Ceylon : Ornithology. By E. L. Layard.—Notes on the Geology of Ceylon : Laterite Formation : Fluvial-tile Deposit of Nuwara Eliya. By E. F. Kelaart, M.D.—The Manufacture of Sugar from the Juice of the Coconut Tree. By J. G. Taylor.—The Sap of the Coconut Tree and its Manufacture into Sugar. By W. S. Taylor.—The Elu Language, its Poetry and its Poets. By James De Alwis.—List of *Mammalia* of Ceylon Observed or Collected. By E. F. Kelaart, M.D.—Description of New Species and Varieties of Mammals found in Ceylon. By E. F. Kelaart, M.D.—Appendix : Proceedings, December, 1849, to August 13, 1850 ; Abstract of Meteorological Register kept at Batticotta in 1849.

Part II.

No. 6.—1853.

Buddhism : *Chariyá Pīṭaka*. By the Rev. D. J. Gogerly.—Laws of the Buddhist Priesthood. By the Rev. D. J. Gogerly.—Statistical Account of the Districts of Chilaw and Puttalam, North-Western Province. By A. O. Brodie.—Rock Inscription at Gnrugoda Viháre, in the Magul Kóralé, Seven Kóralés. By A. O. Brodie.—Catalogue of Ceylon Birds. By E. F. Kelaart, M.D., and E. L. Layard.

No. 7.—1853.

Catalogue of Ceylon Birds (*continued*). By E. F. Kelaart and E. L. Layard.—Notes on some of the Forms of Salutation and

Address known among the Sîphalese. By the Hon. Justice Stark.—Two Rock Inscriptions. By A. O. Brodie.—On the Veddás of Bintenna. By the Rev. J. Gillings.—Rock Inscription at Piramanenkandal. By S. Casie Chitty.—Analysis of the Great Historical Poem of the Moors, entitled *Chitrâ*. By S. Casie Chitty.—Appendix: Proceedings, February 7, 1852, to April 4, 1853.

No. 8.—1855.

Analysis of the Great Historical Poem of the Moors, entitled *Chitrâ (concluded)*. By S. Casie Chitty.—Description of New or Little-known Species of Reptiles found in Ceylon. By E. F. Kelaart.—The Laws of Buddhist Priesthood(*continued*). By the Rev. D. J. Gogerly.—Ceylon Ornithology. By E. F. Kelaart.—Some Account of the Roḍiyás, with a Specimen of their Language. By S. Casie Chitty.—Notice of some Rock Inscriptions in the North-Western Province. By A. O. Brodie.—Appendix: Proceedings, April 30, 1853, to August 17, 1854.

VOLUME III.

No. 9.—1856-58.

Entomological Papers: being chiefly Description of Ceylon *Coleoptera*, with Observations on their Habits, &c. By J. Nietner.—Description of New and Little-known Species of Ceylon Nudi-branchiate Molluscs and Zoophytes. By E. F. Kelaart, M.D.—Description of New and Little-known Species of Ceylon Nudi-branchiate Molluscs and Zoophytes (*continued*). By E. F. Kelaart, M.D.—Account of the Works of Irrigation constructed by King Párákrama Báhu, contained in the 68th and 79th chapters of the *Maháwansa*, with Introductory Remarks. By L. De Zoysa, Mudaliyár.—Topographical and Statistical Account of the District of Nuwarakaláwiya. By A. O. Brodie.

No. 10.—1856-58.

The Principles of Sîphalese Chronology. By Rev. C. Alwis.—Remarks on the supposed Identity between Nágaséna and Nágárjuna. By J. De Alwis.—Introductory Paper on the Investigation of Sîphalese Music. By L. Nell.—Synopsis of the *Chivá Chittántam*. By M. Coomáraswámy.—Terms of Address and Modes of Salutation in use amongst the Sîphalese. By J. De Alwis.—Appendix: Proceedings of Meetings, October 2, 1856, to January 21, 1858.

No. 11.—1858-59.

Laws of the Buddhist Priesthood. By Rev. D. J. Gogerly.—Notes on the Mythological Legends of the Sîphalese. By J. De

Alwis.—Statistical Inquiry into the State of Crime of Ceylon. By J. Capper.—Sinhalese Rhetoric. By J. De Alwis.—Scripture Botany of Ceylon. By W. Ferguson.—Remarks on the supposed Identity between Nágárijuna and Nágaséna (*concluded*). By J. De Alwis.—Expenditure on Public Works in Ceylon. By J. Capper.—Appendix : Proceedings, May 8, 1858, to September 12, 1859.

No. 12.—1860-61.

Health and Disease in Ceylon. By B. Moss.—Cinnamon. By J. De Alwis.—Notes on the District of Badulla and its Natural Products. By W. C. Ondaatje.—The difference between the Páli and the Prákrit Mágadhí of Vararuchi. By J. De Alwis.—On Health and Diet, with special reference to Children and Youths in Ceylon. By Rev. B. Boake.—Appendix : Proceedings, December 17, 1859, to July 6, 1861 ; Letters from Dr. Buist and Sir J. E. Tennent to the *Athenæum*, relative to the Freshwater Wells of Jaffna.

VOLUME IV.

No. 13.—1865-66.

Proceedings, June 21, 1862, to July 6, 1866.—Demonology and Witchcraft in Ceylon. By Dandris de Silva Gunaratna, Mudaliyár.—The First Discourse delivered by Buddha. Translated by the Rev. D. J. Gogerly.—Puttúr Well.—The Air-breathing Fish of Ceylon. By the Rev. B. Boake.—The Origin of the Sinhalese Language : No. 1. By J. De Alwis.—Remarks on the Poisonous Properties of the *Calotropis Gigantea*. By W. C. Ondaatje.—The Crocodiles of Ceylon. By the Rev. B. Boake.—Native Medicinal Oils.

No. 14.—1867-70.

The Origin of the Sinhalese Language : No. 2. By J. De Alwis.—Buddhism : A Lecture. By the Rev. D. J. Gogerly.—Description of Two Birds New to the recorded Fauna of Ceylon. By H. Nevill.—Description of a New Genus and Five New Species of Marine Univalves from the Southern Province, Ceylon. By H. Nevill.—Brief Notice of Robert Knox and his Companions in Captivity in Kandy, discovered among the Dutch Records preserved in Colombo. By J. R. Blake.

No. 15.—1867-70.

Proceedings, November 6, 1866, to March 12, 1870.—Summary of the Contents of the First Book in the Buddhist Canon, called the *Párájika Pôta*, with Translation of a portion. By the Rev. S. Coles.

VOLUME V.

No. 16.—1870-71.

Methods of taking Impressions of Inscriptions. By T. W. Rhys Davids.—Prose Translation of the Introductory Stanzas of *Kusa Jātaka*. By L. F. Lee.—Notes on a Sannas. By L. F. Lee.—Notes on the Geological Origin of South-Western Ceylon. By H. Nevill.—Inscription at Weligama Vihāré : Text, Translation, and Notes. By T. W. Rhys Davids.—Dondra Inscription, No. 1. By T. W. Rhys Davids.—The Second Species of *Zosterops* inhabiting Ceylon. By W. V. Legge.—Further Notes on the Ornithology of Ceylon. By Hugh Nevill.—Various Birds of the Western Province. By W. V. Legge.—The Origin of the *Śri-Pāda*, or Sacred Foot-Print on the Summit of Adam's Peak. By W. Skeen.—Romanized Text of the first Five Chapters of *Bālavatāra*. By L. F. Lee.—Specimens of Sinhalese Proverbs. By L. D. Zoysa, Mudaliyār.—Translations of certain Documents, Family and Historical, found in the possession of the Descendants of Monsieur Nancloas de Lanerolle, French Envoy to the Court of Kandy in 1682. By L. Ludovici.

Proceedings, March 24, 1870, to January 16, 1871.

No. 17.—1871-72.

Extracts from a Memoir left by the Dutch Governor, Thomas Van Rhee, to his successor, Governor Gerrit de Heer, 1697. Translated from the Dutch Records preserved in Colombo. By B. A. Van Cuylenberg.—The Food Statistics of Ceylon. By J. Capper.—Specimens of Sinhalese Proverbs (*continued*). By L. De Zoysa, Mudaliyār.—On the Disease known as *Parangi ledā*. By Dr. Boake.—Text and Translation of Rock Inscription at Kēlaniya. By L. De Zoysa, Mudaliyār.—Ceylon Reptiles : being a Preliminary Catalogue of the Reptiles found in or supposed to be in Ceylon, compiled from various authorities. By W. Ferguson.—On an Inscription at Dondra : No. 2. By T. W. Rhys Davids.—Proceedings, June 15, 1871, to November 7, 1872.

No. 18.—1873.

On Oath and Ordeal. By B. F. Hartshorne.—Note on *Prinophilus Vincens*. By W. V. Legge.—The Sports and Games of the Sinhalese. By L. Ludovici.—On Miracles. By J. De Alwis.—On the Occurrence of *Scolopax Rusticola* (Woodcock) and *Gallinago Scolopacina* (Common Snipe) in Ceylon. By W. V. Legge.—Transcript and Translation of an Ancient Copper-plate Sannas. By L. De Zoysa, Mudaliyār.

No. 19.—1874.

Description of a supposed New Genus of Ceylon Batrachians. By W. Ferguson.—Note on the Identity of Piyadasi and Asóka. By L. De Soysa, Mudaliyár.—On the Island Distribution of the Birds in the Society's Museum. By W. V. Legge.—Brandmarks on Cattle. By J. De Alwis.—Notes on the Occurrence of a rare Eagle (*Limnaetus Kienieri*) new to Ceylon, and other interesting or rare birds. By S. Bligh.—Extracts from the Dutch Records preserved in Ceylon. By R. A. Van Cuylenberg.—The Stature of Gautama Buddha. By J. De Alwis.

Proceedings, January 29, 1873, to November 2, 1874.

VOLUME VI.

No. 20.—1879.

Notes on Ancient Singhalese Inscriptions. By Dr. P. Goldschmidt, Government Archæologist.—The Preparation and Mounting of Insects for the Binocular Microscope. By S. Green.—Notes on *Neophron Pucropterus* (white Scavenger Vulture) from Nuwara Eliya. By A. Whyte.—On the Climate of Dimbula. By E. Heelis.—Notes on the supposed Cause of the Existence of Mountain *Fatanas*, or Grass Lands of the Mountain Zone of Ceylon. By Rev. R. Abbay.

No. 21.—1880.

Address of the President (Hon. Colonel A. D. Fyers, R.E.) at General Meeting, September 11, 1879.—Text and Translation of the Inscription of Mahindo III. at Mibintalé, with Glossary. By E. Müller, Government Archæologist.—The Vedic and Buddhistic Politics. By M. M. Künze.—Customs and Ceremonies connected with Paddy Cultivation. By R. W. Ievers, c.c.s.—*Gramineæ*, or Grasses indigenous to or growing in Ceylon. By W. Ferguson.

No. 22.—1880.

Gramineæ, or Grasses indigenous to or growing in Ceylon (*continued*). By W. Ferguson.—Translation of Two Játakas. By L. De Zoysa, Mahá Mudaliyár.—The supposed Origin of Tammanná Nuwara, Tambapanni, and Taprobane. By W. Ferguson.—The Rocks and Minerals of Ceylon. By A. C. Dixon.

Proceedings, February 1, 1875, to December 16, 1880.

VOLUME VII.

No. 23.—1881.

Hindú Astronomy : as compared with the European Science. By S. Mervin.—Sculptures at Horana. By J. G. Smither, F.R.I.B.A.—Gold. By Alex. C. Dixon, B.Sc. (Honours), London.—Specimens of Sīḥalese Proverbs (*continued* from Vol. V., No. 17, 1871–72). By Louis De Zoysa, Mahā Mudaliyār.—Ceylon Bee Culture. By S. Jayatilaka, Mudaliyār.—A Short Account of the Principal Religious Ceremonies observed by the Kandyans of Ceylon. By C. J. R. Le Mesurier, c.c.s.—Valentyn's Account of Adam's Peak. By A. Spence Moss, Public Works Department.

No. 24.—1881.

The Ancient Emporium of Kalah, &c., with Notes on Fa Hian's Account of Ceylon. By H. Nevill, c.c.s.—The Sīḥalese observance of the *Kalāwa*. By L. Nell.—Note on the Origin of the Vēddās, with specimens of their Songs and Charms. By L. D. Zoysa, Mahā Mudaliyār.—A *Hūṇiyam* Image. By L. Nell.—Note on the *Mira Kantiri* Festival of the Muhammadans. By A. T. Shamsud-din.—Sericulture in Ceylon. By J. L. Vanderstraaten, M.D.—Sīḥalese Omens. By S. Jayatilaka, Mudaliyār.

Proceedings, February 2, 1881, to December 16, 1881.

No. 25.—1882.

Nirvāna. By Professor M. M. Kūnte.—Two Sīḥalese Inscriptions. By B. Guṇasēkara, Government Translator.—Folklore in Ceylon. By W. Guṇatilaka.—Buddha's Sermon on Omens. By L. D. Zoysa, Mahā Mudaliyār.—Notes on the Microscopical Characteristics of Feathers, and their present analogy with a probable aboriginal form. By F. Lewis.—Sīḥalese Folklore Stories. By W. Knight James.—Ruins at Veheragala. By P. A. Templer, c.c.s.—The Connection of the Sīḥalese with the Modern A'ryan Vernaculars of India. By W. P. Ranasiḥa.

Extra No.—1882.

Ibn Baṭūta in the Māldives and Ceylon. By Albert Gray, M.R.A.S.

Proceedings, January 25, 1882, to December 22, 1882.

VOLUME VIII.

No. 26.—1883.

Sinhalese Birdlore. By W. K. James, F.R.G.S., F.R.HIST.S.—
The Papikkans of Munchali. By G. M. Fowler, c.c.s.—Notes on
Ancient Sinhalese Inscriptions. By Dr. E. Müller.—Sinhalese
Customs and Ceremonies connected with Paddy Cultivation
in the Low-country. By H. C. P. Bell, c.c.s.

Proceedings, January 25, 1883, to December 20, 1883.

No. 27.—1884.

Report on Archæological Discoveries at Tisamaharáma.
By Henry Parker, F.G.S., F.Z.S., F.R.HIST.SOC., &c., Irrigation
Officer.

No. 28.—1884.

Papers on the First Fifty Játakas. By the Right Rev.
R. Coplestone, D.D., Lord Bishop of Colombo.

No. 29.—1884.

Notes Illustrative of Buddhism as the Daily Religion of the
Buddhists of Ceylon, and some Account of their Ceremonies
before and after Death. By the Hon. J. F. Dickson, M.A. OXON.—
The Language of the Threshing-floor. By J. P. Lewis,
c.c.s.—Notes on the Ornithology of the Balangoda District. By
F. Lewis.—Ornithological Notes taken in the Bogawantalawa
District, during September, 1882. By F. Lewis.—Tamil
Customs and Ceremonies connected with Paddy Cultivation in
the Jaffna District. By J. P. Lewis, c.c.s.—Kasagal Vihâré.
By E. R. Gnnaratna, Atapattu Mudaliyâr.—Kâli Kôvila. By
Arthur Jayawardana, Mudaliyâr.—Beligala. By R. W. Ievers,
c.c.s.—*An-keliya*. By C. J. R. Le Mesurier, c.c.s.

• Proceedings, February 1, 1884, to December 22, 1884.

VOLUME IX.

No. 30.—1885.

A Systematic Catalogue of the Flowering Plants and Ferns
indigenous to, or growing wild in, Ceylon, with the Vernacular
names, and with references to Thwaites' "Enumeratio." By
Henry Trimen, M.B. LOND. F.L.S., Director of the Royal Botanic
Gardens, Ceylon.

No. 31.—1885.

Remarks on the Composition, Geographical Affinities, and Origin of the Ceylon Flora. By Henry Trimen, M.B.LOND., F.L.S.—Rice Cultivation under Irrigation in Ceylon. By E. Elliott, C.C.S.—Plumbago: with special reference to the position occupied by the Mineral in the Commerce of Ceylon; and the question discussed of the alleged existence in the Island of the allied substance Anthracite. By A. M. Ferguson, C.M.G.

Proceedings, January 29, 1885, to December 21, 1885.

No. 32.—1886.

Professor Virchow's Ethnological Studies on the Siphalese Race. Translated by W. R. Kynsey, F.R.Q.C.P., and J. D. MacDonald, M.D.—Outline of Two Years' Scientific Researches in Ceylon. By Drs. C. F. and P. D. Sarasin.—A Brief Sketch of the Medical History of Ceylon. By J. L. Vanderstraaten, M.D.—The Veddás of Ceylon. By C. J. R. Le Mesurier, C.C.S., F.G.S., &c.


No. 33.—1886.

The Veddás of Ceylon, and their relation to the Neighbouring Tribes. By Professor R. Virchow.

Proceedings, February 13, 1886, to December 16, 1886.

PRINTED AT
THE GOVERNMENT PRINTING WORKS
COLOMBO, CEYLON.







1. The first part of the document is a list of names and titles, including "The Hon. Mr. Justice" and "The Hon. Mr. Justice".

